MICHIGAN DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION FOR HMA SPILLWAY

C&T:JAR 1 of 1 C&T:APPR:JAR:GEN 06-20-03

- **a. Description.** Construct hot mix asphalt (HMA) spillways at the locations shown on the plans. Complete this work according to section 814 of the Standard Specifications for Construction except as herein modified.
- **b. Materials.** Use the same HMA mixture to construct the spillway as specified the adjacent shoulder or gutter or as specified for top course on the project if there is no adjacent shoulder gutter.
 - **c. Construction.** Construct HMA Spillway according to the details shown on the plans.
 - 1. **Preparation of Base.** Shape and compact base to the required cross section. Geotextile lining is not required under HMA spillways, except as shown on the plans or as required by the Engineer.
 - Placing HMA Mixture. Place mixture on the prepared base at the rate shown on the plans. Construct the spillway at the same time the adjacent HMA shoulder gutter is paved. No cold joint is permitted. Place and compact by mechanical or hand methods, as approved by the Engineer
- **d. Measurement and Payment.** The completed work will be measured in place by area based on the limits defined in the plan details and paid for at the contract unit price for the following contract item (pay item).

Contract Item	(Pay Item)	Pay Unit
HMA Spillway		Square Yard

Payment includes HMA mixture and geotextile (when required). Riprap used in conjunction with HMA Spillway will be measured and paid for separately.