

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
**SHOULDER CORRUGATIONS - RETROFIT
(RUMBLE STRIPS)**

C&T:JAR

1 of 2

C&T:APPR:JAR:GEN:06-23-03

a. Description. Mill or diamond grind ½-inch shoulder corrugations (rumble strips) on finished concrete or hot mix asphalt (HMA) paved shoulders. Complete this work according to section 822 of the Standard Specifications for Construction and this special provision. Provide for traffic control according to section 812.

b. Material. None specified.

c. Construction. Construct rumble strips according to the patterns shown on the plans.

At the end of each work day, remove all equipment to a location where it does not present a hazard to traffic; clean the pavement by sweeping or flushing; and reopen the work area to traffic.

d. Measurement and Payment. The total length of rumble strips actually placed, measured longitudinally along the edge of pavement, will be measured for payment. Each shoulder will be measured separately.

Contract Item (Pay Item)

Pay Unit

Shoulder Corrugations, Retrofit Foot

Payment includes installing the shoulder corrugations and removing grindings from the pavement and shoulder. Traffic control is included in the payment for **Shoulder Corrugations, Retrofit**.