

a meter base is furnished by such power company it will be installed by the CONTRACTOR provided it is made available at the time work is in process at the bed site.

(b) Anodes and Wiring,

- (1) Twenty only 3" diameter x 60 " National Carbon graphite anodes will be furnished and installed.
- (2) 600' of #4 AWG type RR single conductor, stranded direct burial cable will be installed in 2' deep trench for header cable to anodes and negative to pipe.
- (3) Approximately 5000 lbs. of coal coke breeze backfill per bed will be furnished and installed.

(c) Test Leads,

- (1) A permanent test lead will be furnished and installed at the mid-points between rectifier stations.

7. For the material and equipment to be furnished and the services to be performed hereunder, including all charges for the complete installation and preliminary engineering and design work as required, the COMPANY agrees to pay the CONTRACTOR as follows:

A. Base Bed:

For each Base Bed as described in Clause 6 of this Agreement the sum of Two thousand and seventy-five (\$2,075.00) Dollars PROVIDED that such Base Bed price shall be subject to the adjustments enumerated hereunder, namely:

Adjustments:

- 1. For each anode installed over 20 anodes required \$35.00
- 2. Additional trenching, in excess of 600' base, per foot. .30
- 3. Additional wire, over base bed requirements of 600';
per foot20
- 4. Reduction of base bed price, should less than 20 anodes
be required, per anode 30.00