

PROJECT ADVERTISEMENT

DEPARTMENT OF MANAGEMENT AND BUDGET
FACILITIES ADMINISTRATION, DESIGN & CONSTRUCTION DIVISION

This form is required for the advertisement of all construction projects. (1984 PA 431)

TO: DESIGN & CONSTRUCTION DIVISION		DATE: April 13, 2009	
FROM: Department of Environmental Quality- Land and Water Division	PROJECT MANAGER Kameron Jordan	DMB FILE NUMBER 761/09289.RRD	INDEX NUMBER(S) 60590
ADVERTISEMENT DATE April 22, 2009		BID OPENING DATE AND TIME May 13, 2009, 2:00 PM	

PROJECT NAME AND LOCATION (INCLUDE STREET ADDRESS)

Mard Wetland Mitigation Restoration Project- South Haven, Michigan

The site is located on the west side of 71 ½ Street, north of 2nd Avenue and south of Baseline Road.
1557 2nd Avenue, South Haven, Michigan 49090

WALK-THROUGH INSPECTION DATE, TIME, AND LOCATION

Pre-Bid Conference is scheduled for May 4, 2009 at 2:00 PM at the project site.

 MANDATORY

DESCRIPTION OF WORK

Restoration of three wetland mitigation sites as presented on the Wetland Mitigation Restoration Plan Drawings 1 of 4 thru 4 of 4, Summary as follows:

Mitigation A (0.53 acres): Removal of +/- 50 cubic yards of Sediment from forebay, Removal of +/- 550 cubic yard from wetland, 0.53 acres wetland seeding, stabilization of stock pile area, Installation of 8 Conservation Easement Signs, Soil Erosion and Control, Restoration, All of items required to complete the work.

Mitigation B (0.70 acres): Removal of +/- 30 cubic yards of Sediment at inlet, Installation of Riprap Spillway, Modification to Stormwater Ou Structure, repair of 5' x 10' area of erosion , 0.7 acres of wetland Seeding, Stabilization of stock pile area, Installation of 17 Conservation Easem Signs, Soil Erosion Control, Restoration, All other items required to complete the work.

Mitigation C (0.5 acres): Excavation and Grading for construction of wetland mitigation (+/- 1100 cubic yards), Placement of 3 Whole Tree Hab Structures, Placement of 1 Branch Bundle Habitat Structure, Placement of 5 Log Habitat Structures, removal of 2 riprap berm, Installation of rip Overflow, installation of riprap channel, plastic pipe modifications, , Placement of approximately 420 cubic yards of Topsoil, 0.5 acres of wetl Seeding, stabilization of stock pile area, Installation of 10 Conservation Easement Signs, Soil Erosion Control, Restoration, All other items requi to complete the work.

Bid Security and Performance Bonds: Required Not Required

All Bidders submitting bids in excess of \$100,000.00 must be certified by the Department of Civil Rights for compliance with State of Michigan Equal Employment Opportunity requirements prior to submission of bids. **Note:** Due to recent processing improvements by the Department of Management & Budget (DMB) and the Department of Civil Rights (DCR) concerning Certificates of Awardability, consideration may be given to bids received while final certification is still pending. In order to qualify for such consideration a bidder who does not possess a Certificate of Awardability valid through the bid opening date must do each of the following:

- Notify MDCR in writing, by sending a facsimile (fax) to 313-456-3826 at least 3 business days prior to the bid opening date, that the bidder has submitted a bid contingent upon a pending Certificate of Awardability. Notice shall indicate the contract bid upon, the scheduled bid opening date, the name and phone number(s) of a contact person able to speak for the bidder on the subject of awardability, and the date on which the bidder's application for Certificate of Awardability was initially filed.
- Ensure that all information required on the application for Certificate of Awardability was provided to MDCR.

Documents may be obtained from: Environmental Consulting & Technology, Inc., 2200 Commonwealth Blvd., Suite 300, Ann Arbor, Michigan 48105 Contact: Don Tilton

Phone: () 734-769-3004

Fax: () 734-769-3164

Date Approved: _____ By: _____