



Department of Natural Resources and Environment  
Office of Land and Facilities  
Design, Construction and Customer Systems Section

## CAMP & MUSKELLUNGE LAKES BOATING ACCESS SITES

### PARKING IMPROVEMENTS

DNR PROJECT No. 27-9002 & 27-9097

#### ADDENDUM No. 1

BID OPENING DATE: Friday, May 12, 2010 at 2:00 p.m., Local Time

DATE ADDENDUM ISSUED: Wednesday, May 6, 2010

STATE UNIT: Recreation Division

TO: ALL BIDDERS

SUBJECT: This Addendum No. 1 is issued to revise the Contract Documents for the above referenced project.

- ITEM #1:** CAMP LAKE – On Sheet C3, “Proposed Site Plan”, Annotation Mark #1, should add “and Re-install Guardrails w/posts on each side”.
- ITEM #2:** CAMP LAKE – Sheet C1, “Demo/SESC Plan”, Annotation Mark #12, should add “removal of vegetation and organic materials are to include any trees, or limbs, within 6 feet horizontally and 15’ vertically of the influence area of the proposed pavement and shoulder area along the drive”.
- ITEM #3:** CAMP LAKE – The Kent County Road Commission Driveway Permit requires the project Performance Bond must remain in effect through one Winter season to Spring season after completion of work allowed under this permit; Sheet 09-008, Note 20.
- ITEM #4:** CAMP LAKE – Sheet C5, “Layout/Grading Plan”, Point Table, Point 90 lists Elevation 75.20; This should be corrected to read Elevation 74.00. This is the Rim Elevation of the new Leaching Basin. Smoothly grade around the toilet vault and to other remaining closest Elevation points and restore.
- ITEM #5:** CAMP LAKE – The existing underground Electrical service is located generally along a direct line from the West DNR property line power pole to the sanitary lift station. This needs to be confirmed with the required MISS DIGG site staking.
- ITEM #6:** MUSKELLUNGE LAKE – Sheet C4, “Sections & Details”, Boardwalk uprights are to be 6”x6”, decking boards are 2”x6”, supporting members must be appropriately and proportionately sized using industry standard deck construction materials and methods. The concrete piers are to be 18” diameter and poured using 3500 psi, exterior, air-entrained concrete in accordance with the Specifications.

**ITEM #7: MUSKELLUNGE LAKE – ALTERNATE #1:**

**Please provide a quotation for the following Additional Work:**

**Furnish and install 6 each new 2” to 2 1/2“ Sugar Maple trees, to be located on site by the DNRE Supervisor. The price is to include the removal of the 4 existing (dead) trees.**

**LUMP SUM ADD (+) \$ \_\_\_\_\_**

**NOTE: The Award of Contract will be based upon the lowest Base Bid submitted by a responsive and responsible Bidder, provided such a bid does not exceed available funds. The Owner may or may not elect to exercise the above Additional Work depending upon available funding.**

**Acknowledgment: Two copies of this Addendum No. 1, properly signed in the space provided below, shall be submitted with your duplicate Proposal and Contract Forms.**

\_\_\_\_\_  
(Firm Name)

\_\_\_\_\_  
(Bidder's Signature and Title)

\_\_\_\_\_  
(Date)



Douglas Gallup, Facilities Engineer  
Design, Construction and Customer Systems  
Office of Land and Facilities  
(517) 241-2299