

Flint Safe Drinking Water Task Force Recommendations Regarding Flint Drinking Water Treatment Performance

This response is intended to identify how the comments received from the Flint Safe Drinking Water Task Force have been addressed.

The city of Flint is preparing a plan on how to bring Karegnondi Water Authority (KWA) water into the Flint Water Treatment Plant (Plant) to conduct full-scale testing and demonstrate that all water quality parameters can be met at the Plant. The process will result in full-scale testing of all the treatment components of the Plant before any treated water is released to the distribution system. Pilot tests will begin this spring utilizing the Saginaw/Midland water supply to conduct bench testing. Pipe loops will be utilized to determine optimization of corrosion control for the KWA water supply.