Michigan Department
Of Transportation
5100B (05/13)

CHECKLIST TO DESIGNATE AREAS OF EVALUATION FOR REQUESTS FOR PROPOSAL (RFP)

REQUISITION NUMBER	DUE DATE	TIME DUE
1295	8/5/2013	noon EST

MDOT PROJECT MANAGER	JOB NUMBER (JN)	CONTROL SECTION (CS)
Gerard Pawloski	Various	82122

DESCRIPTION
As-needed construction testing for I-96, from Telegraph Road to Newburgh Road, in the City of Livonia

MDOT PROJECT MANAGER: Check all items to be included in RFP WHITE = REQUIRED ** = OPTIONAL Check the appropriate Tier in the box below			**CONSULTANT:** Provide only checked items below in proposal
☐ **TIER 1 ($50,000 - $150,000)**	☐ **TIER II ($150,000-$1,000,000)**	☑ **TIER III (>$1,000,000)**	
☐	☐	☑	Understanding of Service **
☐	☐	☐	*Innovations*
☐	☐	☑	Organizational Chart
☐	☐	☑	Qualifications of Team
Not required as part of Official RFP	Not required as part of Official RFP	☑	Quality Assurance/Quality Control **
☐	☐	☑	**Location:** The percentage of work performed in Michigan will be used for all selections unless the project is for on-site p=inspection or survey activities, then location should be scored using the distance from the consultant office to the on-site inspection or survey activity.
N/A	N/A	☐	Presentation **
N/A	N/A	☐	Technical Proposal (if Presentation is required)
3 pages (MDOT Forms not counted) **(No Resumes)**	7 pages (MDOT Forms not counted)	14 pages (MDOT forms not counted)	Total maximum pages for RFP **not including key personnel resumes.** Resumes limited to 2 pages per key staff personnel.

PROPOSAL AND BID SHEET EMAIL ADDRESS – mdot-rfp-response@michigan.gov

GENERAL INFORMATION

Any questions relative to the scope of services must be submitted by e-mail to the MDOT Project Manager. Questions must be received by the Project Manager at least five (5) working days prior to the due date and time specified above. All questions and answers will be placed on the MDOT website as soon as possible after receipt of the questions, and at least three (3) days prior to the RFP due date deadline. The names of vendors submitting questions will not be disclosed.

MDOT is an equal opportunity employer and MDOT DBE firms are encouraged to apply. The participating DBE firm, as currently certified by MDOT's Office of Equal Opportunity, shall be listed in the Proposal.

MDOT FORMS REQUIRED AS PART OF PROPOSAL SUBMISSION

5100D – Request for Proposal Cover Sheet
5100J – Consultant Data and Signature Sheet (Required only for firms not currently prequalified with MDOT)

(These forms are not included in the proposal maximum page count.)

REQUEST FOR PROPOSAL

The Michigan Department of Transportation (MDOT) is seeking professional services for the project contained in the attached scope of services.

If your firm is interested in providing services, please indicate your interest by submitting a Proposal, Proposal/Bid Sheet or Bid Sheet as indicated below. The documents must be submitted in accordance with the latest (Consultant/Vendor Selection Guidelines for Services Contracts" and "Guideline for Completing a Low Bid Sheet(S)*, if a low bid is involved as part of the selection process. **Reference Guidelines are available on MDOT's website under Doing Business > Vendor/Consultant Services >Vendor/Consultant Selections.**

RFP SPECIFIC INFORMATION

☑ ENGINEERING SERVICES ☐ BUREAU OF TRANSPORTATION PLANNING ☐ OTHER

THE SERVICE WAS POSTED ON THE ANTICIPATED QUARTERLY REQUESTS FOR PROPOSALS

☑ NO ☐ YES DATED_____ THROUGH _____

☑ **Prequalified Services** – See the attached Scope of Services for required Prequalification Classifications.

☐ **Non-Prequalified Services** – If selected, the vendor must make sure that current financial information, including labor rates, overhead computations, and financial statements, if overhead is not audited, is on file with MDOT's Office of Commission Audits. This information must be on file for the prime vendor and all sub vendors so that the contract will not be delayed. **Form 5100J is required with Proposal for firms not currently prequalified with MDOT**

☑ **Qualifications Based Selection** – Use Consultant/Vendor Selection Guidelines

For all Qualifications Based Selections, the selection team will review the information submitted and will select the firm considered most qualified to perform the services based on the proposals. The selected firm will be asked to prepare a priced proposal. Negotiations will be conducted with the firm selected.

For a cost plus fixed fee contract, the selected vendor must have a cost accounting system to support a cost plus fixed fee contract. This type of system has a job-order cost accounting system for the recording and accumulation of costs incurred under its contracts. Each project is assigned a job number so that costs may be segregated and accumulated in the vendor's job-order accounting system.

☐ **Qualification Based Selection / Low Bid** – Use Consultant/Vendor Selection Guidelines. See Bid Sheet instructions for additional information.

For Qualification Review/Low Bid selections, the selection team will review the proposals submitted. The vendor that has met established qualification threshold and with the lowest bid will be selected.

☐ **Best Value** – Use Consultant/Vendor Selection Guidelines, See Bid Sheet Instructions below for additional information. The bid amount is a component of the total proposal score, not the determining factor of the selection.

☐ **Low Bid** (no qualifications review required – no proposal required.) See Bid Sheet Instructions below for additional instructions.

BID SHEET INSTRUCTIONS

Bid Sheet(s) must be submitted in accordance with the "Guidelines for Completing a Low Bid Sheet(s)* (available on MDOT's website). Bid Sheet(s) are located at the end of the Scope of Services. Submit bid sheet(s) with the proposal, to the email address: mdot-rfp-response@michigan.gov. Failure to comply with this procedure may result in your bid being rejected from consideration.

PARTNERSHIP CHARTER AGREEMENT

MDOT and ACEC created a Partnership Charter Agreement which establishes guidelines to assist MDOT and Consultants in successful partnering. Both the Consultant and MDOT Project Manager are reminded to review the **ACEC-MDOT Partnership Charter Agreement** and are asked to follow all communications, issues resolution and other procedures and guidance's contained therein.

NOTIFICATION
MANDATORY ELECTRONIC SUBMITTAL

Proposals submitted for this project must be submitted electronically.

The following are changes to the Proposal Submittal Requirements:

- Eliminated the Following Requirements:
  - Safety Program
  - Communication Plan
  - Past Performance as *a separate section*
  - Separate section for DBE Statement of goals. Include information in Qualification of Team section

- Implemented the Following Changes:
  - All proposals require an Organization Chart
  - Resumes must be a maximum of two pages
  - Only Key (lead) staff resumes may be submitted
  - Tier III proposal reduced from 19 to 14 pages
  - Forms 5100D, 5100I, and 5100G combined – 5100D
  - Forms 5100B and 5100H combined – 5100B
  - RFP's will be posted on a weekly basis -- on Mondays

The following are Requirements for Electronic Submittals:

- Proposals must be prepared using the most current guidelines
- The proposal must be bookmarked to clearly identify the proposal sections (See Below)
- For any section not required per the RFP, the bookmark must be edited to include "N/A" after the bookmark title.
  Example: Understanding of Service – N/A
- Proposals must be assembled and saved as a single PDF file
- PDF file must be 5 megabytes or smaller
- PDF file must be submitted via e-mail to MDOT-RFP-Response@michigan.gov
- MDOT's requisition number and company name must be included in the subject line of the e-mail. The PDF shall be named using the following format:
  - Requisition#XXX_Company Name.PDF
- MDOT will not accept multiple submittals
- Proposals must be *received* by MDOT on or before the due date and time specified in each RFP

If the submittals do not comply with the requirements, they may be determined unresponsive.

The Consultant's will receive an e-mail reply/notification from MDOT when the proposal is received. Please retain a copy of this e-mail as proof that the proposal was received on time. **Consultants are responsible for ensuring the MDOT receives the proposal on time.**

****Contact Contract Services Division immediately at 517-373-4680 if you do not get an auto response****

Required Bookmarking Format:

I. Request for Proposal Cover Sheet Form 5100D
   A. Consultant Data and Signature Sheet, Form 5100J (if applicable)
II. Understanding of Service
   A. Innovations
III. Qualifications of Team
   A. Structure of Project Team
      1. Role of Firms
      2. Role of Key Personnel
   B. Organization Chart
   C. Location
IV. Quality Assurance / Quality Control Plan
V. Resumes of Key Staff
VI. Pricing Documents/Bid Sheet (if applicable)

2/14/12

.

NOTIFICATION
E-VERIFY REQUIREMENTS

E-Verify is an Internet based system that allows an employer, using information reported on an employee's Form I-9, Employment Eligibility Verification, to determine the eligibility of that employee to work in the United States. There is no charge to employers to use E-Verify. The E-Verify system is operated by the Department of Homeland Security (DHS) in partnership with the Social Security Administration. E-Verify is available in Spanish.

The State of Michigan is requiring, under Public Act 200 of 2012, Section 381, that as a condition of each contract or subcontract for construction, maintenance, or engineering services that the pre-qualified contractor or subcontractor agree to use the E-Verify system to verify that all persons hired during the contract term by the contractor or subcontractor are legally present and authorized to work in the United States.

Information on registration for and use of the E-Verify program can be obtained via the Internet at the DHS Web site: http://www.dhs.gov/E-Verify.

The documentation supporting the usage of the E-Verify system must be maintained by each consultant and be made available to MDOT upon request.

It is the responsibility of the prime consultant to include the E-Verify requirement documented in this NOTIFICATION in all tiers of subcontracts.

9/13/12

Michigan Department of Transportation

SCOPE OF SERVICE
FOR
CONSTRUCTION SERVICES
As Needed Testing

CONTROL SECTION(S): 82122

JOB NUMBER(S): Various

PROJECT LOCATION: I-96 from Telegraph Road to Newburgh Road, City of Livonia, Redford Township, Wayne County

DESCRIPTION OF WORK:

Provide complete testing services for primarily concrete, with any and all of the following: Aggregate, HMA, and/or Materials, as needed and requested by the MDOT Project Manager. This work includes:

- Completion of all Quality Assurance Testing requirements and any other Testing, for concrete and any of the other above mentioned items, as directed.
- Completion of all paperwork necessary for the project files.
- Delivering quality assurance strength test cylinders from the job site to the Metro Region C&T laboratory including coordinating in advance after-hours and/or weekend drop-offs

The schedule for this project shall be considered to be as much as seven (7) days per week and ten (10) to fourteen (14) hours per day. This project may require the coordination of multiple testing operations at one time. The consultant must demonstrate that it has qualified individuals available to meet this schedule. Weekend work will be required. Night work may be required. **MDOT reserves the right to modify the number of consultant technicians being utilized based on work load.**

OEC plans are available for review at the following link:
ftp://ftpmdot.state.mi.us/96 OEC plans and proposal/

A pre-proposal meeting will be held for all interested vendors prequalified in the Primary Prequalification Classification on July 24th at the Southeast Michigan Transportation Operations Center (formerly known as the Detroit Transportation Service Center) at 9:00am to discuss the scope of this contract. Due to concerns of available space, the attendance will be limited to one (1) representative per prequalified vendor.

ANTICIPATED START DATE: November 15, 2013

ANTICIPATED COMPLETION DATE: November 15, 2015

PRIMARY PREQUALIFICATION CLASSIFICATION:
Portland Cement Concrete Inspection and Testing – Testing Only

SECONDARY PREQUALIFICATION CLASSIFICATION:
Aggregate Testing
Hot Mix Asphalt (HMA) Technician Testing Assistance
Density Inspection and Testing - Testing Only

DBE REQUIREMENT: 10%

ESTIMATED CONSTRUCTION COST: $160,000,000.00

MDOT PROJECT MANAGER:

Gerard Pawloski
Construction Engineer
MDOT I-96 Field Office
Email: Pawloskig@michigan.gov
Phone Number: (248) 451-2428

The Consultant shall contact the Project Manager prior to beginning any work on this Project.

GENERAL INFORMATION:

A. The Consultant shall furnish all services and labor necessary to conduct and complete the Construction Engineering Services described herein. The Consultant shall also furnish all materials, equipment, supplies, and incidentals necessary to perform the Services (other than those designated in writing to be furnished by the Department), and check and/or test the materials, equipment, supplies, and incidentals as necessary in carrying out this work. The Services shall be performed to the satisfaction of the Department consistent with applicable professional standards.

B. The Consultant's principal contact with the Department shall be through the Project Engineer Manager.

C. The Services described herein are financed with public funds. The Consultant shall comply with all applicable Federal and State laws, rules, and regulations.

D. The Consultant agrees to demonstrate knowledge of, and performance in compliance with, the standard construction practices of the Department; the Project construction contract, proposal, and plans; the Standard Specifications for Construction and all applicable publications referenced within; the Michigan Construction Manual; the Materials Sampling Guide; the Materials Quality Assurance Procedures Manual; the Density Control Handbook; and any and all other references, guidelines, and procedures manuals needed to carry out the work described herein in an appropriate manner.

E. The Consultant will notify the MDOT Project Manager, in writing, prior to any personnel changes from those specified in the Consultant's original approved proposal. Any personnel substitutions are subject to the review and approval of the MDOT Project Manager.

F. The selected consultant staff will report directly to the MDOT Project Manager and work closely with MDOT I-96 Field Office Construction Team. This team will consist of a Senior Construction Engineer, a Construction Engineer, two Road Construction Assistant Delivery Engineers, two Bridge Construction Assistant Delivery Engineers, and various Staff Engineers and Technician staff assigned to this project for its entirety and who will be on site as necessary during construction. Consultant staff will operate under the MDOT Senior Construction Engineer, or his designated staff. The MDOT point-of-contact for the Consultant Project Manager, and for day-to-day scheduling and coordination, will be the MDOT Project Engineer Manager (PEM). The PEM will be the MDOT Senior Construction Engineer, or a designated staff on the MDOT Construction Team. MDOT will retain control over all monetary extras and changes and the design revision process. All of the consultant personnel shall meet with the MDOT Construction Team prior to construction of this project. This will familiarize everyone with one another and define/clarify roles and responsibilities.

G. The consultant will be required to document and process all IDRs and other documents using FieldBook as applicable. MDOT staff may review the FieldBook at any time and create FieldManager items.

H. An expectations meeting will be held with the Consultant by the MDOT Project Engineer Manager (PEM) prior to work start. Further, the Consultant shall contact the PEM prior to beginning any work on this contract.

I. The Consultant shall contact the PEM prior to beginning any work on this Project. Key consultant personnel are required to attend a partnering session with the MDOT staff prior to construction.

J. The technicians shall submit time sheets to the PEM for review and approval if requested.

CONSULTANT RESPONSIBILITIES:

The Consultant shall perform field operations in accordance with the Department's Personal Protective Equipment (PPE) Policy as stated in the MDOT Guidance Document #10118. A current copy of MDOT's PPE Policy is available on the Bulletin Board System. The Consultant shall perform field operations in accordance with MIOSHA regulations and accepted safety practices.

A. Provide part and full time experienced testing services as needed and perform testing services under the direction of the Project Engineer Manager. The personnel assigned to this project will report and be directly responsible to the Project Engineer Manager, or their designated MDOT representative. Provide computer equipment necessary to run Field Manager.

B. Provide, to the satisfaction of the Department, testing services required for Portland Cement Concrete construction, aggregate construction, HMA construction and Density. Perform all reporting, measurement, computation, and documentation required by the Specifications, plans, proposal, the Michigan Construction Manual, the MDOT Materials Sampling Guide and any and all other applicable references, guidelines, and procedure manuals required as directed by the Project Engineer Manager.

C. Perform all work in compliance with the contract documents and the standard practices of the Department. Sampling frequencies for testing will be as prescribed by the Specifications, proposal, MDOT Materials Sampling Guide and/ or other applicable references, guidelines, and procedure manuals and instruction furnished by the Department or as directed by the Engineer, and no variation will be permitted except on written order of the Department.

D. That acceptance samples, tests, and reporting procedures will conform to the Specifications, proposal, MDOT Materials Sampling Guide and any and all other applicable references, guidelines, and procedures manuals prescribed by the Department.

E. Consultant personnel will immediately bring to the attention of the Project Engineer Manager, the failure by the Contractor to comply with a plan or specification requirement, any problem, trends toward borderline compliance, or any other occurrence which may require resolution by the Engineer.

F. The testing technician(s) will accurately report, measure, compute, and document all required data for testing work in accordance with the Specifications, plans, proposal, MDOT Materials Sampling Guide and any and all other applicable references, guidelines, and procedures manuals prescribed by the Department.

G. The Consultant shall provide their own transportation to, from, and on the project site to perform the services outlined herein.

H. The Consultant shall provide lap top computers (or equivalent) with Field Manager and/or Field Book software and produce all daily inspection reports in this format. The Consultant shall deliver all inspection reports to the Project Engineer Manager's field office daily unless other arrangements are made.

I. **The inspector(s) shall provide a Troxler Density gauge and comply with all requirements related to the use of this gauge established by the Nuclear Regulatory Commission and MDOT.** This gauge should be calibrated to meet MDOT requirements. **The inspector(s) shall be certified as MDOT density technicians.**

J. The Consultant shall provide all measuring and testing equipment required for this work, including a Roll-O-Meter, Acme or Pres-sure air entrainment gauge for concrete testing, and cylinder molds. The gauge must be calibrated to meet MDOT requirements. In addition, the Consultant shall provide all measuring and testing equipment required for proper and accurate testing services.

K. The Consultant shall provide to its personnel all required reference materials including, but not limited to, MDOT Standard Specifications, Materials Sampling Guide, Construction Manual, and any and all other necessary applicable references, guidelines and procedures manuals.

L. The Consultant shall be responsible for any errors that occur on the project due to an error in the testing services provided, should any such error occur. The Consultant will be responsible to compensate MDOT for any additional costs incurred due to testing errors on the project by one of their employees. At such time the error is discovered MDOT will meet with the Consultant to discuss options to rectify.

M. Keep daily diaries, sketches, logs, and records consistent with Department practice as may be needed to record the Contractor's progress.

N. Withdraw any personnel or halt any services no longer required, at the request of the Department, or within a reasonable time after the lack of need becomes apparent to the Consultant or the Project Manager. The consultant will not be reimbursed for the cost of personnel charged to a project that the Project Manager has determined was unnecessary.

TESTING AND REPORTING:

A. **Material Quality Assurance Sampling and/or Testing:** Perform all material quality assurance sampling and/or Testing in accordance with the attached Special Provision for Quality Control and Acceptance of Portland Cement Concrete (12SP604(B)), Materials Source Guide, Materials Quality Assurance Procedures Manual, and any or all other applicable referenced or included Contract Documents. Determine the acceptability of materials based on their respective specification requirements. Immediately inform the Project Manager of non-compliance work and trends toward borderline compliance. Reject Contractor's work and materials not in compliance with the Contract Documents or as directed by MDOT. **The Prime Consultant will be held accountable for all quality assurance activities and will be reimbursed for these activities unless otherwise indicated in writing by the MDOT project manager that the Prime Consultant is not responsible for these services.**

B. Material Certification: Make certain that acceptable test reports and/or material certifications from the supplier have been received, prior to the incorporation of materials in the work, for materials tested off the Project site.

C. **Material Reports:** Submit Material test reports, including but not limited, the Inspector's Report of Concrete Placed 1174A, Aggregate Inspection Reports 1900 & 1901, Bituminous QA reports, Concrete QA reports, and the "Moisture and Density Determination, Nuclear Method", Form 582B, etc. to the distribution list within one day of the testing. The efficiency of the consultant in getting the "Moisture and Density Determination, Nuclear Method", Form 582B, copy to the Lansing, Density Technology Unit, 8885 Ricks Road, Lansing, MI 48909 will be measured by that unit and reflected on the consultant's evaluation.

The consultant and any sub-consultants contracted by the Michigan Department of Transportation (MDOT) to perform density testing services that use equipment regulated by the Nuclear Regulatory Commission (NRC) shall:

1. **Possess a valid license issued by the NRC, or recognized Agreement State, for ownership and use of sealed sources contained within portable nuclear density gauges.**

2. **Provide the Radiation Safety Office (RSO) of MDOT with a copy of the aforementioned license.**

3. **Comply with all rules and regulations set forth by Title 10 (Energy) and 49 (Transportation).**

Failure of any of the above will be found in noncompliance with the contract.

MEASUREMENT, COMPUTATION AND DOCUMENTATION OF QUANTITIES:

A. **Documentation**: Provide appropriate documentation of all materials incorporated in the work as required by the Special Provision for Quality Control and Acceptance of Portland Cement Concrete, and maintain an item record account using Field Manager software. **The Consultant must obtain and be able to use the FieldManager Suite of Software for this project. Contact Info Tech, Inc. at (352) 381-4400 or fax (352) 381-4444 or (www.fieldmanager.com) to obtain software and information on training. Since this software will be used on all MDOT projects in the future, the cost of this software cannot be charged as a direct expense for this project. Consultants must keep their version of the FieldManager Suite of software current with the version being used by MDOT.**

B. **Insufficient Tested Materials**: Track insufficient tested materials and notify the Contractor on a bi-weekly basis.

REPORTING AND RECORD KEEPING:

A. **Consultant Reports:** Prepare such periodic, intermediate and final reports and records as may be required by the Department and as are applicable to the Project, which may include, but are not limited to:

- **a. Inspector's Daily Reports,**
- **b. Inspector's Report of Concrete Placed (Form 1174A-M)**
- c. **Other records, reports or forms as required by the Special Provision for Quality Control and Acceptance of Portland Cement Concrete (12SP602(F)), or for the individual Project by the Project Manager and/or as required by Specifications, Plans, Proposal, the Michigan Construction Manual, the Materials Sampling Guide, and any and all other applicable references, guidelines, and/or procedures manual**.

CLOSING ALL PROJECT DOCUMENTATION:

A. **Final Measure and Summarize**: Calculate Overall Lot Pay Factor (OLPF) as required by the Special Provision for Quality Control and Acceptance of Portland Cement Concrete (12SP604(B)). Final field measure applicable items of work. Prepare final summaries for applicable items of work.

MDOT RESPONSIBILITIES:

A. The Project Engineer Manager shall furnish to the Consultant all Project-specific construction contracts, proposals, plans, plan revisions, written instructions, and other information and/or data as deemed necessary by the Project Manager for the Services required herein.

B. The Department shall furnish off-site inspections and tests of steel, cement, bituminous mixture designs, sewer and drainage pipe, structural steel, prestressed girders and beams, traffic signs, and any other materials customarily tested in the Department laboratories with its own forces or by statewide contracts. The customary testing is described in the Materials Quality Assurance Manual with exceptions noted within the Specifications, Plans, and Proposal. The Consultant shall be responsible for the sampling and transportation of all materials to be tested by Department personnel.

C. The Project Engineer Manager shall provide general monitoring and quality auditing inspection of the Project to assure that the Project has been completed in reasonable conformance with the plans and specifications for Project Acceptance and to determine that the work performed to date by the Consultant for Services rendered is reasonable and appropriate before approving the Consultant's requests for progress payments.

D. The Department shall perform all concrete Quality Assurance cylinder strength testing at the Metro Region Construction and Technology laboratory.

E. The MDOT Project Engineer Manager will arrange and conduct the Preconstruction meeting as well as prepare and distribute the meeting minutes.

CONSULTANT PAYMENT:

The hours provided are only an estimate. The Consultant will be reimbursed a proportionate share of the fixed fee based on the portion of the authorized total hours in which services have been provided to the Department. Fixed fee on "as needed" projects is computed by taking the percent of actual labor hours billed to labor hours authorized, then applying that percentage to the total fixed fee authorized. The fixed fee for profit allowed for this project is 11.0% of the cost of direct labor and overhead.

Full time services may not be required on all projects at all times. This scope is for "as needed" services, based on the intermittent needs of MDOT. It must be noted that this is not a guarantee that MDOT will use the Consultant's services.

The hours billed for inspectors will not begin until the inspectors report to the project site or to the project office. Compensation for this project shall be on an actual cost plus fixed fee basis. This basis of payment typically includes an estimate of labor hours by classification or employee, hourly labor rates, applied overhead, other direct costs, subconsultant costs, and applied fixed fee.

All billings for services must be directed to the Department and follow the current guidelines. The latest copy of the "Professional Engineering Service Reimbursement Guidelines for Bureau of Highways" is available on MDOT's website. This document contains instructions and forms that must be followed and used for billing. Payment may be delayed or decreased if the instructions are not followed.

Payment to the Consultant for services rendered shall not exceed the maximum amount unless an increase is approved in accordance with the contract with the Consultant. Typically, billings must be submitted within 60 days after the completion of services for the current billing. The final billing must be received within 60 days of the completion of services. Refer to your contract for your specific contract terms.

Direct expenses, if applicable, will not be paid in excess of that allowed by the Department for its own employees in accordance with the State of Michigan's Standardized Travel Regulations. Supporting documentation must be submitted with the billing for all eligible expenses on the project in accordance with the Reimbursement Guidelines. The only hours that will be considered allowable charges for this contract are those that are directly attributable to the activities of this project.

For projects advertised May 1, 2013, or later, MDOT will reimburse the CONSULTANT for vehicle expenses and the costs of travel to and from project sites in accordance with MDOT's Travel and Vehicle Expense Reimbursement Guidelines, dated May 1, 2013. The guidelines can be found at http://www.michigan.gov/documents/mdot/Final_Travel_Guidelines_05-01-13_420289_7.pdf?20130509082418. MDOT's travel and vehicle expense reimbursement policies are intended primarily for construction engineering work. Reimbursement for travel to and from project sites and for vehicle expenses for all other types of work will be approved on a case by case basis

The use of overtime hours is not acceptable unless prior written approval is granted by the MDOT Region Engineer/Bureau Director and the MDOT Project Manager. Reimbursement for overtime hours that are allowed will be limited to time spent on this project in excess of forty hours per person per week. Any variations to this rule should be included in the priced proposal submitted by the Consultant and must have prior written approval by the MDOT Region Engineer/Bureau Director and the MDOT Project Manager.

For projects advertised May 1, 2013, or later, MDOT will pay overtime in accordance with MDOT's Overtime Reimbursement Guidelines, dated May 1, 2013. The guidelines can be found at http://www.michigan.gov/documents/mdot/Final_Overtime_Guidelines_05-01-13_420286_7.pdf?20130509081848. MDOT's overtime reimbursement policies are intended primarily for construction engineering work. Overtime reimbursement for all other types of work will be approved on a case by case basis.