SOIL EROSION AND SEDIMENTATION CONTROL MANUAL March 2021



CONSTRUCTION FIELD SERVICES DIVISION

Attention Department Users

This manual will no longer be printed and distributed to individual users. It can be found on the Michigan Department of Transportation's webpage at MDOT - Manuals & Guides.

FOREWORD

This manual has been developed to aid Michigan Department of Transportation (MDOT) personnel in the selection and application of adequate and efficient soil erosion and sedimentation control (SESC) measures during project development and delivery. The information provided by this manual is used in conjunction with the Standard Specifications for Construction; the project plans and proposal; and other Department publications. When considered as a whole, these documents satisfy the requirement for MDOT as an Authorized Public Agency under Part 91 of Public Act 451 of 1994, Natural Resources and Environmental Protection Act, as amended to develop, implement and enforce approved soil erosion and sedimentation control procedures.

This 2021 edition incorporates input from design, construction, and maintenance staff in Lansing, region offices and the TSCs and the Michigan Department of Environment, Great Lakes, and Energy (EGLE); new and revised legislation; and improved construction materials and processes. This document is formatted to allow revised pages to be easily substituted. It may be necessary to retain superseded pages for reference on projects which have been advertised prior to the date revisions are implemented (ref. Standard Specifications for Construction, subsection 101.01).

The information in this manual is subject to continuous review and evaluation. All revisions to this manual must be approved by EGLE prior to implementation. Comments and questions should be directed to the Environmental Field Services Engineer (EFSE). This manual provides guidance to administrative, engineering, and technical staff. Engineering practice requires that professionals use a combination of technical skills and judgment in decision making. Engineering judgment is necessary to allow decisions to account for unique site-specific conditions and considerations to provide high quality products, within budget, and to protect the public health, safety, and welfare. This manual provides the general operational guidelines; however, it is understood that adaptation, adjustments, and deviations are sometimes necessary. Innovation is a key foundational element to advance the state of engineering practice and develop more effective and efficient engineering solutions and materials. As such, it is essential that our engineering manuals provide a vehicle to promote, pilot, or implement technologies or practices that provide efficiencies and quality products, while maintaining the safety, health, and welfare of the public. It is expected when making significant deviations from the technical information from these guidance materials, that reasonable consultations with experts, technical committees, and/or policy setting bodies occur prior to actions within the timeframes allowed. It is also expected that these consultations will eliminate any potential conflicts of interest, perceived or otherwise. MDOT Leadership is committed to a culture of innovation to optimize engineering solutions.

The National Society of Professional Engineers Code of Ethics for Engineering is founded on six fundamental canons. Those canons are provided below.

Engineers, in the fulfillment of their professional duties, shall:

- 1. Hold paramount the safety, health, and welfare of the public.
- 2. Perform services only in areas of their competence.
- 3. Issue public statement only in an objective and truthful manner.
- 4. Act for each employer or client as faithful agents or trustees.
- 5. Avoid deceptive acts.

6. Conduct themselves honorably, reasonably, ethically and lawfully to enhance the honor, reputation, and usefulness of the profession.

AUTHORIZED PUBLIC AGENCY - POLICY STATEMENT

MDOT is aware of our responsibilities to preserve the natural resources of the State of Michigan when providing transportation services. MDOT's Mission Statement, and more specifically, the Vision Statement, recognizes this responsibility.

MDOT Mission Statement: Providing the highest quality integrated transportation services for economic benefit and improved quality of life.

TABLE OF CONTENTS

Foreword

Terminology Used in this Manual	Terminol	ogy Use	ed in this	: Manual
---------------------------------	----------	---------	------------	----------

1. Introduction	
1.1 Applicable Laws and Administrative Rules	9
1.2 MDOT's SESC Program	10
1.3 Key MDOT Organizational and Procedural Definitions	12
1.4 Related MDOT Documents	14
2. Project Development	
2.1 Planning Phase	17
2.2 Design Phase	18
3. Project Delivery	
3.1 Construction Projects	21
3.2 Maintenance Projects and Maintenance Activities	25
4. Compliance and Enforcement	
4.1 Construction Projects	29
4.2 Maintenance Projects and Maintenance Activities	30
4.3 EGLE Progressive Compliance (Escalation) Process	31
5. Permit Requirements, Acts and Rules	
5.1 MDOT Permit Coordinators	35
5.2 Permit Requirements	36
6. SESC Measures (Erosion & Sedimentation Details)	37
Appendix: Reference Information	
Environmental Procedure for Ditch Cleanout (Activity #1230)	
Sample NPDES and SESC Inspection Report (Form 1126)	
Sample Earth Change Plan	

THIS PAGE BLANK

TERMINOLOGY USED IN THIS MANUAL

In addition to the terms defined in subsection 101.02 of the *MDOT Standard Specifications for Construction* the terms defined here are used in this manual.

Construction Project A project that is administered and completed by Department construction

staff or by a consultant on behalf of the Department. Construction projects may include a full set of plans or may be log projects. Used to

differentiate from a maintenance project.

Contract Agency County or other local unit of government with which MDOT has entered

into a contract for provision of specific functions generally related to the

maintenance of state-owned roadways.

Department As used in this document, Department refers to the Michigan Department

of Transportation (MDOT).

Earth Change A man-made change in the natural cover or topography of land including

cut and fill which may result in or contribute to soil erosion or sedimentation. The term includes, but is not limited to, clearing, grading,

excavating and filling activities (a.k.a. earth disturbance).

Earth Change Plan (ECP) or Soil Erosion And Sedimentation Control Plan

A document that meets all requirements of Part 17 rule R 323.1703. The elements of this plan may be incorporated throughout the construction contract documents or the plan may be a stand-alone document for projects that do not involve preparation of a full set of plans. (e.g., log

project or maintenance projects/activities).

Soil Erosion and Sedimentation Control (SESC)

Measure or Best Management

Practice (BMP) Any of the specific measures described in this manual, section 208 of the

Standard Specifications for Construction or other contract documents; designed, constructed, and maintained to reduce or control soil erosion or off-site sedimentation. SESC measures may be constructed devices or construction practices intended to minimize soil erosion and off-site

sedimentation.

Floodplain An area of land adjoining a river or stream that will be inundated by a 1

percent chance (100 year) flood. (ref: MDOT Drainage Manual, Section

2.9.10.3)

Limits of

Earth Disturbance Unless stated otherwise in the contract documents, the limits of earth

disturbance will extend ten feet beyond the slope stake line except in areas adjacent to wetlands where the earth disturbance limits will be at

the slope stake line.

Log Project Straightforward and uncomplicated construction or maintenance project

for which a full set of plans is not prepared, relying instead on sketches,

written narrative and other information, in the proposal. If an earth change plan is required for a log project, this will also be included in the proposal. The project log is a contract document. (ref. MDOT Road Design Manual, Section 1.04)

Maintenance Project A project that is administered and completed by Department maintenance staff or by a contract agency on behalf of the Department. Maintenance projects are typically limited in scope and impact and are often log projects. Used to differentiate from a construction project.

Maintenance Activity Routine work performed by MDOT direct forces or by a contract agency for the purpose of extending the useful life and ensuring the safe condition of the transportation infrastructure.

Part 31 Inspector

Certified construction storm water operator authorized to conduct inspections as required by Part 31 of Act 451.

Part 91 Inspector

An individual with certification whose responsibilities include ensuring that MDOT maintenance projects/activities and construction projects comply with Part 91 of Act 451.

Part 91 Rules

Terminology generally used in this manual when referring to Part 91 of Act 451 and the Part 91 Rules.

Private Party

Permitted entity that is not a governmental agency and not a utility as defined by the Standard Specifications for Construction. Used in the context of permitted work on MDOT right-of-way.

Stabilization

The establishment of vegetation or the proper placement, grading, or covering of soil to ensure its resistance to soil erosion, sliding, or other earth movement.

Wetland

Land characterized by the presence of water at a frequency and duration sufficient to support and under normal circumstances does support wetland vegetation or aquatic life. Wetland area may be commonly referred to as a bog, fen, swamp or marsh. Consult with Region or Lansing central office staff, if necessary, for wetland designation.

1. INTRODUCTION

EGLE has designated the MDOT as an Authorized Public Agency (APA) under Part 91, Soil Erosion and Sedimentation Control, of Public Act 451 of 1994, Natural Resources and Environmental Protection Act, as amended (hereinafter referred to as Act 451). This status is evaluated on a region-by-region basis through an audit process conducted by EGLE. SESC program audits generally take place on a five-year cycle. As an APA, preparation and approval of individual project specific soil erosion and sedimentation control permits is not required. In return, MDOT accepts responsibility for enforcement of the Department's program and procedures related to soil erosion and sedimentation control. The mechanism for enforcement is through the implementation of this manual, the Standard Specifications for Construction and all other contract documents.

The information and direction provided in this manual satisfies the Part 91 requirement for MDOT to have a documented program and adequate procedures to comply with applicable soil erosion and sedimentation control regulations. To ensure continued APA status, earth change activities on MDOT right-of-way, regardless of size or location, will be conducted in accordance with Part 91, the rules promulgated thereunder, this manual, and all related MDOT manuals and guides.

It is important that all MDOT personnel support the Department's commitment to minimize soil erosion and off-site sedimentation as part of the overall environmental stewardship responsibility accepted by the Department. This is accomplished, in part, by compliance with and enforcement of all contract documents, performance guides and manuals.

1.1 Applicable Laws and Administrative Rules

Act 451 requires various environmental measures to be enacted throughout the life of state transportation projects and activities to ensure that issues related to a healthy environment are appropriately considered. Act 451 includes several parts, two of which (Part 31 and Part 91) govern the soil erosion and sedimentation control procedures described in this manual. The remaining parts of Act 451 involve project specific permits such as those related to floodplains; inland lakes and streams; wetlands; dam safety; shoreline protection; Great Lakes submerged lands; and sand dunes.

1.1.1 Part 31, Water Resources Protection - Part 31 of Act 451 addresses the protection and conservation of the water resources of the state. This includes prohibition of pollution of the waters of the state by storm water runoff carrying sediment from earth change activities.

Part 21 Wastewater Discharge Permit of the state administrative rules contains the administrative rules promulgated for Part 31 of Act 451. These rules were promulgated to implement amendments to Act 451 that authorized the state wastewater discharge permit system compatible with the National Pollutant Discharge Elimination System (NPDES). Whenever this document references NPDES regulations or rules this is construed to mean Part 31 and the rules promulgated thereunder.

NPDES rule R 323.2190(2)(e) requires construction sites disturbing one or more acres of land to undergo NPDES inspections with documentation of these inspections kept on file by MDOT for a period of at least three years from the date of the inspection.

1.1.2 Part 91, Soil Erosion and Sedimentation Control - The primary intent of Part 91 of Act 451 is to protect the waters of the state and adjacent properties by minimizing soil erosion and controlling sediment.

Part 17 Soil Erosion and Sedimentation Control of the state administrative rules contains the administrative rules promulgated for Part 91 of Act 451. Whenever this document references SESC regulations or rules this is construed to mean Part 91 and the rules promulgated thereunder. In general, the term "Part 91 rules" is used in this manual to refer to both the regulations and the rules governing soil erosion and sedimentation control.

SESC rule R 323.1704(1) requires soil erosion and sedimentation control permits for earth change projects which disturb one or more acres of land, and/or is within 500 feet from the water's edge of a lake or stream. MDOT's APA status supersedes the individual permit process provided that the Department enforces soil erosion and sedimentation control procedures approved by EGLE.

1.2 MDOT's Soil Erosion and Sedimentation Control Program

This manual represents one facet of MDOT's overall soil erosion and sedimentation control program. The overall program consists of commitment to environmental stewardship responsibilities; appropriate staff training; specifications and project plans that address erosion control issues; and preparation and/or enforcement of earth change plans as required.

1.2.1 Environmental Stewardship Commitment - The commitment to fully support the activities necessary to maintain APA status is embodied in the MDOT mission statement and vision statement. MDOT is committed to complying with the procedures outlined in this manual and other EGLE permit conditions throughout all phases of project development (planning and design) and delivery (construction and maintenance).

A proactive approach is necessary to effectively minimize erosion from disturbed areas thereby reducing resulting off-site sedimentation. Whenever practicable, stronger contract language; stronger enforcement of this contract language; and better inspection, documentation and follow-up will be implemented to reach this goal.

Project/activity specific inspection and maintenance of soil erosion and sedimentation controls are the responsibility of MDOT and the Contractor. If deficiencies are documented, MDOT will notify the Contractor of the deficiency and work to bring the site into compliance within five days from the date of the notice, or other time frame stated in the notice. A discharge to a surface water of the state will be addressed no later than 24 hours of the inspection.

1.2.2 SESC (Part 31 and 91) Training – Individuals responsible for administering and enforcing Part 31 and 91 through MDOT's SESC program must complete both EGLE-sponsored Construction Stormwater Operator (CSWO) training and the SESC Plan Review and Design (PRD) examination. The CSWO certification must be obtained prior to taking the SESC PRD class. These individuals may prepare to take the examination through either a self-study course using materials available from the EGLE or by completing a training class offered by EGLE. Refer to section 1.2.4 for additional information on recertification.

Administering and enforcing the MDOT program consists of quality assurance oversight; preparation of standards and specifications related to SESC; and preparing and reviewing construction and maintenance project plans involving earth change activities.

At a minimum, SESC program administrators within MDOT include the following positions:

- CFS Resource Specialist
- Design Project Managers
- Construction Engineers and assistants
- Region Resource Analysts/Specialists
- Region Soils Engineers
- Transportation Technicians
- Maintenance Supervisors/Coordinators
- Operations Engineers
- Cost and Scheduling Engineers
- Aeronautics Project Managers; and
- Transportation Maintenance Workers (9 level)

The EGLE-sponsored SESC PRD examination for program administrators covers the following topics:

- Requirements for Administering and Enforcing Part 91 Programs
- Soils, Erosion, and Runoff
- SESC Plan Review Document Exercises

Exception for SESC Inspectors: Individuals responsible <u>only</u> for conducting SESC inspections, including enforcing MDOT standards and specifications to ensure continued site compliance during earth change operations, will complete the EGLE-sponsored CSWO Inspector exam. SESC Inspectors are responsible for ensuring that SESC measures are implemented and maintained according to the plans, procedures and specification requirements and that the prescribed measures are effective in minimizing soil erosion and preventing off-site sedimentation. SESC Inspectors may order a contractor or in-house staff to install or maintain any control measures identified on the plans or in established Activity Guides in the case of maintenance operations. If the prescribed SESC measures included on the plans or performance guides are not effective, the SESC Inspector will seek the advice and assistance of an individual who has completed the SESC PRD exam.

The EGLE-sponsored certification program for SESC <u>inspectors</u> consists of general instruction on sedimentation and erosion control issues including the following topics:

- Storm Water Runoff, Soil Erosion: Processes and Impacts
- Controlling Runoff, Erosion, and Sedimentation on Construction Sites
- Vegetative Stabilization
- Plan Development, Information Sources, Plan Review and Inspections
- Laws, Rules and Inspections Pertinent to CSWO Inspectors
- 1.2.3 Specifications and Project Plans MDOT has a series of contract documents and procedures in the form of specifications and project plans that address erosion control issues. In conjunction with this manual other contract documents include the Standard Specifications for Construction, Road and Bridge Standard Plans and project specific

plans which are used to conduct the SESC program during the execution of MDOT construction projects.

1.2.4 Recertification - The Construction Field Services Resource Specialist will notify the Region Soils Engineer and Region Resource Specialist in November of each year of those MDOT staff that their certifications will expire the following July and are required to be renewed as required by the EGLE.

Certification for either the CSWO or the SESC PRD is valid for five years. Completing the recertification process, for the level of recertification sought, is required for renewal. Recertification for the CSWO is achieved by submitting an EGLE provided renewal form. CSWO certification is a prerequisite to the SESC PRD certification. Recertification for the SESC PRD will be complete upon attending the refresher course and submitting the proper recertification form to EGLE.

1.2.5 Earth Change Plan - An earth change plan conforming to rule R 323.1703 will be prepared by MDOT for projects and activities involving earth changes that are not covered by the approved procedures in this manual. The elements of this plan may be incorporated throughout the MDOT contract documents or the ECP document may be a stand-alone document for projects and activities that do not involve preparation of a full set of plans. At this time, the only exception to this requirement is ditch clean-out (Activity 1230) when this activity is conducted according to MDOT-approved work methods.

The Contractor is required to develop an earth change plan for earth change activity undertaken outside the limits of earth disturbance but within the right-of-way. This earth change plan must be submitted on form 1568, Approval for Project Staging or Excess Material Locations on MDOT ROW. The Engineer will review all earth change plans submitted by the Contractor to determine if all requirements of rule R 323.1703 are addressed and that the plan is effective. This form must be reviewed and approved before the Contractor is allowed to begin any earth change activity in the area between the limits of earth disturbance and the right-of-way. Construction Field Services will enter the earth change plan in MiWaters.

NOTE: The Contractor is required to develop an earth change plan unless the only earth change activity undertaken outside the limits of earth disturbance is within the clearing limits as specified by subsection 201 of the Standard Specifications for Construction and as shown on the plans. However, adequate measures must be implemented and maintained to effectively prevent or reduce erosion and subsequent off-site sedimentation that may result from this activity.

1.3 Key MDOT Organizational and Procedural Definitions

This manual is organized to complement MDOT's Development and Operations structure. The development organization consists of staff dedicated to planning, obtaining right-of-way, and designing construction projects. The operations organization consists of staff overseeing or performing construction and maintenance of the highway system.

During a construction project, construction staff is responsible for contract administration and oversight of private construction firms or vendors (hereinafter referred to as Contractors) performing highway/bridge projects. These projects are constructed in conformance with the MDOT Standard Specifications for Construction, which states: "It is the responsibility of the

Contractor to take such measures as may be necessary and comply with all federal, state and local laws and regulations for the protection of the public health, safety, welfare, and environment in the performance of the work." The Contractor is further bound by contract language to comply with all such laws and regulations throughout the life of the project, including the installation and maintenance of temporary soil erosion control measures and the installation of permanent measures. (Ref. Standard Specifications for Construction subsections 107.01, 107.15 and 208.03).

This contractual obligation placed on the Contractor does not diminish MDOT's ultimate responsibility under Act 451 for minimizing soil erosion and reducing the subsequent off-site sedimentation to the maximum extent practicable during construction of our transportation system.

A maintenance project/activity may be completed by MDOT maintenance forces, contract agencies, or Contractors with oversight provided by maintenance staff. This work includes the installation and maintenance of temporary erosion control measures on maintenance projects. Maintenance staff is also responsible for maintaining permanent erosion control measures along all state highways after a construction project or a maintenance project contract is closed out.

1.3.1 Contract Documents - For MDOT projects, the term 'contract documents' used throughout this manual is construed as, "The written agreement between the Department and the Contractor setting forth the obligations of the parties for the performance of and payment for the prescribed work. The contract includes the advertisement for bids, bidding document, progress schedule, contract form, contract bonds, standard specifications, supplemental specifications, special details, standard plans, plans, proposal, addenda, notice of award, ... "and other documents as applicable. (Ref. Standard Specifications for Construction, subsection 101.03)

This manual is included by reference in the standard specifications and is therefore a contract document. The E&S Details in this manual may be modified within special details, plans, the proposal, or other contract documents to meet site-specific field conditions for a given project.

- 1.3.2 Project Manager The 'Project Manager' referenced in this document is the person responsible for developing the contract documents. By signing the title page of the plans, the Project Manager and Construction Engineer are recommending approval of the contract documents to the Director or designee of MDOT. All project managers responsible for developing construction or maintenance contract documents will complete the EGLE-sponsored SESC (Part 91) PRD Training.
- 1.3.3 Engineer The 'Engineer' referenced in this document is defined in the Standard Specifications for Construction as: "The Director of the Department or the Engineer designated by the Director, acting directly or through authorized representatives, who is responsible for engineering supervision of the construction..." (Ref. Standard Specifications for Construction, subsection 101.03). The Engineer assigned responsibility for a specific project is the TSC Construction Engineer for the geographic area in which the project is located. The Construction Engineer assigns engineers and technicians as authorized representatives to perform inspection and testing on all projects.
- **1.3.4 MDOT Construction Permits -** Non-MDOT work performed by others on MDOT right-of-way requires a permit from MDOT to occupy the right-of-way. In accordance with

definitions contained in the Part 91 rules, an applicant for a utility or other governmental agencies engaged in construction in a public right-of-way is considered to be the landowner for purposes of obtaining and complying with a soil erosion permit, when applicable, from the appropriate enforcing agency (municipal or county). Information related to SESC and storm water management requirements is provided with each application package. (Ref. Construction Permit Manual and Act 368)

Utility companies and private parties performing utility/driveway work under an MDOT permit to occupy the right-of-way must minimize soil erosion and off right-of-way sedimentation. It is the responsibility of the appropriate MEA or CEA to enforce compliance with Act 451 on those projects.

1.4 Related MDOT Documents

This manual includes the procedures for establishing soil erosion and sedimentation controls for earth change activities regulated under Part 31 and Part 91 of Act 451 resulting from the construction, maintenance and operation of the state transportation system. MDOT is committed to the careful consideration and implementation of these procedures during the planning, design and completion of all operations that involve earth change activities.

References are made in this manual to other MDOT publications as well as to specific parts of relevant environmental statutes. Due to the volume of information necessary for MDOT to carry out its mission and the need to stay current with changing laws, rules and engineering technology, no attempt is made to reproduce all related MDOT documents in this manual. Where reference is made in this manual to related MDOT procedures and publications, the portions of those documents that address soil erosion and sedimentation control are considered to be included as if they were repeated here in their totality. Where practical, cross references are specifically listed in this manual. If information, direction, or procedures related to soil erosion and sedimentation control contained in related documents is less restrictive than Part 91, or this manual, then Part 91 and this manual will take precedence.

For projects let under the Standard Specifications for Construction, this manual is considered a contract document. The Contractor is obligated to conform to the information and guidance provided herein and all site specific soil erosion and sedimentation control measures included in the contract documents.

At a minimum, the following MDOT documents contain specifications, standards and/or practices related to soil erosion and sedimentation control and are referenced herein.

- 1.4.1 MDOT Standard Specifications for Construction Contains the current written directions, provisions and requirements pertaining to performance of work on MDOT projects. It is the base document controlling a project. The standard specifications may be modified by supplemental specifications and special provisions contained in the contract documents.
 - Section 107 Legal Relations and Responsibilities to the Public
 - Section 108 Prosecution and Progress
 - Section 109 Measurement and Payment
 - Section 201 Clearing
 - Section 205 Roadway Earthwork
 - Section 208 Soil Erosion and Sedimentation Control
 - Section 813 Slope Protection
 - Section 816 Turf Establishment

- Section 916 Erosion and Sedimentation Control Materials
- Section 917 Turf and Landscaping Materials
- **1.4.2 Standard Plans -** Drawings approved for repetitive use, showing details to be used where appropriate for the construction of road and bridge appurtenances.
 - R-96 Series Soil Erosion and Sedimentation Control Measures
 - R-100 Series Seeding and Tree Planting
- **1.4.3 Road Design Manual -** Provides criteria for the design of roads and for the preparation of road plans.
 - Subsection 2.02.03.F Erosion Control
 - Subsection 10.04.04.B Drainage and NPDES Runoff Controls
 - Subsection 10.04.04 C Soil Erosion and Sedimentation Control
- **1.4.4 Drainage Manual -** Gives the design engineer a basic working knowledge of hydrology, hydraulics and storm water management.
 - Subsection 9.1.2 Soil Erosion and Sedimentation Control
- 1.4.5 Storm Water Management Plan The SESC program is directly related to the MDOT storm water management program as one of six minimum measures required for compliance with the statewide permit issued to MDOT under Part 31 of Act 451. Section 3.5 of the Storm Water Management Plan contains a discussion of the SESC program in the context of storm water control to minimize sediment load to the waters of the state during the construction and operation of MDOT facilities.
- **1.4.6** Planisware Preconstruction Process Documentation Manual Documents the Department's preconstruction process as it pertains to construction project development. The preconstruction process begins with the preliminary planning for projects and ends with the construction contract award.
 - Task 3710 Develop Required Mitigation
 - Task 3720 Submit Environmental Permit Applications
 - Task 3730 Obtain Environmental Permits
- **1.4.7 Construction Manual -** Guide detailing the authority and responsibility for project administration. Provides instructions on project management, construction surveying, construction inspection and materials sampling.
 - Section 103 Work Orders
 - Section 201 Clearing
 - Section 205 Roadway Earthwork
 - Section 208 Soil Erosion and Sedimentation Control
- **1.4.8 Construction Permit Manual -** Guidance on procedures for administering the permit process for public utility or private party work on, or use of, the trunkline right-of-way within the provisions of federal and state laws.
- **1.4.9 Maintenance Activity Guides -** These guides describe the equipment, materials and recommended work methods for various maintenance activities.
- **1.4.10 EGLE Soil Erosion and Sedimentation Control Training Manual -** While not an MDOT publication, this training manual contains useful information on the proper selection, design and construction of SESC measures. The training manual is available from the EGLE website.

THIS PAGE BLANK

2. PROJECT DEVELOPMENT

Project Development involves the planning, design and acquisition of real estate, if required, for the project.

2.1 Planning Phase

Effective erosion control begins in the planning phase of a project. Areas with unstable or transportable soils, such as loess soils, alluvial fans, and some glacial deposits are potential problem areas for erosion during construction. Identification of these soil types is a necessary prerequisite to selecting erosion control measures for a project. If applicable, soil borings and reports will be reviewed, and field investigations conducted during the planning phase of a project to identify these areas. Information on the potential for a given soil to erode can be found in county soil surveys and by contacting the local Conservation District office or the Central Office Geotechnical staff.

During the planning phase of a project, areas susceptible to damage from excessive sedimentation will also be identified. Some examples are rivers, impoundments, irrigation systems, lakes, streams, and wetlands. Cropland, home sites, and other developed areas will also be considered.

Each construction project is subject to one of three types of early preliminary engineering analysis during the planning phase depending on the nature of the project and the anticipated social, economic, and environmental impacts and necessary mitigation. These reviews establish the environmental clearances required from federal, state, and/or local resource agencies. Recommended erosion control measures will be incorporated into the contract documents during the design phase for implementation in the construction phase.

- **2.1.1 Categorical Exclusion -** The basic review level is a Categorical Exclusion. This review considers actions that individually or cumulatively do not involve significant environmental impacts. They are actions that:
 - Do not induce significant impacts to planned growth or land use;
 - Do not require the relocation of significant numbers of people;
 - Do not have a significant impact on any cultural, natural, recreational, historic, or other resources:
 - Do not involve significant air, noise, or water quality impacts; and,
 - Do not have a significant impact on travel patterns.
- 2.1.2 Environmental Assessment The next level of review is an Environmental Assessment. This review is considered a decision document. The assessment is performed when there is uncertainty as to the significance of the impacts of a particular project. The assessment considers the project need, alternatives considered, impacts, and comments and coordination with the Federal Highway Administration (FHWA) and the public. If a Finding of No Significant Impact is received from FHWA, the project proceeds. If significant impacts are found, the project moves to the Environmental Impact Statement process.
- **2.1.3** Environmental Impact Statement The highest, most comprehensive, level of review is an Environmental Impact Statement (EIS). This review considers multiple studies and analyses with extensive involvement of environmental resource agencies throughout the review. The final EIS reports on the environmental impacts and mitigation necessary for

the particular project. A Record of Decision is required from the FHWA for a project to proceed. The EIS process is a comprehensive environmental analysis of the purpose of and need for the project; the potential transportation solutions by considering corridors with various alignments, and a detailed environmental analysis of a recommended alternative.

For major new alignment projects undergoing the EIS environmental process the alignment and grade, especially at stream crossings, will be carefully considered in an attempt to minimize SESC and NPDES concerns. The alignment of a highway may be shifted to eliminate or minimize encroachment into a surface water environment. A change in grade may be made to avoid exposing highly erodible soils.

Proposed alignment and grade changes need to be consistent with highway safety criteria and should be made to blend and fit the highway to the natural landscape. This will minimize the extent of cut and fill during construction and reduce future erosion related maintenance problems. In designing the project's line and grade, it is important that ground water and surface water be allowed to pass through the highway right-of-way or be intercepted with minimal disturbance to streams and without causing erosion problems.

Whenever practical, stream crossings will be made at stable reaches of a stream where straight banks are evident and there are no meanders. The direction and amount of water flowing at various stages must be considered in locating hydraulic openings to avoid excessive scour and erosion problems. To reduce the potential for these problems, stream crossings and encroachments should be kept to a minimum.

2.2 Design Phase

Projects are designed to minimize earth disturbances with emphasis placed on areas with highly erodible soils and areas adjacent to lakes, streams, and wetlands. The Planisware Preconstruction Process Documentation Manual discusses specific responsibilities for development of soil erosion and sedimentation controls as they relate to recommended mitigation measures.

Each region has designated staff responsible for identifying locations and quantities for erosion control measures for projects in the region. Soil erosion and sedimentation control items of work must be practical, reasonable and effective during the construction phase of a project to prevent off-site sedimentation and ensure adequate protection of the waters of the state.

The project manager will review environmental mitigation commitments and EGLE permits and will consult with appropriate staff to ensure that additional erosion control measures, pay items, or quantities are included to protect specific areas with highly erodible soils and areas adjacent to lakes, streams, and wetlands. Staff available to the project manager for this consultation includes Region Soils Engineers, Drainage Engineers, and Resource Analyst/Specialists along with Construction Field Services staff including the Resource Specialist and the Grading and Drainage Engineer. The project manager will refer to Chapter 9 of the MDOT Drainage Manual for additional design and placement considerations for the various temporary and permanent soil erosion and sedimentation control measures to be incorporated into a project. The contract documents will clearly indicate the location for all appropriate measures.

MDOT Standard Plan R-96 Series Soil Erosion and Sedimentation Control Measures serves as the key to the soil erosion and sedimentation control measures typically used by MDOT. The

Soil Erosion and Sedimentation Control (E&S) Details include a brief discussion of appropriate use and application of the measures. The soil erosion and sedimentation control key numbers from Standard Plan R-96 Series associated with pay items will be shown on the plan sheets in the general location where the measure is to be placed in the field. Standard Plan R-96 Series and the E&S Details are included in Section 6 of this manual.

For a log project, the need for erosion control measures will be considered; appropriate erosion control pay items included as required; and an earth change plan prepared for those log projects involving earth change activities.

The success of erosion control and sediment collection during construction is highly dependent on the measures specified in the contract documents and available for use in the field. By providing a sufficient quantity of erosion control measures with clearly written specifications for their use and payment, MDOT will more readily fulfill the commitment to prevent off right-of-way sedimentation.

- **2.2.1 Earth Change Plan -** Projects/activities that involve an earth disturbance are required by rule R 323.1703 to have a soil erosion and sedimentation control plan that includes the following information:
 - Scaled drawing of the work site
 - Legal description (town, range and section number)
 - Site location sketch
 - Proximity to lakes and streams
 - Predominant land features (including wetlands)
 - Slope descriptions or contour intervals
 - General description of soil types
 - Physical limits of each proposed earth change
 - Drainage and/or dewatering features
 - Timing and sequence of earth change
 - Location and description for installing and removing all proposed temporary SESC measures
 - Descriptions and location of temporary and permanent soil erosion control measures
 - Maintenance plan for soil erosion control measures

This information is included as part of the plan set and other contract documents for construction projects. When there is no set of plans, as for log projects and some maintenance projects/activities, this information will be included in the proposal (log projects), or in the MDOT-approved work methods for a specific earth change activity (maintenance projects). In certain circumstances the earth change plan will be a standalone document prepared by MDOT or the Contractor. (Refer to chapter 3 of this manual)

An example of an earth change plan that complies with the SESC rules is included in the Appendix of this manual.

- **2.2.2 Principles of Earth Change Plan Preparation -** Three general principles apply when developing the earth change plan for a project.
 - Erosion prevention is generally more effective than sediment control.
 - Sediment control is generally more effective and less costly than repairing damage caused by uncontrolled sediment.

- Specific erosion control measures and details are more effective than generalized procedures.
- **2.2.3 Design Plan Preparation -** Guidelines for designing to minimize soil erosion and sedimentation control include the following:
 - Design slopes consistent with soil properties.
 - Limit the area of unprotected soil exposure.
 - Minimize and control concentrated flow rates with temporary and permanent barriers, basins, or other measures.
 - Minimize the duration of unprotected soil exposure.
 - Protect soil with vegetative cover, mulch, or other erosion resistant material.
 - Retard or redirect runoff with engineered devices such as, ditches, dikes, and diversions.
 - Trap sediment with temporary or permanent barriers, basins, or other measures as close to the source as possible.
- **2.2.4 Temporary Erosion Control Measures -** Temporary soil erosion and sedimentation control measures will be specified in the contract documents. Temporary measures are used during construction to control erosion and sediment until the disturbed area is stabilized. Temporary measures include those that:
 - Provide direct protection of the soil surface (ground cover, turf establishment, and riprap).
 - Direct the runoff to an area where concentrated flows will not cause erosion (diversion dikes and ditches).
 - Remove sediment from the concentrated flow of waters by filtering or slowing the velocity of the sediment-laden water (gravel filter berms, check dams, and sediment traps).
 - Remove sediment from the non-concentrated overland flow of waters by filtering or slowing the velocity of the sediment-laden water (silt fence)
- 2.2.5 Permanent Erosion Control Measures Permanent soil erosion and sedimentation control measures will be specified in the contract documents. Permanent measures are placed during construction to minimize erosion and sedimentation in the project area during and after construction. Permanent measures remain in place after construction and may require periodic maintenance to remain effective until the area is stabilized.

2.2.6 Notifications During the Design Phase

- NPDES Notification for Construction Projects For projects disturbing five acres
 or more and discharging to waters of the state, a Notice of Coverage (NOC) will be
 prepared by Project Development staff and submitted to the CFS Resource
 Specialist for processing to EGLE. Projects disturbing one to five acres do not
 require a NOC. However, these projects must still comply with the Permit-by-Rule
 requirements. Refer to Section 3.1.1 of this manual for notification requirements for
 these projects.
- County Drain Commissioner Notification When work on an MDOT project involves activities within a designated county drain, the Michigan Drain Code requires that Project Development personnel send plans to the County Drain Commissioner.

3. PROJECT DELIVERY

As used in this section, MDOT right-of-way includes areas covered by Consent to Grade where these areas are shown on the plans.

3.1 Construction Projects

Soil erosion and sedimentation control measures selected during the development phase of a project are included in the contract documents. It is the responsibility of the Contractor as well as the Engineer to implement those measures. The Contractor must maintain temporary and permanent erosion control measures during construction until the disturbed area is stabilized or until the contract is closed out. If a disturbed area has not been stabilized at the time the contract is closed out, arrangements will be made for maintaining the erosion control measures until the area is stabilized and for their removal as necessary. As necessary, erosion control measures may be adapted, adjusted, and added to maintain the level of control required to comply with Act 451, and project specific permits.

3.1.1 Notification for Construction Projects

• SESC Notification for Construction Projects – As an APA, MDOT is exempt from obtaining individual SESC permits from the municipal enforcing agency (MEA) or county enforcing agency (CEA). However, MDOT must notify the MEA or CEA of all construction activities that involve earth disturbances within MDOT right-of-way. The complete list of MEA and CEA contacts is available on the EGLE website at www.michigan.gov/egle. Click on <Land>, then <Soil Erosion and Storm Water Construction>, then <Part 91 Agency Resources>, then <Soil Erosion and Sedimentation Control Agencies>. Only those agencies listed as MEAs or CEAs will be notified. The APAs and Conservation Districts included on the website do not need to be notified.

NOTE: Notification to the enforcing agency of the proposed earth change activity on MDOT construction projects is documented by including the agency(ies) in the distribution of the minutes of the preconstruction meeting.

• NPDES Notification for Construction Projects - On projects for which a NOC is submitted during the design phase, MDOT will receive a letter of authorization from EGLE. The Engineer will complete and submit the Notice of Termination (NOT) to the CFS Resource Specialist for processing to EGLE upon project stabilization.

Submission of the NOT may generate an EGLE site inspection. All NOT requests should go to CFS Resource Specialist and should be submitted by either the Region Resource Specialist or the Region Soils Engineer. The site must be reviewed by either position, and the site must be stabilized, prior to submitting the NOT. Projects disturbing one to five acres, and discharging to the waters of the state, do not require a NOC or NOT but must comply with the requirements of Part 31.

3.1.2 Contractor's Operations

 Off the Right-of-Way - The Contractor is required to coordinate directly with the landowner to obtain all applicable federal, state, and local permits, including SESC and NPDES permits, when working outside of MDOT right-of-way. The Contractor is responsible for the design and implementation of erosion control measures and for site restoration in areas off MDOT right-of-way. Payment for this restoration will not be included in the contract.

Prior to disturbing any site off MDOT's right-of-way for borrow operations, waste or disposal areas, haul roads, storage sites, or any other earth change activity, the Contractor is responsible for ensuring that all required permits and property owner agreements are obtained. The Contractor must provide the Engineer copies of these permits and agreements for the project file.

• On the Right-of-Way but Outside the Limits of Earth Disturbance - When a Contractor chooses to perform earth change activities within MDOT's right-of-way but outside the limits of earth disturbance the Contractor is responsible for preparing the earth change plan for this work. These activities include, but are not limited to, placement of a portable plant, stockpiling materials, or establishing a haul road. The plan must be submitted to, and approved by, the Engineer prior to the start of the earth change activities. The plan must include all details listed in Section 2.2.1 of this manual and recorded on form 1568.

NOTE: The Contractor is required to develop an earth change plan unless the only earth change activity undertaken outside the limits of earth disturbance is within the clearing limits as specified by subsection 201 of the standard specifications and as shown on the plans. However, adequate measures must be implemented and maintained to effectively prevent or reduce erosion and subsequent off-site sedimentation that may result from this activity.

3.1.3 Soil Erosion and Sedimentation Control During Construction - The Engineer will discuss the contract provisions related to soil erosion and sedimentation control with the Contractor prior to the start of related work. The Contractor must not disturb any land or water outside of the limits of earth disturbance but within the project right-of-way or acquired easements without prior authorization from the Engineer and approval of an earth change plan. The plan must include all details listed in section 2.2.1 of this manual. Restoration of any disturbed area beyond the approved limits must be performed by the Contractor - at the Contractor's expense. This work must be completed in accordance with MDOT restoration specifications and as directed by the Engineer.

Construction operations must be conducted in a manner that minimizes erosion and offsite sedimentation. Prior to commencing any construction operation, that constitutes an earth change activity, including clearing; appropriate temporary and permanent erosion and sedimentation control measures must be installed as specified on the plans. Temporary erosion and sedimentation control measures must be installed to minimize potential problems, to correct erosive conditions that develop during construction, and to stabilize inactive construction areas.

3.1.4 Time Limitations During Construction - All grading sections must be brought to final grade as soon as possible. Permanent erosion and sedimentation control for slopes, channels, ditches and other disturbed areas must be completed within five calendar days after final grading or final earth change. Slopes and ditches within 150 feet of a stream, lake or wetland must be permanently restored within 24 hours of final grading or final earth change. A site is considered to be permanently stabilized when all permanent control structures have been installed, maintenance for the permanent controls has been arranged, vegetation is well established, and temporary controls have been removed.

If it is not possible to permanently stabilize a disturbed area after an earth change has been completed or if significant earth change activity ceases, then temporary soil erosion and sedimentation control measures must be maintained until permanent soil erosion and sedimentation control measures are in place and the area is stabilized. Refer to subsection 208.03.B of the Standard Specifications for Construction for additional information on time limitations.

3.1.5 Inspections During Construction - SESC regulations require that temporary erosion control measures be maintained daily. SESC regulations do not explicitly call for regularly scheduled inspections. NPDES regulations require regular inspection and documentation of the condition and effectiveness of soil erosion and sedimentation control measures on earth change activities one or more acres in size and discharging to the waters of the state.

At a minimum, inspection of all soil erosion and sedimentation control measures and devices will be completed once per week and within 24 hours after every precipitation event that results in a discharge from the right-of-way. If an area is temporarily stabilized, as discussed in section 3.1.4 above, inspections will continue in the temporarily stabilized areas to ensure the adequacy of the temporary measures. These inspections will continue until the disturbed area is permanently stabilized.

The need for corrective actions will be documented and followed up on to ensure the actions are carried out. When needed, corrective action is required within 24 hours of the inspection if sediment is discharging to the waters of the state and within 5 days of the inspection in all other circumstances.

These inspections and corrective actions will be documented using the National Pollutant Discharge Elimination System and Soil Erosion and Sedimentation Control Inspection Report (Form 1126). Deficiencies, including a deadline for completing the corrective actions, will be brought to the attention of the Contractor. This notice may be made by providing a copy of Form 1126 to the Contractor with any corrective actions and related deadlines indicated under "Remarks". A log of the inspections and corrective actions will be placed in the project file and will be retained for a period of three years from the date of the inspection.

Completed corrective action will be documented in the project file with reference to the appropriate inspection report(s). If corrective actions are not completed within the specified timeframe, the steps outlined in Section 4 of this manual will be initiated. All resulting documentation placed in the file will also be referenced to the appropriate inspection report(s).

3.1.6 Winter Construction SESC and Storm Water Inspection Reports

EGLE does not accept "frozen ground" as a weather condition for determining construction site inspection frequency. On-site inspections must be resumed within 24 hours of any change in earth disturbance conditions that may allow construction storm water runoff to occur as a result of construction operations resuming, rainfall, or warming conditions that will cause snow melt. Detailed weather conditions must be recorded on Form 1126. If EGLE or MDOT receives a complaint while inspections are suspended, MDOT staff will perform an inspection within 24 hours of receiving the complaint.

Construction activities with an earth disturbance of one acre or greater or located within 500 feet of a lake or a stream must be inspected once every 7 days and within 24 hours after a precipitation event that results in a discharge from the site including weekend days regardless if the contractor is working or not. During inactive periods when a construction site has been temporarily stabilized and below freezing temperatures predominate, the Storm Water Construction Site Operator, without performing an onsite inspection, may certify on Form 1126 that weather and inactive conditions are such that runoff from the site will not occur.

3.1.7 Storm Water Construction Site Operator Procedures

- 1. In order to cease on site weekly inspections during periods of inactive earth change activity and/or during periods of time where discharges from the site are unlikely, each of the following must occur:
 - A. Ensure that earth change activity has ceased. Document this condition on Form 1126.
 - B. Confirm with an onsite inspection that the site has temporary soil erosion and sedimentation control measures implemented to minimize discharge of sediment from the site. Document this condition on Form 1126.
 - C. Document weather conditions. Weather conditions must be consistently below freezing and unlikely to result in runoff from the site. Document this condition on Form 1126.

Once conditions 1A, 1B and 1C are met, subsequent weekly inspection documentation may be completed without a site visit by documenting weather conditions for the site on Form 1126.

During the suspension of weekly inspections and site visits, SESC inspections must be performed at least once every 30 days during the inactive period if weather conditions are deemed safe for travel. If site or weather conditions are deemed unsafe for travel, inspections must resume as soon as feasible. Document these inspections on Form 1126.

- 2. Onsite inspections must resume if any of the following occurs:
 - A. Earth change activity resumes.
 - B. Weather conditions are such that snow melt runoff or precipitation in the form of rain is likely to leave the right of way.
 - C. Weather conditions are consistently above freezing for several days in a row and the possibility exists for surface runoff, an inspection would be required.
 - D. The site becomes unstabilized and erosion could occur.
- 3. Once any of the conditions identified in 2A-2D occur, onsite inspections must resume within 24 hours. Onsite inspections must be performed weekly or within 24 hours of a precipitation event that results in a discharge from the site.

3.1.8 Detailed Reporting of Weather Conditions Affecting a Construction Site

Warming conditions may result in runoff from the site. However, the ground may still be frozen. Typical weather condition documentation that is acceptable may be obtained from any reliable weather source. This documentation should include the reporting period and the high temperature and average for the week.

3.2 Maintenance Projects and Maintenance Activities

Some maintenance operations have potential for impact on lakes, streams, and wetlands. MDOT will conduct maintenance projects and activities in a manner that minimizes potential for soil erosion and off right-of-way sedimentation and will incorporate applicable soil erosion and sedimentation control measures included in this manual.

Appropriate SESC measures and NPDES requirements will be included when planning, designing, and completing maintenance projects and activities involving earth disturbances, regardless of size and location. An earth change plan, as described in section 2.2.1 of this manual, will be prepared for all maintenance projects and activities involving earth disturbances unless an alternate process has been approved by the EGLE for a specific maintenance activity.

NOTE: The environmental procedures for ditch clean-out (Activity #1230), included in the Appendix of this manual, is the only MDOT- approved work method for a specific earth change activity at this time.

Permits are necessary for activities related to draining, dredging or filling a wetland, floodplain, lake or stream. Other EGLE and/or U.S. Army Corp of Engineer permits may be necessary. Contact appropriate MDOT staff to determine the need for additional permits prior to the start of a maintenance project or activity.

3.2.1 Notifications for Maintenance Projects and Activities

• SESC Notification for Maintenance Projects and Activities - As an APA, MDOT is exempt from obtaining individual SESC permits from the MEA or CEA. However, MDOT must notify the MEA or CEA prior to the start of maintenance projects and activities involving earth change activities. The complete list of MEA and CEA contacts is available on the EGLE website at www.michigan.gov/egle: Click on <Land>, then <Soil Erosion and Storm Water Construction>, then <Part 91 Agency Resources>, then <Soil Erosion and Sedimentation Control Agencies>. Only those agencies listed as an MEA or CEA need to be notified. The APAs and Conservation Districts included on the website do not need to be notified.

NOTE: An annual notice can be provided to the MEA/CEA to cover projects and activities planned for the coming year. An individual notice will be required for projects and activities added to the program after the annual notice.

- County Drain Commissioner Notification for Maintenance Projects When a MDOT maintenance project or activity involves work within a designated county drain, the Michigan Drain Code requires notification of the County Drain Commissioner prior to the start of work.
- NPDES Notice of Coverage for Maintenance Projects For projects and activities
 disturbing five acres or more and discharging to the waters of the state, a Notice of
 Coverage (NOC) will be prepared and submitted to the CFS Resource Specialist for
 processing to EGLE.

On projects and activities for which a NOC is submitted, MDOT will receive a letter of authorization from EGLE. The TSC maintenance supervisor/coordinator, or designee, will complete and submit the Notice of Termination (NOT) to CFS Resource Specialist for processing to the EGLE upon stabilization of the affected area.

Submission of the NOT may generate an EGLE site inspection. All NOT requests should go to CFS Resource Specialist and should be submitted by either the Region Resource Specialist or the Region Soils Engineer. The site must be reviewed by either position, and the site must be stabilized, prior to submitting the NOT.

Projects and activities disturbing one to five acres, and discharging to the waters of the state, do not require a NOC or NOT but must comply with the requirements of Permit-by-Rule.

- 3.2.2 Soil Erosion and Sedimentation Control for Maintenance Projects and Activities Maintenance projects and activities that involve earth changes will be conducted in a manner that minimizes soil erosion and off-site sedimentation. Before starting any maintenance project or activity involving earth changes, appropriate erosion and sedimentation control measures will be installed. Temporary soil erosion and sedimentation control measures will be installed to minimize potential problems, to correct erosive conditions that develop during the maintenance operation, and to stabilize inactive work areas. All necessary erosion control measures will be maintained until disturbed areas are stabilized.
- 3.2.3 Time Limitations for Maintenance Projects and Activities Permanent soil erosion and sedimentation control measures for all slopes, channels, ditches, or any disturbed land area will be complete within five calendar days after final grading or the final earth change is complete. If it is not possible to permanently stabilize a disturbed area after an earth change is complete or if significant earth change activity ceases, temporary soil erosion and sedimentation control measures will be maintained until permanent soil erosion and sedimentation control measures are in place and the area is stabilized.
- 3.2.4 Inspections for Maintenance Projects and Activities SESC regulations require that temporary erosion control measures be maintained daily. SESC regulations do not explicitly call for regularly scheduled inspections. NPDES regulations require regular inspection and documentation of the condition and effectiveness of soil erosion and sedimentation control measures on earth change activities one or more acres in size and discharging to the waters of the state.

At a minimum, inspection of all soil erosion and sedimentation control measures and devices will be completed once per week and within 24 hours after every precipitation event that results in a discharge from the right-of-way. If an area is temporarily stabilized, as discussed in section 3.2.2 above, inspections will continue in the temporarily stabilized areas to ensure the adequacy of the temporary measures. These inspections will continue until the disturbed area is permanently stabilized.

The need for corrective actions will be documented and followed up on to ensure the actions are carried out. When needed, corrective action is required within 24 hours of the inspection if sediment is discharging to the waters of the state and within 5 days of the inspection in all other circumstances.

This inspection may be documented using the National Pollutant Discharge Elimination System and Soil Erosion and Sedimentation Control Inspection Report (Form 1126) and the notice may be made by providing the Contractor or appropriate Maintenance staff with a copy of Form 1126 with any corrective actions and related deadlines indicated under "Remarks." A log of the inspections and corrective actions will be maintained on

file at the TSC for review and will be retained for a period of three years from the date of the inspection.

Alternate methods of documenting inspections must be approved by the maintenance supervisor/coordinator or other individual designated by the TSC Manager or Region Engineer. Regardless of the form or format used, all documentation of erosion and sedimentation control inspections must be retained for a period of three years from the date of the inspection.

3.2.5 Maintenance Activity Guides - Operational guidelines for maintenance activities are described in the performance guides found on MDOT's Transportation Asset Management (TAMS) SharePoint site. The ditch clean-out activity has been identified as the most common maintenance activity subject to SESC and NPDES regulations and therefore is included in the Appendix for reference. The procedures for minimizing soil erosion and sedimentation described in the ditch clean-out performance guide will be followed in lieu of preparation of individual earth change plans.

THIS PAGE BLANK

4. COMPLIANCE AND ENFORCEMENT

During the course of construction and maintenance of transportation facilities, even well designed and properly placed erosion control measures can fail to perform as originally expected. Compliance and enforcement actions may be necessary to ensure that erosion control measures are implemented or improved to preserve the natural resources of the State of Michigan and to prevent off-site sedimentation.

Subsections 4.1 and 4.2 identify options available to MDOT when progressive enforcement of the contract becomes necessary to correct and/or prevent soil erosion and sedimentation control problems. Current Department specifications, procedures, and guidance documents will be followed when implementing any of the actions listed in subsections 4.1 and 4.2. Subsection 4.3 identifies coordination efforts with EGLE to resolve on-going soil erosion and sedimentation control issues.

The Department's goal is not to wait until EGLE has to get involved before taking steps to bring the project into compliance with the approved MDOT SESC program. A successful and effective APA program is one in which EGLE is not relied upon to provide the level of enforcement needed to ensure compliance with our program. All compliance and enforcement actions will be documented carefully so that in the event that a Contractor claim results, the Department will have the necessary information to determine the validity of the claim. This documentation will also be used to support the Contractor Performance Evaluation for the environmental category.

4.1 Construction Projects

MDOT contracts will be enforced to ensure the Contractor installs, inspects, and maintains appropriate soil erosion and sedimentation control measures in the field. Depending on the site and contract specific issues, the Engineer will determine the appropriate and progressive compliance and enforcement actions, including but not limited to the following. (Ref. Standard Specifications for Construction sections 108 and 109; MDOT Construction Manual section 103 and 208).

The first action is always to conduct adequate inspections throughout the project. If necessary, communicate deficiencies to the Contractor with specific actions that must be taken to repair, replace or modify SESC measures.

4.1.1 Minor Deficiencies

- Conditions of SESC measures observed by any Department employee can be noted on the IDR and brought to the Contractor's attention (project staff) or brought to the attention of the Construction Engineer (non-project staff).
- Use Form 1126 to document the condition, effectiveness and need for additional SESC measures during required inspections.
- Contact region or Lansing CFS staff with responsibility for SESC activities to discuss methods to improve site specific soil erosion and sedimentation control.
- If an EGLE field inspector visits the site, use this opportunity to get their input on methods to effectively minimize erosion and reduce off-site sedimentation.
- **4.1.2 Moderate and Continuing Problems** When taking any of the following actions, provide as much detail as necessary to convey the scope of the problem and the required action to bring the site into compliance.
 - Issue Notice of Non-Compliance with Contract Requirements (Form 1165).

- Invoke special provision for Non-Compliance with Soil Erosion and Sedimentation Control Requirements.
- Issue a Work Order (Form 1137) directing the Contractor to correct deficiencies in a specified time frame.
- Withhold payment for erosion control devices, erosion control maintenance and/or related items of work.
- Report deficiencies using interim and final Contractor Performance Evaluations as
 detailed in subsection 102.01 of the MDOT Construction Manual. Refer to the rating
 guidance included in the manual for this item. The guidance, which was current at
 the time of approval of this manual, is included here for reference. Always refer to
 the most current Department guidance on this subject when completing a Contractor
 Performance Evaluation.

14. To what degree does the Contractor meet the environmental requirements of the contract?

Rating of 10: The Contractor exceeds the environmental requirements and provides required documentation without prompting by the Engineer.

<u>Rating of 8:</u> The Contractor meets the environmental requirements and provides required documentation without prompting by the Engineer.

Rating of 5: The Contractor meets the environmental requirements and provides required documentation only after notification by the Engineer.

Rating of 1: The Contractor meets environmental requirements only after repeated notification from the Engineer. The Engineer may issue orders to stop work, hold up payments, or have work completed by others.

- **4.1.3 Severe and Non-Responsive** These steps require advice and consent from one or more of the following: TSC Manager, Associate Region Engineer for Operations, Region Engineer and the Assistant Attorney General Transportation.
 - Arrange for others to perform the work.
 - Involve the performance bond company.
 - Place the contract in default.

4.2 Maintenance Projects and Activities

Maintenance work involving earth change activities performed by direct forces, contract agencies, or Contractors will incorporate appropriate soil erosion and sedimentation control measures. The Part 91 Inspector is responsible for compliance and enforcement on these projects. All individuals who have decision-making authority for enforcement on a site must be SESC PRD certified. In the event that progressive compliance and enforcement is necessary, the Part 91 Inspector will work with Maintenance Supervisors/Coordinators, Maintenance Superintendents, Operations Engineers, and, if necessary, TSC Managers to seek appropriate action as follows:

4.2.1 Direct Forces Work - Minor to Moderate

- Issue directions to staff to correct deficiencies in a specified time frame; follow up to ensure corrective action has been completed.
- Arrange additional staff training on proper work methods and the importance of soil erosion and sedimentation control.
- Arrange for others to perform the work.

4.2.2 Contract Agency Work - Minor to Moderate

- Issue work orders (Form 1137) to correct deficiencies in a specified time frame; follow up to ensure corrective action has been completed.
- Arrange additional agency training on proper work methods and the importance of soil erosion and sedimentation control.
- **4.2.3 Contract Agency Work Severe -** These steps require advice and consent from one or more of the following: Maintenance Superintendent, Operations Engineers, TSC Manager, Associate Region Engineer for Operations, Region Engineer and possibly the Assistant Attorney General Transportation.
 - Withhold payment.
 - Issue stop work notices.
 - Arrange for others to perform the work.
- **4.2.4 Contractor Work** Use actions described above for construction projects experiencing minor to moderate SESC problems. Follow the Department's Vendor Performance process to document unsatisfactory performance of the work. If the Contractor is non-responsive and the problem is severe, take steps necessary to terminate the contract and arrange for others to perform the work.

4.3 EGLE Progressive Compliance (Escalation) Process


Every effort will be made to resolve soil erosion and sedimentation control issues as quickly as possible rather than wait for EGLE to issue a notice of noncompliance.

If progressive compliance involving EGLE becomes necessary, the process shown in the flow chart at the end of this section will be followed by EGLE and MDOT. It may not be necessary to follow each step in the order shown provided the appropriate actions are taken to minimize the impacts to the environment and to bring the work area into compliance.


The TSC Manager will work to resolve the concerns as expeditiously as possible and in a time frame that is mutually agreed upon by EGLE and the TSC Manager. TSC staff may work with designated region and Lansing central office staff to make the best decisions possible to improve deficient erosion control measures. If additional information is required, EGLE may arrange a site meeting with the TSC staff. TSC staff will invite region resource staff and, if necessary, Lansing central office staff to this meeting.

When written correspondence is advised or required, e-mail or formal letters are acceptable. When formal correspondence is necessary, this correspondence may be sent electronically to save time but must be followed up with a signed hard copy. All correspondence will be copied to the appropriate Region Engineer and the Environmental Field Services Engineer in Bureau of Development.

MDOT SESC COMPLIANCE PROCESS



EGLE SESC PROGRESSIVE COMPLIANCE PROCESS



THIS PAGE BLANK

5. PERMIT REQUIREMENTS, ACTS AND RULES

This section contains information on additional permits that may be required on MDOT construction or maintenance projects. Always consult with designated staff in the region, TSC or Lansing central office on project specific permit requirements.

The full text of Parts 31 and 91 of Act 451 and the related administrative rules, Parts 21 and 17, respectively, are found on the EGLE website.

Part 91 and Part 17 (SESC)

www.michigan.gov/egle, click on <Land>, then <Soil Erosion and Storm Water Construction>, then <Part 91 Agency Resources>, then Laws <Part 91, as Amended (pdf)>, and/or <Rules: R323. 1701-1714 (pdf)

Part 31 and Part 21 (NPDES)

www.michigan.gov/egle, click on <Water>, then <Michigan Surface Water Programs>, then <NPDES Permits>, then <Applicable Rules and Regulations>, then <Part 31 statute> or <Part 21 Rules>

5.1 MDOT Permit Coordinators

When an activity conducted by MDOT requires a permit from EGLE under state and/or federal statutes it will be coordinated in the following manner.

Permit acquisition for projects located in the Grand Region will be coordinated by the Environmental Permit Coordinator of the MDOT Grand Region Office at 1420 Front Ave. N.W., Grand Rapids, MI 49504, Phone: 616-451-3091.

Permit acquisition for projects located in the University Region will be coordinated by the Environmental Permit Coordinator of the MDOT University Region Office at 4701 W. Michigan Ave., Jackson, MI 49201, Phone: 517-750-0401.

Permit acquisition for projects located in the Bay and North Regions will be coordinated by the Environmental Permit Coordinator of the MDOT Bay Region Office at 5859 Sherman Rd, Saginaw, MI 48604: Phone: 989-233-5475.

Permit acquisition for projects located in the Southwest Region will be coordinated by the Environmental Permit Coordinator of the MDOT Southwest Region Office at 1501 E. Kilgore Road, Kalamazoo, MI 49001, Phone: 269-337-3900.

Permit acquisition for projects located in Metro Region will be coordinated by the Environmental Permit Coordinator of the MDOT Metro Region Office at 18101 W. 9 Mile Rd, Southfield, MI 48075: Phone: 248-483-5100

Permit acquisition for projects located in the Superior Region will be coordinated by the Environmental Permit Coordinator of the MDOT Superior Region Office at 1818 Third Avenue North, Escanaba, MI 49829, Phone: 906-786-1800.

This coordinated approach will ensure compliance with the current state and federal permit requirements and allow for efficient processing of MDOT applications by EGLE.

5.2 Permit Requirements

One or more of the following permits may be required for a construction project, maintenance project or maintenance activity.

- **5.2.1 Floodplain and Floodways -** Part 31 of Act 451 requires a Floodplain Permit from EGLE for construction in a floodplain of any river or stream having a contributing drainage area of two square miles or more upstream of the crossing. In addition, MDOT must comply with the Governor's State Executive Order 1977-4, "State Flood Hazard Management Plan" which establishes flood standards and design requirements.
- **5.2.2 Inland Lakes and Streams -** Part 301 of Act 451 requires an Inland Lakes and Streams Permit from EGLE for construction in, over or adjacent to inland lakes or streams.
- **5.2.3 Wetland Protection -** Part 303 of Act 451 requires a Wetland Permit from EGLE for construction in wetland areas. Any unavoidable wetland impacts resulting from construction activities in a regulated wetland must be properly mitigated based on specific ratios. Wetland mitigation plans must be developed and coordinated with EGLE during the project development stage.
- **5.2.4 Dam Safety -** Part 315 of Act 451 requires a Dam Safety Permit from EGLE for construction, enlargement, repair, reconstruction, alteration, removal or abandonment of any dam in the State of Michigan.
- **5.2.5 Shorelands Protection and Management -** Part 323 of Act 451 may require a permit for work in EGLE designated high-risk erosion areas, environmental areas, and flood risk areas. Such work includes erection of permanent structures in designated high-risk erosion areas or flood plain areas, or grading, dredging and filling in designated environmental areas.
- **5.2.6 Great Lakes Submerged Lands -** Part 325 of Act 451 requires a Great Lakes Submerged Land Permit from EGLE for any dredging, filling or related construction activities in, over, or adjacent to any of the Great Lakes.
- **5.2.7 Sand Dunes Protection and Management -** Part 353 of Act 451 may require EGLE permits for uses in critical dunes areas, as designated by the EGLE, which would include grading, filling or excavating activity.
- **5.2.8 Section 404C (Federal) -** The Federal 404 Permit Program of the Clean Water Act authorizes coordination of federal permits under the joint permit system with the U.S. Army Corps of Engineers (USACE). EGLE is the responsible agency for this coordination of permits. A separate permit from the USACE is required for navigable watercourses.

6. SESC MEASURES (E & S DETAILS)

This section contains the current MDOT soil erosion and sedimentation control measures for use on construction and maintenance projects. All measures shown reflect MDOT's experience with soil erosion and sedimentation control for road and bridge construction and, as such, are considered best management practices. Additional design and placement considerations for these measures are found in Chapter 9 of the MDOT Drainage Manual.

Refer to Standard Plan R-96 Series for the key numbers to be shown on plan sheets and information on when to use various control measures. Discussion of measurement and payment is included on the E&S details for information only. In the case of conflict between the contract items shown on these details and contract items included in the contract documents for a specific project, the contract documents will prevail.

Dimensions on E&S Details not shown as maximum or minimum dimensions may be modified to fit existing field conditions or to improve the effectiveness of the soil erosion or sedimentation control of the device. Dimensions shown as maximum or minimum dimensions must be adhered to unless modifications are discussed with region or Lansing SESC staff and approved changes are noted in the inspection reports. The designer and construction engineer will determine the need for all items shown as optional on the E&S Details. Refer to the contract documents for additional information on the materials, construction or placement of these devices.

Individual erosion control devices will be constructed to provide the most effective and efficient soil erosion and sedimentation control for a specific construction or maintenance site. Based on site conditions, the Engineer or the Part 91 Inspector may authorize minor adjustments to the E&S Details. Any major deviations, especially in areas of concentrated flows, will be discussed with the appropriate staff and approved changes must be noted in the inspection reports. Prior review and approval is not required if the changes are needed to mitigate the effects of a pending sediment release.

The Department has a process to experiment with and evaluate new materials for possible use during the execution of construction and maintenance projects. These new materials can include BMPs used for SESC measures. To strive to provide continuous improvement to the SESC program the Department is willing to use innovative products that may be more effective for controlling erosion and any subsequent sedimentation. Typically, a manufacturer or distributor will contact the Department and submit a request for consideration to use a product as a SESC BMP. The Department provides an initial assessment of the product and either accepts it, rejects it or is willing to try it on a trial basis. In most cases new SESC products are considered on a trial basis where the performance is monitored throughout the life of the installation. After the trial period the effectiveness of the product as a SESC BMP is evaluated and consideration is given for future use.

APPLICABLE SOIL EROSION AND SEDIMENTATION CONTROL MEASURES

COMPREHENSIVE DETAILS ARE LOCATED IN SECTION 6 OF THE SOIL EROSION & SEDIMENTATION CONTROL MANUAL A

A = SLOPES

В = STREAMS AND WATERWAYS

= SURFACE DRAINAGEWAYS

= ENCLOSED DRAINAGE (INLET & OUTFALL CONTROL) D

= LARGE FLAT SURFACE AREAS Ε

F BORROW AND STOCKPILE AREAS

DNRE PERMIT MAY BE REQUIRED

KEY	DETAIL	CHARACTERISTICS	A	В	С	D	E	F	G
1	TURBIDITY CURTAIN	A Turbidity Curtain is used when slack water area is necessary to isolate construction activities from the watercourse. The still water area contains the sediments within the construction limits.		•					
2	GRUBBING OMITTED	Retains existing root mat which assists in stabilizing slopes. Assists in the revegetation process by providing sprout growth. Reduces sheet flow velocities preventing rilling and gullying. Discourages off-road vehicle use.					•		
3	PERMANENT/TEMPORARY SEEDING	Inexpensive but effective erosion control measure to stabilize flat areas and mild slopes. Permits runoff to infiltrate soil, reducing runoff volumes. Proper preparation of the seed bed, fertilizing, mulching and watering is critical to its success.	•		•		•	•	
4	DUST CONTROL	Dust control can be accomplished by watering, and/or applying calcium chloride. The disturbed areas should be kept to a minimum. PERMANENT/TEMPORARY SEEDING (KEY 3) should be applied as soon as possible.	•				•	•	
5	mana pama mana ngan a amanag pama mbanagan s mbangan a rabutang di na apan mbanangan a rabu na yaran n pana mbanagan a rabu nagan mba di na araban na rabunara na mbanagan mbanagan na sabanagan na saba	Provides immediate vegetative cover such as at spillways and ditch bottoms. Proper preparation of the topsoil, placement of the sod, and watering is critical to its success.					•	•	
6	VEGETATED BUFFER STRIPS	Reduces sheet flow velocities preventing rilling and gullying. Assists in the collection of sediments by filtering runoff. Assists in the establishment of a permanent vegetative cover.					•		
	DEBARTME	MICHICAN DEDARMENT OF	TDA	NO		TAT		_	\dashv

PREPARED BY DESIGN DIVISION

DRAWN BY: B.L.T. CHECKED BY: W.K.P.

DEPARTMENT DIRECTOR Kirk T. Steudle

APPROVED BY: . ENGINEER OF DELIVERY

ENGINEER OF DEVELOPMENT

APPROVED BY: Mark a Van

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR

SOIL EROSION & SEDIMENTATION CONTROL MEASURES

SHEET 9-10-2010 6-3-2010 R-96-E 1 OF 6 F.H.W.A. APPROVAL PLAN DATE

KEY	DETAIL	CHARACTERISTICS	A	В	С	D	Е	F	G
7		Used where vegetation cannot be established. Very effective in protecting against high velocity flows. Should be placed over a geotextile liner.		•	•	•			•
	RIPRAP								
8	AGGREGATE COVER	Can be used in any area where a stable condition is needed for construction operations, equipment storage or in heavy traffic areas. Reduces potential soil erosion and fugitive dust by stabilizing raw areas.	•				•	•	
9	BENCHES	Reduces sheet flow velocities preventing rilling and gullying. Assists in the collection and filtering of sediments. Provides access for stabilizing slopes.	•					•	
	DENCHES	Assists in the diversion of runoff to a stable outlet or sediment						H	Н
10	***	Assists in the diversion of runoff to a stable outlet or sediment control device. Reduces sheet flow velocities preventing rilling and gullying. Collects and diverts runoff to properly stabilized drainage ways. Works well with INTERCEPTING DITCH (KEY 11)	•				•	•	
	DIVERSION DIKE								
11		Assists in the diversion of runoff to a stable outlet or sediment control device. Reduces sheet flow velocities preventing rilling and gullying. Works well with DIVERSION DIKE (KEY 10)	•				•	•	
	INTERCEPTING DITCH								
12	INTERCEPTING DITCH AND DIVERSION DIKE	Assists in the diversion of runoff to a stable outlet or sediment control device. Reduces sheet flow velocities preventing rilling and gullying.	•				•	•	
13	GRAVEL FILTER BERM	Useful in filtering flow prior to its reentry into a lake, stream or wetland. Works well with SEDIMENT TRAP (KEY 20) and TEMPORARY BYPASS CHANNEL (KEY 35). Not to be used in lieu of a CHECK DAM (KEY 37) in a ditch.			•			•	
14	GRAVEL ACCESS APPROACH	Provides a stable access to roadways minimizing fugitive dust and tracking of materials onto public streets and highways.				•	•		
MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR									

SOIL EROSION & SEDIMENTATION CONTROL MEASURES

SHEET 9-10-2010 6-3-2010 R-96-E 2 OF 6 F.H.W.A. APPROVAL PLAN DATE

KEY	DETAIL	CHARACTERISTICS	A	В	С	D	E	F	G
15	SLOPE DRAIN SURFACE	Excellent device for carrying water down slopes without creating an erosive condition. Generally used in conjunction with DIVERSION DIKE (KEY 10), INTERCEPTING DITCH (KEY 11) and INTERCEPTING DITCH AND DIVERSION DIKE (KEY 12) to direct flow to a stable discharge area or SEDIMENT TRAP (KEY 20).			•				
16	TREES, SHRUBS AND PERENNIALS	Trees, shrubs and perennials can provide low maintenance long term erosion protection. These plants may be particularly useful where site aesthetics are important along the roadside slopes.					•		
17	PIPE DROP	Effective way to allow water to drop in elevation very rapidly without causing an erosive condition. Also works as a sediment collector device. May be left in place as a permanent erosion control device.			•				
18		It may be necessary to dewater from behind a cofferdam or construction dam to create a dry work site. Discharged water must be pumped to a filter bag. A GRAVEL FILTER BERM (KEY 13) may be placed downslope of the filter bag to provide additional filtration prior to entering any stream or wetland.		•					•
19	DEWATERING WITH FILTER BAG ENERGY DISSIPATORS	A device to prevent the erosive force of water from eroding soils. Used at outlets of culverts, drainage pipes or other conduits to reduce the velocity of the water. Prevents structure scouring and undermining.		•	•	•			
20	SEDIMENT TRAP	Used to intercept concentrated flows and prevent sediments from being transported off site or into a watercourse or wetland. The size of a Sediment Trap is 5 cubic yards or less. Works well when used with CHECK DAM (KEY 37).			•	•			
21	SEDIMENT BASIN	A Sediment Basin is used to trap sediments from an upstream construction site. Requires periodic inspections, repairs, and maintenance. Where practical, sediments should be contained on site. A Sediment Basin should be the last choice of sediment control. The size of a Sediment Basin is greater than 5 cubic yards.		•					•
22	VEGETATIVE BUFFER AT WATERCOURSE	This practice is used to maintain a vegetative buffer adjacent to a watercourse. When utilized with SILT FENCE (KEY 26) it will, under normal circumstances, prevent sediment from leaving the construction site.		•	•		•	•	
MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR SOIL EROSION & SEDIMENTATION CONTROL MEASURES							N		

9-10-2010

F.H.W.A. APPROVAL

6-3-2010

PLAN DATE

SHEET

3 OF 6

R-96-E

KEY	DETAIL	CHARACTERISTICS	A	В	С	D	E	F	G
23	STREAM RELOCATION	A detail depicting the proper procedures for stream relocation. Maintains same width, depth, and flow velocity as the natural stream. Revegetate banks with PERMANENT/TEMPORARY SEEDING (KEY 3), MULCHING AND MULCH ANCHORING (KEY 28), MULCH BLANKETS AND HIGH VELOCITY MULCH BLANKETS (KEY 33) and woody plants to shade the stream.		•					•
24		Sand and stone bags are a useful tool in the prevention of erosion. Can be used to divert water around a construction site by creating a DIVERSION DIKE (KEY 10). Works well for creating a CONSTRUCTION DAM (KEY 36) and temporary culvert end fill.	•	•	•	•	•	•	•
	SAND AND STONE BAGS								
25	SAND FENCE AND	A Sand Fence traps blowing sand by reducing wind velocities. Can be used to prevent sand from blowing onto roads. Must be maintained until sand source is stabilized.	•				•	•	
	DUNE STABILIZATION								
26	SILT FENCE	A permeable barrier erected below disturbed areas to capture sediments from sheet flow. Can be used to divert small volumes of water to stable outlets. Ineffective as a filter and should never be placed across streams or ditches where flow is concentrated.	•				•	•	
27	PLASTIC SHEETS OR GEOTEXTILE COVER	Plastic Sheets can be used to create a liner in temporary channels. Can also be used to create a temporary cover to prevent erosion of stockpiled materials.	•	•	•			•	
28	MULCHING AND MULCH ANCHORING	Anchored mulch provides erosion protection against rain and wind. Mulch must be used on seeded areas to promote water retention and growth. Should be inspected after every rainstorm and repaired as necessary until vegetation is well established.	•		•		•	•	
29		Provides settling and filtering of silt laden water prior to its entry into the drainage system. Can be used in median and side ditches where vegetation will be disturbed. Allows for early use of drainage systems prior to project completion.			•		•		
	INLET PROTECTION FABRIC DROP		1						
30	INLET PROTECTION GEOTEXTILE AND STONE	Provides settling and filtering of silt laden water prior to its entry into the drainage system. Should be used in paved areas where drainage structures are existing or proposed. Allows for early use of drainage systems prior to project completion.			•		•		
MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR									

SOIL EROSION & SEDIMENTATION CONTROL MEASURES

9-10-2010 6-3-2010 R-96-E SHEET 4 OF 6

KEY	DETAIL	CHARACTERISTICS	A	В	С	D	E	F	G
31		An Inlet Protection Sediment Trap is a temporary device that can be used in areas where medium flows are anticipated. Effective in trapping small quantities of sediments prior to water entering the drainage system. Can be used in areas such as median and side ditches.			•		•		
	INLET PROTECTION SEDIMENT TRAP								
32	SLOPE ROUGHENING AND SCARIFICATION	A simple and economical way to reduce soil erosion by wind and water. Can be accomplished by harrowing with a disk, back blading, or tracking with a dozer perpendicular to the slope.	•				•	•	
33	MULCH BLANKETS AND HIGH VELOCITY MULCH BLANKETS	Mulch blankets provide an immediate and effective cover over raw erodible slopes affording excellent protection against rain and wind erosion. High velocity mulch blankets work well for stabilizing the bottom of ditches in waterways.	•		•		•	•	
34	COFFERDAM	Used to create a dry construction area and protect the stream from raw erodible areas. Must be pumped dry or dewatered according to DEWATERING WITH FILTER BAG (KEY 18).		•					•
35	TEMPORARY BYPASS CHANNEL	Utilized when a dry construction area is needed. Isolates stream flows from raw erodible areas minimizing erosion and subsequent siltation. Can incorporate SEDIMENT BASIN (KEY 21), CHECK DAM (KEY 37), and GRAVEL FILTER BERM (KEY 13) to remove sediments from water. Construction sequence of events may be necessary.		•					•
36	CONSTRUCTION DAM	Used to create a dry or slack water area for construction. Isolates the stream from raw erodible areas. Can be created out of any non-erodible materials such as SAND AND STONE BAGS (KEY 24), a gravel dike with clay core or plastic liner, steel plates or plywood.		•					•
37		Can be constructed across ditches or any area of concentrated flow. Protects vegetation in early stages of growth. A Check Dam is intended to reduce water velocities and capture sediment. A Check Dam is not a filtering device.	•		•			•	
	CHECK DAM								

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR


SOIL EROSION & SEDIMENTATION CONTROL MEASURES

9-10-2010 6-3-2010 R-96-E SHEET 5 OF 6

NOTES: THIS STANDARD PLAN WILL SERVE AS A KEY IN THE SELECTION OF THE APPROPRIATE SOIL EROSION AND SEDIMENTATION CONTROL DETAILS. THIS PLAN ALSO PROVIDES THE KEY TO THE NUMBERED EROSION CONTROL ITEMS SPECIFIED ON THE CONSTRUCTION PLANS. REFER TO THE MODIT SOIL EROSION & SEDIMENTATION CONTROL MANUAL, SECTION 6 FOR SPECIFIC DETAILS, CONTRACT ITEMS (PAY ITEMS), AND PAY UNITS. COLLECTED SILT AND SEDIMENT SHALL BE REMOVED PERIODICALLY TO MAINTAIN THE EFFECTIVENESS OF THE SEDIMENT TRAP, SEDIMENT BASIN, AND SILT FENCE, AGGREGATES PLACED IN STREAMS SHOULD CONTAIN A MINIMUM OF FINES. TEMPORARY EROSION AND SEDIMENTATION CONTROL PROVISIONS SHALL BE COORDINATED WITH THE PERMANENT CONTROL MEASURES TO ASSURE EFFECTIVE CONTROL OF SEDIMENTS DURING CONSTRUCTION OF THE PROJECT. ALL TEMPORARY EROSION CONTROL DEVICES SHALL BE REMOVED AFTER VEGETATION ESTABLISHMENT OR AT THE DISCRETION OF THE ENGINEER. CARE SHALL BE TAKEN DURING REMOVAL TO MINIMIZE SILTATION IN NEARBY DRAINAGE COURSES. MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR SOIL EROSION & SEDIMENTATION CONTROL MEASURES SHEET 6-3-2010 9-10-2010 R-96-E 6 OF 6

F.H.W.A. APPROVAL

PLAN DATE





DESIGN DIVISION

DRAWN BY: B.L.T. CHECKED BY: W.K.P. DEPARTMENT DIRECTOR


APPROVED BY:


Mark a Van Pars APPROVED BY: . DIRECTOR, BUREAU OF HIGHWAY DEVELOPMENT MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR

SEEDING AND TREE PLANTING

9-30-2014 F.H.W.A. APPROVAL 9-26-2013 PLAN DATE

R-100-H






SHRUB BED DETAIL

FIRST AND SECOND WATERING AND CULTIVATION SHALL INCLUDE SHRUB BEDS.

CUT 6" X 12" (MIN.) EDGING AROUND THE PERIMETER OF ALL SHRUB BEDS SHOWN ON THE PLANS. SPRAY A NON-PERSISTANT GLYPHOSATE HERBICIDE TO ENTIRE SHRUB BEDS PRIOR TO PLANTING AND BARK PLACEMENT.

SHRUB BEDS ARE TO BE PAID FOR BY THE PAY ITEM 'SITE PREPARATION'.

ALL PLANTS SHALL BE SET PLUMB AND HAVE THE BEST SIDE OF PLANT FACING THE MAIN VIEWING DIRECTION.



PLANTING NOTES:

ALL EXCAVATED MATERIAL SHALL BE REMOVED FROM THE SITE - IMMEDIATELY.

LOOSEN SUBSOIL TO A DEPTH OF 4". LOOSEN EARTH ON SIDES OF PLANT POCKET TO BREAK ANY GLAZING CAUSED BY DIGGING.

FILL PREPARED SOIL TO $\frac{1}{2}$ THE DEPTH OF THE ROOT BALL, PACK FIRMLY, AND PUDDLE WITH WATER.

BACKFILL WITH PREPARED SOIL WHICH, AFTER COMPACTION, IS FLUSH WITH SURROUNDING GROUND LEVEL.

COVER ENTIRE PLANT POCKET AREA WITH 5"-6" MULCH. PRUNE, WRAP, AND BRACE AND GUY.

WHEN PLANTS ARE FURNISHED IN CONTAINERS, CONTAINERS SHALL BE COMPLETELY REMOVED AT THE TIME OF PLANTING.


TREE HEIGHTS ARE SHOWN BEFORE PRUNING. TREE PLANTING DEPTHS ARE SHOWN AFTER SETTLING.

TREES AND SHRUBS SHALL NOT BE PLANTED WITHIN 50' AND 30' RESPECTIVELY OF THE NEAREST EDGE OF METAL - EXCEPT WHERE INACCESSIBLE TO VEHICLES.


MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR

SEEDING AND TREE PLANTING

9-30-2014 F.H.W.A. APPROVAL PLAN DATE R-100-H SHEET 3 OF 4



MEDIAN PLANTING NOT TO SCALE



BARE ROOT PLANTS

PLANTING BARE ROOT PLANT MATERIAL

REFER TO THE "SPECIAL PROVISIONS FOR BARE ROOT PLANTING" FOR SHIPPING, STORAGE AND HANDLING REQUIREMENTS.

MAINTAIN ROOT MOISTURE BY KEEPING ROOTS IMMERSED IN WATER PRIOR TO PLANTING.


ROOT PRUNE AS NECESSARY TO REMOVE ALL DAMAGED OR BROKEN ROOTS, AND AS REQUIRED BY THE DISTRICT FORESTER OR RESOURCE SPECIAL IST.

DIG PLANTING HOLES AT LEAST 12" WIDE AND 12" DEEP TO ACCOMODATE ROOT MASS.

SET PLANTS PLUMB WITH THE ROOTS SPREAD PUT IN A NATURAL POSITION AT A DEPTH EQUAL TO THE DEPTH AT THE NURSERY.

HOLD PLANT FIRMLY AND PUDDLE (NOT TAMP) THE BACKFILL AROUND THE ROOTS WITH WATER. SUFFICIENT WATER SHALL BE USED TO ENSURE SATURATION OF THE BACKFILL, BUT CARE SHOULD BE TAKEN NOT TO OVERWATER, CAUSING A FLOATING SOIL MASS THAT PREVENTS COMPACTION AND MAY RESULT IN AIR POCKETS ADJACENT TO THE ROOTS. BACKFILL SHOULD BE FLUSH WITH THE GROUND AFTER COMPACTION.

COVER ENTIRE PLANT POCKET AREA WITH 5" - 6" MULCH AS SHOWN.



PERENNIAL PLANTS

FIRST AND SECOND WATERING AND CULTIVATION SHALL INCLUDE PERENNIAL BEDS.

PERENNIALS ARE TO BE FULLY DEVELOPED TWO YEAR #2 CONTAINER PLANTS.

ENTIRE PERENNIAL BED SHALL BE EXCAVATED DOWN 12" AND REPLACED WITH 12" OF PREPARED SOIL.

PERENNIAL BEDS ARE TO BE PAID FOR BY THE PAY ITEM 'SITE PREPARATION'.

SEEDING NOTES:

THIS STANDARD ILLUSTRATES THE TYPICAL USE OF SEEDING WITH MULCH, AS THESE ITEMS RELATE TO ROADWAY CONSTRUCTION. THE ACTUAL DESIGN AND MATERIALS USED TO CONSTRUCT THE COMPLETE SECTION, WHICH INCLUDES SEEDING WITH MULCHING, WILL BE ACCORDING TO THE PLANS AND CURRENT SPECIFICATIONS.

ITEMS CALLED FOR ON THIS STANDARD MAY ALSO BE USED DURING CONSTRUCTION AS AN EROSION CONTROL MEASURE. SEE STANDARD PLAN R-96-SERIES.

ALL DITCHES SHOULD HAVE HIGH VELOCITY MULCH BLANKET FOR EROSION CONTROL.

THE FIRST 6' BEHIND THE CURB OR SHOULDER IN URBAN MEDIAN AREAS WILL BE SEEDED, FERTILIZED, AND MULCHED WITH MULCH BLANKET. THE REMAINING AREAS WILL BE SEEDED, FERTILIZED, AND MULCHED WITH MULCH BLANKET OR STANDARD MULCH ANCHORED IN PLACE WITH A MULCH ADHESIVE OR WITH A MULCH NET.


ALL AREAS WHERE MULCH BLANKET IS CALLED FOR SHALL BE SEEDED, FERTILIZED, AND TOPSOILED AS SPECIFIED ON PLANS. NO MULCH OR ANCHORING MULCH IS REQUIRED WHERE MULCH BLANKET IS INSTALLED.

BACKSLOPE RESTORATION TREATMENT SHALL BE THE SAME AS THE FRONT SLOPE.

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT STANDARD PLAN FOR

SEEDING AND TREE PLANTING

9-30-2014 9-26-2013 R-100-H SHEET 4 OF 4



A Turbidity Curtoin is used when slock water area is necessary to isolate construction activities from the watercourse,

The Turbidity Curtoin system shall be designed to handle site specific drainage or flow patterns.

When water is less than 2 feet deep and has low flow, Turbidity Curtain (Shallow) may be used, Curtain shall be securely fastened to stokes. Water greater than 2 feet deep or where high flow exists requires the use of Turbidity Curtain (Deep).

Installation and Maintenances

The Turbidity Curtain shall be installed at the location shown on the plans and according to the special provision.

The Turbidity Curtain shall be placed parallel to the direction of flow and anchored upstream, downstream, and to the stream bed to maximize protection to the watercourse.

The Contractor shall maintain the Turbidity Curtain until the construction activity within the watercourse is camplete or as approved by the Engineer. Retained sediment shall be removed to the maximum extent practicable prior to removing

The Turbidity Curtain may include a re-directional borrier on the upstream and of the work area.

Related SESC Measures:

- E & S-18 Dewatering with Filter Bog E & S-24 Sand and Stane Bags
- E & S-34 Cofferdom

Measurement and Payments

Turbidity Curtoin requires inclusion of the appropriate special provision in the contract documents. Payment includes furnishing and installing sufficient onehors, tle-dawns, or other mechanisms to ensure proper position and performance of the Turbidity Curtain Optional work shown, when installed and maintained as directed by the Engineer, will be poid using the associated contract item listed here.

Contract Item (Pay Item) Turbidity Curtoin (Shotlow) Turbidity Curtain (Deep)

Pay Unit Faot Foot


MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Turbidity Curtain

&MDO1

09-30-2005 PLAN DATE

E&S-1-A



When long, steep slopes are proposed to be aleared and grubbed, it is a good sali erosion control practice to leave strips of ungrubbed slopes running perpendicular to the flow of water. This practice will reduce sheet flow velocities and prevent rilling and guilying. This practice works well an all slopes regardless of length.

This practice is similar to Vegetative Buffer Strips (E & S-6) since it leaves a partian of the natural vegetation in place to pratect and assist in stabilizing the slope.

This practice is not effective in areas of cancentrated flows.

Installation and Maintenance:

The strips of natural vegetation to be left undisturbed should be approximately 20 teet wide and spaced approximately 50 feet apart. The spacing of the strips of natural vegetation may be closer than 50 feet on steep slopes.

This grading practice may incorporate the use of SHT Fance (E & S-26) for added protection to off-site areas.

A Diversion Dike (E & S-10), intercepting Ditch (E & S-1)), and intercepting Ditch and Diversion Dike (E & S-12) may be placed at the top of the slope to prevent water from running over the graded area.

Related SESC Measures:

- Vogatotivo Buffer Strips
- E & S-10 Diversion Dike E & S-11 Intercepting Ditch
- E & S-12 Intercepting Ditch and Diversion Dike E & S-26 Silt Fence

Measurement and Payments

There is no separate contract item for this £ & S measure, Payment for Grubbing Omitted will be included in related items of work. Optional work shown, when installed and maintained as directed by the engineer, will be paid using the associated contract item listed here.

Contract Item (Pay Item)

Pay Unit

Ditch, Intercepting

Statlon

Embankment, LM

Cubic Yord

Erosian Control, Silt Fence

Faot

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Grubbing Omitted

EMIDO1

04-07-2006 PLAN DATE

E&S-2-A

Permanent/Temporary Seeding of grasses and legumes is the most common and economical means of establishing protective cover. The advantages of seeding over other means of establishing vegetation includes low initial cost, a wide variety of available grasses and legumes, lower labor input and ease of application.

Permonent/Temporary Seeding controls erosian by physically protecting bare soll from raindrop impact, flowing water and wind. Vegetation binds soil particles together with a dense root system and reduces the velocity and valume of overland flow. Wherever site conditions permit, this is the preferred method of surface stabilization.

Problems to consider are the patential for erasion during the establishment period, the need to resead areas, seasonal limitations on seeding, weed competition, and the need for water during germination and early growth.

Installation and Maintenance:

Permanent/Temporory seedbed preparation, seeding mixtures, rate of application for seed, fertilizer, mulch and water, as well as seeding limitations, shall be in accordance with the Michigan Department of Transportation Standard Specifications for Construction Section 816 Turf Establishment and the Standard Plans, R-100 Series,

Optional Measures:

Temporary seeding shott only be done with the approval of the Engineer.

Related SESC Measures:

E & S-28 Mulching & Mulch Anchoring

E & S-32 Surface Roughening & Scorification

E & S-33 Mulch Blankets and High Velocity Mulch Blankets

Measurement and Payments

Optional measures, when installed and maintained as directed by the Engineer, will be paid using the associated pay items listed here.

Contract Item (Pay Item)

<u>Poy Unit</u>

Seeding, Mixture __.. Water, Sodding/Seeding Pound

* Note: Soeding Mixture may be modified by Special Provision.


MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Permanent/Temporary Seeding

EMDOT

09-30-2005

E&S-3-A PLAN DATE



For disturbed areas not subject to traffic, vegetation (temporary or permanent) provides the most practical and effective means of Dust Control. For other areas, Dust Control measures include, but are not limited to, mulching, sweeping, watering, and applying calcium chloride or polymers.

installation and Maintenance:

For off-road areas where vegetatian will be the final stabilization method, calclum chiarlie shall not be used since it would inhibit vegetation establishment.

Optional Measures:

Related SESC Measures:

- E & S-3 Permonent/Temporory Seeding E & S-8 Aggregate Cover

- E & S-14 Grovel Access Approach
 E & S-28 Mulching and Mulch Anchoring
 E & S-32 Surface Roughening and Scarification
 E & S-33 Mulch Bionkets and High Velocity Mulch Biankets

Measurement and Payments

If not shown as a pay Item, payment for Dust Control will be included in related Items of work.

Contract Item (Pay Item)

Poy Unit

Dust Pollative, Applied


MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Dust Control

MDOT

04-07-2008 PLAN DATE

E&S-4-A



Lay sod in a staggered pattern with strips butted tightly against each other.
A sharpened mason's trowel can be used to tuck down the ends and trim pleces,



Correct





Incorract

Angled Ends must be matched correctly.

Sodding provides an immediate vegetative cover for spillways and ditches.

installation and Waintenances

Due to high maintenance and difficult roadside establishment canditions, Sodding should only be used in areas where Permonent/Temporary Seeding (E & S-3) or Much Blankets (E & S-33) will not work. Since Sod requires frequent watering for its survival it is not a good substitute for seeding.

Optional Measures:

in areas of concentrated ditch flow, seed and High Velocity Mulch Blankets (E & S-33) may be used.

See subsection 816,03 of the Standard Specifications for details and limitations for sadding.

Related SESC Measures:

E & S-33 Mulch Blankets and High Velocity Mulch Blankets

Measurement and Payments

Contract Item (Pay Item)

Poy Unit

Sodding Woter, Sodding/Seeding

Square Yord Unit


MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Sodding

MOOT

04-07-2006 PLAN DATE

E&S-5-A



Use;

When slapes are proposed to be graded, it is a good practice to leave Vegetoted Buffer Strips or undisturbed areas running perpendicular to the flow of water. This practice will reduce sheet flow velocities and prevent rilling and guilying.

Vegetated Buffer Strips will also assist in the establishment of a permanent vegetative cover, preventing slope sloughing and loss of seed and mulch. Vegetative Buffer Strips also provide wind breaks, reducing the potential for wind erosion.

This practice is similar to Grubbing Omitted (E & S-2) since it leaves a partian of the natural vegetation in place to protect and assist in stabilizing the slope.

This practice is not effective in areas of concentrated flows.

Installation and Maintenance:

The strips of natural vegetation to be left undisturbed should be approximately 20 feet wide and spaced approximately 50 feet apart. The spacing of the strips of natural vegetation may be closer than 50 feet on steep slapes.

Optional Measures:

For added protection to off-site areas, this grading practice may include the use of SIIt Fence (E & S-26).

A Diversion Dike (E & S-10), Intercepting Ditch (E & S-11), and Intercepting Ditch and Diversion Dike (E & S-12) may be placed at the top of the slope to prevent water from running over the graded area.

Related SESC Measuress

- E & S-2 Grubbing Omitt E & S-10 Diversion Dike Grubbing Omitted
- E & 5-11 Intercepting Ditch
- Intercepting Olich and Diversion Dike
- E & S-26 Still Fence

Measurement and Payment:

There is no separate contract item for this E & S measure. Payment for Vegetated Buffer Strips will be included in related Items of work. Optional work shown, when installed and maintained as directed by the Engineer, will be paid using the associated contract item listed here.

Contract Item (Pay Item)

<u>Pay Unit</u>

Ditch, Intercepting Erosion Control, Silt Fence Station Foot

Embankment, LM Embankment, CP Cubic Yord Cubic Yord

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Vegetated Buffer Strips

EMDOT

04-07-2008 PLAN DATE

E&S-6-A

SHEET 1 OF I



Ųse

Riprop should be sized to ensure that the size of stone is adequate to protect the grea from erosion and subsequent sittation to off-site locations. Refer to Chapter 9 of the Drainage Manual for additional information on specifying Riprop.

Riprap provides an immediate and effective, non-eradible cover over row eradible areas. A properly designed layer of stone can be used to control erasion. Riprap protects the soil surface from direct erasive forces such as wind, roin and surface runoff. It is often used on steep slopes subject to weathering or seepage, for channel liners, inlet and outlet protection of culverts, streambook protection and to protect sharelines subjected to wave action.

Clean, well-graded Riprap forms a dense, flexible, self-healing cover that will adapt well to uneven surfaces. Care must be exercised in the design and installation process so that the Riprap is clean, free of visible rebar, sized correctly and placed to the proper thickness.

Riprop placed at culvert outlets can be used to protect the stream bed and channel, thus reducing the flow velocity to a level that is non-erosive.

Riprop is used at the outlet of storm drains and as channel linings when flow velocities and concentrations are high and/or the channel slope is steep. Riprop is effective on the banks of channels, at changes in flow direction and to stabilize eradible slopes.

installation and Maintenance:

Riprop shall be placed on Geotextile Liner to prevent soil 'piping' from seepage or runoff. The edges of the Geotextile Liner shall be overlopped a minimum of 2 feet, Place Riprop immediately after installing Geotextile Liner.

When Riprop, Heavy is specified, Geotextile Liner, Heavy must be used.

Refer to Subsection 813,03,E of the Standard Specifications for Construction for additional installation details,

Core must be taken to properly secure edges of Geotextile Liner to prevent piping,

When Riprop is placed as a permanent erasion control measure, the top of Riprop should be approximately level with surrounding soil surface.

Do not mix eradible soil with Riprop during placement.

Optional Measures:

Related SESC Measures:

S & E-19 Energy Dissipotors

Measurement and Payments

Contract Item (Poy Item)	Poy Unit
Riprop, Heovy	Square Yard
Riprop, Heavy, LM	Cubic Yard
Riprop, Piain	Squore Yard
Riprop. Plain LN	Cubic Yord
Grouted Riprop	Square Yard

Note: Grodatians and dimensions of Riprop may be modified by Special Provision.

PERMITS FROM THE MICHIGAN DEPARTMENT OF ENVIRONMENTAL QUALITY MAY BE REDUIRED.

NICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Riprap

EMDOT

04-07-2006 PLAN DATE

E&S-7-A

SHEET 2 OF 2



liset

Temporary Aggregate Cover can be used anywhere an a construction site where a stable area is desired for construction operations, equipment storage, heavy traffic use, or any areas which could develop into a soil erosion problem, as a result of intensive activities and loss of vegetative cover.

Aggregate Cover may be used in conjunction with Gravel Access Approach (E & S-14).

Installation and Maintenances

Replace or replanish aggregate cover during construction if it is no longer preventing soil erasion.

Optional Measures:

Related SESC Measuresi

E & S-14 Grovel Access Approach

Measurement and Payments

Contract Item (Pay Item)

<u>Pay Unit</u>

Erosion Control, Aggregate Cover Erasion Control, Gravel Access Approach

Square Yord Each

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Aggregate Cover

EMIDOT

04-07-2006 PLAN DATE

E&S-8-A

SHEET 1 07 1



Benches are generally placed on long slopes to reduce runoff velocity by reducing the effective slope length,

Benches prevent sheet flow from gaining velocity and developing concentrated flows, preventing rilling and guilying.

Installiation and Maintenance:

Bench dimensions to be determined by the engineer in field to maximize effectiveness.

If sediment is being transported by sheet flow coming down the slopes, it will be deposited on the benched area and not transported to the toe of slope or aff-site. Sediment can then be removed or stabilized in place by the use of seed, fertilizer and mulch.

Optional Measuresi

A Diversion Dike (E & S-10), intercepting Ditch (E & S-11), and intercepting Ditch and Diversion Dike (E & S-12) may be used at the top of slopes to minimize flow over the benched areas.

A Silt Fence (E & S-26) may be installed at the toe of slope far added protection to off-site areas,

Related SESC Measures:

- Permonent/Temporary Seading

- E & S-10 Diversion Oike
 E & S-11 Intercepting Ditch
 E & S-12 Intercepting Ditch and Diversion Dike
- E & S-26 Slit Fence

Measurement and Payments

There is no separate contract item for this E & S measure. Payment for Benches will be included in related items of work. Optional work shown, when installed and maintained as directed by the Engineer, will be pold using the ossociated contract Item listed here.

Contract Item (Pay Item)

Ditch, Intercepting Erosion Control Silt Fence Embankment, Lli Embonkment, CP

Pay Unit Stotion Foot Cubic Yord Cubic Yard


MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Benches

EMDOT

04-07-2008 PLAN DATE

E&S-9-A



Refer to the Droinage Manual for additional design considerations when specifying this device.

A Diversion Dike is a temporary or permanent ridge of compacted earth constructed across slaping land, on a predetermined grade, to protect work areas or sensitive areas from upslope runoff by diverting flow away from the site to an oppropriate outlet. The Diversion Dike shall be stabilized.

Installation and Maintenance:

This practice is best utilized in construction oreas where runoff can be diverted and properly outletted to control erosion, sedimentation or flood damage. Specific locations and conditions may include:

- Above disturbed slopes to prevent runoffs over the slope;
- Across unprotected slopes or at slope breaks to reduce slope length;
- Below slopes to divert excess runoff to stobilized outlets:
- Diversion of sediment-loden water to sediment trops;
- At or near the perimeter of the construction area to keep sediment from leaving the site;

Optional Measures:

Related SESC Measures:

- E & S-11 Intercepting Ditch
- E & S-12 Intercepting Ditch and Diversion Dike E & S-13 Grove) Filter Berm
- E & 5-13 Grovel Filter berm
 E & 5-15 Stope Drain Surface
 E & 5-20 Sediment Trap
- E & S-37 Check Dom

Measurement and Payment:

There is no separate contract item for this E & S measure. Payment for Diversion Dika will be included in related Items of work. Optional work shown, when installed and maintained as directed by the Engineer, will be poid using the associated contract Items listed here.

Contract Item (Pay Item)

<u>Pay Unit</u>

Embonkment, LM

Embonkment, CIP

Cubic Yard Cubic Yard

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Diversion Dike

MDOT

04-07-2008 PLAN DATE

E&S-10-A

SHERT 1 OF 1



Usea

Refer to the Drainage Manual for additional design considerations when specifying this device.

An intercepting Ditch is a long, narrow ditch excevated into the earth on the upslape or downslope side of a drainage area. It is used to intercept storm runoff and divert it to a safe outlet location where sediment can be removed by reducing water velocity.

installation and Maintenance:

This practice is best utilized in construction areas where runoff can be diverted to cantrol erosion, sedimentation or flood damage. Specific locations and conditions may include:

- Above disturbed slopes to prevent runoff over the slope;
- Across unprotected slopes or at slope bracks to reduce the slope langth;
 Below slapes to divert excess runoff to stabilized outlets;
- Diversion of sediment-laden water to sediment traps:
- At or near the perimeter of the construction area to keep sediment from leaving the site:

If the intercepting Ditch (E & S-11) is used as a temporory measure on multi-year projects or remains as a permanent device, exposed areas shall be stabilized throughout the limits of the ditch.

Optional Measures:

Check Dam &E & S-37) and Sediment Irap (E & S-20) may be installed at upstream end of ditch, if Ditch is discharging water containing sediments, discharge to Sediment Trap (E & S-20) or Sediment Basin (E & S-21).

Related SESC Measures:

- £ & 5-3 Permanent/ Temporary Seeding
- E & S-10 Diversion Dike
- E & S-12 Intercapting Ditch and Diversion Dike
 E & S-13 Grovel Filter Berm
 E & S-15 Slope Droin Surface
 E & S-20 Sediment Frap
 E & S-21 Sediment Bosin

- E & S-27 Plastic Sheets or Geotextlie Cover E & S-33 Mulch Blankets and High Velocity Mulch Blankets
- E & S-37 Check Dam

Measurement and Payments

Optional work shown, when installed and maintained as directed by the Engineer, will be paid using the associated contract Item listed here. Stabilizing expased stapes for permanent application of this measure will be included in project quantities


tot planted world	
Contract Item (Pay Item)	Pay Unit
Ditch, Intercepting Erosion Control, Check Bom, Stone	Station Foot
Erosian Control, Sediment Trap	Each
Erosian Control, Sediment Basin	Each
Erosian Cantro I, Maintenance,	
Sødimant Removol	Cubic Yard

MICHICAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Intercepting Ditch

EMIDO

04-07-2006 E&S-11-A PLAN DATE



Uses

Refer to the Drainage Manual for additional design considerations when specifying this device.

An intercepting Ditch and Diversion Dike is used to intercept storm runoff by diverting it to safe outlet areas where sediments can be removed by reducing the water velocity. The ditch is excovated into the earth at the upslope or downslope side of a drainage area. The dike is created and stabilized immediately downslope of the newly created altch.

This measure is best installed in construction areas where Hunoff can be diverted to control erosion, sedimentation or flood domage. Specific locations and conditions may include:

- Abovo disturbed slopes to prevent runoff over the slope;
- Across unprotected slopes or of slope breaks to reduce slope length;
- Below slopes to divert excess runoff to stabilized outlets;
- Diversion of sediment-loden water to sediment trops;
- At or near the perimeter of the construction area to keep sediment from leaving the site;

If the intercepting Ditch and Diversion Dike is used as a temporary measure on multi- year projects or remains as a permanent device, exposed areas shall be stabilized throughout the limits of the ditch.

If the Engineer determines that excavated soil is suitable, it may be placed and compacted on the downhill side of the ditch to create the dike.

Dotlono: Measures:

Check Dam IE & S-37) and Sediment Trap (E & S-20) may be required at upstream end of ditch. If ditch is discharging water containing sediment, discharge to Sediment Trap (E & S-20) or Sediment Bosin (E & S-21),

Related SESC Measures:

E & S-3 Permanent/Temporary Seeding

E & S-10 Diversion Dike

E & S-11 Intercepting Ditch E & S-15 Stape Drain Surface

£ & 5-20 Sediment Trop £ & 5-31 Mulch Blankets and High Velocity Mulch Blankets

E & S-37 Check Dom

Measurement and Payments

Optional work shown, when installed and maintoined as directed by the Engineer, will be paid using the associated contract Item listed here. Stobilizing exposed slopes for permonent application of this measure will be included in project quantities for similar work. Additional material and work required to construct the Diversion Dike will be poid as Embankment.

Contract Item (Pay Item)

Embonkment, CP

Erosion Control, Check Dom, Stone Erasion Control, Sediment Trop Ditch, Intercepting Embankment, LM

<u>Pay Unit</u> Foot Each


Station Cubic Yard Cubic Yard MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Intercepting Ditch and Diversion Dike

EMDOT

04-07-2006 PLAN DATE

E&S-12-A



Uses

Refer to the Drainage Manual far additional considerations when specifying this device.

A Grayet Filter Berm is a temporary structure to be placed wherever water flaw requires filtering before leaving a construction site.

Gravel Filter Berm shott not be used in Neu of a Check Dom (E & 5-37). Check Doms may provide some filtration, but the primary function is to dissipote energy to allow particle settlement.

Installation and Maintenance:

This device may require periodic maintenance to ensure adequate filtration.

Lorger stone may be used as coorse aggregate to provide stable berm on steep slopes.

Related SESC Measures:

E & S-18 Dewatering with Filter Bog E & S-20 Sediment Trap

Measurement and Payments

Payment for Gravet Filter Berm Includes larger stone use to stabilize berm.

Contract Item (Pay Item)

Pay Unit

Erosian Cantrol, Grovel Fliter Berm

Faot

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Gravel Filter Berm

EMDOT

04-07-2008 PLAN DATE

E&S-13-A

SHEET 1 DF L



Use

Providing a stable Gravel Access Approach, minimizes the tracking of loase materials from the construction site anto public roadways. Coarser aggregate is more effective in reducing tracking. Any materials tracked anto public roadways shall be removed as specified in the Standard Specifications for Construction, or as directed by the Engineer.

Installation and maintenance of Gravel Access Approach is effective in reducing sediment laading to inlet protection devices.

Installation and Maintenance:

The Gravel Access Approach should be located in accordance with the pions or as directed by the Engineer. All vegetation and other objectionable material shall be ramoved from the foundation area. Geotextile Separator must be placed beneath the aggregate to stabilize the foundation.

Replace or replanish aggregate if it is no longer preventing tracking.

Dottonal Measures

A Gravel Access with Diversion Ridge is recommended where access grade exceeds 2%, This will also old in dislodging soil or debris from tires.

Related SESC Measures:

Measurement and Payments

Optional work shown, when installed and maintained as directed by the Engineer, will be included in the Item Gravel Access Approach

<u>Contract (tem (Poy Item)</u>

<u>Pay Unit</u>

Erosion Control, Grovel Access Approach Each


MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Gravel Access Approach

EMDOT

04-07-2005 PLAN DATE

E&S-14-A



Usex

Refer to the Oralnoge Manual for additional design considerations when specifying this device.

Slape Drain Surface is a temporary device intended to corry water down slape in a controlled manner, to prevent slope erosion and subsequent sedimentation.

Installation and Maintenance:

The pipe shall be secured to prevent movement. The material used to secure the pipe shall be approved by the Engineer. Place the Slape Drain Surface on undisturbed soil or well compacted fill. It is important to properly size the pipe and stabilize the outlet of these devices.

Material to be recommended or approved by the Engineer.

Optional Measures:

A Slape Broin Surface pipe may be used in conjunction with a intercapting Ditch and Diversion Dike (E & 5-10, 11, and 12),

A Grovel Filter Berm (E & 5-13) may be used prior to entering the conduit when a bridge deck is undergoing hydrodemolition.

Related SESC Measures:

- E & S-7 Riprop E & S-10 Diversion Dike
- E & S-11 Intercepting Ditch
- E & S-12 Intercepting Ditch and Diversion Dike
 E & S-19 Energy Obsolpators
 E & S-24 Sand and Stone Bags
 E & S-26 Stit Fence

Measurement and Payments

There is no separate contract item for this E & S measure, Payment for Slope Drain Surface will be included in related items of work. Optional work shown, when installed and maintained as directed by the Engineer, will be paid using the associated contract Item listed here.

Contract Item (Pay Item)	<u>Pay Unit</u>
Riprop, Pioin	Square Yord
Riprop, Plain, LM	Cubic Yord
Erosion Control, Gravet Filter Berm	Foot
Enosion Control, Sand Bag	Eoch
Enosion Control Stone Bag	Eoch

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Slope Drain Surface

EMDO

04-07-2006 PLAN DATE

E&S-15-A

SHEET I OF I



Treas, shrubs, and some selected grasses and legumes can provide low maintenance, long-term erasion protection. These plants may be particularly useful where site aesthetics are important. There are many different species of plants to choose from and care must be taken in their selection. Assistance in selecting proper types of vegetation can be obtained from the Roadside Development Unit of the Design Support Area, or the Region Resource Specialist.

Woody plants are particularly adaptable for use on steep or rocky slopes where maintenance is difficult. They provide long-term erosion protection to slapes, including steep slopes (1 on 3 or greater).

Installiation and Maintenance:

Planting trees, shrubs and evergreens

Specific planting requirements are os follows:

- 1. Dig plant packet for deciduous and evergreen trees a minimum of 36 wider and 6 deeper than root ball unless otherwise specified.
- Dig plant packet for shrubs a minimum of 12 wider and 6 deeper than the root ball unless otherwise specified,
- 3. Loosen subsolt to a depth of 4. Loosen earth on sides of plant packet to break any glazing caused by digging,
 4. Set plant at the same or slightly higher depth than that at the nursery,
 5. Fill prepared soil 1/2 the depth of the root boll, pack firmly and puddle with water.
 6. Loosen and remove burlap and all lacing from upper half of the root ball.

- 7. Backfill remaining plant packet with prepared soil and pack firmly, After compaction, the disturbed area should be flush with the surrounding ground.
- 8. Cover entire plant packet area with 2 to 4 inches of mulch Prune, wrap, brace and guy as specified.

Optional Measures:

Related SESC Measures:

- E & S-3 Permonent/Temporary Speding
- E & S-28 Mulching and Mulch Anchoring
- E & S-33 Mulch Blonkets and High Velocity Mulch Blonkets

Measurement and Payments

Contract Item (Pay Item) (Botanica i Name)

Pay Unit Each

Refer to plans or contract documents for specific Items as determined by the Roadside Development Unit of the Dasign Support Area Refer to section 815 of the Standard Specifications for Construction for requirements for site preparation, watering and cultivating.

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Trees, Shrubs, and Perennials

CMDOT

09-30-2005 PLAN DATE

E&S-16-A

SHEET 2 OF 2



Usa

Refer to the Drainage Manual for additional design considerations when specifying this device.

A Pipe Drop is an effective way to allow water to drop or flow very rapidly down elevation without causing erosion and sedimentation to the down slope area, in addition, they function effectively as a sediment trap. A Pipe Drop is generally a permanent soil erosion and sadimentation control device.

Installation and Maintenance:

The size of the riser and outlet pipes shall be approved by the Engineer. If high outlet velocities are anticipated, the size and quantity of Riprop will also be determined by the Engineer. Energy Dissipators (E. & S-19) may be required.

This device will require consultation with the Hydroulic/Hydrology Unit of the Design Support Area prior to specifying on the plans.

Optional Measures:

Energy Dissipators (E & S-19) may be required. For additional Energy Dissipators reference Standard Plan R-85 Series (outlet headwalls with baffles).

Installation of Trash Rack is optional for temporary Pipe Drop.

Related SESC Measures:

E & S-7 Riprop

E & 5-19 Energy Dissipotors

Measurement and Payment:

Pipe Drop requires includen of the appropriate Special Pravision in the contract documents. Payment includes furnishing and installing Trash Rack, when specified, and stabilization of all disturbed area.

Refer to Special Provision for additional details.

Cantract Item (Pay Item)

<u>Pay Unit</u>

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Pipe Drop

MDOT

04-07-2006 PLAN DATE

E&S-17-A

SHEET



U561

Dewotering aperations may utilize a filter Bog located a sufficient distance from the watercourse or wetland to allow for proper settling or filtering through natural vegetation.

Installation and Maintenance:

The filter Bag must be of adequate size or the pumping rate must be reduced to still the water for a sufficient time to allow particles to settle.

When Dewatering with a Filter Bag on a barge, care sholl be taken during the removal of the Filter Bag to ensure that sediment does not enter the watercourse.

Optional Measures:

Installation of a Gravel Filter Barm (E & S-13) may be required to provide additional sediment ramoval Placement of a Sadiment Bosin (E & S-21) may be required if the water returning to the streams or wetland area remains turbid.

Related SESC Measuress

- E & S-13 Gravel Filter Berm
- E & S-20 Sediment Trop
- E & S-21 Sediment Basin
- E & S-34 Cofferdam
 E & S-36 Construction Dam

Measurement and Payments

Dewatering and associated £ & S measures are generally not paid for separately but are included in related items of work. When a filter Bag is used to aid in removing sediment, it will be paid for separately. Optional work shown, when installed and maintained as directed by the Engineer, will be paid using the associated contract items listed here unless otherwise specified.

Contract Item (Pay Item)

Erasion Control, Sediment Basin
Erosion Control, Maintenance, Sediment Removal
Erosion Control, Cravel Filter Berm
Erasion Control, Filter Bag

Eoch

PERMITS FROM THE MICHIGAN DEPARTMENT OF ENVIRONMENTAL OUALITY MAY BE REQUIRED.


MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Dewatering with Filter Bag

EMDOI

04-07-2006 PLAN DATE

E&S-18-A



Refer to the Drainage Manual for additional design considerations when specifying this device.

Energy Dissipotors must be designed by a Hydraulic Engineer. The Hydraulic Engineer will determine the outlet velocities and the size and type of the structural device.

Energy Dissipators are structures used to control erosion at the outlet of a channel or conduit. Energy Dissipators raduce the velocity of flow and dissipate the energy. This practice applies where the discharge velocity of a pipe, box autvert, diversion, open channel or other water conveyance structure exceeds the erodible velocity of the receiving channel or disposal area.

Energy Dissipators are generally not required ar recommended on natural watercourses since atream crossing structures must be designed without excessive stream velocities or potentially damaging back water.

Riprop (E & S-7) stilling basins or plunge pools work well and rapidly reduce flow velocity. They should be considered In lieu of concrete oprons or other rigid structures.

For other Energy Dissipator details, reference Standard Plan R-85 Series lautlet headwalls with bafflesk

Installiation and Maintenance:

follow manufacturer's recommendations and contract documents for installation and maintenance of prefabricated or site built Energy Dissipators.

Cotional Measuress

Reliated SESC Measures:

E & S-7 Riprap

Measurement and Payments

Unless otherwise specified, there is no separate Pay Item for this E & S measure.

Riprap may be included as a Pay Item using one of the following contract Items.

Contract Item (Pay Item) Riprap, Heavy

<u>Poy Unit</u>

Riprop, Heavy, LM

Square Yard

Riprap, Plain

Cubic Yard

Riprop, Pioln, LN

Square Yord Cubic Yard

Riprop, Crouted

Square Yard

Note: Gradations and dimensions of Riprop may be

modified by Special Provision

PERMITS FROM THE MICHIGAN DEPARTMENT OF

ENVIRONMENTAL QUALITY MAY BE REQUIRED.

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Energy Dissipators

MDOT

04-07-2008 PLAN DATE

E&S-19-A

SHEET



Refer to the Drainage Manual for additional design considerations when specifying this device.

Foot

A Sediment Trap can be used in any area where concentrated flow would result in the transport of sediments off site into a body of water or wetland area. A Sediment Trap is an effective device used to settle out sand sized particles and larger. The size of a Sediment Trap is 5 cubic yords or less.

Installation and Maintenance:

Sediment Trap dimensions are highly variable as required by project site conditions. Sediment should be removed and the Sediment Trap restored to its original design when the sediment has occumulated up to approximately 50 parcent of its copacity.

Optional Measures:

A Check Dam (E & S-37) may be used in conjunction with the Sediement Trop. The Check Dam should be located immediately down slope of the Sediment Trop. Multiple trops may be required, as recommended by the Engineer.

Related SESC Measuresi

E & S-37 Check Dom

Measurement and Payments

Optional work shown, when installed and maintained as directed by the Engineer, will be paid using the associated contract Item listed here.

Contract Item (Pay Item) <u>Pay Unit</u> Eroslan Cantrol, Sedlment Trap Each Erosian Contral, Maintenance, Sediment Removal Cubic Yord

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Sediment Trap

PERMITS FROM THE MICHIGAN DEPARTMENT OF ENVIRONMENTAL QUALITY MAY BE RECURRED.


Eroslan Control, Check Dam, Stone

EMDOT

04-07-2008 PLAN DATE

E&S-20-A

SHEET I OF 1



lise:

Refer to the Droinage Manual for additional design considerations when specifying this device.

A Sediment Basin should be used as a lost effort to collect sediments. Whenever possible, sediments shall be prevented from reaching the ditch (or watercourse if basin is permitted) by the use of Construction Dom (E & S-36), Cofferdom (E & S-34), Gravel Filter Berm (E& S-13), Sediment Trap (E & S-20), Slit Fence (E & S-26), Temporory Byposs Channel (E & S-35), Dewatering with Filter Bag (E & S-18), or Diversion Dike (E & S-10), intercepting Ditch (E & S-11), or Intercepting Ditch and Diversion Dike (E & S-12). These devices will isolate the construction activity from the ditch (or watercourse if permitted).

NOTE: Sediment Basins are allowed in streoms by permit only.

Installation and Maintenance:

A Sediment Basin is an effective device used to settle out sand sized particles and larger. Sediment Basin is greater than 5 cubic yards.

The width of the Sediment Bosin should not extend beyond the ditch sippe. The length of the Sediment Bosin should be approximately four times greater than the stream width.

The Basin must be periodically cleaned when it reaches approximately 50 percent of its capacity under the pay item Erosian Control, Maintenance, Sediment Removal. Upon stabilization of the construction area, the basin shall receive a final cleaning and the Check Dom removed.

Optional Measures:

A Check Dom (E & S-37), may be used and shall be lacated immediately downslope of the Sediment Basin.

A Grave/Filter Berm (E & S-13) may be installed downslope of the Sediment Bosin and Check Dom to provide additional sediment removal.

Raioted SESC Measures:

- E & S-10 E & S-11 Diversion Dike
- Intercepting Ditch Intercepting Ditch and Diversion Dike Gravel Filter Berm E & S-12
- & 5-13
- E & S-18 Dewatering with Fliter Bag
- E & S-20 Sediment Trap
- E & S-24 E & S-26 Sond and Stone Bags
- Silt Fence
- E & S-34 E & S-35 Cofferdam
- Temporory Bypass Channel
- E & 5-36 Construction Dom
- E & S-37 Chack Dom

Measurement and Payments

Optional work shown, when installed and maintained as directed by the Engineer, will be poid using the associated contract Item listed here.

Contract Item (Pay Item)	<u>Pay Unit</u>
Erosion Control, Sediment Basin	Cubic Yord
Erosion Control, Maintenance, Sediment Removal	Cubic Yard
Erosion Control Check Dom, Stone	Foot
Frasion Control Gravel Filter Berm	Foot

PERMITS FROM THE MICHIGAN DEPARTMENT OF ENVIRONMENTAL QUALITY WILL BE REQUIRED.

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Sediment Basin

EMDOT

04-07-2006 PLAN DATE

E&S-21-A

SHEET 2 OF 2



itse:

Vegetative Buffer at Watercourse is used along the top of slopes to filter sediment from runoff, Vegetative Buffer is also used during ditch clean out operations.

installation and Maintenance:

Silt Fence, if used, should be placed down slope and immediately adjacent to the Vegetative Buffer at Watercaurse to ensure that sediments do not migrate into the watercourse or wetland. If clearing and grubbing is necessary up to the waters edge, the clearing adjacent to the watercourse should be done after the up-slope area is adequately stabilized to prevent erosion and subsequent siltation.

Optional Measuresi

A Silt Fence (E &S-26) or Diversion Dike (E & S-10), intercepting Ditch (E & S-11) or intercepting Ditch and Diversion Dike (E & S-12) can also be used at the top of the graded area to prevent runoff from flowing down the ray slape,

Related SESC Measures:

- E & S-2 Grubbing Omltted
- E & S-3 Permanent/Temporary Seeding
- E & 5-10 Diversion Dike
- E & S-11 Intercepting Ditch
- E & 5-12 Intercepting Ditch and Diversion Dike
- E & 5-26 Sill Fence

Measurement and Payments

There is no separate contract Item for this E & S measure. Payment for Vegetative Buffer at Watercaurse will be included in related Items of work. Optional work shown, when installed and maintained as directed by the Engineer, will be paid using the associated contract Item listed here.

Contract Item (Pay Item)

<u>Pay Unit</u>

Erosian Control, Silt Fence

Faot


MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Vegetative Buffer at Watercourse

EMDOT

04-D7-2006 PLAN DATE

E&S-22-A



Refer to the Drainage Manual for additional design considerations when specifying this device.

When a Stream Relocation is specified it shall be designed by an Engineer. Certain habitat structures may be incorporated into its design to mitigate for habitat impacts. These structures include, but are not limited to, rack weirs, plumbs, and others as specified by the Michigan Department of Environmental Quality (MDEQ) Permit Provisions. This dovice requires consultation with the Hydroulics/Hydrology Unit of the Design Support Area prior to specifying on the pions.

Installation and Maintenance:

Example of Construction Sequence and Controls:

- Excevate new stream leaving an earthen plug at the upstream and downstream ends.
- Dewoter new stream in accordance with Dewatering with Filter Bag IE & S-18).
 Install structures if required by MDEO Permit Provisions and plans.
 Place Ceatextile Blanket over the entire stream bed and banks,

- Place Stream Bed Protection.
- Stabilize all disturbed areas.
- When the streom is stable, remove the downstream plug, then remove the upstreom plug. Create a plug at the upstreom and downstream end of the old channel and backfill old channel.
- Stabilize bockfill oreos.

Optional Measures:

Downstering with Filter Bag (E & S-18) may be required where vegetated area is not available for filtering.

Related SESC Measures:

- E & S-3 E & S-7 Permonent/Temporary Seeding
- Riprop
- E & S-18 Dewatering with Filter Bog
- Mutching and Mutch Anchoring
- E & S-33 Nulch Blankets and High Yelocity Mulch Blankets
- E & 5-37 Check Dom

Measurement and Payments

Streom Relocation, including optional work shown, when installed and maintained as directed by the Engineer, will be paid using the associated contract Item listed here.

Contract Item (Pay Item)

Pay Unit

Each

Excavation, Channal Riprop, Heavy Riprop, Heavy, LM

Cubic Yord Square Yard Cubic Yord

Riprop, Special Eroslon Control, Streembed Protection

By Special Provision By Special Provision MICHIGAN DEPARTMENT OF TRANSPORTATION
BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Erosion Contral, Filter Bag PERMITS FROM THE MICHICAN DEPARTMENT OF ENVIRONMENTAL QUALITY WILL BE REQUIRED.


Stream Relocation


MDOT

04-07-2006 PLAN DATE

E&S-23-A

SHERT 1 OF 1





Either Sond or Stone Bogs used as headwall on temporary culvert crossing

Sond and Stone Bags are a useful tool in the prevention of erosion and subsequent sedimentation Sand Bags can be used to divert water around a construction area or create a Construction Dam (E & S-36) to offerd a stack water area or dry construction site,

Stone Bags also work well as temporary Check Dam. Sand or Stone Bags may be used as temporary Culvert

Sand and Stone Bags should never be used as a filtering device since they do not allow for adequate movement of water and are subject to failure.

Installation and Maintenances

Layers of stone or sand bags should be staggered and placed tightly together. Bottom layer of bags should be trenched in.

Optional Measures:

Related SESC Measures:

E & S-10 Diversion Dike

E & S-23 Streom Relocation E & S-35 Temporary Byposs Channel E & S-36 Construction Dam

Measurement and Payments

Contract Item (Pay Item)

Pay Unit

Erosion Control, Sond Bog Erosion Cantrol, Stone Bag Eoch Each

PERMITS FROM THE MICHIGAN DEPARTMENT OF ENVIRONMENTAL QUALITY MAY BE REQUIRED.


MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Sand and Stone Bags

EMIDO1

04-07-2006 PLAN DATE

E&S-24-A



Use:

A Sand Fence is made of wood or plastic and is installed perpendicular to the prevailing wind. The fence traps blowing sand by reducing the wind velacity at the ground surface. Dune grass is planted to stabilize the area.

Installation and Maintenance:

These fences can be used to prevent sand from blowing anto raads or off-site areas. A Sand Fence works well for building up areas of sand where blowouts have occurred. When re-establishing a dune, a Sand Fence should be installed in spring or early summer, install a windward Sand Fence parallel to the existing dune, generally perpendicular to the prevailing an-shore wind, above the ordinary high water mark. Support fencing material with sturdy pasts. Revegetation of the dune shall be in accordance with the Standard Specifications for Construction Section 818, Dune Gross Planting and the contract documents.

Optional Measures:

Additional parallel fences may be needed.

Related SESC Measures:

Measurement and Payments

Optional work shown, when installed and maintained as directed by the Enginear, will be paid using the associated contract Item listed here.

Cantract Item (Pay Item)

<u>Pay Unit</u>

Erosion Control, Sond Fence

Foot

Duna Grass Planting

Square yard

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Sand Fence and Dune Stabilization


EMDOT

09-30-2005

PLAN DATE

E&S-25-A

SHEET



Use:

A SIIT Fence is a permeable barrier erected adjacent to disturbed areas to capture sediment from sheet flow, it is mode of woven geotextile fobric which is stretched and supported by wooden posts and trenched in at the bottom.

The Silt Fence retards the movement of sediment-laden water allowing the deposition and retention of sediment.

Do not install Sitt Fence across streams or ditches where flows are concentrated,

The use of a SIIt Fence should never be substituted for the application of permanent or temporary vegetative cover.

Installiation and Maintenance:

It is critical to thoroughly trench in the bottom at Silt Fence as shown to maximize its performance and to prevent failure from undercutting, overtapping or collapsing. Geotextile should extend along side and bottom of trench.

Ensure that stoble overflow outlets are available.

Remove all sediment from behind Silt Fence when it reaches approximately 50 percent of its capacity and make

Silt Fance shall remain in place and properly maintained until the disturbed area is completely stabilized.

As an extro precautionary measure when there is a steep disturbed area adjacent to a watercourse, two rows of Silt Fence may be placed.

Sond and Stone Bags (E & S-24) may be used to provide additional support for Sitt Fence, installed at cuivert extensions as shown in the detail obove

Related SESC Measures:

- E & S-2 Grubbing Omitted
- E & 5-6 Vegetative Buffer Strips
- Benches
- Sond and Stone Bags
- Mulching and Mulch Anchoring
- E & S-28 E & S-32 Surface Roughening and Scarification
- E & S-33 Mulch Blankets and High Velocity Mulch Blankets.

Measurement and Payment:

Eroslan Control, Stone Bag

Optional work shown, when installed and maintained as directed by the Engineer, will be paid using the associated contract item listed here.

Contract Item (Pay Item) <u>Pov Unit</u> Erosion Control, Silt Fence Foot Erosion Control, Maintenance, Sediment Removal Erosion Control, Sand Bag Cubic Yard Each

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Silt Fence

EMIDOT

04-07-2006 PLAN DATE

E&S-26-A

SHEET 2 OF 2



Use:

Plastic Shaets or Geotextile Cover can be used to create a finer in temporary channels or to create a temporary cover to prevent erosion from rain or wind on stockpiled materials or other small erodible areas.

Plastic Sheets or Geofextile Cover should not be used in lieu of permanent stabilization measures.

installation and Maintenance:

When used as a temporary channel liner the plastic sheeting should be laid in a manner which will minimize the number of joints. Where two pieces of plastic must be joined they shall be overlapped a minimum of 18 inches in the downstream direction. Joints should be secured with non-eradible device as approved by the Engineer.

Plastic Sheets or Geotextile Cover shall be held down by use of Sand and Stone Bogs & & S-24) or other non-eradible device approved by the Engineer.

Optional Measures:

Silt fence may be installed on one or both sides of the temporary channel as shown,

Related SESC Measures:

E & S-3 Permonent/Temporary Seeding

E & S-24 Sand and Stone Bags

E & S~26 Silt Fence

Measurement and Payments

Optional work shown, when installed and maintained as directed by the Engineer, will be paid using the associated contract item listed here.

Stone or Sand Bags used to anchor Plastic Sheets or Geotextile Cover as shown will be included in payment for Eroslan Control, Temp. Plastic Sheets/Geotextile Cover unless specified otherwise and approved by the Engineer.

Contract Item (Pay Item)

<u>Pay Unit</u>

Eroslon Control, Temp. Plastic Sheet/Geotextile Cover

Square Yard Each

Erosian Control, Sand Bag Erosian Control, Stane Bag Erosian Control, Stit Fence

Each Each Foot

Plastic Sheets or Geotextile Cover

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

PERMITS FROM THE MICHIGAN DEPARTMENT OF ENVIRONMENTAL QUALITY MAY BE REQUIRED.

EMDOT

04-07-2008 PLAN DATE

E&S-27-A

Sheet 1 of 1

Mulching and Mulch Anchoring provides erosian protection and promotes growth of vegetation. This is one of the most important, effective and economical erosion control practices available. Installation and Maintenance: The in-place mutch shall be loose ar open enough to allow some sunlight and air to penetrate to the salt. The mutch should be thick enough to shade the ground, conserve sall maisture and prevent or reduce wind and water erosion. Mulch should not be used in creas where flowing water will occur or adjacent to the shoulder of the readway, unless approved by the Engineer. Loose mutch material shall consist of any straw or marsh hay in an air-dry condition. Hay in an air-dry condition will be permitted only when straw mutch or marsh hay is unavailable. Mutch material shall be clean, undamaged and rot free, it shall be substantially free of weeds and other objectionable foreign matter, Optional Measures: ithen hay is permitted, herbicide opplication, if necessary, shall be applied as per specification. Herbicide application shall be made at the contractor's expense. Nutching and Mulch Anchoring shall be in accordance with Michigan Deportment of Transportation Standard Specifications for Construction Section 816 Turf Establishment and Standard Plan R-100 Series. Related SESC Measures: E & S-3 Permanent/Temporary Soading E & S-33 Mutch Blankets and High Velocity Nutch Blankets MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR Measurement and Payments Contract Item (Pay Item) <u>Pay Unit</u> Mutch Mutch Anchoring Square Yord Square Yord Mulching and Mulch Anchoring

EMDOT


SHEET

1 OF 1/


E&S-28-A

09-30-2005


PLAN DATE



Inlet Protection in Unpaved Area



Plan View Inlet in Curb - Payed Area Behind Curb



Crass Section Inlet in Curb - Paved or Unpaved Area Behind Curb

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Inlet Protection Fabric Drop

MDOT

04-07-2006 PLAN DATE

E&S-29-A

Use

Inlet Protection Fobric Orop is a temporary device used to prevent sediment from entering drainage structure inlets.

Installation and Maintenances

Inlet Protection Fabric Drop requires frequent maintenance to function properly,

For droinage structures not located in the curb, SIIt Fence (E & S-26) is Installed around the outside of the droinage structure. The SIIt Fence must be trenched in an all sides.

For droinage structures with covers located in the curb, a nonwoven geotextile blanket is installed between the cover and the frame of the droinage structure cover. The Geotextile Blanket must be trenched in an otherwise held in place behind the curb line.

If the inlet protection is placed prior to the installation of the cover, wire mesh shall be placed over the opening to support the Geotextile Blanket.

Care must be taken when removing fabric to prevent loss of sediment into the Inlet.

Optional Measures:

For those instances where the volume of storm water may be high, a Grovel Filter Bern (E. & S-13) may be installed in one corner of the lalet Protection Fobric Drop to enoble storm water to be filtered prior to entering the drainage structure.

Trench in fobric behind curb in unpoved oreas if this will not result in exposing undisturbed orea to accelerated erosion,

Related SESC Measures:

E & S-13 Grovel Filter Berm E & S-31 Orop Inlet Protection Sediment Trap

Measurement and Payment:

Payment for Inlet Protection Fabric Drop includes all labor and materials required to secure Geotextile Fabric as shown. Optional work shown, when installed and maintained as directed by the Engineer, will be paid using the associated contract items listed here.

Contract Item (Pay Item)

Erosion Control, Inlet Protection, Fabric Drap Erosion Control, Grave | Filter Borm Erosion Control, Sitt Fence Erosion Control, Maintenance,

Sediment Removal

<u>Pay Unit</u>

Each · Foot Foot

Cubic Yord

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Inlet Protection Fabric Drop

EMDOT

04-07-2008 PLAN DATE

E&S-29-A

SHEET 2 of 2



Use

The Inlet Protection Geotextile and Stone is a recommended sedimentation control device in poved areas and some smoll drainage areas. Espacially useful where there is no cover or inlet as in the curb inlet shown,

Installation and Maintenances

This device can be used on storm inlets at curb openings where flows ore minimal. It consists of geotextile blanket placed on tap of the structure covered with clean stone such as 34R or 6A aggregate. The Geotextile Blanket must be trenched in an otherwise held in place behind the curb line.

This method of inlet protection is opplicable at curb inlets, where pending in front of the structure is not likely to cause inconvenience or damage to adjacent structures and unprotected areas.

If the device is to be placed prior to the installation of the grate, a wire mash shall be placed over the opening to support the Geotextile Blanket and Stone.

Core must be taken when removing stane and fabric to prevent loss of sediment into the inlet.

(Intinoni Vensuresu

Trench in tabric behind curb in upaved areas if this will not result in exposing undisturbed area to accelerated erosion.

Related SESC Measures:

Measurement and Payments

Payment for Injet Protection Geotextile and Stone includes oil lobor and materials required to secure Geotextile Fabric as shown and to maintain the device as necessary.

Contract Item (Pay Item)

Erosion Control, Inlet Protection,
Gaotextile and Stane

<u>Pay Unit</u>

Each

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL POR


Inlet Protection Geotextile and Stone

EMDOT

04-07-2006 PLAN DATE

E&S-30-A

SHEET 1 of 1



HAR:

A Inlet Protection Sediment Trop is a temporary device that can be used in areas where minimal flows are anticipated.

Installation and Maintenance

At all times the inlet shall be protected with a nonwoven geatextile blanket. The nonwoven geotextile blanket shall be placed over the inlet of the structure and tucked under the grate to hold it in place.

When the sediment has accumulated to approximately 50 percent the design dopth of the trap, it should be removed and the trap restored to the original dimensions. The trap should be maintained daily as needed.

A layer of 34R aggregate may be installed over the geotextile and grate to provide additional sedimentation control. Support for the Pea Stone layer must be provided while allowing inlet to function.

Related SESC Measures:

- E & 5-3 Permonent/Temporory Seeding E & 5-29 Inlet Protection Fabric Drap
- E & S-30 Inlet Protection Geotextile and Stane

Measurement and Payments

Payment for Inlet Protection, Sediment Trop includes furnishing and placing Geotextile Blanket.

Unless otherwise specified, Class 34R aggregate placed as shown will be included in the payment for this E & S measure.

Contract Itom (Pay Item) Erosian Control, Mointenance, Sediment Removal Erosion Contol, Inlet Pratection, Sediment Trop

Pay <u>Unit</u>

Cubic Yord


Fach

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Inlet Protection Sediment Trap

EMDOT

04-07-2006 PLAN DATE E&S-31-A



Surface Raughening and Scarlfication is accomplished by placing horizontal grooves in a slope perpendicular to the direction

Installation and Maintenance:

This can be done by either disc harrowing, back blading, or running the treads of a dozer perpendicular to the

A Diversion Ditch (E & S-10), intercepting Ditch (E & S-11) and intercepting Ditch and Diversion Dika (E & S-12) may be placed at the tap of the slope to minimize the amount of runoff draining fram the undisturbed area onto the new slope,

Related SESC Measures:

- E & S-3 Permanent/Temporary Seeding E & S-10 Diversion Dike
- E & S-11 Intercepting Ditch
- E & S-12 Intercepting Oitch and Diversion Dike E & S-28 Mulching and Mulch Anchoring

Measurement and Payments

There is no separate contract item for this E & S measure. Payment for Surface Roughening and Scorification will be included in related items of work. Optional work shown, when installed and maintained as directed by the Engineer, will be poid using the associated contract item listed hero.

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Surface Roughening and Scarification

MDOT

09-30-2005 PLAN DATE

E&S-32-A

SHEET I OF 1



Uses

Refer to the Drainage Manual for additional design considerations when specifying this device.

Mulch Blankets and High Velocity Mulch Blankets provide an immediate and effective cover over raw erodible slopes and in ditch bottoms.

There are currently two types of mulch blankets acceptable for stabilizing slopes and ditch bottoms,

Mulch blankets have netting on one side and shall be used on slopes flatter than 1:2 along shoulders, ditch, and behind curbs. These mulch blankets shall be placed with the netting on top and the fibers in contact with the soil.

High velocity mulch blankets have netting on both sides and shall be used on $\frac{1}{2}$ slopes or steeper and in ditch bottoms,

Installation and Maintenances

In waterways and ditches, High Yelacity Mulch Blankets shall be placed in the direction of the flow and extend 12 inches up the slope.

On backslopes, the blankets shall be placed perpendicular to the roadbed.

On foreslopes, the first strip adjacent to the road shall be laid parallel to the road. The remainder of the strips shall be piaced either parallel or transverse to the road.

Install according to Standard Specifications for Construction and Standard Plan R-100 Series,

Optional Measures:

Related SESC Measuress

E & S-3 Permonent/Temporary Seeding E & S-28 Mulching and Mulch Anchoring

Vegsurement and Payments

Mulch Blanket, High Yelocity

Contract Item (Pay Item) Mulch Blanket


<u>Pay Unit</u> Square Yard Square Yard MICHICAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Mulch Blankets and High Velocity
Mulch Blankets

EMDOT

04-07-2006 PLAN DATE

E&S-33-A



Uses

A Cafferdam is the preferred method to isolate stream flow from a construction site when a dry work condition must exist for a prolonged period of time or in a deap water condition.

A major benefit of the Cofferdom is that it results in a minimum amount of disturbance to the stream bottom during the installation and remaval process.

Installation and Maintenance:

Cofferdams are generally constructed using steel sheet pile. Refer to section 704 of the Standard Specifications for Construction and the contract documents for additional Information on Cafferdam design and construction.

Dewater Cofferdoms in accordance with the Standard Specifications for Construction and contract documents.

Care must be taken when removing Caffordam to prevent sedimentation to the extent practicable.

Optional Measures:

Related SESC Measures:

- E & 5-13 Gravel Filter Berm E & 5-18 Dewatering with Filter Bog E & 5-21 Sediment Basin
- E & S-36 Construction Dom

Measurement and Payments

Contract Item (Pay Item)

Cofferdam

Erosion Control, Fifter Bag

Pay Unit Lump sum Each


MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Cofferdam

MDOT

04-07-2006 PLAN DATE

E&S-34-A



A Temporary Bypass Channelis used when a dry construction site is needed. The Temporary Bypass Channel must be properly sequenced and made an integral part of the construction plans.

This device requires consultation with the Hydroulics/Hydrology Unit of Design Support Area prior to specifying on the pions.

Refer to the Drainage Manual for additional design considerations when specifying this device.

The erosian control devices shown in this detail may be used only when included in the MDEO permit.

Installation and Maintenances

Example Construction Sequence and Controls

- Dredge Bypass Channel (), leaving on earthen plug at the upstream (1) and downstream (3) ends. Construct a large Sediment Bosin (6 & S-21) at the downstream limits of the Bypass Channel (2), leaving sufficient distance between the outlet of the Sediment Bosin and the stream to allow placement of a Check Dam (6 & S-37) and Gravel Filter Berm (6 & S-13). See Section A-A. Install Check Dam and Gravel Filter Bern (E & S-13).
- As directed by the Engineer, line the Temporary Byposs Channel with Plastic Sheets Œ & S-27) with joints

- As directed by the Engineer, line the Temporary Bypass Channel with Plastic Sheets & \$-27\) with joints over topping 18 inches in the downstream direction.

 Remove the Downstream Plug (3) and stabilize channel from the Check Dam to the stream using Ceatextile Blanket and a sturdy, non-eradible material such as Riprop IE & \$-7\).

 Remove the Upstream Plug (4), allowing water to pass through the Temporary Bypass Channel, install Construction Dam (6 & \$-36\) in the existing stream of the upstream end.

 Install Construction Dam (6) of the downstream end of the natural stream,

 Dewater site in accordance with Dewatering with Filter Bag IE & \$-18\).

 When construction is complete and all areas are stabilized, the removal process shall begin with the removal of the Canstruction Dam (6) at the downstream end of the natural stream.

 Remove Construction Dam (5) at the upstream end of the natural stream.

 Remove Construction Dam (5) at the upstream end of the natural stream. This will allow the stream flow to pass through the natural streambed.

 Place on earther plum at the upstream (4) and downstream (3) limits of the Temporary Bypass Channel, Stabilize
- Place on earthen plug at the upstream (4) and downstream (3) limits of the Temporory Byposs Channel. Stabilize earthen plug with Riprap.
- Backfill Temporary Byposs Channel If dewatering is necessory, reference Dewatering with Filter Bag (E & S-18).
- Stabilize all disturbed areas,

Optional Measures:

Silt Fence may be installed adjacent to existing stream and/or Bypass channelif existing vegetation is not sufficient to prevent sediment from entering watercourse.

Related SESC Measures:

- E & S-3 Permonent/Temporery Seeding
- E & S-7 Riprap
- E & S-13 Grovel Filter Berm E & S-18 Dewatering with Filter Bag
- S-21 Sedimont Bosin
- E & S-24 Sand and Stone Bags
- F & S-26 Silt Fence
- E & S-27 Plastic Sheets or Geotextile Cover E & S-28 Mulching and Mulch Ancharing
- E & S-33 Mulch Blankets and High Velocity Mulch Blankets
- E & S-36 Construction Dom E & S-37 Check Dom

Measurement and Payments

Temporary Byposs Channel, including optional work shown, when installed and maintained as directed by the Engineer, vill be poid using the associated contract item listed here.

Contract Item (Pay Item)

Excavation, Channel Eroston Control, Stone Bag Erosion Control, Sand Bag Erosian Control, Sediment Basin Erosian Control, Filter Bag Erosian Control Check Dam, Stone

Erosian Control, Maintenance, Sediment Removal Erasian Control, Silt Fence Erosion Contral, Temp Plastic Sheet/Geotextile Cover

PERHITS FROM THE MICHIGAN DEPARTMENT OF ENVIRONMENTAL QUALITY WILL BE REDUIRED.

<u>Pay Unit</u>

Cubic Yard Eoch

Each Cubic Yord Each Foot

Cubic Yord Foot Square Yard

MICHICAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Temporary Bypass Channel

MIDOT

04-07-2006 PLAN DATE

E&S-35-A

SHEET 2 OF 2



Refer to the Orainage Manual for additional design considerations when specifying this device.

A Construction Dam is used when a dry or slack water ared is necessary to isolate construction activities from the wotorcourse.

Installation and Maintenances

A Construction Dom can be created out of any non-eradible material. Sand or Stone Bags (E & 5-24) is an effective device for a Construction Dam. Steal shoet pilling, steel plates, ar concrete barriers with a geotextile membrane may olso be used to construct Construction Dams in lieu of sand and stone bogs, if allowed by the Engineer.

Prior to the removal of the Construction Dam, remove sediment and stabilize all disturbed areas.

Core must be taken when removing Construction Dam to prevent sedimentation to the extent practicable.

Optional Measures:

If dewatering is necessory to create a dry work area, all dewatering aperations may be corried out utilizing Dewatering with Filter Rag (E & S-18). Locate the filter bag a sufficient distance from the watercourse or wetland to allow for proper filtering through natural vegetation or Gravel Filter Berm (E & S-13).

Sit Fence (E & 5-26) may be installed as shown to provide additional Erosian and Sedimentation Control.

All excovated or surplus soils, including filter bags, shall be disposed of in an upland area outside any floodplain or watland areas. Excovated or surplus soils must be adequately stabilized with seed and muich or mulch blankets in sufficient quantity to prevent erosion and subsequent sedimentation to any off-site areas, floodplains, wetlands, lakes, or streams.

Related SESC Measures:

E & 5-13

E & S-18

GravelFilter Berm Dewatering with filter Bag Sand and Stone Bags Mulch Blankets and High Velocity Mulch Blankets E & S-24 E & S-33

E & S-34 Cofferdom

Measurement and Payments

Poyment for Construction Dom will be included in related Items of work. Optional work shown, when installed and maintained as directed by the Engineer, will be paid using the associated contract item listed here. Stabilizing exposed slopes for permanent application of this measure will be included in project quantities for similar work.

Contract Item (Pay Item)	Pay Unit
Erosion Control, Sond Bag	Each
Erosion Control, Stone Bag	Each
Erosion Control, Silt Fence	Faot

PERMITS FROM THE MICHIGAN DEPARTMENT OF ENVIRONMENTAL CHALITY WILL BE REQUIRED.

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR


Construction Dam

EMDOT

04-07-2008 PLAN DATE

E&S-36-A

SHEET



Refer to the Drainage Manual for additional design considerations when specifying this device.

Check Doms are often used in ditches to reduce flow velocity.

Check Dams are temporary and shall be completely removed after vegetation becomes established, or as directed by the Engineer.

installation and Maintenances

If conditions require multiple Check Dams to be placed in series, the propor spacing shall be determined based on the steepness of the ditch grade. As a general guideline, the crest elevation of the dawnstream Check Dam should be equal in elevation to the tae of the upstream Check Dam.

A notch should be formed in the top of the Check Dam to direct flow over the center of the dam and prevent erosion of the ditch slopes.

Stone size for Check Dam is per subsection 916.01 of the Standard Specifications for Construction.

Optional Measuresi

Sediment Trops (E & S-20) may be installed directly up stream of the Check Dam to Improve sediment collection.

Religited SESC Measuresi

E & S-7 Riprop E & S-20 Sediment Trop

Measurement and Payments

Optional work shows, when installed and mointained as directed by the Engineer, will be pold using the associated contract Item listed here.

Contract Item (Pay Item)
Erosion Control, Check Dom, Stone
Erasian Control, Sediment Trop
Frasion Control Maintenance.

Sediment Romovol

Poy Unit Foot

Cubic Yard

MICHIGAN DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAY DEVELOPMENT SESC DETAIL FOR

Check Dam

EMDO1

04-07-2008 PLAN DATE E&S-37-A

SHEET

APPENDIX REFERENCE INFORMATION

Activity Name: Ditch Cleanout & Check Dam Maintenance

Methods:

- 1) Ditch Clean-Out
- 2) Check Dam Maintenance

Description/Purpose: Roadside Ditch Clean-Out includes the removal and disposal of debris to ensure proper drainage. Check Dam Maintenance consists of inspecting and removing accumulated sedimentation to maintain proper functioning of permanent structures.

Activity #: 1230

Recommended Crew Size			Equipment					
5 (2 traffic regulators included)	<u>Qty</u>	<u>Code</u>	Description					
, ,	1	02/03	Pickup					
<u>Material</u>	3	04	Trucks (see table below)					
Follow SESC Manual	1	12	Flashing arrow					
	1	26	Gradall (if available) or					
Average Daily Production	1	05	Tractor/backhoe/extendahoe (alternate)					
2000 lineal feet (gradall/excavator)			<u>Optional</u>					
500 lineal feet (tractor/backhoe)	1	32	Grader					
2000 lineal feet (grader/dozer)	1	05	Bulldozer					
	1	12	Flashing Arrow					
Measurement	1	38	Loader					
Lineal Feet Cleaned	1	67	Trailer					
Calculation								
	Equip	pment may vary depending on availability and operational						
Lineal Feet Cleaned = (Total Hours ÷ 8) x ADP	need.							
			ffic and Safety policies shall be followed for					
	equipment and personnel.							
	Additional equipment and personnel will increase the cost to perform this activity.							

Recommended Work Method: Ditch Clean-Out

Caution: Check with utility companies for buried gas lines, telephone, or electric cables, etc. Call MISS DIG.

Contact your resource staff or appointed region representative if questions arise regarding storm water or soil erosion control to determine if an earth change plan, inspections, or Part 301 and Part 303 permits are required.

If required, complete MDOT forms 1126 (National Pollutant Discharge Elimination System Inspection Report) and 0408 (Work Schedule) when performing this operation (MDOT Forms Repository).

- 1. Review environmental, training, and safety precautions. Also see 1a: Notifications, 1b: Inspections, and 1c: SESC Plan below.
- 2. Establish the ditch flow line (use appropriate measuring device).
- 3. Determine the location where the water will outlet.
- 4. If spoils are left on site, remove all debris, grade properly, and prepare spoils for seeding.
- 5. If spoils cannot be left at the ditching site, find an appropriate use on the right-of-way (i.e. slope flattening behind guardrail, washout repair, or filling ruts from runoffs). Refer to Maintenance Advisory 2018-03 "Environmental Requirements for the Disposal of Surplus and Unsuitable Soils".
- 6. Remove spoils and load into trucks with minimum interference with traffic.
- 7. Avoid creating a "V" bottom ditch; a 2-foot round-bottom ditch is the minimum requirement. 3 feet or wider ditches are desirable for drainage and snow storage.
- 8. As required, dress, mulch, and seed and/or sod slopes to prevent erosion. See sections 816 and 917 of the standard specifications.

Equipment Requirements										
Cuary Sina	Round Trip Distance	Number of 04								
Crew Size	Stockpile to Dumpsite 0 - 5 miles	Trucks Needed								
5	6 - 10 miles	3								
6	11 - 15 miles	4								

Recommended Work Method: Ditch Clean Out (continued)

- 1a. Notifications: If the operation disturbs less than five acres of earth and is to restore the ditch to original grades (match inlet and outlet grades) a National Pollutant Discharge Elimination System (NPDES) Notice of Coverage (NOC) is not required. If the project disturbs five acres or more of earth and alters the original ditch grade (new outlet or inlet grade) a NOC is required. Regardless of size of earth disturbance, notification of the municipal enforcing agency (MEA) or county enforcing agency (CEA) is required.
- **1b. Inspections:** A certified storm water operator (SWO) will inspect the project after installation of the SESC measures and at the completion of the ditching operation. For ditching operations that create an earth disturbance 1 acre or greater a SWO will inspect the project once every seven days or within 24 hours of a precipitation event that results in a discharge from the right-of-way until the project is stabilized. NPDES Inspection Report (Form 1126) will be used to document these inspections. Any deficiencies or corrective actions will be recorded on the form and will be brought to the attention of the Contractor or maintenance staff performing the work. The SWO is responsible for ensuring that corrective actions are completed within the time allotted. A log of the inspections will be maintained on file for review and retained for a period of three years from the date of the inspection or the date corrective actions were complete, whichever is longer.

Non-emergency corrective actions will be completed by those doing the ditch clean out, or by others if necessary, within five calendar days. If the SWO determines that an emergency condition exists for a discharge to waters of the state, corrective actions will be completed by those doing the work within 24 hours of the inspection. Emergency conditions include sediment entering drainage structures or the waters of the state and erosion that affects the support of the roadbed or the safety of the public. Emergency action will be documented as such on Form 1126.

1c. SESC Plan: The following soil erosion and sedimentation control (SESC) procedure has been reviewed by the Michigan Department of Environment, Great Lakes and Energy (EGLE) and is approved for this activity. This procedure is intended to minimize soil erosion and off right-of-way sedimentation during ditch clean out activities. If this procedure is not followed, a site-specific SESC plan meeting the requirements of rule R323.1703, promulgated in accordance with Part 91 of Act 451, is required.

Every effort should be made to avoid off right-of-way disposal, however if spoils are taken to an off-right-of-way location, the Standard Specifications for Construction controls the disposal of the surplus material. The property owner or easement holder where the material is to be placed must obtain a SESC permit from the appropriate enforcing agency if the placement covers one acre or more or if the material is placed within 500 feet of the waters of the state. If excess materials will be transported off the right-of-way for disposal, notify the appointed maintenance representative or region resource staff prior to beginning the ditch clean out operation and request that they contact the enforcing agency to determine if a permit is required. If a permit is required, the permit must be obtained prior to beginning this work.

If the ditch slope is one percent or more, install sediment traps (E&S-20) in the ditch bottom, spaced approximately 300 feet apart (\pm 50 feet).

Maintain a vegetative buffer (E&S-6) between the lower limit of the ditch clean out operation and the outfall to the watercourse. If the vegetative buffer cannot be left in place while the disturbed area upstream stabilizes, place high velocity mulch blanket (E&S-33) on the ditch bottom a minimum of 150 feet upstream from the lower limit of the ditch clean out operation.

If the ditch carries water continuously, install a check dam (E&S-37) and sediment trap (E&S - 20) at the downstream end of the ditch.

- Begin ditching operation at the highest elevation and progress downstream.
- Remove the vegetative buffer only after the disturbed area has been stabilized. After removing the vegetative buffer, stabilize that area with high velocity mulch blanket.
- Within five days of completing the work, seed and mulch (E&S-3; E&S-28) all exposed areas resulting from the ditch cleanout activities. If the work is completed outside of the seasonal limitations for seeding, place high velocity mulch blanket over the entire disturbed area. Contact appropriate region resource staff for alternative restoration recommendations.

Recommended Work Method: Check Dam Maintenance

Contact your resource staff or appointed region representative if questions arise regarding storm water or soil erosion control and to determine if any permits are required.

- 1. Review environmental, training, and safety precautions.
- 2. Inspect check dams for piping under structure or around banks. Correct all damage. If severe erosion is evident consider other stabilization options.
- 3. Sedimentation should be removed when built up to one-half the height of the check dam. This allows water to flow through check dam properly in the event of large flows.
- 4. Spoils may be left on site. Remove all debris and grade properly.
- 5. As required, dress mulch and seed slopes and any spoils left on site to prevent erosion. See sections 816 and 917 of the standard specifications.
- 6. Inspect culverts and other structures below the check dams for damage or blockage due to displaced stones.

Michigan Department of Transportation 1126 (01/19)

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) AND SOIL EROSION AND SEDIMENTATION CONTROL (SESC)

INSPECTION REPORT

Completed form to project files — cc: Construction Field Services Division.

Page 1 of 2

FILE 108

INSTRUCTIONS:

CONTROL SECTION

INSPECTOR NAME (Please print)

- 1. Construction sites must be inspected every 7 days or within 24 hours after a precipitation event that results in a discharge from the site including weekend days regardless if the contractor is working or not.
- 2. A discharge is defined as storm water runoff that does not infiltrate into the ground and leaves the construction site or enters waters of the state after a precipitation event.
- 3. Engineering judgement must be used when determining if a discharge from the site has occurred.

ROUTE

- 4. Corrective actions must be made within 24 hours if sediment has entered waters of the state, left department right-of-way or if public safety may be compromised. Otherwise, corrective actions must be made within 5 calendar days.
- 5. Inspectors must be Certified Storm Water Operators.

JOB NUMBER

CONSTRUCTION ENGINEER OR MAINTENANCE COORDINATOR

- 6. Individuals who authorize changes to SESC measures shown on the plans must have a valid comprehensive SESC training certificate.
- 7. Inspections must continue until the site is stabilized and, if appropriate, the Notice of Termination has been submitted.

INSDECTOR

REPORT NUMBER

STORM WATER OPERATOR NO.

INSPECTION DATE

COMPREHENSIVE TRAINING NO.

8. This form must be used when documenting SESC inspections.

	(SIGNATU										
CONTRACTOR													
AMOUNT, TYPE, & DATE OF LAST PRECIPITATION RESULTING IN DISCHARGE FROM THE SITE DATE OF LAST INSPECTION													
COMPLETE THIS SECTION FOR WINTER CONSTRUCTION INSPECTIONS WEEKLY REPORTING PERIOD AVERAGE TEMPERATURE HIGH TEMPERATURE													
WEEKLY REPORT	ING PERIOD	AVERAGE TEN	MPERATURE		HIGH TEMPERATURE								
LOCATION/ STATION	TYPE OF SESC MEASURI	E INSTALL DAT		CORRECTIVE AC REQUIRED (See Instruction		NOTIFICATION DATE	COMPLETION DATE						
		ENTE	R REMARKS	S ON PAGE 2									

MDOT 1126 (01/19) Page 2 of 2


_																		 						
	REMARKS																							
														S	KET	CHE	S							
		ļ																 						
		ļ																 		 	 	 		
						-																		
		ļ	<u> </u>			ļ												 						
		ļ	ļ			<u></u>												 	 		 	 	 	
		ļ	<u> </u>		ļ	ļ												 						
						ļ												 	 	 	 	 	 	
		ļ	ļ			ļ												 						
																						: :		


SAMPLE SESC Plan (Rule 1703)

(may be hand drawn)

Example: Placement of a concrete plant between Ramp C slope stake line and Ramp C right of way Soils: Sandy loam Gradient: 0.6% XXXXXX Limits of earth change covered by this Plan Notes: May 15, 2020 Start: October 20, 2020 Finish:

- 1. Install SESC measures prior to grading the site.
- Strip sod and topsoil and stockpile as directed by the engineer.
- 3. Grade and spread gravel base on the site.
- 4. When project is complete:
 - a. Remove concrete plant, gravel base, and gravel access approach.





Key to SESC Plan Components

