

# Construction Advisory

CA 2015-11  
May 18, 2015


From Brenda O'Brien, Engineer of Construction Field Services

MDOT-Construction Field  
Services Division  
P.O. Box 30049  
Lansing, Michigan 48909  
Phone/517-322-1087  
Fax/517-322-5664  
[www.michigan.gov/mdot/](http://www.michigan.gov/mdot/)

Index: Documentation

Questions regarding this  
Construction Advisory  
should be directed to:

Jason Gutting, Construction  
Operations Engineer at  
517-636-6334 or  
[guttingj@michigan.gov](mailto:guttingj@michigan.gov)



BJO:JG

## Final Acceptance and Project Clauses for High-Tension Cable Barrier

The Special Provision for High-Tension Cable Barrier, 12SP807(F), requires corrective action for end terminal foundation movement exceeding one inch within 12 months of final cable tensioning. This requirement dictates that high-tension cable barrier projects must have delayed final acceptance. The final acceptance date must occur after the 12 month acceptance period for the barrier and after any corrective work required of the contractor. This will ensure specification compliance and allow the completion of any corrective actions.

Progress clause documentation must also take this 12 month acceptance period into account for final project completion dates. The contractor must have time to complete the required measurements and perform any corrective action that is required. It is suggested that an additional 60 days be included on these projects in addition to the 12 month period to allow for completion of corrective action.

Please share this construction advisory with local agencies and consultants within your jurisdiction as well as TSC staff.