

CHECKLIST TO DESIGNATE AREAS OF EVALUATION FOR REQUESTS FOR PROPOSAL (RFP)

	REQUISITION NUMBER	DUE DATE	TIME DUE
MDOT PROJECT MANAGER	JOB NUMBER (JN)	CONTROL SECTION (CS)	

DESCRIPTION

MDOT PROJECT MANAGER: Check all items to be included in RFP			CONSULTANT: Provide only checked items below in proposal
WHITE = REQUIRED ** = OPTIONAL Check the appropriate Tier in the box below			
<input type="checkbox"/> TIER I (\$50,000 - \$150,000)	<input type="checkbox"/> TIER II (\$150,000-\$1,000,000)	<input type="checkbox"/> TIER III (>\$1,000,000)	
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Understanding of Service **
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<i>Innovations</i>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Organizational Chart
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Qualifications of Team
Not required as part of Official RFP	Not required as part of Official RFP	<input type="checkbox"/>	Quality Assurance/Quality Control **
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Location: The percentage of work performed in Michigan will be used for all selections unless the project is for on-site inspection or survey activities, then location should be scored using the distance from the consultant office to the on-site inspection or survey activity.
N/A	N/A	<input type="checkbox"/>	Presentation **
N/A	N/A	<input type="checkbox"/>	Technical Proposal (if Presentation is required)
3 pages (MDOT Forms not counted)	7 pages (MDOT Forms not counted)	14 pages (MDOT forms not counted)	Total maximum pages for RFP not including key personnel resumes. Resumes limited to 2 pages per key staff personnel.

PROPOSAL AND BID SHEET EMAIL ADDRESS – mdot-rfp-response@michigan.gov

GENERAL INFORMATION

Any questions relative to the scope of services must be submitted by e-mail to the MDOT Project Manager. Questions must be received by the Project Manager at least five (5) working days prior to the due date and time specified above. All questions and answers will be placed on the MDOT website as soon as possible after receipt of the questions, and at least three (3) days prior to the RFP due date deadline. The names of vendors submitting questions will not be disclosed.

MDOT is an equal opportunity employer and MDOT DBE firms are encouraged to apply. The participating DBE firm, as currently certified by MDOT's Office of Equal Opportunity, shall be listed in the Proposal.

MDOT FORMS REQUIRED AS PART OF PROPOSAL SUBMISSION

5100D – Request for Proposal Cover Sheet

5100J – Consultant Data and Signature Sheet (Required for all firms performing non-prequalified services on this project.)

(These forms are not included in the proposal maximum page count.)

REQUEST FOR PROPOSAL

The Michigan Department of Transportation (MDOT) is seeking professional services for the project contained in the attached scope of services.

If your firm is interested in providing services, please indicate your interest by submitting a Proposal, Proposal/Bid Sheet or Bid Sheet as indicated below. The documents must be submitted in accordance with the latest (Consultant/Vendor Selection Guidelines for Services Contracts) **AA**

~~AAAA~~
.....

RFP SPECIFIC INFORMATION

ENGINEERING SERVICES BUREAU OF TRANSPORTATION PLANNING OTHER

THE SERVICE WAS POSTED ON THE ANTICIPATED QUARTERLY REQUESTS FOR PROPOSALS
 NO YES DATED _____ THROUGH _____

<input type="checkbox"/> Prequalified Services – See the attached Scope of Services for required Prequalification Classifications.	<input type="checkbox"/> Non-Prequalified Services – If selected, the vendor must make sure that current financial information, including labor rates, overhead computations, and financial statements, is on file with MDOT’s Office of Commission Audits. This information must be on file for the prime vendor and all sub vendors so that the contract will not be delayed. Form 5100J is required with proposal for all firms performing non-prequalified services on this project.
---	--

Qualification Based Selection - Use Consultant/Vendor Selection Guidelines.

For all Qualifications Based Selections, the selection team will review the information submitted and will select the firm considered most qualified to perform the services based on the proposals. The selected firm will be asked to prepare a priced proposal. Negotiations will be conducted with the firm selected.

For a cost plus fixed fee contract, the selected vendor must have a cost accounting system to support a cost plus fixed fee contract. This type of system has a job-order cost accounting system for the recording and accumulation of costs incurred under its contracts. Each project is assigned a job number so that costs may be segregated and accumulated in the vendor’s job-order accounting system.

Qualification Based Selection / Low Bid – Use Consultant/Vendor Selection Guidelines. See Bid Sheet instructions for additional information.

For Qualification Review/Low Bid selections, the selection team will review the proposals submitted. The vendor that has met established qualification threshold and with the lowest bid will be selected.

Best Value – Use Consultant/Vendor Selection Guidelines, See Bid Sheet Instructions below for additional information. The bid amount is a component of the total proposal score, not the determining factor of the selection.

Low Bid (no qualifications review required – no proposal required.)

BID SHEET INSTRUCTIONS

Bid Sheet(s) are located at the end of the Scope of Services. Submit bid sheet(s) with the proposal, to the email address: mdot-rfp-response@michigan.gov. Failure to comply with this procedure may result in your bid being rejected from consideration.

À

PARTNERSHIP CHARTER AGREEMENT

MDOT and ACEC created a Partnership Charter Agreement which establishes guidelines to assist MDOT and Consultants in successful partnering. Both the Consultant and MDOT Project Manager are reminded to review the [ACEC-MDOT Partnership Charter Agreement](#) and are asked to follow all communications, issues resolution and other procedures and guidance’s contained therein.

**NOTIFICATION
MANDATORY ELECTRONIC SUBMITTAL**

Proposals submitted for this project must be submitted electronically.

The following are changes to the Proposal Submittal Requirements:

- Eliminated the Following Requirements:
 - Safety Program
 - Communication Plan
 - Past Performance as *a separate section*
 - Separate section for DBE Statement of goals. Include information in Qualification of Team section

- Implemented the Following Changes:
 - All proposals require an Organization Chart
 - Resumes must be a maximum of two pages
 - Only Key (lead) staff resumes may be submitted
 - Tier III proposal reduced from 19 to 14 pages
 - Forms 5100D, 5100I, and 5100G combined – 5100D
 - Forms 5100B and 5100H combined – 5100B
 - RFP's will be posted on a weekly basis -- on Mondays

The following are Requirements for Electronic Submittals:

- Proposals must be prepared using the most current guidelines
- The proposal must be bookmarked to clearly identify the proposal sections (See Below)
- For any section not required per the RFP, the bookmark must be edited to include “N/A” after the bookmark title.
Example: Understanding of Service – N/A
- Proposals must be assembled and saved as a single PDF file
- PDF file must be 5 megabytes or smaller
- PDF file must be submitted via e-mail to MDOT-RFP-Response@michigan.gov
- MDOT's requisition number and company name must be included in the subject line of the e-mail. The PDF shall be named using the following format:
 - Requisition#XXX_Company Name.PDF
- MDOT will not accept multiple submittals
- Proposals must be *received* by MDOT on or before the due date and time specified in each RFP

If the submittals do not comply with the requirements, they may be determined unresponsive.

The Consultant's will receive an e-mail reply/notification from MDOT when the proposal is received. Please retain a copy of this e-mail as proof that the proposal was received on time. **Consultants are responsible for ensuring the MDOT receives the proposal on time.**

****Contact Contract Services Division immediately at 517-373-4680 if you do not get an auto response****

Required Bookmarking Format:

- I. Request for Proposal Cover Sheet Form 5100D
 - A. Consultant Data and Signature Sheet, Form 5100J (if applicable)
- II. Understanding of Service
 - A. Innovations
- III. Qualifications of Team
 - A. Structure of Project Team
 - 1. Role of Firms
 - 2. Role of Key Personnel
 - B. Organization Chart
 - C. Location
- IV. Quality Assurance / Quality Control Plan
- V. Resumes of Key Staff
- VI. Pricing Documents/Bid Sheet (if applicable)

2/14/12

**NOTIFICATION
E-VERIFY REQUIREMENTS**

E-Verify is an Internet based system that allows an employer, using information reported on an employee's Form I-9, Employment Eligibility Verification, to determine the eligibility of that employee to work in the United States. There is no charge to employers to use E-Verify. The E-Verify system is operated by the Department of Homeland Security (DHS) in partnership with the Social Security Administration. E-Verify is available in Spanish.

The State of Michigan is requiring, under Public Act 200 of 2012, Section 381, that as a condition of each contract or subcontract for construction, maintenance, or engineering services that the pre-qualified contractor or subcontractor agree to use the E-Verify system to verify that all persons hired during the contract term by the contractor or subcontractor are legally present and authorized to work in the United States.

Information on registration for and use of the E-Verify program can be obtained via the Internet at the DHS Web site: <http://www.dhs.gov/E-Verify>.

The documentation supporting the usage of the E-Verify system must be maintained by each consultant and be made available to MDOT upon request.

It is the responsibility of the prime consultant to include the E-Verify requirement documented in this NOTIFICATION in all tiers of subcontracts.

9/13/12

Michigan Department of Transportation

**SCOPE OF SERVICE
FOR
DESIGN SERVICES**

CONTROL SECTION(S): 82022

JOB NUMBER(S): 115863D, 115865D, and 118967D

PROJECT LOCATION:

S02 of 82022, I-94 EB over Wayne Rd. – JN 118967D
S03 of 82022, I-94 WB over Wayne Rd. – JN 115863D
S05 of 82022, I-94 EB over Middlebelt Rd. – JN 118967D
S09 of 82022, I-94 EB over Ecorse Rd. – JN 118967D
S10 of 82022, I-94 WB over Ecorse Rd. – JN 115865D
S11 of 82022, I-94 EB over Beech Daly Rd. – JN 118967D

All in Wayne County

PROJECT DESCRIPTION:

Work involved in the design of the project consists of:

S02, S03, and S09 of 82022– Capital Preventive Maintenance (CPM) work including epoxy overlay, deck patching, barrier repair, beam end repair, substructure repair, and slope paving repair.

S05 and S11 of 82022 – CPM work including epoxy overlay and joint replacement.

S10 of 82022 – Bridge replacement and approach work.

Load rating of S10 and S11 of 82022.

The link to the as-built plans available on the FTP site is as follows:

<ftp://ftpm.dot.state.mi.us/82022-115863,115865,118967/As-built%20plans/>

ANTICIPATED SERVICE START DATE: 1/4/16

ANTICIPATED SERVICE COMPLETION DATE: 1/5/18

DBE PARTICIPATION REQUIREMENT:

5%

PRIMARY PREQUALIFICATION CLASSIFICATION(S):

Design - Bridges

SECONDARY PREQUALIFICATION CLASSIFICATION(S):

Design – Geotechnical: Advanced
Design – Bridges: Load Rating
Design – Hydraulics I
Design – Roadway
Design – Utilities: Municipal (**precautionary**)
Design – Utilities: Roadway Lighting
Design – Traffic: Capacity & Geometric Analysis
Design – Traffic: Pavement Markings
Design – Traffic: Safety Studies
Design – Traffic: Signal (**precautionary**)
Design – Traffic: Signal Operations (**precautionary**)
Design – Traffic: Signing – Freeway
Design – Traffic: Work Zone Maintenance of Traffic
Design – Traffic: Work Zone Mobility & Safety
Surveying: Road Design
Surveying: Structure
Environmental: Contamination

PREFERRED QUALIFICATIONS AND CRITERIA (FOR NON-CLASSIFIED SERVICES):

1) UTILITY COORDINATION

The Consultant and MDOT shall share responsibilities for project Utility Coordination.
See attached “Scope of Services for Utility Coordination”.

MDOT PROJECT ENGINEER MANAGER:

James Ranger, P.E., Lansing Bridge Project Manager
Van Wagoner Building
425 W. Ottawa
Lansing, MI 48909
(517)373-0737
rangerj@michigan.gov

CONSTRUCTION COST:

A. The estimated cost of construction is:

1.	Approaches and Maintaining Traffic	\$ 395,000
2.	Geometric Improvement	\$
3.	Environmental	\$
4.	Drainage	\$
5.	Safety	\$
6.	Non-Motorized	\$
7.	Bridge Cost	
	S02 of 82022	\$ 83,000
	S03 of 82022	\$ 202,000
	S05 of 82022	\$ 244,000
	S09 of 82022	\$ 331,000
	S10 of 82022	\$4,754,000
	S11 of 82022	\$ 173,000

CONSTRUCTION TOTAL **\$ 6,182,000**

B. The estimated cost of real estate is: \$

The above construction total is the amount of funding programmed for this project. The Consultant is expected to design the project within the programmed amount.

If at any time the estimated cost of construction varies by more than 5% of the current programmed amount, then the Consultant will be required to submit a letter to the MDOT Project Manager justifying the changes in the construction cost estimate.

REQUIRED MDOT GUIDELINES AND STANDARDS:

Work shall conform to current MDOT, FHWA, and AASHTO practices, guidelines, policies, and standards (i.e., Road Design Manual, Standard Plans, Published MDOT Design Advisories, Drainage Manual, Roadside Design Guide, A Policy on Geometric Design of Highways and Streets, Michigan Manual of Uniform Traffic Control Devices, etc.).

The Consultant is required to use the MDOT Current Version of Bentley Microstation/GEOPAK or PowerGEOPAK (published at Section 2.2.2 of the Design Submittal Requirements) with the current MDOT workspace (published at Section 2.2.1 of the Design Submittal Requirements). 3D Models are required for all applicable projects. See Chapter 2 of the Design Submittal Requirements for a complete listing of applicable projects. The consultant shall comply with all MDOT CADD standards and file naming conventions.

MDOT RESPONSIBILITIES:

- A. Schedule and/or conduct the following:
 - 1. Project related meetings
 - 2. The Plan Review
 - 3. Omissions/Errors/Check
 - 4. Final Trnsport item cost estimates
- B. Furnish pertinent reference materials.
- C. Furnish prints of an example of a similar project and old plans of the area, if available.
- D. Obtain all permits for the project as outlined in previous section.
- E. Furnish FTP site for software download and instructions for the MDOT Stand Alone Proposal Estimator's Worksheet (SAPW).

CONSULTANT RESPONSIBILITIES:

Complete the design of this project including, but not limited to the following:

The Consultant must adhere to all applicable OSHA and MIOSHA safety standards, including the appropriate traffic signs for the activities and conditions for this job and perform field operations in accordance with the Department's Personal Protective Equipment (PPE) policy as stated in the MDOT Guidance Document #10118.

Meet with the MDOT Project Manager to review project, location of data sources and contact persons, and review relevant MDOT operations. The Consultant shall review and clarify project issues, data needs and availability, and the sequence of events and team meetings that are essential to complete the design by the project plan completion date. Attention shall be given to critical target dates that may require a large lead time, such as geotechnical requirements, Railroad coordination requirements, utility conflict resolution, local agency meetings, etc.

- A. Perform and Prepare soils investigations. The Consultant will be responsible for compiling and preparing the investigation results into report format for the project design and construction information to be developed.

The Consultant will be responsible for obtaining any necessary permits to perform this work within MDOT ROW and abide by working hour restrictions and use proper signing per TSC traffic engineer. This includes providing all Traffic Control Devices and Flaggers when needed.

Bridge borings will be needed at the substructure units as defined in P/PMS task 3530 and in accordance with MDOT's Geotechnical Investigations and Analysis Requirements for Structures and current AASHTO LRFD Design Methodologies.

- B. Perform design surveys. (See Attachment A).

- C. Prepare required plans, typical cross-sections, details, and specifications required for design and construction.
- D. Compute and verify all plan quantities.
- E. Prepare staging plans and special provisions for maintaining traffic during construction. As part of the Maintaining Traffic, conduct a comprehensive mobility analysis and investigate alternative maintenance of traffic schemes. If the threshold criteria contained in MDOT's Work Zone Safety and Mobility Policy are exceeded, mitigation measures shall be analyzed and recommended. The consultant shall prepare a Transportation Management Plan per the Work Zone Safety and Mobility Manual which shall include a Temporary Traffic Control Plan, a Transportation Operations Plan and a Public Information Plan. The Consultant shall submit these items prior to the OEC submittal.
- F. Provide solutions to any unique problems that may arise during the design of this project.
- G. The Consultant may be required to provide Design Services during the construction phase of this project. If Construction Assistance is required, then a separate authorization for those services will be issued.
- H. Maintain a Design Project Record in ProjectWise, which includes a history of significant events (changes, comments, etc.) which influenced the development of the plans, dates of submittals and receipt of information.
- I. The Consultant shall prepare and submit in ProjectWise (in PDF format) a CPM network for the construction of this project.
- J. The Consultant representative shall record the minutes and submit in ProjectWise (in PDF format), for all project related meetings to the MDOT Project Manager within two weeks of the meeting. The Consultant shall also distribute the minutes to all meeting attendees. MDOT will provide and distribute official meeting minutes for The Plan Review Meeting.
- K. The Consultant will provide to MDOT, by entering into MDOT ProjectWise at the scheduled submittal dates, electronic documents (in PDF format) of the required specifications and plan set materials for distribution by MDOT for all reviews for this project.
- L. Prepare and submit electronically (native format or PDF) into MDOT ProjectWise, any information, calculations, hydraulic studies, or drawings required by MDOT for acquiring any permit (ie. NPDES, DEQ, etc), approvals (i.e. county drain commission) and related mitigation. MDOT will submit permit requests.

- M. If excavation is required, submit the excavation locations which may contain contamination. Project Manager then can proceed in requesting a Project Area Contamination Survey (PACS).). If the PACS report identifies areas of potential contamination, a Preliminary Site Investigation should be completed.
- N. Attend any project-related meetings as directed by the MDOT Project Manager.
- O. Attend information meetings (i.e., public hearings, open houses, etc.) with the public and public officials to assist in responding to concerns and questions. May require the preparation of displays such as maps, marked-up plans, etc.
- P. The MDOT Project Manager shall be the official MDOT contact person for the Consultant **and shall be made aware of all communications regarding this project**. The Consultant must either address or send a copy of all correspondence to the MDOT Project Manager. This includes all Subcontractor correspondence and verbal contact records.
- Q. The Consultant shall contact the MDOT Project Manager whenever discoveries or design alternatives have the potential to require changes in the scope, limits, quantities, costs, or right-of-way of the project.
- R. The Consultant shall be responsible for obtaining and showing on the plans the location and names of all existing utilities within the limits of the project. In the course of resolving utility conflicts, the Consultant shall make modifications to the plans or design details and provide assistance as directed by the MDOT Utility Coordinator and/or Project Manager. The Consultant shall attend any utility meetings called to ensure that the concerns are addressed on the plans involving utilities. The Consultant shall assist in the review of utility permit requests to ensure compatibility with the project.
- S. The Consultant shall be responsible for all traffic control required to perform the tasks as outlined in this Scope of Design Services.
- T. The Consultant shall be responsible for obtaining up to date access permits and pertinent information for tasks in MDOT Right of Way (ROW). This information can be obtained through Joe Rios, Utilities/Permits Section, Development Services Division at (517) 241-2103.
- U. On the first of each month, the Consultant Project Manager shall submit in ProjectWise a monthly project progress report to the Project Manager.
- V. Consider other alternatives, at the study phase that may deviate from the “Description of Work” to determine the most cost effective option. A **detailed** cost estimate is required for each option. A cost per square foot estimate is **not** acceptable. The vertical clearance must be considered. A design exception, if required, should be submitted to MDOT with the structure study.

- W. Prior to submitting proposal, inspect the job site to determine the need for any additional work not included in the “Description of Work”. If possible changes to the description of work are needed, submit a letter with your proposal detailing the changes that are recommended. (MDOT will not be reimbursing the consultant for the initial site visit, as the consultant is not yet authorized to do the work).
- X. Consider Accelerated Bridge Construction (ABC) techniques at the study phase, including bridge slide and Precast Bridge Elements and Systems (PBES).
- Y. The Consultant shall submit a Pre-Final Design Package six weeks prior to Plan Completion which shall consist of the following: all final detail sheets complete with the exception of reinforcement details (e.g. bar lengths), all special provisions revised as requested at the Plan Review meeting, and an updated cost estimate. Plan Review comments should be reflected in all sheets. Slab and Screed sheets and Bar Schedule sheets are not required.
- Z. The Consultant shall analyze crash data and prepare a crash analysis for the project as a whole as well as for any Design Exceptions for the project and submit them for review by the MDOT Taylor TSC Traffic and Safety Engineer.
- AA. Prepare Design Exception Requests if necessary for road and/or bridge issues (ie: superelevation transition rates, SSD, shoulder widths, under clearance, etc.) a list of possible design exceptions will be required at the Base Plan Review, with final drafts being submitted at the Plan Review Meeting.
- BB. The Consultant shall be responsible for the coordination work required to incorporate additional rehabilitation or Capital Preventive Maintenance (CPM) bridge designs provided by others, if necessary, into the total project. The coordination work will include all of the work required to incorporate and prepare a comprehensive Plan Review, Pre-Final, OEC, and Final Plan submittal. This work will include the Final QA/QC on all submittals, the SAPW file, the Critical Path Network, and all other required coordination.

DELIVERABLES:

The Consultant shall enter in MDOT ProjectWise, in the appropriate folders all electronic files associated with the project in their native format (spreadsheets, CADD files, GEOPAK files, Roadway Designer Templates etc.) as directed by the MDOT Project Manager. All CADD/GEOPAK files shall be created and identified with standard MDOT file names. It is the Consultant’s responsibility to obtain up to date MicroStation and GEOPAK seed/configuration files necessary to comply with MDOT’s CADD standards which are published monthly to the MDOT website. Any CADD/GEOPAK files that do not conform to MDOT standards will be returned to the Consultant for correction at the Consultant’s expense.

Proposal documents shall be submitted, to MDOT ProjectWise, in the appropriate folders, in their native format with standard naming conventions as well as combined into one PDF file in

the sequence specified by MDOT. To provide text search capabilities the combined proposal shall be created by converting native electronic files to PDF. Scanning to PDF is discouraged except in instances where it is necessary to capture a legally signed document or a hard copy version of a document is all that exists.

Plan sheets shall be submitted to MDOT ProjectWise in the appropriate folders in a set in PDF 11" x 17" format. For final Plan Turn-In, a title sheet shall be printed, signed, sealed, and then scanned for inclusion with the PDF set. The original title sheet shall be sent to the MDOT Project Manager.

Reference Information Documents (RID) shall be entered into MDOT ProjectWise in the appropriate folder with standard naming conventions and content at milestone submittals as defined by Chapter 4 of the Design Submittal Requirements. The RID files included will depend on the design survey deliverables and project template (See Chapter 2 of the Design Submittal Requirements). These files range from CADD, existing terrain, proposed cross sections, 3D models and files generated for Automated Machine Guidance (AMG) and automated inspection/stakeout activities.

Stand Alone Proposal Estimator's Worksheet (SAPW) shall be used to generate the txt and xml files necessary for import into the Trns*port bid letting software. The SAPW files shall be entered into MDOT ProjectWise in the appropriate folder.

The project removal, construction, and profile sheets will require a scale of **1"=80' or as approved by the Project Manager**. See Section 1.02.12 of the Road Design Manual for further direction.

All plans, special provisions, estimates, and other project related items shall meet all MDOT requirements and detailing practices (i.e., format, materials, symbols, patterns, and layout) or as otherwise directed by the Project Manager. All plans, specifications, and other project related items are subject to review and approval by MDOT.

PROJECT SCHEDULE:

The Consultant shall use the following events to prepare the proposed implementation schedule as required in the Guidelines for the Preparation of Responses on Assigned Design Services Contracts. These dates shall be used in preparing the Consultant's Monthly Progress Reports.

MDOT PRECONSTRUCTION TASKS CONSULTANT CHECKLIST

STUDY (EARLY PRELIMINARY ENGINEERING)

		P/PMS TASK NUMBER AND DESCRIPTION	DATE TO BE COMPLETED BY (mm/dd/yyyy)
		CONSULTANT CONTRACT AUTHORIZATION/EXECUTION	/ /
YES	NO		
<u>INFORMATION GATHERING/STUDIES</u>			
<input type="checkbox"/>	<input type="checkbox"/>	1115 Traffic Data Collection for Studies	/ /
<input type="checkbox"/>	<input type="checkbox"/>	1120 Prepare Traffic Analysis Report for Studies	/ /
<input type="checkbox"/>	<input type="checkbox"/>	1125 Traffic Capacity Analysis for Studies	/ /
<input type="checkbox"/>	<input type="checkbox"/>	1155 Request/Perform Safety Analysis for Studies	/ /
<input type="checkbox"/>	<input type="checkbox"/>	1300 Traffic Impact Study	/ /
<input type="checkbox"/>	<input type="checkbox"/>	1350 Determine Need for Interstate Access Change Request	/ /
<input type="checkbox"/>	<input type="checkbox"/>	1400 Feasibility Study	/ /
<input type="checkbox"/>	<input type="checkbox"/>	1500 Corridor Study	/ /
<input type="checkbox"/>	<input type="checkbox"/>	1555 Interstate Access Change Request	/ /
<input type="checkbox"/>	<input type="checkbox"/>	<u>155M FHWA Approval of Interstate Access Change Request</u>	/ /
<input type="checkbox"/>	<input type="checkbox"/>	1600 Access Management Study Plan	/ /
<input type="checkbox"/>	<input type="checkbox"/>	1700 Other Miscellaneous Studies	/ /
<u>EPE SCOPING ANALYSIS</u>			
<input type="checkbox"/>	<input type="checkbox"/>	2100 Scope Verification and Initiation of EPE Activities	/ /
<input type="checkbox"/>	<input type="checkbox"/>	2115 Prepare Traffic Analysis Report for EPE/Design	/ /
<input type="checkbox"/>	<input type="checkbox"/>	2120 Traffic Data Collection for EPE/Design	/ /
<input type="checkbox"/>	<input type="checkbox"/>	2125 Traffic Capacity Analysis for EPE/Design	/ /
<input type="checkbox"/>	<input type="checkbox"/>	2130 Prepare Project Purpose and Need	/ /
<input type="checkbox"/>	<input type="checkbox"/>	<u>213M Concurrence by Regulatory Agencies with the Purpose and Need</u>	/ /
<input type="checkbox"/>	<input type="checkbox"/>	2140 Develop and Review Illustrative Alternatives	/ /
<input type="checkbox"/>	<input type="checkbox"/>	2155 Request/Perform Safety Analysis for EPE/Design	/ /
<input type="checkbox"/>	<input type="checkbox"/>	2160 Prepare and Review EIS Scoping Document	/ /
<input type="checkbox"/>	<input type="checkbox"/>	<u>216M Public Information Meeting</u>	/ /

MDOT PRECONSTRUCTION TASKS CONSULTANT CHECKLIST

STUDY (EARLY PRELIMINARY ENGINEERING) (cont'd)

		P/PMS TASK NUMBER AND DESCRIPTION	DATE TO BE COMPLETED BY (mm/dd/yyyy)
YES	NO		
<u>EPE DRAFT ANALYSIS</u>			
<input type="checkbox"/>	<input type="checkbox"/>	2310 Conduct Technical SEE Studies	/ /

- | | | | | |
|--------------------------|--------------------------|--|---|---|
| <input type="checkbox"/> | <input type="checkbox"/> | 2311 Cultural Resources Survey | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2312 Recreational Survey – Section 4(f)/6(f) | / | / |

EPE DRAFT ANALYSIS (cont'd)

- | | | | | |
|--------------------------|--------------------------|--|---|---|
| <input type="checkbox"/> | <input type="checkbox"/> | 2313 Endangered Species Survey | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2314 Wetland Assessment | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2315 Wetland Mitigation | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2316 Other Technical Reports | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2321 Prepare for Aerial Photography | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2322 Finish/Print Aerial Photography | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2330 Collect EPE Geotechnical Data | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2340 Develop and Review Practical Alternatives | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | <u>233M Aerial Photography Flight</u> | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2360 Prepare and Review EA | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | <u>236M Approval of EA by FHWA</u> | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2370 Prepare and Review Draft EIS | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | <u>237M Approval of Draft EIS by FHWA</u> | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2380 Distribute EA | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | <u>238M Public Hearing for EA</u> | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2390 Distribute DEIS | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | <u>239M Public Hearing for DEIS</u> | / | / |

EPE FINAL ANALYSIS

- | | | | | |
|--------------------------|--------------------------|---|---|---|
| <input type="checkbox"/> | <input type="checkbox"/> | 2510 Determine and Review Recommended Alternative | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | <u>250M Concurrence by Reg Agencies with Recom Alternatives</u> | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2525 Prepare and Review Engineering Report | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2530 Prepare and Review Request for FONSI | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | <u>252M Approval of FONSI by FHWA</u> | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2540 Prepare and Review FEIS | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | <u>254M Approval of FEIS by FHWA</u> | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2550 Obtain ROD | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | <u>255M ROD Issued by FHWA</u> | / | / |
| <input type="checkbox"/> | <input type="checkbox"/> | 2570 ITS Concept of Operations | / | / |

CONTAMINATION INVESTIGATION

- | | | | |
|-------------------------------------|--------------------------|---|-----------|
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | 2810 Project Area Contamination Survey (PCS) | 2/29/2016 |
| <input checked="" type="checkbox"/> | <input type="checkbox"/> | 2820 Preliminary Site Investigation (PSI) for Contamination | 4/28/2016 |

MDOT PRECONSTRUCTION TASKS CONSULTANT CHECKLIST

PRELIMINARY ENGINEERING - DESIGN

		P/PMS TASK NUMBER AND DESCRIPTION	DATE TO BE COMPLETED BY
YES	NO		(mm/dd/yyyy)

DESIGN SCOPE VERIFICATION AND BASE PLAN PREPARATION

<input type="checkbox"/>	<input type="checkbox"/>	3130	Verify Design Scope of Work and Cost	/	/
<input type="checkbox"/>	<input type="checkbox"/>	3310	Prepare Aerial Topographic Mapping	/	/
<input type="checkbox"/>	<input type="checkbox"/>	3320	Conduct Photogrammetric Control Survey	/	/
<input type="checkbox"/>	<input type="checkbox"/>	3321	Set Aerial Photo Targets	/	/
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3325	Geotechnical Structure Site Characterization	4/28/2016	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3330	Conduct Design Survey	2/29/2016	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3340	Conduct Structure Survey	2/29/2016	
<input type="checkbox"/>	<input type="checkbox"/>	3350	Conduct Hydraulics Survey	/	/
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3360	Prepare Base Plans	4/28/2016	
<input type="checkbox"/>	<input type="checkbox"/>	<u>311M</u>	<u>Utility Notification</u>	/	/
<input type="checkbox"/>	<input type="checkbox"/>	3365	Pre-Conceptual ITS Design and Meeting	/	/
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3370	Prepare Structure Study	4/28/2016	
<input type="checkbox"/>	<input type="checkbox"/>	3375	Conduct Value Engineering Study	/	/
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3380	Review Base Plans	4/28/2016	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3385	Preliminary Load Rating	10/18/2016	
<input type="checkbox"/>	<input type="checkbox"/>	<u>332M</u>	<u>Base Plan Review (Pre-GI Inspection)</u>	/	/
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3390	Develop the Maintaining Traffic Concepts	4/28/2016	

PRELIMINARY PLANS PREPARATION

<input checked="" type="checkbox"/>	<input type="checkbox"/>	3500	Develop Transportation Management Plan	6/2/2017	
<input type="checkbox"/>	<input type="checkbox"/>	3510	Perform Roadway Geotechnical Investigation	/	/
<input type="checkbox"/>	<input type="checkbox"/>	3520	Conduct Hydraulic/Hydrologic and Scour Analysis	/	/
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3522	Conduct Drainage Study, Storm Sewer Design, and use Structural Best Management Practices	/	/
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3530	Geotechnical Foundation Engineering Report	10/18/2016	
<input type="checkbox"/>	<input type="checkbox"/>	3535	Conduct Str. Review for Arch. & Aesthetic Improvements	/	/
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3540	Develop the Maintaining Traffic Plan	10/18/2016	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3551	Prepare/Review Preliminary Traffic Signal Design Plan	10/18/2016	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3552	Develop Preliminary Pavement Marking Plan	10/18/2016	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3553	Develop Preliminary Non-Freeway Signing Plan	10/18/2016	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3554	Develop Preliminary Freeway Signing Plan	10/18/2016	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3555	Prepare/Review Preliminary Traffic Signal Operations	10/18/2016	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3570	Prepare Preliminary Structure Plans	10/18/2016	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3580	Develop Preliminary Plans	10/18/2016	
<input type="checkbox"/>	<input type="checkbox"/>	3585	Final ITS Concept Design and Meeting	/	/
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3590	Review The Plans	11/8/2016	
<input type="checkbox"/>	<input type="checkbox"/>	<u>352M</u>	<u>THE Plan Review Meeting</u>	/	/
<input type="checkbox"/>	<input type="checkbox"/>	3595	Conduct ITS Structure Foundation Investigation	/	/

MDOT PRECONSTRUCTION TASKS CONSULTANT CHECKLIST

PRELIMINARY ENGINEERING - DESIGN (cont'd)

		P/PMS TASK NUMBER AND DESCRIPTION	DATE TO BE COMPLETED BY (mm/dd/yyyy)
YES	NO		
<u>UTILITIES</u>			
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3610 Compile Utility Information	10/18/2016
<input type="checkbox"/>	<input type="checkbox"/>	3615 Compile ITS Utility Information	/ /
<input type="checkbox"/>	<input type="checkbox"/>	3650 Coordinate RR Involvement for Grade Separations	/ /
<input type="checkbox"/>	<input type="checkbox"/>	3655 Coordinate RR Involvement for At-Grade Crossings	/ /
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3660 Resolve Utility Issues	5/2/2017
<input type="checkbox"/>	<input type="checkbox"/>	<u>360M Utility Conflict Resolution Plan Distribution</u>	/ /
<input type="checkbox"/>	<input type="checkbox"/>	<u>361M Utility Meeting</u>	/ /
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3670 Develop Municipal Utility Plans	5/2/2017
<input type="checkbox"/>	<input type="checkbox"/>	3672 Develop Special Drainage Structures Plans	/ /
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3675 Develop Electrical Plans	5/2/2017
<input type="checkbox"/>	<input type="checkbox"/>	3680 Preliminary ITS Communication Analysis	/ /
<input type="checkbox"/>	<input type="checkbox"/>	3690 Power Design (Power Drop in Field)	/ /
<u>MITIGATION/PERMITS</u>			
<input type="checkbox"/>	<input type="checkbox"/>	3710 Develop Required Mitigation	/ /
<input type="checkbox"/>	<input type="checkbox"/>	3720 Assemble Environmental Permit Applications	/ /
<input type="checkbox"/>	<input type="checkbox"/>	3730 Obtain Environmental Permit	/ /
<u>FINAL PLAN PREPARATION</u>			
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3815 Geotechnical Structure Design Review	5/2/2017
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3821 Prepare/Review Final Traffic Signal Design Plan	5/2/2017
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3822 Complete Permanent Pavement Marking Plan	5/2/2017
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3823 Complete Non-Freeway Signing Plan	5/2/2017
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3824 Complete Freeway Signing Plan	5/2/2017
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3825 Prepare/Review Final Traffic Signal Operations	5/2/2017
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3830 Complete the Maintaining Traffic Plan	5/2/2017
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3840 Develop Final Plans and Specifications	5/2/2017
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<u>380M Plan Completion</u>	6/2/2016
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3850 Develop Structure Final Plans and Specifications	5/2/2017
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3870 Hold Omissions/Errors Check (OEC) Meeting	6/22/2016
<input checked="" type="checkbox"/>	<input type="checkbox"/>	3875 Final Load Rating	5/2/2017
<input type="checkbox"/>	<input type="checkbox"/>	<u>387M Omissions/Errors Checks Meeting</u>	/ /
<input type="checkbox"/>	<input type="checkbox"/>	<u>389M Plan Turn-In</u>	/ /
<input type="checkbox"/>	<input type="checkbox"/>	3880 CPM Quality Assurance Review	/ /
<input type="checkbox"/>	<input type="checkbox"/>	3890 Final ITS Communication Analysis	/ /

MDOT PRECONSTRUCTION TASKS CONSULTANT CHECKLIST

PRELIMINARY ENGINEERING – RIGHT OF WAY

P/PMS TASK NUMBER AND DESCRIPTION

DATE TO BE COMPLETED BY

YES	NO		(mm/dd/yyyy)
		<u>EARLY RIGHT OF WAY WORK</u>	
<input type="checkbox"/>	<input type="checkbox"/>	4100 Real Estate Pre-Technical Work (combines 411M, 4120)	/ /
<input type="checkbox"/>	<input type="checkbox"/>	4150 Real Estate Technical Work (combines 4130, 4140)	/ /
<input type="checkbox"/>	<input type="checkbox"/>	<u>413M Approved Marked Final ROW</u>	/ /
		<u>ROW APPRAISAL</u>	
<input type="checkbox"/>	<input type="checkbox"/>	4350 Real Estate Appraisals (combines 4411, 4412, 4413, 4420)	/ /
		<u>ROW ACQUISITION</u>	
<input type="checkbox"/>	<input type="checkbox"/>	4450 Real Estate Acquisitions (combines 4430, 4710, 4720)	/ /
<input type="checkbox"/>	<input type="checkbox"/>	4510 Conduct Right Of Way Survey & Staking	/ /
<input type="checkbox"/>	<input type="checkbox"/>	<u>442M ROW Certification</u>	/ /

MDOT PRECONSTRUCTION TASKS CONSULTANT CHECKLIST

POST LETTING/AWARD TASKS (for reference only)

YES	NO	P/PMS TASK NUMBER AND DESCRIPTION	DATE TO BE COMPLETED BY (mm/dd/yyyy)
<input type="checkbox"/>	<input type="checkbox"/>	4810 Complete Acquisition Process	/ /
<input type="checkbox"/>	<input type="checkbox"/>	4820 Manage Excess Real Estate	/ /
<input type="checkbox"/>	<input type="checkbox"/>	4830 Provide Post-Certification Relocation Assistance	/ /
<input type="checkbox"/>	<input type="checkbox"/>	4910 Conduct ROW Monumentation	/ /
<input type="checkbox"/>	<input type="checkbox"/>	5010 Construction Phase Engineering and Assistance	/ /
<input type="checkbox"/>	<input type="checkbox"/>	5020 Prepare As-Built Drawings	/ /

CONSULTANT PAYMENT – Actual Cost Plus Fixed Fee:

Compensation for this project shall be on an **actual cost plus fixed fee** basis. This basis of payment typically includes an estimate of labor hours by classification or employee, hourly labor rates, applied overhead, other direct costs, subconsultant costs, and applied fixed fee. The fixed fee for profit allowed for this project is 11.0% of the cost of direct labor and overhead.

All billings for services must be directed to the Department and follow the current guidelines. Payment may be delayed or decreased if the instructions are not followed.

Payment to the Consultant for services rendered shall not exceed the maximum amount unless an increase is approved in accordance with the contract with the Consultant. Typically, billings must be submitted within 60 days after the completion of services for the current billing. The final billing must be received within 60 days of the completion of services. Refer to your contract for your specific contract terms.

Direct expenses, if applicable, will not be paid in excess of that allowed by the Department for its own employees in accordance with the State of Michigan's Standardized Travel Regulations. Supporting documentation must be submitted with the billing for all eligible expenses on the project in accordance with the Reimbursement Guidelines. The only hours that will be considered allowable charges for this contract are those that are directly attributable to the activities of this project.

MDOT will reimburse the consultant for **vehicle expenses and the costs of travel** to and from project sites in accordance with MDOT's Travel and Vehicle Expense Reimbursement Guidelines, dated May 1, 2013. The guidelines can be found at http://www.michigan.gov/documents/mdot/Final_Travel_Guidelines_05-01-13_420289_7.pdf?20130509082418. MDOT's travel and vehicle expense reimbursement policies are intended primarily for construction engineering work. Reimbursement for travel to and from project sites and for vehicle expenses for all other types of work will be approved on a case by case basis.

MDOT will pay **overtime** in accordance with MDOT's Overtime Reimbursement Guidelines, dated May 1, 2013. The guidelines can be found at http://www.michigan.gov/documents/mdot/Final_Overtime_Guidelines_05-01-13_420286_7.pdf?20130509081848. MDOT's overtime reimbursement policies are intended primarily for construction engineering work. Overtime reimbursement for all other types of work will be approved on a case by case basis.

ATTACHMENT A

SCOPE OF SERVICE FOR DESIGN SURVEYS

September 2015

Survey Limits: As needed for Design, Right of Way, and Construction. A description of survey limits detailing length, width and cross roads must be included in the Survey Work Plan.

NOTES: The Selected Consultant shall discuss the scope of this survey with an MDOT Region Surveyor or an MDOT Lansing Design Surveyor before submitting a priced proposal.

The Selected Consultant surveyor must contact the Region or TSC Traffic and Safety Engineer for work restrictions in the project area prior to submitting a priced proposal.

A **detailed Survey Work Plan** must be included in the project proposal. A **spreadsheet estimate** of hours by specific survey task such as horizontal control, leveling, mapping, alignment determination, etc., must be included in the **priced proposal**.

It is the responsibility of the Professional Surveyor to safeguard all corners of the United States Public Land Survey System, published Geodetic Control and any other Property Controlling corners that may be in danger of being destroyed by the proposed construction project.

GENERAL REQUIREMENTS:

1. Surveys must comply with **all Michigan law** relative to land surveying.
2. Surveys must be done under the **direct supervision** of a Professional Surveyor licensed to practice in the State of Michigan, according to Public Act 299 of 1980.
3. Work in any of the following Survey Services Categories: Surveying: Hydraulics, Surveying: Right of Way, Surveying: Road Design, Surveying: Structure and Surveying: Geodetic Control and Leveling must be completed by a survey firm which is pre-qualified by MDOT for that category.
4. Surveys must meet all requirements of the Michigan Department of Transportation (MDOT) Design Surveys *Standards of Practice* dated May 2014, except for naming conventions. Please contact the MDOT Design Survey office to clarify any specific questions regarding these standards.
5. Consultants must obtain all necessary permits required to perform this survey on any public and/or private property, including an up-to-date permit from the MDOT Utilities

Coordination and Permits Section.

6. Prior to performing the survey, the Consultant must contact all landowners upon whose lands they will enter. The contact may be personal, phone or letter, but must be documented. This notice must include the reasons for the survey on private land, the approximate time the survey is to take place, the extent of the survey including potential brush cutting (which must be minimized), and an MDOT contact person (the MDOT Project Manager or designate).
7. The Consultant must contact any and all Railroads prior to commencing field survey on railroad property. The cost for any permit, flaggers and/or training that is required by the Railroad will be considered as a direct cost, but only if included in the Consultant's priced proposal.
8. The Consultant must adhere to all applicable OSHA and MIOSHA safety standards, including the appropriate traffic signs for the activities and conditions for this job.
9. Consultants are responsible for a comprehensive and conscientious research of all records, including MDOT records, essential for the completion of this project.
10. The Horizontal and Vertical datums and coordinate system must be clearly stated in the Survey Work Plan and subsequent submittal. Refer to the Design Surveys *Standards of Practice* for acceptable datums and coordinate systems.
12. **Electronic submittal only.** Each structure must be submitted separately.
13. Each Survey-Classification Folder is divided into six sections. These sections are as follows: **Admin, Align & ROW, Control, Mapping, Misc,** and **RID** (Reference Information Documents).
14. To be included in the **Admin** section shall be a copy of the **Survey Project Portfolio QA/QC Check-off list**, May 2014 revision, available from the MDOT Survey Support Unit. This document shall be signed and certified by the Professional Surveyor responsible for the project QA/QC. It is highly recommended that the consultant become familiar with this document prior to preparing the proposal and again prior to assembling the final portfolio. **Failure to use and include this document may result in the immediate return of the project portfolio for completion.**
15. All submitted files must be scanned and/or converted to one PDF format file. A Table of Contents in PDF format is required that has all PDF files bookmarked/linked so each place in the PDF archive can be accessed with a single click of the computer mouse. Specified format files such as Microsoft Word and MicroStation GEOPAK must have separate access in native format outside of the PDF file.
16. The MDOT Project Manager is the official contact for the Consultant. The Consultant must send a copy of all project correspondence to the MDOT Project Manager. The

MDOT Project Manager shall be made aware of all communications regarding this project. Any survey related questions regarding this project should be directed to an MDOT Survey Consultant Project Manager or MDOT Region Surveyor. **The MDOT Project Manager must be copied on any and all correspondence.**

At the completion of this survey for this project, legible copies of all field survey notes, all electronic data, and all research records obtained for this project will be considered the property of MDOT. Please include MDOT's Form 222(5/01) entitled "SURVEY NOTES: RECEIPT AND TRANSMITTAL" for all transmittals. A copy of this transmittal form must be sent to the MDOT Project Manager for Design and the MDOT Supervising Land Surveyor.

Acceptance of this survey by the MDOT Project Manager and/or the MDOT Supervising Land Surveyor does not relieve the Consultant of any liability for the content of the survey.

WORK RESTRICTIONS

The Selected Consultant, and the Selected Consultant only, is advised to discuss Traffic Control scenarios with the MDOT Taylor TSC Traffic and Safety Engineer Mike Budai at (313) 375-2403 or budaim@michigan.gov prior to submitting a priced proposal. Traffic Control costs not included in the priced proposal will not be paid by MDOT.

The Consultant must submit a five (5) day advanced notice through the permit system prior to work.

No work shall be performed or lane closures allowed during the Memorial Day, Independence Day, Thanksgiving, Christmas, New Year or Labor Day holiday periods. The holiday periods will be defined by the local Traffic and Safety Engineer which has jurisdiction over the project area.

All work on the road shall be conducted during daylight hours Monday through Saturday only. Lane closures may only occur between the hours of 9:00 am and 2:00 pm, shoulder closures may only occur between the hours of 9:00 am and 3:00 pm. Weekend work is permitted on Saturdays between the hours of 7:00 am and 5:00 pm. Double lane closures are only permitted on Saturdays.

All traffic control devices shall conform to the current edition, as revised, of the *Michigan Manual of Uniform Traffic Control Devices* (MMUTCD) available on line at http://mdotcf.state.mi.us/public/tands/Details_Web/mmutedcompleteinteractive.pdf. All warning signs for maintenance of traffic used on this project shall be fabricated with prismatic retro-reflective sheeting. Sign covers shall be placed over existing regulatory signs that are not applicable during Survey work.

The Consultant shall use MDOT standard "maintaining traffic" typicals for any and all closures. Typical MDOT traffic control diagrams are available on line at <http://mdotcf.state.mi.us/public/tands/plans.cfm>

The Consultant may also use MDOT Maintenance Work Zone Traffic Control Guidelines, found

on line at http://www.michigan.gov/documents/zonecontrol_112912_7.pdf.

The Consultant must have a vehicle with markings/logo that identifies the company within sight distance of survey activity and must have a 360 degree flashing strobe light on the top of the vehicle whenever they are working on or near the road.

Traffic control on city streets and county roads is under the jurisdiction of the local authorities where the project is located.

COORDINATION WITH OTHER CONTRACTS IN THE VICINITY

The Consultant shall coordinate operations with contractors performing work on other projects within or adjacent to the Construction Influence Area (CIA).

MDOT maintenance crews and/or Contract Maintenance Agencies may perform maintenance work within or adjacent to the CIA. The Maintenance Division of MDOT and/or Contract Maintenance Agency will coordinate their operations with the MDOT Project Manager or Designate to minimize the interference to the Consultant.

The Consultant must contact the Operations Engineer at the MDOT Taylor TSC for information regarding project coordination.

The Consultant's attention is called to the requirements of cooperation with others as covered in Article 104.08 of the 2012 Standard Specifications for Construction <http://mdotcf.state.mi.us/public/specbook/2012/>. Other contracts or maintenance operations may occur during the life of the project.

No claim for extra compensation or adjustment in contract unit prices will be allowed on account of delay or failure of others to complete scheduled work.

POST SURVEY CLEAN-UP

Once the survey is complete, all stakes must be removed from the MDOT median and ROW to aid the maintenance crews and adjacent property owners. All benchmarks and control points and their witnesses must remain in place.

FINAL REPORT: ELECTRONIC SUBMITTAL for each separate structure

The final report for this project shall include:

1. In the **Admin** subfolder, the following will appear:

- **XXXXXXX_Survey_Notes_Receipt_and_transmittal-20YY-MM**
- **XXXXXXX_Survey_20YY-MM-DD.pdf**
 - An Adobe PDF with all of the contents of the portfolio scanned into it and bookmarked for ease of location within the PDF file. Table of Contents – should

appear bookmarked on the left side of the Adobe screen. Note: Upon completion, use Adobe's "Reduce File Size" command.

- **XXXXXX_Surveyors_Report_20YY-MM-DD.pdf**
 - Surveyor's Project Report, divided into subsections, containing a complete synopsis of project survey including, but not limited to:
 - Explanation of any deviation from the Scope and/or the Standards
 - Basis of horizontal and vertical control, with specific emphasis on datum sources used (list CORS and NAVD benchmarks tied), equipment, software, methods used to establish the coordinates and methods used to detect errors and eliminate them. If RTK is used, explain the methodology, equipment and procedure used. Include a detailed explanation relating to CORS usage or site calibration (Base Station) (for level loops, Primary and Intermediate Control networks)
 - Provide a complete discussion of all Alignments relative to the project. Include all information and methods used to determine the location and designation of each.
 - Property boundary issues addressed, with specific information that may be useful for a surveyor to retrace or an engineer during design. If necessary, include a summary of conversations with property owners and their concerns.
 - Any mapping issues encountered, with specific information that may be useful for an engineer during design.
 - Any information obtained regarding drainage issues observed or reported by local authorities or residents should be discussed.
 - Discuss the contents of anything that appears in the miscellaneous section.
 - The signed, sealed, and dated "PROFESSIONAL SURVEYOR'S CERTIFICATION FOR MDOT PROJECTS" as detailed in the Standards of Practice.
 - Alignment information must be certified, signed and sealed by the Professional Surveyor as described in the Alignment section of the Standards of Practice.
 - Mapping information for the project should be summarized per the Standards of Practice dialog.
 - Explanation of how the Reference Point locations were determined.
- **XXXXXX_Vicinity_Map.pdf**
 - Screen capture from Street Atlas, Google Maps, or some other resource, with the POB and POE labeled.
- **XXXXXX_QA/QC_Certification_20YY-MM-DD.pdf**
 - QA/QC Certification, signed and sealed by the lead QA/QC person (See the Survey Standards of Practice Quality Assurance/Quality Control section – Page 24).
- **XXXXXX_MDOT_QA/QC_Checklist_20YY-MM-DD.pdf**

- MDOT QA/QC Checklist and Certification Statement is filled out, signed and sealed by the Survey QA/QC Manager

A. **Correspondence** (subfolder):

- **XXXXXXX_emails.pdf**
 - Copy of all correspondence pertaining to the project saved as a .pdf file.
- **XXXXXXX_Phone_Log.pdf**
 - Transcript of all phone conversations pertaining to the project in a .pdf file format.
- **XXXXXXX_Meeting_Minutes.pdf**
 - Copy of all Meeting Minutes pertaining to the project in a .pdf file format.

B. **Scopes** (subfolder):

- **Work_Permit_Permit_Name.pdf**
 - Copy of all work permits required for the project.
- **XXXXXXX_Advanced_Notice_XXXXXX_20YY-MM-DD.pdf**
 - Notice to proceed with work on the project.
- **XXXXXXX_Form5102_Change_of_Scope_20YY-MM-DD.pdf**
 - Change of scope form.
 - This forms only needs to be filled out if the scope actually changes
- **XXXXXXX_Notice_to_Proceed.pdf**
 - MDOT Form 5180 filled out and added to Scopes Folder
- **XXXXXXX_Price_Proposal.pdf**
 - MDOT Price Proposal Package saved as a .pdf, wages and costs redacted
- **XXXXXXX_Traffic_Control_Quotes.pdf**
 - Copies of the quotes obtained for traffic control in .pdf format.
- **XXXXXXX_Work_Plan.pdf**
 - Detailed Description of the work that will be performed on the project.

2. In the **Align & ROW** subfolder, the following will appear:

- **XXXXXXX_132_Survey_Owner_Name.pdf**
 - Final Certificate of Survey saved as a .pdf file.

- If multiple surveys are required for a project they should each have a unique name.
- **Deed_C-123.pdf**
 - Copy of each deed used for the project.
 - Each deed saved as a separate file.
- **LCRC_J-10_TXXN_RXXE.pdf**
 - Copy of all LCRC Documents used for the project.
 - Each LCRC saved as a separate document.
- **Plat_Westgate_Park.pdf**
 - Copy of all Plats used for the project.
 - Each Plat saved as a separate document.
- **Tax_Desc_07-26-100-001.pdf**
 - Copy of all Tax Descriptions used for the project.
 - Each Tax Description saved as a separate Document.
- **Tax_Map_10-13H.pdf**
 - Copy of all Tax Maps used for the project.
 - Each Tax Map saved as a separate Document.
- **XXXXXX_Prop_20YY-MM-DD.doc**
 - Document containing all found property monumentation.
- **XXXXXX_Prop_20YY-MM-DD.txt**
 - Text document containing all found property monumentation.
 - Data saved in a comma separated format (csv).
 - Point Number, Northing, Easting, Elevation, Desc.

3. In the **Control** subfolder, the following will appear:

- **XXXXXX_GPS_EDM_Control_Comparison.xls**
 - Table comparing GPS grid and EDM ground observations for primary control as described in the Standards of Practice – Item 7 Control
- **XXXXXX_NGS_Mark_Recovery_Form.pdf**
 - Form detailing the NGS marks recovered during the project.
- **XXXXXX_MDOT Monument Establishment**
 - MDOT Monument Establishment Data Sheets of all Primary Control Points established and or used as part of this project (Contact Lansing Survey Office for template).

A. **Horizontal** (subfolder);

- **XXXXXX_Intermediate_Control_Plot.pdf**
 - Plot(s) of the GPS network(s) from GPS software and Sketch(s) or plot(s) of network or traverse with legible point numbers.
- **XXXXXX_Primary_Control_Plot.pdf**
 - Plot(s) of the GPS network(s) from GPS software and Sketch(s) or plot(s) of network or traverse with legible point numbers.
- **XXXXXX_Primary_Minimally_Constrained_Adjustment_Report.pdf**
 - Input parameters, a-priori, centering error, etc.
 - Raw unadjusted closures,
 - Final coordinates with standard deviations (2 sigma)
 - Vector input data and analysis.
 - Histograms.
 - Error ellipses.
 - Traverse closures.
 - Statistical test results.
 - Horizontal and vertical datums, ellipsoid, SPC zone, and units (international feet)
 - Name of the adjustment program used with version or release.
 - Only Non-trivial vectors used
- **XXXXXX_Primary_Fully_Constrained_Adjustment_Report.pdf**
 - Input parameters, a-priori, centering error, etc.
 - Raw unadjusted closures,
 - Final coordinates with standard deviations (2 sigma)
 - Vector input data and analysis.
 - Histograms.
 - Error ellipses.
 - Traverse closures.
 - Statistical test results.
 - Horizontal and vertical datums, ellipsoid, SPC zone, and units (international feet)
 - Name of the adjustment program used with version or release.
 - Only Non-trivial vectors used
- **XXXXXX_Intermediate_Minimally_Constrained_Adjustment_Report.pdf**
 - Input parameters, a-priori, centering error, etc.
 - Raw unadjusted closures,
 - Final coordinates with standard deviations (2 sigma)
 - Vector input data and analysis.
 - Histograms.
 - Error ellipses.
 - Traverse closures.

- Statistical test results.
- Horizontal and vertical datums, ellipsoid, SPC zone, and units (international feet)
- Name of the adjustment program used with version or release.
- Only Non-trivial vectors used
- **XXXXXX_Intermediate_Fully_Constrained_Adjustment_Report.pdf**
 - Input parameters, a-priori, centering error, etc.
 - Raw unadjusted closures,
 - Final coordinates with standard deviations (2 sigma)
 - Vector input data and analysis.
 - Histograms.
 - Error ellipses.
 - Traverse closures.
 - Statistical test results.
 - Horizontal and vertical datums, ellipsoid, SPC zone, and units (international feet)
 - Name of the adjustment program used with version or release.
 - Only Non-trivial vectors used
- **XXXXXX_OPUS_Observation_Logs.pdf**
 - All OPUS log sheets combined together into one .pdf file
- **XXXXXX_OPUS_Manual_Conversion.pdf**
 - Manual conversion of OPUS Solution from Meters to International Feet.
- **XXXXXX_OPUS_Extended.pdf**
 - Extended output solution from OPUS for all Control Points that have been submitted to OPUS.
- NOTE: The Consultant is responsible to archive raw data for a period of five (5) years.

B. Vertical (subfolder):

- **XXXXXX_Data_Sheets.pdf**
 - A copy of all NGS Data Sheets used for the project
- **XXXXXX_V_Minimally_Constrained_Adjustment_Report.pdf**
 - input parameters,
 - raw unadjusted closures,
 - final elevations with standard deviations
 - loop closures.
 - Statistical test results.
 - Horizontal and vertical datums, ellipsoid, SPC zone, and units (international feet)
 - Name of the adjustment program used with version or release.

- OR supply all written calculations to support the final results.
 - Provide separate subfolders for each adjustment which contain the files used in the processing and analysis software. e.g.: Levproc, StarLev, MicroSurvey's StarNet only.
- **XXXXXX_V_Fully_Constrained_Adjustment_Report.pdf**
 - input parameters,
 - raw unadjusted closures,
 - final elevations with standard deviations
 - loop closures.
 - Statistical test results.
 - Horizontal and vertical datums, ellipsoid, SPC zone, and units (international feet)
 - Name of the adjustment program used with version or release.
 - OR supply all written calculations to support the final results.
 - Provide separate subfolders for each adjustment which contain the files used in the processing and analysis software. e.g.: Levproc, StarLev, MicroSurvey's StarNet only.
- NOTE: The Consultant is responsible to archive raw data for a period of five (5) years.

4. In the **Mapping** subfolder, the following will appear:

- **XXXXXX_Struc_Inventory_20YY-MM-DD.xls**
 - Drainage structure inventory report compatible with MDOT software and correlated to the connectivity drawing in Excel spreadsheet format
- **XXXXXX_Connectivity_20YY-MM-DD.dgn**
 - Map of the project area generated from PowerGEOPAK that shows all the drainage structures collected for the project with lines connecting each structure.
- **XXXXXX_Images_20YY-MM-DD.zip**
 - Digital photos of the structure(s) and end sections or headwalls with names or tags correlating the photo with the information in Drainage Structure Inventory Report. (**Note: If deliverables generated with SS3 the image should be integrated into the 3D.dgn**)
- **XXXXXX_Utility_List.doc**
 - Word document containing a utility company listing to include company name, address, phone number, and contact person, if required.
- **XXXXXX_Feature_Code.txt**
 - Individual utility / drainage station and offset reports generated by feature code in .dgn format drawing.

- e.g.: Catch Basin.txt, if required.

5. In the **RID** subfolder, the following will appear:

- **S-XXXXXXX_Align_ROW_20YY-MM-DD.dgn**
- **S-XXXXXXX_Align_LandXML_20YY-MM-DD.xml**
- **S-XXXXXXX_Survey_Info_Sheet_20YY-MM-DD.doc**
- **S-XXXXXXX_ControlPts_20YY-MM-DD.txt**
- **S-XXXXXXX_ExTriangle_20MM-YY-DD.dgn**
- **S-XXXXXXX_ExTriangle_LandXML_20YY-MM-DD.xml**
- **S-XXXXXXX_Survey_2D_20YY-MM-DD.dgn**
- **S-XXXXXXX_Survey_3D_20YY-MM-DD.dgn**

6. In the **Misc** subfolder, the following will appear:

- Data not assignable to one of the other sections may be placed here and must be discussed in the survey report. Examples of appropriate site specific information might be: newspaper articles, photos of the project site looking up and down the roadway, various aspects of a structure, up and down stream and side to side at Hydro chains, etc. Photos shall be submitted in native format and annotated. All items must be included in the master PDF.
- **Images** (subfolder)
 - This folder contains all pictures taken for the project.
 - All pictures should be sorted into separate sub folders and labeled according to their content for example:
 - XXXXXXX_Hydro_Photos
 - XXXXXXX_Drainage_Structures

ATTACHMENT D

SCOPE OF SERVICE FOR UTILITY COORDINATION

The Consultant is directly responsible for all aspects of the project's utility coordination. The Consultant is expected to provide technical assistance to MDOT, utilities and other stakeholders regarding utility identification, project utility coordination and utility conflict resolution.

A utility is defined as any privately, publicly, municipal or cooperatively owned line, facility, or system for producing, transmitting, or distributing communication, cable television, power, electricity, light, heat, gas, oil, crude products, water, steam, waste, or any other similar commodity, including any fire or police signal system or street lighting system.

MDOT shall -

- Provide a preliminary list of utilities, with contact information, that may have facilities located within the project limits. This list may not be 100% accurate and/or complete.
- Provide assistance, if necessary, in contacting utilities to obtain facility records.
- Provide Consultant with utility responses and facility records if utility information solicitation has been performed.
- Organize and host a kick-off meeting with Consultant and MDOT prior to Consultant beginning utility coordination services.
- Prepare the "Utilities Status Report" (MDOT Form 2286) and "Notice to Bidders - Utility Coordination" documents.

Consultant shall -

- Maintain a Utility Conflict Matrix* spreadsheet and deliver as the bi-weekly status report.
- Distribute form letters, plans, etc. as outlined in 14.16 (Request for Utility Information) and 14.26 (Distribution of Preliminary Plans to Utilities and Utility Coordination Meeting) of the MDOT Road Design Manual.
 - Identify existing/proposed utility owners and facilities.
 - Collect and compile utility responses.
 - Follow up with non-responsive utilities.
- Schedule and conduct utility meetings for the resolution of conflicts between utility facilities and proposed construction.
 - Identify conflicts, discuss possible design modifications, develop utility relocation schemes, discuss reimbursable relocations, and discuss project scope and schedule.
 - Identify the utility's design and construction contacts and ensure the plan's note sheet utility contact information is accurate.
 - Record meeting minutes and distribute to all attendees.
- Schedule and conduct field meetings with individual utilities to resolve conflicts.
- Schedule and conduct meetings convened for the purpose of utility betterments.

- Ensure municipal utility relocations, betterments and reimbursements follow Chapter 9 of the MDOT Road Design Manual.
- Identify eligible reimbursable utility relocations, for public/private utilities, as outlined in 23 Code of Federal Regulations (CFR) Part 645 Subparts A and B – Utilities and ensure 23 CFR Part 635.410 - Buy America Requirements are met.
 - Collect documentation to evaluate reimbursable utility relocations.
- Evaluate utility relocation plans for compatibility with the proposed project.
- Ensure utility relocation schedules do not impact the project schedule.
- Confirm utility relocation permit applications are submitted to the TSC.
- Assist in the preparation of the “Utilities Status Report” (MDOT Form 2286) and “Notice to Bidders - Utility Coordination” documents.
- Track and monitor utility relocation progress.

Deliverables (Provided to the TSC Utility Coordinator and Project Manager):

- Courtesy copies of all correspondence with the utilities
- Utility Conflict Matrix
- Utility coordination meeting minutes
- Reimbursable utility relocation documentation
- Utilities Status Report and Notice to Bidders - Utility Coordination

* The Utility Conflict Matrix (UCM) is located on the <http://www.trb.org/Main/Blurbs/166731.aspx> website under Training materials > Prototype 1 – Stand-alone UCM. The UCM was developed as part of the Transportation Research Board’s (TRB) second Strategic Highway Research Program (SHRP 2) Report S2-R15B-RW-1: Identification of Utility Conflicts and Solutions which provides concepts and procedures to identify and resolve utility conflicts. Tools described in the report include utility conflict matrices that enable users to organize, track, and manage conflicts that frequently arise.