

# System Operations Advisory

SOA 2016-03  
September 13, 2016

From Mark Geib, Engineer of Operations Field Services Division

MDOT  
Operations Field Services  
6333 Lansing Road  
Lansing, MI 48917  
Fax/517-322-3385

Questions regarding this advisory should be directed to:

Chris Brookes  
Work Zone Delivery  
Engineer  
(517) 636 -0300  
[Brookesc@michigan.gov](mailto:Brookesc@michigan.gov)

Or

Chuck Bergmann  
Work Zone Tech Specialist  
(517) 322-3314  
[Bergmannc@michigan.gov](mailto:Bergmannc@michigan.gov)

## WZD-100-A Ground Driven Sign Supports for Temp Signs Update

The Work Zone Device Special Detail (WZD) 100-A was updated on 07/20/2016. The updates included changes to two notes on page 11 of 11.

Note 11. The word "cover" was removed.

*"All labor, materials, and equipment, including temporary supports required to install, maintain, relocate, ~~cover~~, and/or remove the temporary sign. Including supports, are considered to be included in the cost of the temporary sign."*

Note 14 was added.

*Temporary wood supports do not require preservative treatment.*

When a temporary sign on driven supports is required to be covered, and it is done so in a manner that covers the entire sign legend or symbol and is in accordance with section 812.03.D.2 of the MDOT specifications for construction, MDOT will then pay for the maximum number of sign covers in use during the course of the project.

Sign covers will be paid for as detailed in 812.03.D.2 as either **Sign Cover Type 1 .... Each**, or **Sign Cover .... Each**.

Please contact the Work Zone Delivery Engineer for any additional guidance.