



# PHASE II STORM WATER MANAGEMENT PROGRAM ANNUAL REPORT

for January 1, 2006 - December 31, 2006


**Permit No. MI0057364** 

Prepared by:

Tetra Tech Lansing, Michigan

April 1, 2007





### **Acronyms**

The following acronym list is provided as a resource for those reading this report.

BMP - Best Management Practice

BOH IM - Bureau of Highway Instructional Memorandum

CSS - Context Sensitive Solutions

DIT – Department of Information Technology

IDEP - Illicit Discharge Elimination Program

MDEQ - Michigan Department of Environmental Quality

MDOT – Michigan Department of Transportation

MEA – Municipal Enforcing Agency

MEP – Maximum Extent Practicable

MPO – Metropolitan Planning Organization

MS4 – Municipal Separate Storm Sewer System

NPDES - National Pollutant Discharge Elimination System

PIPP - Pollution Incident Prevention Plan


SESC – Soil Erosion and Sedimentation Control

SWMP – Storm Water Management Plan

TMDL - Total Maximum Daily Load

TSC – Transportation Service Center

UA – Urbanized Area



### **Table of Contents**

Acronyms	ii
Status At A Glance	vi
Overview	
Introduction	
Report Objectives	
Report Organization	
MS4 Committee	
Program Assessment	
Revised Fiscal Analysis	
Annual Budget	
MDOT-Sponsored Education and Outreach	
Objective	
Training	
Conference Presentations	
Storm Water Educational Materials	
MDOT Storm Water Public Web Page http://www.michigan.gov/stormwatermgt	
MDOT Library	
Storm Water Management Awareness Survey	
Focus for 2007	
Measurable Goals	5
Public Involvement and Participation	
Objective	
Early Coordination Procedure	
Early Coordination Database	
Projects Affecting Waterways with Total Maximum Daily Loads	
Watershed Group Meetings	
Alliance of Rouge Communities Meetings	<del>(</del>
Focus for 2007	
Measurable Goals	<del>(</del>
Illicit Discharge Elimination Program	
Objective	
Dry Weather Screening	
Reported Illicit Discharges	
IDEP Reporting System	
Legal Authority for Illicit Discharge/Connection Removal	
IDEP Construction Advisory	
Statewide Outfall Mapping	
Tap-in/Discharge Permit	
Outfall Labeling	
Focus for 2007	
Measurable Goals	8
Post Construction Storm Water Management	9
Objective	
Drainage Manual	
Native Planting Demonstration Projects	
Post Construction BMP Recommendations	
Post Construction BMP Installations	
Post Construction BMP Maintenance	
List of Post Construction BMPs	
Transportation Enhancement Fund Projects	11

Focus for 20	007	11
Measurable	Goals	11
Dollastion Duo	vention/Good Housekeeping	13
Objective	venuon/Good Housekeeping	12 12
	Ilution Prevention Practices	
	ee Performance Guide Updates	
	e Truck Inspections	
	re Facility Pollution Prevention	
	pplicator Programpplicator Program	
	Sand Application	
Roadside M	faintenance Activities	13
	Up Programs	
	pplication	
	007 Goals	
wicasurable	Cours	17
Soil Erosion &	& Sedimentation Control	15
	SC Practices	
	SC Manual	
	ity Assurance/Quality Control (QA/QC) Reviews	
	oration Construction Advisory	
Focus for 20	007	
Measurable	Goals	16
<b>Figures</b>		
Figure 1 MDC	OT IDEP Reporting System	7
	led MDOT Outfall, 2006	
riguie 2 Lavei	icu WDOT Outlan, 2000	
<b>Tables</b>		
Table 1 Annua	al Storm Water Management Program Expenditure and Budget	2
	wed Categorical Exclusion Projects	
	Police Truck Inspections	
Table 4 Salt U	sage	13
	Usage	
	T Staff SESC Trained and Certified	
Append	lices	
Appendix A	Storm Water Management Plan Activity Sheets	
Appendix B	MDOT-Sponsored Education and Outreach	
Appendix C	Public Involvement and Participation	
Appendix D	Illicit Discharge Elimination Program	
Appendix E	Post Construction Storm Water Management	
Appendix F	Pollution Prevention/Good Housekeeping	
Appendix G	Soil Erosion & Sedimentation Control	




### STATUS AT A GLANCE

### Storm Water Management Plan Annual Report

IMPLEMENTATION TEAMS/TASKS 2006	Status	Schedule
MDOT Sponsored Education and Outreach	l .	<u> </u>
1. Training attendance tracking	0	☆
2. Training review and updates	0	☆
3. Conference participation	•	☆
4. Article publication	•	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$
5. Annual progress report	•	☆
6. Storm water awareness survey	•	₩
7. Lansing Information Center	•	☆
8. General public education	•	☺
9. Public Web site administration	•	☆
Public Involvement & Participation	<u> </u>	l
1. Project early coordination process	•	☆
2. Total Maximum Daily Load (TMDL) review	•	<del>\$</del>
Illicit Discharge Elimination Program		
Illicit discharge reporting database	•	☆
2. Monitor illicit discharges and follow up	•	<b>☆</b>
3. Illicit discharge notification and reporting training	•	☆
4. Dry weather screening at priority outfalls	0	☺
5. Legal authority for illicit discharge removal	•	☆
6. Dry weather screening outfall mapping	0	☺
7. Statewide outfall mapping	•	☺
8. Tap-in/Discharge permits tracking	•	☆
Post Construction Storm Water Management		
1. Post-construction BMP maintenance guidelines	0	☆
2. Post-construction BMP field maintenance tracking (MARS)	0	<b>(</b>
3. Post-construction BMP selection, design, and maintenance procedures	0	<b>(</b>
4. Drainage Manual update	•	☆
5. Existing flow control structure review	0	<b>(</b>
Pollution Prevention & Good Housekeeping		
1. PIPP audits	•	₩
2. Maintenance training	•	₩
3. Contract agency coordination (salt storage, winter maintenance)	0	<b>(</b>
4. Pesticide Applicator Program and fertilizer training	•	☺
5. Adopt-a-Highway Program	•	☺
Soil Erosion & Sedimentation Control	I	<u> </u>
1. SESC Program	•	₩
2. SESC Program review	•	₩
3. Part 91 and Part 31 training	•	ф ф
4. Outfall labeling	•	☆

Status: Procedure/Program in Development = ⊙ Being Implemented = ●

Schedule: Ahead =  $\odot$  On Schedule =  $\heartsuit$  Behind =  $\odot$ 



### Overview

#### Introduction

This Annual Report describes storm water pollution control activities implemented by MDOT over the past reporting period of January 1, 2006-December 31, 2006 to comply with reporting requirements described in the National Pollutant Discharge Elimination System (NPDES) Permit (No. MI0057364, hereinafter referred to as the Permit) issued by the Michigan Department of Environmental Quality (MDEQ). The Permit, which expires on April 1, 2009, is expected to be reissued in five year cycles thereafter.

The Permit directs MDOT to develop and implement a comprehensive Storm Water Management Program (SWMP) designed to reduce the discharge of pollutants from the MDOT drainage systems to the maximum extent practicable (MEP), protect the designated uses of the waters of the state, increase awareness of storm water as a potential source of pollutants, and satisfy the applicable state and federal water quality requirements.

### **Report Objectives**

The objectives for this report are as follows:

◆ To inform MDOT Staff about SWMP activity accomplishments.

- To satisfy MDOT's annual reporting requirement of the Permit.
- To evaluate and assess the appropriateness and effectiveness of MDOT's SWMP.
- To present information about new programs, changes to current programs and procedures developed by MDOT.
- To document changes to MDOT's fiscal analysis and to summarize annual expenditures and budget information.

### **Report Organization**

The annual report highlights actions MDOT completed or is working on to fulfill the Permit requirements during 2006 and also what activities it will focus on in 2007. The reported information is organized by the six implementation teams responsible for the completion of storm water-related activities. The activities of the teams closely follow the requirements of the six minimum

measures of the Permit. The implementation teams include the following:

- ♦ MDOT-Sponsored Education and Outreach
- Public Involvement and Participation
- ♦ Illicit Discharge Elimination Program (IDEP)
- ♦ Post Construction Storm Water Management
- Pollution Prevention/Good Housekeeping
- ♦ Soil Erosion and Sedimentation Control (SESC)

### **MS4 Committee**

MDOT's Municipal Separate Storm Sewer System (MS4) Committee continues to meet on a quarterly basis to discuss progress of the program. Members of the MS4 Committee also serve as chairs of the implementation teams.

### **Program Assessment**

Program assessment is primarily determined by the Storm Water Management Program's adherence to the activities and measurable goals committed to in the SWMP as well as regular evaluation of storm water-related procedures.

training, and programs.

As MDOT's Storm Water Management Program undergoes development and implementation, care is taken to ensure that MDOT's commitments, as written in the SWMP, are fulfilled; however, as the program flourishes, it sometimes becomes evident that modifications need to be made to the original activity, the measurable goal, or both. For more detail regarding activities and schedules committed to in the SWMP. see Appendix A, SWMP Activity Sheets. Appendix A contains all of the activity sheets from Chapter 3, Plan Elements and Activities, of the SWMP. Each activity sheet denotes modifications to the activity's interim

milestones and measurable goals and also indicates which interim milestones and measurable goals have been completed.

Overall, MDOT is on schedule for fulfilling their commitments and the intent of their commitments by the end of the 5-year permit cycle on April 1, 2009. MDOT's vision is to have its Storm Water Management Program be incorporated into the daily activities of the Department with the storm water-related procedures compiled into a



Storm Water Management Manual. Once the original measurable goals are completed, program assessment will be based on evaluation mechanisms built into each of the procedures, trainings, and programs.

### **Revised Fiscal Analysis**

No revisions were made to the fiscal analysis for this reporting period.

### **Annual Budget**

Table 1 provides a summary of MDOT's past annual expenditures and estimated expenditures for fiscal year 2007. The fiscal year is from October 1<sup>st</sup> through September 30<sup>th</sup> of each year. Finalized budget information is also provided for FY 2006. The FY 2006 estimated budget will be updated in the next Annual Report.

Table 1 Annual Storm Water Management Program Expenditure and Budget

Fiscal	Annual
Year	Expenditure
FY 1999	\$142,111
FY 2000	\$1,017,346
FY 2001	\$764,142
FY 2002	\$638,881
FY 2003	\$508,123
FY 2004	\$395,837
FY 2005	\$372,372
FY 2006	\$477,000
FY 2007*	\$575,000

<sup>\*</sup> Budgeted amount for FY 2007.

### **MDOT-Sponsored Education and Outreach**

### **Objective**

To spread awareness of MDOT's Storm Water Management Program to MDOT staff, contractors, and the traveling public and to train MDOT staff and contractors on job-related expectations.

### **Training**

The MDOT storm water training program for 2006 focused on MDOT's Illicit Discharge Elimination Program (IDEP). IDEP Coordinators were designated for each region and were charged with 1) taking illicit discharge complaints, 2) following up on complaints and any confirmed illicit discharges, 3) training applicable field staff, and 4) recording information related to the complaints. Training materials were developed including an updated IDEP training module for field staff and a comprehensive training binder for IDEP Coordinators. The IDEP Coordinators were trained by an outside consultant on their responsibilities and on the new IDEP Reporting Database on April 27, 2006. All region IDEP Coordinators were in attendance, among others (12 attendees).

In addition to the targeted IDEP training, several other trainings were held on soil erosion and sedimentation control, pesticide application, and permanent storm water best management practices. The following details these trainings.

- ♦ SESC Training
  - Concrete Pavers Association of Michigan September 14, 2006, Grand Rapids; October 4, 2006, Detroit; October 11, 2006, Lansing (112 attendees)
  - MITA Superconferences January 27, 2006, Metro; February 10, 2006, Grand Rapids; February 24, 2006, Lansing (114 attendees)
  - Michigan Local Technical Assistance Program (LTAP) September 14, 2006; October 4, 2006; October 11, 2006 (104 attendees)
- ♦ MDOT Pesticide/Certification Training April 25-26, 2006 (67 attendees)
- ♦ NHI Course # 142047 Water Quality Management of Highway Runoff December 6-7, 2006 (23 attendees)

- ♦ Izaac Walton League of America Highway Stormwater Management Webcast May 18, 2006; June 15, 2006; October 26, 2006; February 2, 2007
- Federal Highway Administration, Great Lakes Storm Water Workshop August 10, 2006 (2 attendees from MDOT)

### **Conference Presentations**

In addition to the formal training sessions, MDOT spoke at several conferences internal to MDOT and at outside conferences regarding storm water-related topics. MDOT also provided storm water educational materials and applicable display boards as handouts and exhibits, respectively, at various conferences and public events. The following summarizes these opportunities: (For more information see Appendix B, MDOT-Sponsored Education and Outreach.)

#### **Oral Presentations**

- ♦ MDOT/American Council of Engineering Companies (ACEC) Partnering Conference February 2, 2006
- MDOT Construction Conference March 7-9, 2006
- ♦ MDOT Career Day April 27, 2006, May 2-3, 2006
- ♦ MDOT Design Conference June 27, 2006
- Michigan Association of County Drain Commissioners February 15-17, 2006

#### Display Exhibits & Handouts

- AWWA & MWEA Joint Expo February 6-7, 2006
- ♦ Michigan Stormwater-Floodplain Association Conference, February 13-14, 2006
- Michigan Association of County Drain Commissioners February 15-17, 2006; June 7, 2006; June 8, 2006; June 26, 2006; June 28, 2006
- Kalamazoo Home Expo March 8-11, 2006
- ♦ MDOT Shadow Day April 27, 2006

- ◆ MDOT Operation CARE April 26-29, 2006; July 1-4, 2006; September 1-4, 2006
- "Galesburg Days", Galesburg, Michigan Summer 2006
- "UP Fair", Upper Peninsula, Michigan Summer 2006
- ◆ Kalamazoo County Fair August 7-11, 2006
- ♦ MDOT Maintenance Conference August 22, 2006
- ◆ Texas Township, Kalamazoo Co. Fire Department Open House, October 1, 2006
- ♦ MDOT Real Estate Conference October 12-13, 2006
- ♦ Metropolitan Detroit Science Teachers Assoc. October 21, 2006
- ♦ Kalamazoo River Storm Water Management Plan Public Meeting, October 26, 2006
- Community Expo: Watersheds, Water Quality, Lakes, Rivers, Land Use Issues, Lawrence, Michigan, October 31, 2006
- ◆ Sodus Township, Michigan November 8, 2006
- ◆ MDOT Utilities Conference December 5-7, 2006

#### **Storm Water Educational Materials**

New storm water educational materials were developed in 2006 to increase awareness of MDOT's storm water program to MDOT staff, contractors, and the traveling public. As the targeted audiences become more aware of the program, it is MDOT's goal to transition that awareness to knowledge of expected participation in the storm water program, and then to behavior that supports the storm water program. This transition is expected to occur over many years.

The following materials were created in 2006 and were distributed at conferences, public events, through existing MDOT media such as the Monday Memo, and through existing industry newsletters. (For more details see Appendix B.)

- ◆ Soil Erosion and Sedimentation Control Pocket Guide, January 2006
- ◆ 'Dot the Drop' Soil Erosion and Pollution Prevention animation, February 2006

- Michigan Infrastructure and Transportation Association (MITA) Cross-Section publication, "MDOT's Storm Water Management Program Findings – Soil Erosion and Sedimentation Control", Spring 2006
- ◆ Illicit Discharge Elimination Program Display and Brochure, August 2006
- MITA Cross-Section publication, "MDOT's Storm Water Management Program – Illicit Discharge Elimination Program", Summer 2006
- ◆ LTAP, The Bridge publication, "MDOT's Maintenance Performance Guides Updated for Phase II Storm Water Permit Compliance", September 2006
- ♦ MITA Cross-Section publication, "MDOT's Storm Water Management Program – Pollution Prevention and Good Housekeeping on Construction Sites", Fall 2006

#### Other Agencies Borrowing MDOT Material

With many of the educational materials being posted on the MDOT Storm Water Public Web Page, MDOT has received several requests from other public agencies to use MDOT educational materials for their own reprinting and distribution. MDOT encourages usage of these materials and supplies the native graphic files when requested. The following is a list of agencies requesting to use MDOT materials:

- ◆ Watertown Township, Michigan Storm Water Tip Sheets
- Universal City, Texas
   Received all native graphic files
- ◆ Arizona Department of Transportation Storm Water Flyer for Kids and Storm Water Jeopardy-style Game
- Village of Pinckney, Michigan IDEP Brochure

### **MDOT Storm Water Public Web Page**

http://www.michigan.gov/stormwatermgt

The MDOT Storm Water Public Web Page is part of MDOT's Public Web Site and is updated on a quarterly basis. The page is dedicated to Phase II storm water information and provides a means for MDOT staff, contractors, and the traveling public to view and download MDOT's storm water materials, including reports and educational materials, and to link to other storm water-related Web sites. New information downloaded to the Web page this year includes the following:

- 'Dot the Drop' Soil Erosion and Pollution Prevention animation. February 2006
- Interactive storm water Jeopardy-style game September 2006
- MDOT Outfall Location Maps December 2006

Documentation of the number of Web page visits and downloads is located in Appendix B.

### **MDOT Library**

The MDOT Library is located in the Murray D. Van Wagoner Building in downtown Lansing. The library participates in interlibrary loaning to other state agencies, approved consultants, other governmental agencies, and universities. A separate storm water section is included in the library with materials that are catalogued and can be checked out. In 2006, the storm water materials were not checked out of the library and new materials were not added to this section.

Due to the tremendous amount of storm water materials available on the Web and employee tendency to search for up-to-date materials on the Web, it is believed that keeping the latest storm water material in the library is no longer of value to the storm water management program. In the future, usage of the library materials will not be recorded in the annual report.

### **Storm Water Management Awareness** Survey

In 2005, a storm water management awareness survey was distributed throughout MDOT. The storm water awareness survey results were compiled in 2006 and a report was developed to establish baseline data regarding storm water management. The executive summary of the report is included in Appendix B.

The survey helped identify trends in perceptions, knowledge, actions, and learning modes pertinent to storm water management awareness. The results of the survey are helping to target specific job-related audiences for training using preferred methods of learning.

#### Focus for 2007

The education/outreach focus for 2007 is to continue to broaden the storm water training effort through conference discussions and training, specifically targeting roadway designers on the early coordination procedure and post-construction storm water best management practice design and maintenance considerations.

Upcoming education and training activities:

♦ MITA Superconferences

- MDOT/ACEC Partnering Conference
- MDOT Design Conference
- Construction Site Soil Erosion and Pollution Prevention Pocket Guide
- IDEP Tap-in/Discharge Permit Flyer
- IDEP Residential Illicit Discharge Flyer
- Maintenance Garage Training Video
- MDOT Watershed Boundary Map
- NHI Course # 142047 Water Quality Management of Highway Runoff for MDOT highway design staff
- Early Coordination Training for applicable staff at the Transportation Service Centers
- Training Evaluations and Follow-Up Tests
- Incorporating pollution prevention practices in existing environmental training

#### **Measurable Goals**

See Appendix A, Activities E-1, E-2, E-3, E-4, E-6, T-1, T-2, T-3, and T-4 to view the progress in reaching the interim milestones and measurable goals as defined in the SWMP.

### **Public Involvement and Participation**

### **Objective**

To coordinate early planning of MDOT projects with local watershed organizations (Context Sensitive Solutions) and the Michigan Department of Environmental Quality (MDEQ) on environmental aspects.

### **Early Coordination Procedure**

Over the past two years, MDOT has been working with the Michigan Department of Environmental Quality (MDEQ) to formalize and expand on an existing practice which instructs MDOT Staff to consider storm water Best Management Practices (BMPs) early in the project planning process. Once the BMPs are recommended by MDOT Staff, they are submitted to the MDEQ for comment for selected projects. The Early Coordination Procedure was approved by the MDOT Environmental Committee in 2006 and is being implemented as of the 2007 Scoping process. Evaluation of the procedure will be conducted annually as written in the procedure by a workgroup of selected MDOT, MDEQ, and Michigan Department of Natural Resources (MDNR) Staff.

See Appendix C, *Public Involvement and Participation*, for a copy of the MDOT office memorandum and the procedure.

### **Early Coordination Database**

The MDOT Bureau of Transportation Planning Environmental Section is working with the Department of Information Technology (DIT) to create a web-based platform to facilitate early coordination. Project information will be posted and the site will track how many projects were sent for review and how many concurrences or comments were received. As it could be two to four years before this database is functional, tracking in the interim will be conducted manually by the Aquatic Resource Specialist within the Bureau of Transportation Planning Environmental Section.

### Projects Affecting Waterways with Total Maximum Daily Loads

Three projects were reviewed in 2006 for their affect on waterways with a promulgated Total Maximum Daily Load (TMDL). Two of these projects were reevaluations from 2005 and one was a review during preliminary scoping, which is completed at least five years prior to construction. In 2006, no construction projects affected TMDL waterways.

### **Watershed Group Meetings**

To help facilitate project coordination between MDOT and local watershed and environmental groups, region staff attend local watershed/environmental group meetings when appropriate and when possible. In addition, the MDOT Storm Water Program Manager receives and reviews meetings minutes from 15 to 20 watershed groups to ensure proper MDOT coordination when possible. In 2006 the following meetings were attended:

- ♦ Kalamazoo River Mainstem 3 (4 meetings)
- Macatawa Area Coordinating Council and the Macatawa Watershed Project - Great Lakes Basin Grant to address soil erosion (3 meetings)
- Muskegon River Watershed Assembly (2 meetings)
- ◆ Portage River Watershed Management Plan Meetings (2 meetings)

### Alliance of Rouge Communities Meetings

The Alliance of Rouge Communities (ARC) is a voluntary public watershed entity currently comprised of 39 municipal governments and two counties (i.e., Wayne, and Washtenaw). The ARC members represent public agencies with water management responsibilities whose jurisdictional boundaries are totally or in part located within the Rouge River watershed located in southeast Michigan. As a stakeholder in the Rouge River watershed, MDOT attends the biannual Full Alliance meetings to keep updated on watershed happenings and to ensure appropriate coordination of MDOT and ARC activities.

### Focus for 2007

- To implement the early coordination procedure.
- ♦ Continue attending watershed meetings

### **Measurable Goals**

See Appendix A, Activities C-2, C-4 and C-5, to view the progress in reaching the interim milestones and measurable goals as defined in the SWMP.

### **Illicit Discharge Elimination Program**

### **Objective**

To effectively implement MDOT's approved Illicit **Discharge Elimination Program including dry** weather screening of priority outfalls and a procedure for accepting and following through with reported illicit discharges/connections.

### **Dry Weather Screening**

Initial dry weather screening of 128 priority road-stream crossings over impaired water bodies, as set forth in the SWMP, was completed in 2006. Three hundred and ninety-three (393) outfalls were identified at these crossings and 361 of them were ruled as having no apparent illicit connections. The thirty-two (32) remaining outfalls are pending further investigation as follows: (See Appendix D, Illicit Discharge Elimination *Program*, for investigation maps saved on a CD-ROM.)

- ♦ 1 needs to be cleared of sediment with work scheduled for early spring 2007 (Bay Region)
- 1 needs to be televised with work scheduled for early spring 2007 (Bay Region)
- 1 letter was sent to property owner, follow-up investigation was conducted and no sign of discharge remaining (Bay Region) (See Appendix D for a copy of the letter)
- 2 letters were sent to appropriate local agencies to continue illicit confirmation work as illicit connections are located outside of the MDOT right-of-way (ROW) (Metro Region) (See Appendix D for copies of letters)
- 27 need to be tracked further upstream

More details regarding dry weather screening investigations, such as sample analysis results and upstream tracking, are located in MDOT's dry weather screening database.

### **Reported Illicit Discharges**

In addition to illicit discharges found during dry weather screening, illicit discharges were found by MDOT staff or outside sources and reported to MDOT. The status of these reports is as follows: (See Appendix D for reported discharges.)

- ♦ February 3, 2006 Secondary containment lagoon discharge into MDOT's system -Resolved (Southwest Region)
- July 26, 2006 Concrete-laden runoff into storm drain at M-14 construction site - Resolved (Metro Region)
- August 21, 2006 Pipes entering ROW with dark water - Resolved (Southwest Region)
- September 5, 2006 Pipe entering ditch with black discharge and odor. Letter has been sent to suspected source. – *Unresolved* (Southwest Region)
- November 2, 2006 Concrete slurry/dust entering ditch. Source is reconstructing driveway to prevent discharge. MDOT will follow-up. – *Monitoring* (Southwest Region)

### **IDEP Reporting System**

For tracking purposes, the reported illicit discharges are recorded in the IDEP Reporting System database. The database was developed in 2005 using Microsoft Access. Each region maintains its own database and is responsible for tracking its reported illicit discharges in the database. The database allows the user to input pertinent information regarding illicit discharges and helps track communications concerning the discharge.




Figure 1 MDOT IDEP Reporting System

Training for the use of the database was conducted at the spring region resource specialist conference on April 27, 2006 as detailed in the MDOT-Sponsored Education and Outreach section of this report. See Figure 1 for a screenshot of the database.

### **Legal Authority for Illicit Discharge/Connection Removal**

There has been no change to MDOT's legal authority requiring illicit discharges/connections be removed from its drainage system.

### **IDEP Construction Advisory**

In September 2006, a Construction Advisory (CA 2006-12), Reporting Illicit Discharges and Illicit Connections, was issued to the Department reminding construction staff to follow Bureau of Highway – Instructional Memorandum 2004-10, Illicit Discharge Elimination Program Procedure, when an illicit discharge/connection is encountered. The procedure is summarized in the Construction Advisory and also contains the name of the IDEP Coordinator for each region. See Appendix D for a copy of CA 2006-12.

### Statewide Outfall Mapping

As required by MDOT's Storm Water Phase II NPDES Permit, MDOT has developed a statewide outfall map, using Geographic Information System (GIS) software. showing the locations of known MDOT outfalls. The outfalls were located based on 1) design-survey data and 2) GPS coordinates from the dry weather screening effort. The map is posted on the MDOT Storm Water Public Web Page and is organized by region and county. The map link is located on the "illicit discharge" page. The maps will be updated annually with the latest information and will continue to be posted on the Web site. It is the intent of MDOT to expand on (or keep maps current) these maps in coordination with the MDOT Asset Management group, which has an interest in the attributes of the outfalls as well. See Appendix D for copies of the maps saved on a CD-ROM.

### **Tap-in/Discharge Permit**

MDOT distributes storm water educational material with its tap-in/discharge permit application. Entities requesting to tap-in/discharge to MDOT's drainage system are required to obtain a permit. In 2006, 25 permit applications with educational information were distributed. In 2007, new storm water educational information, focusing on illicit discharge prevention, will be distributed with the permit applications.

### **Outfall Labeling**

As reported last year, MDOT requires all work which includes culvert end sections, headwalls or other locations such as wing walls, retaining walls, etc. where storm water will discharge directly from the MDOT drainage system to the waters of the state be labeled with 'MDOT'. See Figure 2 for a photograph of a labeled outfall. For outfalls labeled in 2006, see Appendix D. Note that in the future, these outfalls will be included on the statewide outfall map once the procedure for doing so is established.

Figure 2 Labeled MDOT Outfall, 2006



### Focus for 2007

The IDEP focus for 2007 is to continue to train field staff on their role in identifying and reporting illicit discharges/connections and to continue to accept and follow-up on reported illicit discharges/connections. Reported illicit discharge complaints will be recorded in the IDEP Reporting Database within each region.

Upcoming IDEP activities:

- Section 9.13, *Illicit Discharges into MDOT* Storm Water Drainage Systems, of the Construction Permit Manual will be revised and reissued.
- In coordination with MDOT's asset management efforts, a procedure will be developed to streamline the process for compiling new outfall locations and updating outfall maps annually.

#### **Measurable Goals**

See Appendix A, Activities I-1, I-2, I-3, I-4, I-5, C-10, C-12 to view the progress in reaching the interim milestones and measurable goals as defined in the SWMP.

### **Post Construction Storm Water Management**

### **Objective**

To determine and implement the procedure for choosing post construction storm water BMPs, which may be structural, vegetative, or operational, as appropriate. The procedure includes coordination between environmental, design, construction, and maintenance staff early in project planning.

### **Drainage Manual**

Revisions of the MDOT Drainage Manual were distributed to MDOT staff and appropriate construction and consulting staff. The Revised Drainage Manual is located on the MDOT Public Web Site.

### **Native Planting Demonstration Projects**

MDOT is planning three native planting/water quality demonstration projects along three Michigan roads. The projects will be incorporated into 2008 construction projects as vegetated swales and will include an assortment of native plants.

Research suggests that one benefit of using native plants versus traditional roadside vegetation is that the native plants in combination with uncompacted soil will reduce storm water runoff to the waters of the state. The native plants reduce discharge through their extensive root system, which promotes infiltration and evapotranspiration, and through their adaptability to the Michigan environment. MDOT will also be looking at maintenance requirements associated with these projects.

Funding for the projects has been requested through Transportation Enhancement funds and is included below under the sub-heading Transportation Enhancement Fund Projects.

### **Post Construction BMP** Recommendations

Although the formalized procedure for selecting, applying, and maintaining post construction BMPs will not be approved until 2007, a considerable effort has been in place for many years to review all projects for their affect on water quality. In 2006, 295 categorical exclusion projects and 2 major action projects [those requiring an Environmental Assessment (EA) or an Environmental Impact Statement (EIS)] were reviewed. It was determined that neither of the major action projects will have an adverse impact on water quality associated with storm water runoff. Table 2 shows a breakdown of

the number of categorical exclusion projects reviewed in each region in 2006.

**Table 2 Reviewed Categorical Exclusion Projects** 

Region	No. of	% of Total
	Projects	Projects
Grand	69	23
Bay	55	19
University	43	15
Metro	38	13
Southwest	38	13
North	31	11
Superior	21	7
Total	295 <sup>1</sup>	100

<sup>1</sup> The total number of projects reviewed only includes those reviewed from March through December 2006.

The major action projects include the following:

- ♦ US-2 EA (Lake Michigan and the Brevoort River) (creating roadside ditches)
- ♦ I-75 Bay Region EA (Dutch Creek, Squaconning River, Zeigler Drain, Goetz Drain, Davis Drain, and Kochville Drain) (enclosing median)

Most project reviews result in general water quality mitigation recommendations such as retaining existing open drainage where possible, avoiding tree removals within 25 feet of water bodies, and reducing runoff velocities where possible. In some cases, project reviews result in specific water quality mitigation recommendations. A sample of projects receiving specific recommendations is included below:

### M-52, City of Manchester, Washtenaw County: River Raisin

Extensive new curb and gutter were proposed. Alternatives to curb and gutter were discussed but none were feasible given the location. Mitigation for increased water quantity was not feasible, so hydrodynamic separator units were recommended to remove sediments and gross solids from the runoff prior to discharge to the River Raisin.

### Reconstruct M-99 through Hillsdale, Hillsdale County: St. Joseph Tributary

Reconstruction and realignment of road includes upgrade to storm sewer outlets. Widening of riprapped ditch was recommended to slow water and allow more sediment to settle out prior to discharge to Wolf Creek. This was the only feasible solution to reduce sediment and water velocities at this location.

### <u>US-31, Manistee County: unnamed stream and adjacent</u> wetland

Catch basins and storm sewer will be adjusted to correct drainage problems. This project is anticipated to have a positive impact on water quality in the area of this project and be an improvement over the current drainage situation. Recommendations include distributing runoff, using riprap, using drop structures or baffles, and requiring additional maintenance.

### <u>Drainage corrections along M-44 west of Belding, Ionia</u> County: Flat River

Curb and gutter must be installed to correct drainage conditions. This project will result in an increased volume of water being discharged, although at a decreased rate, to the Flat River, the majority of which is listed by the State as a designated natural river. The potential exists for water quality to be impacted unless mitigation measures are provided. Runoff from this road discharges from a culvert under Wells Road and enters the Flat River via a 400-foot riprapped ditch containing established vegetation. Recommendations include not disturbing the 400-foot ditch, using drop structures, inspecting for erosion problems after construction, and requiring additional maintenance.

### M-43 through Delton, Barry County: wetland adjacent to Crooked Lake

M-43 will be reconstructed with slight widening. Water from neighborhoods will be discharged at the same point as the road runoff. This project will result in an increase in the volume and flow rate of water being discharged to a wetland area adjacent to upper Crooked Lake. Minor impacts to water quality are anticipated; therefore, mitigation measures should be provided to the maximum extent practicable. Given the narrow ROW, location of underground utilities, and ownership of the outlet and other contributing drainage areas by the Barry County Drain Commissioner, options for storm water treatment by MDOT are limited. Recommendations included using a drop structure, using catch basin sumps, and requiring additional maintenance.

Also, a hydrodynamic separator will be included to treat commercial and residential runoff, retaining one of the existing drainage outlets near Bush Street. Placement of a sediment settling basin at the outlet is being coordinated with the MDEQ.

### <u>Culvert and major ditch reconstruct on I-196, Van Buren</u> <u>County: Deerlick Creek</u>

MDOT has severe erosion problems in the roadside ditches. This project is not anticipated to have any long term, negative impacts to water quality or the fisheries resource but, in fact, will create a better situation for these resources. This project includes work in and around

Deerlick Creek, a coastal tributary to Lake Michigan and listed by MDNR as a designated trout stream, making it a sensitive water body. Recommendations included shade tree replacement, fish protection during bypass pumping, and restoring ditches to a vegetated condition. The project is currently being implemented and will include all recommendations except shade tree replacement. Shade tree replacement was determined to not be necessary.

### Riverwalk to be built by the Detroit Riverfront Conservancy

This project is located adjacent to the Detroit River and impacts to water quality need to be considered. MDOT is a partner in the project and has agreed to help with the National Environmental Policy Act (NEPA) process. The feasibility of using Best Management Practices to protect water quality should be evaluated during the drainage analysis. The parking lot area is a logical location to use BMPs (e.g. rain gardens, oil/grease separators, catch basin inserts, etc.). Recommendations include providing for a vegetated buffer strip between the riverwalk and the river, considering local watershed plans, using proper precautions/procedures when constructing near/in contaminated areas, disposing of contaminated materials properly, and developing a risk management plan.

### Bridge replacement on M-53, Lapeer County: Peter's Drain

Water quality in Peter's Drain is being impacted by high inputs of sediment, fertilizers, and pesticides from a highly agricultural area. Possible revisions to the design of the bridge approaches were discussed at the plan review meeting on May 9, 2006. As a result of the group's discussion, the 12-inch downspouts at the end of the curb and gutter approaches in all four quadrants of the bridge will be removed from the plans and replaced with shortened curb and gutter approaches which will terminate onto short spillways, then riprap.

### **Post Construction BMP Installations**

Several post construction BMP installations were completed in 2006 as described below. Note that these BMP installations are considered non-typical and MDOT conducts storm water activities regularly that are not typically tracked for inclusion in the storm water annual report, such as on-the-job training for waste oil disposal and repairing failing slopes at road-stream crossings.

### **Grand Region**

A number of storm water BMPs were installed at the I-96/36th Street Interchange in Kent County. These BMPs include use of riprap and drop structures to slow down water, basins, and permanent check dams and cobble ditches.

#### Metro Region

In 2007, an engineered rain garden will be constructed at the Robert Scott Correctional Facility at 5 Mile and Beck in Northville Township.

#### Southwest Region

In April 2006, MDOT's first rain garden was constructed at the Turkeyville Rest Area, I-69 southbound in Calhoun County. The 500 square foot rain garden is designed to collect parking lot runoff and is planted with a variety of perennial plants. The storm water BMP is working well so far and two additional rain gardens are planned at Adair Rest Area (I-94 Eastbound, Saint Clair County) and Belleville Rest Area (I-94 Westbound, Wayne County). Maintenance, including weeding, is the responsibility of the contractor for the first year and of the rest area maintenance staff thereafter.

Lovers Lane Dry Pond Detention Basin in Kalamazoo / Portage was constructed north of I-94 and west of Lovers Lane. Construction of five new detention basins, also in Kalamazoo/Portage, along I-94 to the east of Oakland Drive in Kalamazoo County is planned in 2007.

The Marshall TSC coordinated with the Barry County Drain Commission to have a hydrodynamic separator installed in conjunction with a 2007 construction project.

### Superior Region

The Superior Region had the following BMP installations:

- Storm sewer installation with detention basin, Cemetery Road, City of Houghton.
- ◆ Drop structure at Mill Rd/US-41 intersection Houghton County near City of Houghton.

### **Post Construction BMP Maintenance**

As new post construction storm water BMPs are evaluated and approved by MDOT for regular use, a Performance Maintenance Guide will be developed. Currently, there is a maintenance guideline written in the Drainage Manual for each approved post construction storm water BMP.

### **List of Post Construction BMPs**

A list of post construction BMPs has been initiated to help track the location and purpose of each MDOT post construction storm water BMP. In 2007, MDOT will select several known storm water BMPs for field inspection and maintenance recommendations, and as part of this effort, each region will have the opportunity to review the current BMP list and add to it as they become aware of existing BMPs and as new BMPs are constructed. See Appendix E for a copy of the list to date.

### **Transportation Enhancement Fund Projects**

MDOT manages the federal Transportation Enhancement funds for Michigan and encourages grant applicants to include a water quality benefit within their project. Planned Transportation Enhancement fund projects with a noted water quality benefit include the following:

- ◆ Ingham County Road Commission is installing a storm water treatment structure on Hagadorn Road in coordination with the Grand River bridge replacement project just south of M-43
- ◆ The City of Lansing is installing engineered rain gardens and an oil/grit separator on Michigan Avenue from Larch Street to Pennsylvania Avenue to collect runoff in an ultra-urban area.
- ♦ MDOT is planning three native planting/water quality demonstration projects along three Michigan roads.

#### Focus for 2007

The Post Construction Storm Water focus for 2007 is to train roadway design staff on their role in integrating cost-effective post construction storm water management BMPs into their design projects.

Upcoming Post Construction Storm Water activities:

- ◆ MDOT/American Council of Engineering Companies (ACEC) Partnering Conference – cost-effective storm water BMP breakout sessions, February 1, 2007
- ◆ MDOT Design Conference cost-effective storm water BMP presentation, June 2007
- Updating the existing Post Construction Storm Water BMP Training Module
- Post construction storm water BMP inspections
- Updating procedures and guidance materials regarding design and maintenance of post construction storm water BMPs
- Coordination with West Grand
   Neighborhood Organization and Roosevelt Park
   Neighborhood Association (Grand Rapids)
   Turner Gateway rain garden project

#### Measurable Goals

See Appendix A, Activities C-1, C-3, C-6, C-8, and C-11 to view the progress in reaching the interim milestones and measurable goals as defined in the SWMP.

### **Pollution Prevention/Good Housekeeping**

### **Objective**

To enhance current activities with the ultimate goal of preventing or reducing pollutant runoff from MDOT operations and properties.

### **Existing Pollution Prevention Practices**

Many of MDOT's pollution prevention and good housekeeping practices have been in place at MDOT for many years and are described in facility Pollution Incident Prevention Plans (PIPP), procedure manuals, and guides maintained by the Maintenance Division and the Construction & Technology Division.

### Maintenance Performance Guide Updates

In 2006, the maintenance performance guides for Catch Basin Cleanout (Activity #12200) and Ditch Cleanout (Activity #12300) were updated for Phase II Storm Water Permit Compliance.

The Catch Basin Cleanout guide was revised to require that contract agencies provide landfill test results and waste disposal quantities to MDOT with every invoice.

The Ditch Cleanout guide now requires 1) a Notice of Coverage when five or more acres of earth are disturbed, 2) an inspection by a certified storm water operator when more than one acre of earth is disturbed, and 3) specific soil erosion and sedimentation control procedures.

Contract agencies should have received a copy of these updates. In addition, a summary of these changes was published in the September 2006 Michigan Local Technical Assistance Program (LTAP) newsletter, "The Bridge."

### **State Police Truck Inspections**

Each year, the Michigan State Police (MSP) uses MDOT facilities (rest areas, weigh stations) to host their truck inspections. The truck inspections derive from federal safety requirements but also benefit water quality as some inspection protocols look for leaking fluids. There are several levels of inspections ranging from an extensive 30-point inspection to a simple driver certification check.

In 2006, 50,348 inspections were conducted across Michigan. See Table 3 for an approximate break down of these inspections by region.

**Table 3 State Police Truck Inspections** 

MSP Districts	Equivalent MDOT Regions <sup>1</sup>	2006 Total Inspections
1	University	8,872
2North	Metro	9,558
2South	University	10,769
3	Bay	5,705
5	Southwest	7,319
6	Grand	3,132
7	North	1,210
8	Superior	3,783
TOTAL		50,348

The MSP District boundaries and MDOT Regions do not match up exactly in the Bay, Grand, North, and University Regions. They differ by one or two boundary counties.

### Maintenance Facility Pollution Prevention

MDOT performed/installed a number of pollution prevention mechanisms in 2006 including the following:

- ◆ Installed concrete containment and covers (leak and squirt proof) for brine tanks (Southwest Region)
- Removed the underground storage tanks (USTs) and installed concrete aboveground storage tanks (ASTs) with spill proof secondary containment (Bay Region)
- ◆ Installed a new chemical storage building to store fertilizers, pesticides, etc. (North Region)
- Implemented new mercury switch disposal procedure. Central Maintenance in Lansing will store switches until they are recycled.
- ♦ Conducted pit cleaning of two bascule bridges. The collected storm water was tested and disposed of properly. (Bay, Southwest Regions)
- USTs are being tested annually for line tightness and leak protection. (Statewide)

### **Pollution Incident Prevention Plan Audits**

The Pollution Incident Prevention Plan (PIPP) audits conducted in 2005 revealed no major problems at MDOT's maintenance garages and there were no major spills at any MDOT facilities in 2006. The next round of audits is scheduled for 2008.

Based on the results of the PIPP audits, a 3-year cycle of maintenance training (safety, hazmat, environmental) is being discussed.

### **Pesticide Applicator Program**

Pesticides are applied on MDOT right-of-way in accordance with Applicator Certification Regulation 636 and Pesticide Use Regulation 637 of Part 83, Pesticide Control, of the Natural Resources and Environmental Protection Act, 1994 Public Act 451, as amended, (NREPA) and all other applicable state and federal regulations. These regulations require all applicators to be registered or certified to apply pesticides in the State of Michigan. MDOT requires all applicators to be certified if making roadside, guardrail, and brush pesticide applications on MDOT right-of-way. These applicators consist of MDOT, County and/or contractor personnel.

No changes were made to the existing Pesticide Applicator Program in 2006 and training scheduled for April 2007 will follow the same format as past years. The training is approved and attended by the Michigan Department of Agriculture (MDA). MDA will also issue recertification credits for the certified applicators. Approximately 60 attendees are anticipated for the 2007 training.

### **Road Salt/Sand Application**

MDOT tracks biweekly salt and sand usage from MDOT crews and contract agencies. A salt storage program is also in affect to assist contract agencies in updating their salt sheds. Salt and sand usage on state trunklines from October 2005 through April 2006 are shown in Table 4 and Table 5, respectively. It should be noted that it is difficult to make any year to year comparisons using the data due to variation in weather conditions and road conditions. See Appendix F, Pollution Prevention/Good Housekeeping, for more details regarding salt and sand application.

**Table 4 Salt Usage** 

	Winter 2004-2005	Winter 2005-2006
Region	Salt Tonnage per	Salt Tonnage per
	Lane Mile	Lane Mile
Superior	24	23.9
North	23	25.3
Grand	24	25.1
Bay	19	16.1
Southwest	17	14.3
University	18	14.8
Metro	36	20.6
Average	23	20.0

Note: Lane mile totals per region are within 10% from year to year.

**Table 5 Sand Usage** 

	Winter 2004-2005	Winter 2005-2006
Region	Sand Tonnage per	Sand Tonnage per
	Lane Mile	Lane Mile
Superior	13.2	9.4
North	8.2	7.3
Grand	3.7	4.1
Bay	0.0	0.0
Southwest	0.1	0.0
University	2.9	2.3
Metro	0.0	0.0
Average	4.1	3.3

Note: Lane mile totals per region are within 10% from year to year.

As discussed in the MITA Cross-Section, Winter 2007, MDOT is conscious of its salt and sand usage and tests new de-icing and anti-icing technologies to reduce salt and sand usage. These technologies include pre-wetting, surface overlay systems, and global positioning systems.

#### **Roadside Maintenance Activities**

MDOT's Maintenance Environmental Team is involved with maintenance activities that help prevent storm water pollution, such as street sweeping, catch basin maintenance, ditch clean out, culvert and underdrain maintenance, mowing, brush control, and bank stabilization. Depending on the location, MDOT's direct forces or local public agencies working under contract for MDOT will conduct these maintenance activities on a regular basis.

Catch basin cleaning, approach sweeping, and curb sweeping conducted by MDOT crews is tracked using the Maintenance Activity Reporting System (MARS). The Program Cost Accounting (PCA) details and costs are tabulated in Appendix F. Street sweeping and flushing. culvert/underdrain maintenance, and ditch clean-out activities for the contracted agencies are tracked using

Local Agency Payment System (LAPS) and are tabulated in Appendix F.

The culvert/underdrain maintenance activities include repair, removal, or replacement of catch basins, pipe culverts, pipe boxes, pipe headwalls, and underdrain tiles to culverts in a clean and serviceable condition. \$1,297,112 were spent for roadside and general maintenance activities conducted by MDOT, including cleaning catch basins and sweeping approaches and curbs. \$4,628,214 were spent for approximately 55,826 hours of activities conducted by local agencies, including street sweeping and flushing of approximately 21,680 lane miles, maintaining approximately 17,294 lane miles of culverts and underdrains, and cleaning out approximately 16,576 lane miles of ditches.

### **Litter Pick-Up Programs**

MDOT continues to work with external groups for litter pick-up along their roadways. These groups include Adopt-A-Highway Program, Youth Corps, and cooperation with the Department of Corrections. MDOT also conducts litter pick-up using MDOT maintenance crews. Additionally, mowing contracts require contractors to pick up litter before mowing. It is difficult to get an accurate quantity of litter removal as landfill receipts are not necessary for these programs. However, public feedback for these programs has been very positive.

### **Fertilizer Application**

Fertilizer application is not currently regulated by the government. The application of fertilizer on MDOT right-of-way is typically done on construction projects. These fertilizer applications are completed in accordance with MDOT's Standard Specifications for Construction, Section 816 and Section 917. There are very limited fertilizer applications made by MDOT Maintenance staff. No changes were made to the fertilizer specifications in 2006

### Focus for 2007

The primary focus in 2007 will be to work with the Post Construction Storm Water Management Implementation Team to update procedures and guidance materials regarding maintenance of post construction storm water BMPs. In addition, the following is planned:

- Working with a contract agency, for demonstration purposes, to better track sediment removal from the MDOT drainage system.
- New contracts for pesticide work at tourist facilities (rest areas) in the Bay Region will include language that pesticide and fertilizer materials may not be left on impervious surfaces.

- All regions are encouraged to use similar language in contracts for this work.
- ◆ The capital outlay fund (\$500,000) for environmental remediation continues to fund new projects at MDOT facilities such as aboveground storage tanks and chemical storage buildings.
- Incorporating pollution prevention on construction sites, such as bridge cleaning and concrete truck washout, into appropriate trainings.

### **Measurable Goals**

See Appendix A, Activities C-9 and C-12 to view the progress in reaching the interim milestones and measurable goals as defined in the SWMP.

### **Soil Erosion & Sedimentation Control**

### **Objective**

To enhance the current activities to effectively reduce accelerated soil erosion and resulting sedimentation on MDOT construction and maintenance projects.

### **Existing SESC Practices**

Many of MDOT's soil erosion and sedimentation control procedures have been in place at MDOT for many years and are described in the MDOT SESC Manual and Standard Specifications for Construction maintained by the Construction & Technology Division.

### **MDOT SESC Manual**

A revised SESC Manual was approved by MDEQ in July 2006. Since its approval, the manual has been distributed statewide and is now available to download from the MDOT Public Web Site at www.michigan.gov/mdot/. The manual was developed in cooperation with MDEQ to qualify MDOT as an Authorized Public Agency (APA). An APA is exempt from obtaining a Part 91 permit from a county or local enforcing agency but must still notify the agency of each proposed earth change.

### SESC Quality Assurance/Quality Control (QA/QC) Reviews

MDOT is proceeding with the SESC QA/QC review process. From now until the end of the permit cycle (April 1, 2009), each Transportation Service Center will be reviewed twice per the QA/QC Plan. The reviews will be triggered by the Engineer Certification Program (ECP). The recent change in the ECP from a three-year cycle to a four-year cycle will require revisiting the SESC QA/QC process to determine if changes are necessary.

In 2006, over 50 SESC QA/QC reviews were conducted at construction sites statewide following the SESC Program Review Process which was approved by the Environmental Committee in 2006. See Appendix G, *Soil Erosion & Sedimentation Control*, for review locations and a copy of the SESC Program Review Process. Overall, MDOT was pleased with the outcome of the reviews but noted a few key deficiencies which were immediately addressed with the applicable parties at the time of the QA/QC reviews. These deficiencies will also be addressed in the upcoming construction season through additional advisories and discussions and include the following:

 An Earth Change Plan is required for work outside of the grading limits but within the MDOT Right-of-Way per R 323.1703.

- ♦ Silt fence must be trenched in.
- ♦ Inlet protection must be maintained and in cooperation with pavement sweeping.

### Training: Part 91 and Part 31 of Act 451

Pursuant to Part 91 of Act 451, MDOT has established procedures for soil erosion and sedimentation control, as detailed in the MDOT SESC Manual. Targeted MDOT staff are trained and certified as required under Part 91. MDOT utilizes Certified Storm Water Operators as required under Part 31 of Act 451. Table 6 lists the number of staff in each region that are SESC trained and certified. Additionally, 435 MDOT staff are certified as Storm Water Operators.

Table 6 MDOT Staff SESC Trained and Certified

	Number of
	Staff SESC
Region	Certified
<b>Lansing Central Office</b>	16
Bay	74
Grand	75
Metro	119
North	86
Southwest	77
Superior	74
University	67
Total	588

The number of MDOT Staff trained and certified in Part 91 and Part 31 of Act 451 in 2006 increased substantially from 2005. In 2005, 171 MDOT Staff were certified as Storm Water Operators and 164 MDOT Staff were certified in Part 91.

### Slope Restoration Construction Advisory

In October 2006, a Construction Advisory (CA 2006-15), *Slope Restoration*, was issued reminding those involved with MDOT construction to conduct timely slope restoration during the construction phase to minimize soil erosion and subsequent off-site sedimentation. The primary components of slope restoration include topsoil, fertilizer, seed and mulch. See Appendix G for a copy of CA 2006-15.

### Focus for 2007

A SESC pocket guide will be developed for distribution at the 2007 MITA Superconferences and to the jobrelated public. This pocket guide will include an increased number of SESC details and photographs of

both acceptable and not acceptable construction site BMPs.

Upcoming SESC Activities:

♠ MDOT is currently working with industry to develop a Construction Quality Partnership (CQP). MDOT has selected five projects to pilot the CQP for the 2007 construction season. For these projects, MDOT staff will provide training for key Department and Contractor personnel involved with the projects. Each project will include four specific work items to improve construction quality. One of the work items will be SESC. This training is intended to enhance communication, decision-making skills and team building. The desired outcome will be improved project quality and regulatory compliance.

### **Measurable Goals**

See Appendix A, Activity C-7 to view the progress in reaching the interim milestones and measurable goals as defined in the SWMP.

### **Michigan Department of Transportation** Phase II Storm Water Management Program Annual Report for January 1, 2006 - December 31, 2006

### **Appendices**

Appendix A	Storm Water Management Plan Activity Sheets
Appendix B	MDOT-Sponsored Education and Outreach
Appendix C	Public Involvement and Participation
Appendix D	Illicit Discharge Elimination Program
Appendix E	Post Construction Storm Water Management
Appendix F	Pollution Prevention/Good Housekeeping
Appendix G	Soil Erosion & Sedimentation Control

## Appendix A Storm Water Management Plan Activity Sheets

Appendix A contains all of the activity sheets from Chapter 3 of the Storm Water Management Plan. Each activity sheet denotes modifications to the activity's interim milestones and measurable goals and also indicates which interim milestones and measurable goals have been completed or implemented as shown with gray shading.

Activity E-1:	Maintain and Use Lansing Information Center	1
Activity E-2:	Publish Articles in MDOT Publications	2
Activity E-3:	Provide Information on Watershed Stewardship on the MDOT Public Web Site	3
Activity E-4:	Provide Education Materials along with Tap-In/Discharge Permit Applications	4
Activity E-5:	Notify and Invite Public to Review and Comment on the Storm Water Management Plan (SWMP)	5
Activity E-6:	Determine Partnership Potential with MDEQ Statewide Public Education Program	6
Activity T-1:	Present Applicable Training Modules to the Job-Related Public	7
Activity T-2:	Certify MDOT's Staff for Pesticide/Fertilizer Application	9
Activity T-3:	Train Staff Responsible for Administering Part 91 and those having Decision Making Author SESC Plan Development or Review, Inspections, or Enforcement; and Storm Water Operators as Required under Part 31	•
Activity T-4:	Survey MDOT Staff on Storm Water Knowledge	
Activity I-1:	Submit and Implement Mapping Schedule for Outfalls (urbanized areas only)	12
Activity I-2:	Perform Inventory and Dry Weather Screening on Outfalls	13
Activity I-3:	Receiving and Notifying MDEQ of Illicit Discharges and Actions Taken	14
Activity I-4:	Report Updates and Changes to Legal Authority Status	15
Activity I-5:	Map Known Outfalls (statewide)	16
Activity C-1:	Maintenance Requirements for MDOT Permanent Best Management Practices (BMPs) (Po Construction)	
Activity C-2:	Identify and Coordinate with Metropolitan Planning Organizations (MPOs) Having Storm Water Quality Control Programs.	19
Activity C-3:	Procedure to Select, Apply, and Maintain Permanent Best Management Practices (BMPs) for Storm Water Management Activities (Post-Construction)	
Activity C-4:	Procedure to Work With MDEQ for Early Coordination on Initial Design Projects	21
Activity C-5:	Review Projects with Storm Water Discharges to Water Bodies with a Promulgated Total Maximum Daily Load (TMDL)	22
Activity C-6:	Implement Procedures to Select, Apply, and Maintain Permanent Best Management Practic for Storm Water Management Activities (Post-Construction)	
Activity C-7:	Internal Quality Assurance/Quality Control (QA/QC) Protocol for Construction Storm Water Control	
Activity C-8:	Periodically Update Drainage Manual	25
Activity C-9:	Documentation and Tracking of Road Maintenance Activities	26
Activity C-10:	Procedure for Outfall Labeling	27
Activity C-11:	Review Flow Control Structures	28
Activity C-12:	Audit the Pollution Incident Prevention Plan (PIPP) Requirements	29
Activity A-1:	Program Assessment and Reporting	30

### MDOT WILL NO LONGER REPORT ON THIS ACTIVITY.

**Activity E-1:** Maintain and Use Lansing Information Center

**Affected Party:** MDOT Employees involved with the storm water plan.

**Objective:** To maintain a library of storm water-related materials for training and educating

the job-related public, including video tapes, reference manuals and publications.

**Description:** A library of informational materials compiled to support activities performed for

the MDOT Storm Water Management Plan. The Lansing Information Center is open and located in the MDOT Library housed at the Murray D. Van Wagoner Building, 425 W. Ottawa Street, Lansing MI 48909. Materials can be checked out by contacting the Aquatic Resource Specialist within the Environmental

Section or the MDOT librarian.

**Annual Reporting:** Track the material usage, and the source and number of articles in library.

**Related Activities:** Activity A-1 - Program Assessment and Reporting; Activity T-1 - Training

Modules; Activity T-3 - Part 91 and Part 31 Training; Activity T-4 - Storm Water

Knowledge Survey

Permit Requirement: Part I.B.1.a(1): Educate the job-related public of hazards associated with

improper disposal of waste/illicit discharges.

Part I.B.1.a(3): Educate the job-related public of watershed stewardship and

implement program.

No.	Measurable Goals	Schedule	Responsible
1	The library of storm water related materials will be	Quarterly, On-going	MDOT
	updated quarterly with the most recent guidance,		Sponsored
	research, publications and training materials.		Education and
	[This goal is discontinued as it is not effective.		Outreach Team
	Updated educational materials are better found		(E&O Team)
	online.]		
2	A list of Storm water-related materials links will be	Starting December	
	updated quarterly on the MDOT Storm Water Public	31, 2006	
	Web Site. [Modified]	[On-going]	
3	Quarterly notices will be made in the Monday Memo to	By August 1, 2005	
	advertise the storm water-related library material.	[On-going]	
	[Modified] The MDOT Storm Water Public Web Site		
	is noted on all MDOT storm water educational		
	materials.		
4	The library of storm water related materials will be	By August 1, 2005	
	moved to a more prominent location. [Refer to MG #1]	<del>[Completed]</del>	
5	A system will be developed to track the checkout of	By August 1, 2005	
	library materials. [Refer to MG #1]	<del>[Completed]</del>	
6	A general survey of storm water awareness will be	Baseline Survey-	Storm Water
	conducted as described in Activity T-4. The survey	2005	Program
	will be designed to assess the educational program as a	[Completed]	Manager
	whole including the effectiveness of article publication.		
7	A follow up survey will be conducted in 2008 to assess	Follow up Survey-	Storm Water
	the need for program modifications.	2008	Program
			Manager

### **Activity E-2:** Publish Articles in MDOT Publications

**Affected Party:** Job-Related Public

**Objective:** To educate the job-related public on watershed stewardship, the MDOT storm

water program, illicit discharges, construction and post-construction BMPs,

and/or new program announcements.

**Description:** Prepare storm water program articles for publication using internal MDOT

publications. The articles are to provide information about the MDOT storm water program in a manner to gain understanding and support for implementing

the program by the job-related public.

**Annual Reporting:** Track topics and number of articles circulated.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity E-1 - Lansing Information Center Activity E-3 - MDOT Public Web Site

Activity T-4 - Storm Water Knowledge Survey

Permit Requirement: Part I.B.1.a(1): Educate the job-related public of hazards associated with

improper disposal of waste/illicit discharges.

Part I.B.1.a(3): Educate the job-related public of watershed stewardship and

implement program.

No.	Measurable Goals	Schedule	Responsible
1	Develop and publish storm water-related articles in a Region-based newsletter, Adopt-A-Highway newsletter, Monday Memo, or other appropriate newsletters at least quarterly throughout the Permit cycle. Contract agencies will be included on the newsletter distribution list.	Quarterly beginning April 1, 2006 [On-going]	E&O Team and MDOT Communications Staff.
2	Provide storm water information to contract agencies through the Michigan Local Technical Assistance Program (LTAP).	By February 1, 2006 [On-going]	E&O Team and Maintenance Environmental Team (MET)
3	A general survey of storm water awareness will be conducted as described in Activity T-4. The survey will be designed to assess the educational program as a whole including the effectiveness of article publication.	Baseline Survey-2005 [Completed]	Storm Water Program Manager
4	A follow up survey will be conducted in 2008 to assess the need for program modifications.	Follow up Survey- 2008	Storm Water Program Manager

### Activity E-3: Provide Information on Watershed Stewardship on the MDOT

**Public Web Site** 

**Affected Party:** Job-Related Public and Traveling Public

Objective: To educate the job-related and traveling public on MDOT's watershed

stewardship practices and promote these practices on all projects where feasible.

**Description:** MDOT developed a public information Web site about the Phase II storm water

program. The Web site provides general information about watershed stewardship practices as well as links to pertinent storm water-related materials. This information will be maintained and monitored to report Web site usage.

Annual Reporting: Track internal and external Web site hits and the number of SWMP document

downloads on the MDOT Storm Water Public Web Site.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity E-1 - Lansing Information Center

Activity E-2 - Publish Articles in MDOT Publications

Activity T-4 - Storm Water Knowledge Survey

Permit Requirement: Part I.B.1.a(1): Educate the job-related public of hazards associated with

improper disposal of waste/illicit discharges.

Part I.B.1.a(3): Educate the job-related public of watershed stewardship and

implement program.

Part I.B.6: Ensure MDOT employees maintain and follow proper pollution

prevention controls.

No.	Measurable Goals	Schedule	Responsible
1	The MDOT Storm Water Public Web Page will be	Quarterly	E&O Team and
	updated quarterly with the most recent MDOT storm	[On-going]	MDOT Information
	water information and news.		and Technology Mgr.
2	A link to the MDOT Storm Water Public Web Page	By April 1, 2006	Storm Water Program
	will be added to the MDOT Public Web Site home	[When possible]	Manager
	page.		
	[This is turning out to be difficult as it is highly		
	competitive to be allotted space on the homepage.]		
3	A storm water-related quiz/comment form will be	By December	E&O Team and
	developed for inclusion on the MDOT Storm Water	31, 2005	MDOT Information
	Public Web Page.	[Completed]	and Technology Mgr
	[Modified] A Jeopardy-type format has been selected		
	for this activity.		
4	A general survey of storm water awareness will be	Baseline Survey-	Storm Water Program
	conducted as described in Activity T-4. The survey	2005	Manager
	will be designed to assess the educational program as	[Completed]	
	a whole including the effectiveness of article		
	publication.		
5	A follow up survey will be conducted in 2008 to	Follow up	Storm Water Program
	assess the need for program modifications.	Survey- 2008	Manager

### Activity E-4: Provide Education Materials along with Tap-In/Discharge Permit Applications

Affected Party: Applicants obtaining a Discharge/Tap-In Permit and Region/TSC Staff involved

with reviewing and approving permits.

**Objectives:** To inform applicants of acceptable discharges into the MDOT drainage system,

and also of the potential negative impacts to water quality from unacceptable or illegal discharges and ways to mitigate these impacts. To inform MDOT permitting and utilities staff statewide that this education material will be distributed with the tap-in/discharge permit and that educating applicants is

important to protecting water quality.

**Description:** Prepared education materials for typical development activities connecting to

MDOT facilities. Established and implemented procedures for distributing these

materials.

**Annual Reporting:** Track quantity of permit applications/educational materials distributed.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity I-4 - Updates to Legal Authority

Permit Requirement: Part I.B.1.c: Provide pollutant prevention information to applicants that apply to

tap into the MDOT drainage system.

Part I.B.1.c: Train MDOT employees to provide pollution prevention education

during application process.

No.	Interim Milestones	Schedule	Responsible
1	Develop educational material to be included in the	Completed in	IDEP Team
	tap-in/discharge permit application.	November 2004	
No.	Measurable Goals	Schedule	Responsible
1	Distribute education materials to 100% of tap-	Ongoing beginning	MDOT Permitting
	in/discharge permit applicants.	December 2004	Staff
2	Instruct MDOT staff to distribute materials as	By June 1, 2005	
	instructed in the revised Construction Permit	[Completed]	
	Manual (CPM).		
3	Review the adequacy of the procedure for	Every five years	
	distributing materials.		

Activity E-5: Notify and Invite Public to Review and Comment on the Storm

Water Management Plan (SWMP)

Affected Party: Traveling Public, Job-Related Public, NPDES Watershed Permit Stakeholders,

Local Stream / Watershed Protection Groups

**Objective:** To obtain comments, statewide, from the public on the SWMP.

**Description:** Establish procedures for the public notice and distribution of the draft SWMP.

Provide at least 30 days for public review and comment.

Annual Reporting: Track public comments. Track number of downloads of the draft SWMP from

Web site

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity E-3 - MDOT Public Web Site

Permit Requirement: Part I.B.2: Encourage public input.

Part I.B.2.a: Notify public of when and where preliminary and final SWMP are

available for review.

Part I.B.2.b: Input actively sought from stakeholder groups and local

organizations for comment on SWMP.

### THIS ACTIVITY IS COMPLETE AND WAS REPORTED ON IN THE ANNUAL REPORT FOR 7/1/03-12/31/04

Activity E-6: Determine Partnership Potential with MDEQ Statewide Public

**Education Program** 

**Affected Party:** Traveling Public

**Objective:** To evaluate the potential for MDOT to educate the public through the MDEQ

statewide public education program.

**Description:** As an alternative to performing a stand-alone education program for the traveling

public, MDOT will evaluate providing financial support to a statewide campaign being developed by MDEQ. If MDOT decides not to support the MDEQ campaign, they would be required to perform their own program, in which case, a

program plan will be developed and submitted to MDEQ for approval.

Annual Reporting: MDOT will decide whether or not to participate in statewide program.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Permit Requirement: Part I.B.1.b: If the MDEQ develops a statewide public education program,

MDOT may either seek a partnership agreement with the MDEQ for implementation of Part I.B.1.b. of this Permit, or develop and implement a

program to increase awareness and seek positive public behavior.

No.	Measurable Goals	Schedule	Responsible
1	Attend meetings with MDEQ statewide education	Once MDEQ	Consultant
	advisory committee and MDEQ decision makers.	finalizes their	and MDOT
		statewide public	Storm water
		education program,	Program
		MDOT will decide	Manager
2	Obtain statewide campaign materials including cost to	within 6 months	
	participate and evaluate the potential value of entering	whether or not to	
	into a partnership with MDEQ.	participate. A public	
3	Develop participation agreement with MDEQ or	education plan will	
	develop an MDOT Public Education Plan (PEP).	be developed within	
	•	12 months if MDOT	
		chooses not to	
		participate.	

**Activity T-1: Present Applicable Training Modules to the Job-Related Public** 

**Target Audience:** Lansing and Region/TSC Staff and contract agencies

**Objective:** Educate the Job-Related Public about the Storm Water Management Program.

Use the four 15 minute MDOT storm water program training modules to train **Description:** 

Lansing and Region/TSC staff and contract agencies.

Module One: Introduction to SW Management

Module Two: Best Management Practices

Module Three: Maintenance Considerations

Module Four: Illicit Discharge & Maintenance

**Annual Reporting:** Track training attendance. Track contract agencies receiving modules. **Related Activities:** 

Activity T-4 - storm water survey; Activity I-3 - illicit discharge notification;

Activity T-3 - Part 91 and Part 31 training

Permit Requirement: Part I.B.1.a(1), Part I.B.1.a(2), Part I.B.1.a(3), Part I.B.4.b(2), Part I.B.6

No.	Interim Milestones	Schedule	Responsible
1	Determine target audiences for the storm water	By June 1, 2005	Implementation
	modules. [Modified] Determine target audiences	[Modified]	Teams as
	annually for new procedure training.	On-going	appropriate
2	Add storm water awareness training to existing MDOT	During 2006	E&O Team
_	training database (On-Track) to track individual	[On-going]	
	employee training. Include training modules as part of	[- 8- 8]	
	select employee performance evaluations in 2006.		
	[Modified] Incorporate routine trainings into existing		
	MDOT training database (On-Track) to track		
	individual employee training.		
3	Provide train-the-trainer preparation for presenters.	On-going	Implementation
			Teams as
			appropriate
4	Ensure modules are delivered during staff meetings and	On-going	Implementation
	other meetings as warranted.		Teams as
			appropriate
5	Develop training evaluation surveys.	July 1, 2005	E&O Team
		[Modified]	
		On-going	
No.	Measurable Goals	Schedule	Responsible
1	Review and update modules.	Annually starting	E&O Team and
	[Modified] Review and update routine trainings.	October 1, 2005	MDOT Staff
		[Modified]	
	T 1 D 1 TGG G G G 11	On-going	* .
2	Train Region/TSC Staff with storm water-related	By April 1, 2009	Implementation
	responsibilities on the four storm water modules.		Teams as
	[Modified] Train Region/TSC Staff with storm water-		appropriate
	related responsibilities on storm water issues relevant to their job.		
3	Encourage trainees to complete training evaluation at	Start Aug. 1, 2005	Implementation
3	the close of each training session.	[Modified]	Teams as
	are cross of each duming session.	On-going	appropriate
4	Provide modules to contract agencies and contracting	By February 1, 2006	Maintenance
	associations with a request to use the modules. Provide	[On-going]	Environmental
	information through the Michigan Local Technical	[on going]	Team (MET)
	Assistance Program (LTAP).		104111 (11221)
	[Modified] Provide training and information		
	regarding storm water issues to contract agencies and		
	associations. Provide information through LTAP.		
5	A general survey of storm water awareness will be	Baseline Survey-	Storm Water
	conducted as described in Activity T-4. The survey	2005	Program
	will be designed to assess the educational program as a	[Completed]	Manager
	whole including the effectiveness of article publication.		
6	A follow up survey will be conducted in 2008 to assess	Follow up Survey-	Storm Water
	the need for program modifications.	2008	Program
			Manager

### Activity T-2: Certify MDOT's Staff for Pesticide/Fertilizer Application

Target Audience: MDOT Maintenance Staff and Contract Agencies

**Objective:** To reduce pollution entering waters of the state, statewide, that originates from

pesticide/fertilizer application.

**Description:** The existing training and certification program for pesticide/fertilizer

applications will be evaluated and tracked to document performance and to prevent storm water pollution. Results will be used to recommend changes if

appropriate.

**Annual Reporting:** 

• Track the number of individuals attending annual pesticide training.

• Track number of MDOT personnel certified as a pesticide applicator.

 Summarize evaluation and review of programs, policies, procedures and information.

Report changes to fertilizer specifications.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Permit Requirement: Part I.B.6.f: Minimize the discharge of pollutants related to storage, handling

and use of herbicides/fertilizers. Provide employee training for

herbicides/fertilizers to protect water quality.

No.	Measurable Goals	Schedule	Responsible
1	MDOT Staff applying pesticides will be trained and	On-going	MDOT
	certified annually per Michigan Department of		Maintenance
	Agriculture requirements.		Staff
2	MDOT Staff or Contract Agencies will follow	On-going	MDOT
	MDOT's Standard Specifications for Construction,		Maintenance
	Sections 816 and 917 for fertilizer application		Staff
	practices.		
3	Evaluate application practices and pollution	Annually starting	Maintenance
	prevention measures and recommend and formalize	April 1, 2006	Environmental
	any changes if appropriate.	[On-going]	Team, MDOT
			Maintenance
			Staff

# Activity T-3: Train Staff Responsible for Administering Part 91 and those having Decision Making Authority for SESC Plan Development or Review, Inspections, or Enforcement; and Storm Water Operators as Required under Part 31

**Affected Party:** MDOT Maintenance Supervisors and Coordinators and Construction Supervisors

**Objective:** To reduce non-storm water discharges to the MEP to receiving water bodies.

**Description:** The existing MDEQ sponsored Soil Erosion and Sedimentation Control (SESC)

training program will be attended by appropriate maintenance staff. Successful completion of the training and certification of storm water operators will be

documented.

**Annual Reporting:** Total number of staff trained and certified for compliance with Part 31 and Part

91 requirements.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity C-7 - QA/QC Protocol for Construction Storm Water Control

Permit Requirement: Part I.B.5.a: MDOT shall meet the following requirements on MDOT

construction sites statewide, but may rely on the MDOT SESC Plan and Michigan's Permit by Rule to the extent that those controls meet the requirements: 1) Implement soil erosion and sedimentation controls, 2) Control demolition and construction waste materials at construction sites, 3) Consider potential water quality impacts during road construction plan reviews, and 4) Inspect sites to assure that pollution control measures are appropriate and

functional.

Part I.B.6: The program shall include employee and contractor training to prevent and reduce storm water pollution through proper implementation and maintenance of BMPs. The program may be developed and implemented using BMP guidance and training materials that are available from federal, state or

local agencies.

No.	Measurable Goals	Schedule	Responsible
1	MDOT Staff Responsible for Administering Part 91	On-going	MDOT
	and those having Decision Making Authority for		Maintenance
	SESC Plan Development or Review, Inspections, or		Supervisors and
	Enforcement will receive NPDES training.		Coordinators
2	MDOT Staff Responsible for Administering Part 91	By April 1, 2006	and
	and those having Decision Making Authority for	[On-going]	Construction
	SESC Plan Development or Review, Inspections, or		Supervisors
	Enforcement will be certified as Storm Water		
	Operators as Required under Part 31.		
3	Add NPDES training to MDOT Performance	By April 1, 2006	MDOT Storm
	Excellence Division tracking system (On-Track).	[Completed]	Water Program
	• •		Manager

**Activity T-4:** Survey MDOT Staff on Storm Water Knowledge

**Affected Party:** Representative MDOT Staff

**Objective:** To determine the current level of storm water knowledge for a statistical mix of

administrative, technical, professional, and engineering staff to evaluate the

effectiveness of the education program.

**Annual Reporting:** 

• Report the survey results.

• Report the results of subsequent survey and compare.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity E-1 - Lansing Information Center

Activity E-2 - Publish Articles in MDOT Publications

Activity E-3 - MDOT Public Web Site

Activity T-1 - Training Modules for Job-Related Public

Permit Requirement: Part I.B: The MAXIMUM EXTENT PRACTICABLE requirement shall be met

by implementation of BMPs to comply with minimum measures for which the permittee has authority, implementation of BMPs to comply with minimum levels of storm water pollution control established in TMDLs if applicable, and a

demonstration of effectiveness or environmental benefit for each BMP.

No.	Interim Milestones	Schedule	Responsible
1	Develop and prepare baseline survey for	Completed	Consultant and
	distribution.		MS4 Team
No.	Measurable Goals	Schedule	Responsible
1	A general survey of storm water awareness	Baseline Survey-2005	Storm Water
	will be conducted as described in Activity T-	[Completed]	Program Manager
	4. The survey will be designed to assess the		
	educational program as a whole including the		
	effectiveness of article publication.	E 11 G	C. W.
2	A follow up survey will be conducted in 2008	Follow up Survey-	Storm Water
	to assess the need for program modifications.	2008	Program Manager
3	Review the 2005 survey for baseline	By April 1, 2006	Consultant and
	information.	[Completed]	MS4 Team
4	Review the 2008 survey to determine program	By April 1, 2009	MDOT Storm
	effectiveness.		Water Program
			Manager
5	Increase the number of staff who are fully	2005 to 2008	N/A
	aware of MDOT's storm water program by		
	20% from 2005 to 2008.		

Activity I-1: Submit and Implement Mapping Schedule for Outfalls

(urbanized areas only)

**Affected Party:** MDOT Staff and Contractor/Consultant

**Objective:** To develop a mapping schedule and complete mapping of outfalls in MDOT

right-of-way in urbanized areas including MDOT roads crossing 305(b)-listed

water bodies and other non-impaired water bodies.

**Annual Reporting:** Track completed maps.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity I-5 - Map Known Outfalls

Activity C-10 - Procedure for Outfall Labeling

**Permit Requirement:** Part I.B.3.a: Within one year, submit schedule for maps of known outfalls.

Maps shall be developed for outfalls at roadway crossings no later than

expiration of Permit.

No.	Interim Milestones	Schedule	Responsible
1	Complete maps of outfalls at stream crossings over or within 300 feet of impaired waters of the state within urbanized areas based on field inspection of top priority outfalls.	By April 1, 2009	Consultant And IDEP Team
2	Complete maps of outfalls at stream crossings over waters of the state within urbanized areas that are not field screened based on a GIS analysis.	By April 1, 2006 [Completed]	Consultant And IDEP Team
3	Develop process for notifying consultant of newly constructed outfalls.	By April 1, 2009	Consultant And IDEP Team
4	Link outfall screening/investigations to the asset management team's inventory database procedure.	By April 1, 2009	Consultant And IDEP Team
No.	Measurable Goals	Schedule	Responsible
1	Map outfalls in MDOT right-of-way in urbanized areas according to the schedule posted in the SWMP.	See Table 3-3 of the SWMP	Consultant And IDEP Team

**Activity I-2:** Perform Inventory and Dry Weather Screening on Outfalls

Affected Party: Consultant, MDOT Region Storm Water Coordinators, and Storm Water

Program Manager

Objective: To identify illicit discharges and connections from the MDOT storm sewer

system within 2000 Census urbanized areas as prioritized in the IDEP Plan.

**Annual Reporting:** 

• Number and location of confirmed outfalls.

• Total number of suspected illicit connections/discharges identified.

• Number and location of manholes tested for each suspected illicit connection/discharge.

• Results of sample analysis.

• Description and number of illicit connections/discharges verified.

• Estimated amount and type of pollutant removed.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity I-1 - Submit and Implement Mapping Schedule for Outfalls

Activity I-4 - Updates to Legal Authority

Activity I-5 - Map Known Outfalls

Permit Requirement: Part I.B.3.b: Outfalls prioritized and top priority outfalls (305(b)-listed water

bodies impaired by untreated sewage, bacteria, pathogens, nutrient enrichment, nuisance plant growth, nuisance algal growth, low dissolved oxygen, sediments, oil or grease, fish kills, and fish or macroinvertebrate communities rated poor)

shall be screened for dry weather discharges.

Part I.B.3.b: Use screening results to identify and eliminate illicit discharges as

expeditiously as practicable.

Part I.B.3.b: Illicit connections that cannot be disconnected immediately shall be

identified in annual report and eliminated as soon as possible.

No.	Measurable Goals	Schedule	Responsible
1	Follow illicit discharge procedure (Section 3.3)	Beginning April 1,	Consultant,
	for 100% of illicit discharges found.	2005	IDEP Team, And
		[On-going]	Region IDEP
			Coordinators
2	Update MDEQ of the areas selected for dry	Monthly starting	Consultant,
	weather screening.	November 1, 2004	IDEP Team, And
		[On-going]	Region IDEP
			Coordinators

Activity I-3: Receiving and Notifying MDEQ of Illicit Discharges and Actions

**Taken** 

Affected Party: MDOT Region Storm Water Coordinators, TSC Managers, and Storm Water

Program Manager

**Objective:** To receive reports and notify the MDEQ of illicit discharges, statewide, to the

MDOT storm sewer system. To take action toward removing these discharges.

**Description:** Procedure for receiving and responding to reports of illicit discharges is

established as part of Section 9.13 of the Construction Permit Manual. Training to effectively implement the procedure will be conducted. Procedure for receiving reports from construction site runoff is already in place as part of the

SESC Manual.

**Annual Reporting:** 

• Track the number of reports received and the follow-up actions taken.

Track the number of illicit connections/discharges identified and removed.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity T-1 - Present Training Modules to Region/TSC staff

Activity I-4 - Updates to Legal Authority

Permit Requirement: Part I.B.3.c: Provide a system to accept and respond statewide to reports of illicit

discharges received from job-related public.

No.	Interim Milestone	Schedule	Responsible
1	Add illicit discharge reporting and notification	By June 1, 2005	E&O Team
	information to Training Module Four.	[Modified]	
	[Modified] Develop illicit discharge reporting and	By May 1, 2006	
	notification training and provide to region IDEP	[Completed]	
	coordinators.		
No.	Measurable Goals	Schedule	Responsible
1	Train Maintenance and Construction staff with storm	By December 1,	E&O Team and
	water responsibilities to follow the illicit discharge	2005	Region IDEP
	notification procedure.	[On-going]	Coordinators
2	Add Illicit Discharge Notification training to	By April 1, 2006	Storm Water Program
	existing MDOT employee training database (On-	[Completed]	Manager
	Track).		

**Activity I-4:** Report Updates and Changes to Legal Authority Status

**Affected Parties:** Landowners discharging or planning to discharge to MDOT's drainage system,

MDOT Permit & Utilities Staff

**Objective:** To regulate discharges to MDOT's drainage system and require compliance with

its permit.

**Annual Reporting:** Report changes to legal authority by revising Sections 9.13 and 14.01 of the

Construction Permit Manual.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity I-2 - Perform Inventory and Dry Weather Screening on Outfalls

Activity I-3 - Receiving and Notifying MDEQ of Illicit Discharges and Actions

Taken

**Permit Requirement:** Part 1.B.3.d(1): Legal authority to regulate the contribution of pollutants to the

drainage system.

Part 1.B.3.d(2): Legal authority to regulate the rate of water inflow.

Part 1.B.3.d(3): Legal authority to prohibit illicit connections/discharges into

drainage system.

Part 1.B.3.d(4): Legal authority requiring compliance with conditions in Permit.

No.	Measurable Goal	Schedule	Responsible
1	Assess legal authority annually to determine if any	Annually	Permits/
	updates or changes are necessary.	[On-going]	Utilities
			[Modified]
			IDEP
			Workgroup

**Activity I-5:** Map Known Outfalls (statewide)

Affected Parties: MDOT Region Storm Water Coordinators, Planning and Design, Construction &

Technology Staff, and Asset Management

**Objective:** To map known outfalls statewide based on existing survey information. To

develop and implement a procedure to revise the known outfall maps annually.

Annual Reporting: Document the procedure for making annual map revisions, and track updated

outfalls.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity I-2 - Perform Inventory and Dry Weather Screening on Outfalls

Activity C-10 - Procedure for Outfall Labeling

Permit Requirement: Part 1.B.3.a: Within one year following the effective date of this Permit, the

permittee shall submit a schedule for providing maps showing the location of

known outfalls.

### **Known Outfall Mapping Schedule (statewide)**

(from Table 3-2 in the MDOT Storm Water Management Plan)

Activity	Schedule	Responsible Party
Compile survey data.	By August 1, 2005 [Completed]	MDOT Supervising Surveyor
Develop guideline to define	By August 1, 2005 [Completed]	Consultant, Outfall Mapping
outfalls.		Workgroup
Develop draft known outfall	By December 31, 2005	Consultant
maps.	[Completed]	
Provide draft known outfall	By February 1, 2006	Consultant
maps to region storm water	[Modified] <i>By May 1, 2006</i>	
coordinators.	[Completed]	
Review draft maps.	By May 1, 2006	Region Storm Water
	[Completed]	Coordinators and TSC/Region
		Staff
Revise maps.	By August 1, 2006 [Completed]	Consultant
Provide final known outfall	By September 1, 2006	Consultant
maps to MS4 Committee.		
Review final maps.	By December 1, 2006	MS4-Committee
Finalize Maps.	By March 1, 2007 [Completed]	Consultant
Develop and implement an	By April 1, 2007	Outfall Mapping Workgroup,
internal process for making		Consultant
annual map revisions.		
Update known outfall maps	Annually starting April 1, 2008	Consultant, MS4 Committee
annually and include in the	[On-going]	
annual progress reports.		

No.	Interim Milestones	Schedule	Responsible
1	Compile survey data.	By August 1, 2005	MDOT
		[Completed]	Design
			Surveys
2	Develop guideline to define outfalls.	By August 1, 2005	IDEP Team
		[Completed]	
No.	Measurable Goals	Schedule	Responsible
1	Map known outfalls in MDOT right-of-way	Starting April 1, 2005	Consultant
	statewide according to the schedule posted in the	(See Table 3-2 in the	and IDEP
	SWMP.	SWMP) [Completed]	
2	Develop and implement an internal process for	By April 1, 2007	Consultant
	making annual map revisions.		and IDEP
3	Update known outfall maps annually and include	Annually starting	Consultant
	in the annual progress report.	April 1, 2008	and IDEP

Activity C-1: Maintenance Requirements for MDOT Permanent Best

**Management Practices (BMPs) (Post-Construction)** 

Affected Party: MDOT Maintenance, Maintenance Activity Reporting System (MARS) Team,

Delivery, and Design Staff

**Objective:** To protect receiving water quality statewide by developing and implementing

maintenance requirements for permanent MDOT-approved BMPs.

**Annual Reporting:** Track BMP maintenance activities using MARS.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity C-6: Implement Procedures to Select and Apply Best Management

Practices for Storm Water Management Activities (Post-Construction)

Permit Requirement: Part I.B.4.b(2): Requirements for long-term operation and maintenance of

BMPs.

Part I.B.6.a(1): Statewide routine maintenance for structural controls.

Part I.B.6.a(2): In urbanized areas, cleaning schedules may need to be enhanced if control measures fail to adequately reduce the discharge of pollutants to or

from the drainage system.

No.	Interim Milestones	Schedule	Responsible
1	Review draft procedure for maintenance of permanent BMPs with appropriate MDOT entities for approval.	By June 1, 2006 [Modified] By July 1, 2007	Post- Construction Storm Water
2	Document maintenance procedures and issue staff guidance.	By August 1, 2006 [Modified] By Sept. 1, 2007	Management (Post-Const.) Team
3	Review Maintenance Performance Guides and update accordingly.	By October 1, 2006 [Modified] By Dec. 1, 2007	[Modified] And Maintenance Environmental
4	Notify appropriate staff of changes to manuals.	By December 31, 2006 [Modified] By Feb. 1, 2008	Team (MET)
No.	Measurable Goals	Schedule	Responsible
1	Develop and implement procedures for maintaining permanent BMPs not already having a maintenance procedure.	By December 31, 2006 [Modified] By Feb. 1, 2008	Post-Const Team [Modified] And MET
2	Develop and implement a procedure for maintaining each <u>new</u> permanent BMP within one year of formal adoption of the new permanent BMP.	As needed beginning December 31, 2006 [Modified] Feb. 1, 2008	Post-Const Team [Modified] And MET
3	Maintain existing permanent BMPs according to existing MDOT procedures.	Ongoing	
4	Evaluate ways to improve maintenance practices in urbanized areas if control measures fail to adequately reduce discharge of pollution.	As needed beginning April 1, 2006	

and Coordinate with Metropolitan **Activity C-2: Identify Planning** 

Organizations (MPOs) Having Storm Water Quality Control

Programs.

**Affected Parties:** MDOT Staff and MPOs

**Objective:** To identify and coordinate, statewide, with MPOs having storm water quality

control programs to properly handle storm water management issues during

construction and maintenance activities.

#### **Annual Reporting:**

Track letters distributed to the planning organizations.

- Track letters distributed to watershed and environmental groups soliciting area of concern comments.
- Track the major action environmental documents (environmental assessments and environmental impact statements) distributed to watershed groups for their comments.
- Track responses from watershed and environmental groups concerning areas of concern.
- Track any early coordination meetings held with watershed and environmental groups including whether groups attend a public meeting or comment on one of the major action documents.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity C-4 - MDEQ Early Coordination

Activity C-5 - Storm Water Discharges to TMDL Water Bodies

**Permit Requirement:** Part I.B: Within areas with watershed management plans, reducing discharge to the maximum extent practicable shall include implementation of BMPs to comply with watershed goals.

> Part I.B.2.c: Where MPOs exist, MDOT shall identify and cooperate with local storm water master planning processes and the MPO. MDOT shall implement storm water controls as necessary to cooperate with local storm water master plans.

> Part I.B.4.a: Program to coordinate with local planning efforts that conform with the cooperative planning requirements of 23 CFR 450.210 and 23 CFR 450.312 and which considers potential environmental effects of impervious surfaces. Part I.B.4.a: MDOT shall make information available to local planning efforts.

No.	Measurable Goals	Schedule	Responsible
1	Notify recognized watershed and environmental	By June 1, 2005	Consultant,
	groups that MDOT is accepting input on special BMP	[Letter mailed	Storm Water
	requirements for sensitive streams or portions of	February 2006]	Program
	streams.		Manager
2	Consider watershed and environmental group input	Ongoing beginning	MDOT Region
	during early coordination of MDOT transportation	April 1, 2006	Planning and
	projects. [through Context Sensitive Solutions]		Design Staff

Activity C-3: Procedure to Select, Apply, and Maintain Permanent Best

**Management Practices (BMPs) for Storm Water Management** 

**Activities (Post-Construction)** 

Affected Party: MDOT Maintenance, Planning and Design, Traffic & Safety, Maintenance

Environmental Team (MET), and MS4 Team

**Objective:** To develop a procedure for selecting, applying and maintaining permanent BMPs

for selected MDOT projects statewide.

**Annual Reporting:** Track permanent BMP installation and maintenance.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity C-4 - MDEQ Early Coordination

Activity C-5 - Storm Water Discharges to TMDL Water Bodies

Activity C-6 - Select, Apply, Maintain Permanent BMPs

Activity C-8 - Update Drainage Manual

**Permit Requirement:** Part I.B.4.b(1): Requirements for implementation of BMPs.

PartI.B.4.b(2): Requirements for long-term operation and maintenance of BMPs.

No.	Interim Milestones	Schedule	Responsible
1	Evaluate procedures for selecting, applying, and	By December 31,	Post-Const
	maintaining permanent BMPs. Approved MDOT	2005 [Completed]	Team
	permanent BMPs are located in the Drainage Manual.		
	Develop a procedure to add new BMPs to the MDOT-		
	approved BMP list.		
2	Review options with appropriate MDOT entities		
	including development of a funding source based on		
	research from other states.		
3	Make a recommendation for approval.		
4	Lay out a detailed framework for the approved	By August 1, 2006	
	procedure.	[Modified]	
5	Document procedure and issue staff guidance.	By July 1, 2007	
6	Update the existing process in the Drainage Manual	By December 31,	
	and tie the process into the scope verification	2006	
	procedure.	[Modified]	
7	Notify appropriate staff of changes to manuals.	By Dec. 31, 2007	
No.	Measurable Goals	Schedule	Responsible
1	Develop procedure for selecting, applying, and	By December 31,	Post-Const
	maintaining permanent BMPs.	2005 [Completed]	Team
2	All projects will be evaluated for permanent storm	Beginning December	MDOT
	water BMP inclusion during scoping/early design.	31, 2006	Design Staff
		[Modified]	
		By Dec. 31, 2007	

Activity C-4: Procedure to Work With MDEQ for Early Coordination on

**Initial Design Projects** 

Affected Parties: MDOT Development, Design, Real Estate, Environmental, and Maintenance

Staff and MDEQ Staff

**Objective:** To have early coordination with MDEQ for input on BMP type and placement of

select projects statewide.

**Annual Reporting:** 

 Track projects where early coordination was sought with MDEQ and other regulatory agencies.

• Track projects where MDEQ provided timely recommendations.

• Document actions taken based on comments received from MDEQ.

• Document the results of the annual meeting with MDEQ Water Bureau on

early coordination issues.

**Related Activities:** Activity A-1 - Program Assessment and Reporting; Activity C-2 - Coordinate

with MPOs; Activity C-5 - Storm Water Discharges to TMDL Water Bodies;

Activity C-8 - Update Drainage Manual

**Permit Requirement:** Part I.B.4.c: Allow MDEQ review of preliminary construction plans and provide

input on placement of drainage and BMPs.

No.	Interim Milestones	Schedule	Responsible
1	Develop draft procedure for early coordination	By April 1, 2005	Public Involvement and
	on initial design projects.	[Completed]	Participation (PIP)
2	Meet with MDEQ to further evaluate the early		Implementation Team
	coordination procedure.		
3	Review options with appropriate MDOT and	By August 1, 2005	
	MDEQ entities and make a recommendation	[Completed]	
	for approval. Update manuals and issue staff		
	guidance accordingly.		
No.	Measurable Goals	Schedule	Responsible
1	Develop procedure for coordinating with	By August 1, 2005	PIP Team
	MDEQ on initial design projects.	[Completed]	
2	Train design staff with storm water	By April 1, 2006	Region Permitting,
	responsibilities.	[Modified]	Planning, and TSC
		By August 1, 2007	Design Staff
3	All projects triggering early coordination with	By April 1, 2006	Cost/Sched. Engineer,
	the MDEQ-Water Bureau as described in the	[Modified]	Region Permitting,
	Early Coordination for Post-Construction	By 2007 Scoping	Planning, and TSC
	BMPs Procedure will seek involvement from	Process	Design Staff
	appropriate regulatory agencies.		

Activity C-5: Review Projects with Storm Water Discharges to Water Bodies

with a Promulgated Total Maximum Daily Load (TMDL)

Affected Party: MDOT Maintenance, Planning and Design, Traffic & Safety, Maintenance

Environmental Team (MET), MS4 Team and TSC Staff

**Objective:** To develop a procedure to review projects with storm water discharges to water

bodies with a promulgated TMDL and to and implement storm water controls

statewide to meet responsibilities established by TMDLs to the MEP.

Annual Reporting: Track location of projects, location of TMDL waters and how MDOT complied

with TMDL requirements.

**Related Activities:** Activity A-1 - Program Assessment and Reporting; Activity C-2 - Coordinate

with MPOs; Activity C-4 - MDEQ Early Coordination; Activity C-8 - Update

Drainage Manual

Permit Requirement: Part I.B.paragraph 2: If a water body has a TMDL, the appropriate water quality

requirements for that pollutant may be defined in the TMDL. In that event, MEP includes, but is not limited to, the development, implementation and enforcement of storm water controls designed to meet the permittee's responsibilities established by the TMDL. Any reduction achieved through implementation of controls in accordance with Part I.B. of this permit shall count toward

compliance with the waste load allocation of the TMDL.

No.	Interim Milestones	Schedule	Responsible
1	Post interactive mapping system on the MDOT Storm	By June 1, 2005	Consultant
	Water Web Site showing MDOT trunklines crossing	[Modified] By June 1,	
	305(b)-listed water bodies.	2006	
	[Modified] A mapping system will be posted on the	[Completed]	
	Storm Water Web site with the new maps showing		
	outfalls investigated as part of dry weather screening.		
2	Evaluate various options to review projects	By October 1, 2004	PIP Team
	discharging to TMDL water bodies.	[Completed]	
3	Review options with appropriate MDOT entities.		
4	Make a recommendation for approval.		
5	Lay out a detailed framework for the approved	By June 1, 2006	
	procedure.		
6	Document procedure and issue staff guidance.		
7	Review manuals and update accordingly.	February 1, 2007	
8	Notify appropriate staff of changes to manuals.		
No.	Measurable Goals	Schedule	Responsible
1	Review all new projects that discharge to waters of the	By April 1, 2005	MDOT
	state with a promulgated TMDL.	[Completed]	Planning,
			Design, and
			TSC Staff

Activity C-6: Implement Procedures to Select, Apply, and Maintain

Permanent Best Management Practices for Storm Water

**Management Activities (Post-Construction)** 

Affected Parties: MDOT Maintenance, Traffic & Safety, Planning, Design, and Construction Staff

and Contractors

**Objective:** To protect receiving water quality by implementing post-construction BMPs

statewide.

Annual Reporting: Track the permanent BMPs selected for earth-disturbing projects using existing

databases. Report pollutant discharge reduction based on theoretical BMP

performance.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity T-1 - Present Training Modules to Region/TSC Staff

Activity C-1 - Maintenance Requirements for MDOT Permanent Best

Management Practices (BMPs)

Activity C-3 - Select, Apply, and Maintain Permanent BMPs

Activity C-8 - Update Drainage Manual

**Permit Requirement:** Part I.B.4.b(1): Requirements for implementation of BMPs.

Part I.B.4.b(2): Requirements for long-term operation and maintenance of BMPs. Part I.B.6.a(2): In urbanized areas, structural controls may need to be enhanced if control measures fail to adequately reduce the discharge of pollutants to or

from the drainage system.

No.	Interim Milestones	Schedule	Responsible
1	Upon having a BMP selection, application, and maintenance procedure in place (see Activity C-3), add procedural information to training modules.	By August 1, 2007	MDOT Planning, Design Staff
No.	Measurable Goals	Schedule	Responsible
1	Train design staff with storm water responsibilities on applying the permanent BMP procedure.	By April 1, 2007 [Modified] By July 1, 2007	MDOT Planning, Design Staff
2	Implement procedure to select, apply, and maintain permanent BMPs.	Ongoing beginning April 1, 2007 [Modified] By Jan. 1, 2008	MDOT Planning, Design, and Maintenance Staff
3	Develop a procedure to estimate pollutant discharge reduction based on theoretical BMP performance.	By December 1, 2007	Post-Const. Team
4	BMPs will be modified, replaced, or enhanced if they are not properly installed, maintained, and/or applied for pollutant control.	As needed beginning April 1, 2007 [Modified] Jan. 1, 2008	MDOT Planning, Design, and Maintenance Staff

Activity C-7: Internal Quality Assurance/Quality Control (QA/QC) Protocol

for Construction Storm Water Control

**Affected Parties:** MDOT Construction & Technology (C&T), Planning, Design, and Maintenance

Supervisors

**Objective:** To improve the effectiveness of temporary BMPs statewide through internal

QA/QC for construction storm water control.

**Description:** Development of the QA/QC protocol is underway and will be submitted to EC

for approval.

**Annual Reporting:** Track number and result of internal reviews and actions taken per procedure.

**Related Activities:** Activity A-1 - Program Assessment and Reporting

Activity T-3 - Train Staff Responsible for Administering Part 91 and those having Decision Making Authority for SESC Plan Development or Review, Inspections, or Enforcement; and Storm Water Operators as Required under Part

31

Permit Requirement: Part I.B.5.a: MDOT shall meet the following requirements on MDOT

construction sites statewide, but may rely on their SESC Plan and the State of Michigan's Permit by Rule to the extent that those controls meet the requirements: 1) Implement soil erosion and sedimentation controls. 2) Control demolition and construction waste materials, concrete truck washout, chemicals, litter, and sanitary waste at construction sites that may cause adverse impacts to water quality. 3) Consider potential water quality impacts during road construction plan reviews. 4) Inspect sites to assure pollution control measures

are appropriate.

No.	Interim Milestones					
1	Develop draft QA/QC protocol.	By December 31,	SESC Team,			
		2005	Design, Planning			
		[Completed]	and Maintenance			
No.	Measurable Goals	Schedule	Responsible			
1	Develop a QA/QC protocol for construction	May 1, 2006	SESC Team			
	storm water control.	[Completed]				
2	Inspect all sites disturbing at least one acre.	Per the SESC	Part 91 Inspector			
		Manual				
		[On-going]				
3	Follow up on all deficiencies noted in site	[On-going]	Part 91 Inspector			
	inspections within the specified time frame.		and Engineer			

**Activity C-8:** Periodically Update Drainage Manual

Affected Party: MDOT Design, Construction & Technology and Region/TSC Staff

**Objective:** To update MDOT's policies and procedures for the design of drainage facilities

by reviewing and revising MDOT's Drainage Manual as needed to include the

latest details of the storm water management program.

**Annual Reporting:** Track changes made to the Drainage Manual

**Related Activity:** Activity A-1 - Program Assessment and Reporting

Activity C-4 - MDEQ Early Coordination

Activity C-5 - Storm Water Discharges to TMDL Water Bodies

Activity C-6 - Implement Procedures to Select, Apply, Maintain Permanent

**BMPs** 

Activity C-3 - Procedure to Select, Apply, Maintain Permanent BMPs

**Permit Requirement:** Part I.B.6.a(1): Routine maintenance on structural controls.

Part I.B.5.a(2): Control demolition and construction waste materials, concrete truck washout, chemicals, litter, and sanitary waste at construction sites that may

cause adverse impacts to water quality.

Part I.B.4.c: Develop and implement a process for review of BMPs.

No.	Measurable Goals	Schedule	Responsible
1	Assess the need to update the Drainage Manual.	Annually beginning	MDOT
		April 1, 2005	Design
		[On-going]	(Hydraulics)
2	Update the Drainage Manual. Changes to manual	As needed.	Staff
	must be approved by the Engineering Operations	[On-going]	
	Committee (EOC).		
3	Notify appropriate staff of changes to the manual.		

### **Activity C-9:** Documentation and Tracking of Road Maintenance Activities

Affected Party: MDOT Maintenance Staff, MARS Team, Maintenance Environmental Team

(MET), and Contract Agencies

**Objective:** MDOT roadways will be operated and maintained and storage facilities will be

constructed to reduce pollutants washing into surface waters statewide.

**Annual Reporting:** 

• Estimate actual quantity of salt used for de-icing versus maximum calculated amount based on Maintenance Performance Guide 14100.

• Track hours of street sweeping and catch basin cleaning conducted.

**Related Activity:** Activity A-1 - Program Assessment and Reporting

Activity C-1 - Maintenance Requirements for MDOT Permanent BMPs

**Permit Requirement:** Part I.B.6: Ensure MDOT employees maintain and follow proper pollution prevention controls.

Part I.B.6.a(1): Describe and implement procedures for proper disposal of operation and maintenance waste.

Part 1.B.6.b(1):Construct, operate, and maintain surfaces statewide to reduce discharge of pollutants into system. Salt and sand applied for improved traction shall be prevented from entering receiving streams to the maximum extent practicable.

Part 1.B.6.b(1) Good Housekeeping implemented at salt and sand storage facilities.

Part I.B.6.b(2): Maintain existing street cleaning and catch basin maintenance activities.

No.	Measurable Goals	Schedule	Responsible
1	Investigate how to track contracted road	By April 1, 2007	Pollution Prevention &
	maintenance activities. using a pilot study	[Modified]	Good Housekeeping
	with a county. In the interim, discuss	By Dec. 1, 2007	(PP&GH) Team,
	maintenance activities in terms of hours of		Maintenance Staff,
	labor.		Contract Agency
2	20,000 hours of street sweeping will be	Annually	Maintenance Staff,
	completed annually.		Contract Agency
3	23,000 hours of catch basin cleaning will be	Annually	Maintenance Staff,
	completed annually.	_	Contract Agency

**Activity C-10:** Procedure for Outfall Labeling

Affected Parties: MDOT Construction & Technology and Maintenance Staff

Objective: MDOT will provide permanent identification for all outfall structures installed

after April 1, 2006 statewide.

**Annual Reporting:** 

Track the location and size of outfalls not labeled between April 1, 2005 and

April 1, 2006.

• Track the location and size of outfalls labeled.

**Related Activity:** Activity A-1 - Program Assessment and Reporting

Activity T-1 - Training Modules to the Job-Related Public

Activity I-5 - Map Known Outfalls Activity C-8 - Update Drainage Manual

Permit Requirement: Part I.B.6.c: Provide permanent identification of outfalls installed after April 1,

2005 that discharge directly into waters of the state. The primary operator of the

drainage system shall be readily identifiable by observation of the outfall.

No.	Interim Milestones	Schedule	Responsible
1	Assess various procedures for labeling outfalls.	By January 31, 2005	SESC Team
2	Review procedures with appropriate MDOT entities	[Completed]	
	and make a recommendation for approval.		
3	Develop a special provision for labeling.	By April 1, 2005	
4	Document procedure and issue staff guidance.	[Completed]	
5	Review and update manuals accordingly.		
6	Notify appropriate staff of changes to manuals.		
No.	Measurable Goals	Schedule	Responsible
1	Develop procedure for labeling all new outfall	By April 1, 2005	SESC Team
1	Develop procedure for labeling all new outfall structures statewide.	By April 1, 2005 [Completed]	_
1	1 1	-	_
2	1 1	-	_
	structures statewide.	[Completed]	SESC Team
	structures statewide.  All new outfall structures will be labeled and	[Completed] Starting April 1, 2006	SESC Team  MDOT

### **Activity C-11:** Review Flow Control Structures

**Affected Party:** MDOT Design and Planning Staff

**Objective:** MDOT will ensure that new flow control structures in urbanized areas assess

impacts on water quality and whenever possible will examine existing flow

control structures for inclusion of water quality BMPs to the MEP.

Description: MDOT is currently reviewing all new flow control structures as part of

environmental clearance and will continue to do so. Existing flow control

structures will be examined whenever possible.

Annual Reporting: Number of flow control structures reviewed and water quality benefits gained

based on the theoretical pollutant removal rates.

**Related Activity:** Activity A-1 - Program Assessment and Reporting

Activity C-3 - Procedure to Select, Apply, and Maintain Permanent BMPs for

Storm Water Management Activities (Post-Construction)

**Permit Requirement:** Part I.B.4.c: Develop and implement a process for review of BMPs.

Part I.B.6.d: Ensure new storm water flow management projects assess impacts of water quality on the receiving water and, whenever possible, examine existing

projects for incorporation of water quality protection.

No.	Measurable Goals	Schedule	Responsible
1	All new flow control structures will be reviewed for	Beginning August 1,	MDOT
	inclusion of water quality BMPs.	2005	Planning
2	All new flow control structures will be evaluated for	Beginning April 1,	Specialists
	water quality benefit based on the theoretical pollutant	2006	and Post-
	removal rate.	[Modified]	Const team
		December 31, 2007	
3	Maintenance requirements for existing water quality	By December 31,	
	controls having a water quality benefit will be	2006	
	developed to the maximum extent practicable.	[Modified]	
		December 31, 2007	
4	Applicable MDOT Staff will be trained to review new	By April 1, 2007	
	and existing flow control structures.	[Modified]	
		December 31, 2007	

Activity C-12: Audit the Pollution Incident Prevention Plan (PIPP)

Requirements

Affected Party: MDOT Maintenance Staff, Region Resource Analyst/Specialist, Region/TSC

Storm Water Coordinator, and Safety & Homeland Security

**Objective:** Assure that vehicle maintenance activities statewide do not pollute storm water

runoff to the maximum extent practicable.

**Description:** Internal auditing of the PIPP is already conducted and implemented.

**Annual Reporting:** 

• Summary of PIPP audits

• Document new programs, policies, procedures and information.

**Related Activity:** Activity A-1 - Program Assessment and Reporting

Activity T-1 - Training Modules to the Job-Related Public

Activity C-1 - Maintenance Requirements for MDOT Permanent BMPs

Permit Requirement: Part 1.B.6.: Ensure MDOT employees maintain and follow proper pollution

prevention controls.

Part 1.B.6.a(1): Routine maintenance on structural controls.

Part 1.B.6.a(2): If necessary, enhance structural controls and cleaning schedules

for adequate pollutant control.

Part 1.B.6.e.: Assure vehicle maintenance activities do not pollute storm water

runoff.

No.	Measurable Goals	Schedule	Responsible
1	Conduct an audit of the PIPP requirements every three	Beginning April	Region Resource
	years.	1, 2006	Analyst/Specialist,
2	Follow-up on any delinquent plan requirements and	As needed.	Region /TSC Storm
	revise appropriately.		Water Coordinator,
3	Formally accept the changes made to the PIPP.		or Safety &
			Homeland Security,
			PP&GH Team

**Activity A-1:** Program Assessment and Reporting

Affected Party: MDOT employees involved with the storm water program.

**Objective:** To assess and report on the status of the MDOT Storm Water Management Plan

(SWMP) on an annual basis through compiling measurable goal data, perform

Conduct a yearly program assessment of the MDOT Storm Water Program and

program assessment, review auditing activities, and prepare annual report.

conduct annual reporting.

**Annual Reporting:** 

**Description:** 

• Track and document SWMP activities.

• Complete annual progress report.

• Conduct evaluation of program and make changes as needed.

**Related Activities:** All Activities

Permit Requirement: Part I.C: Program Assessment and Reporting

No.	Interim Milestones	Schedule	Responsible
1	Develop tracking protocol for entire plan to combine tracking and reporting for each activity. Coordinate with existing databases.	By April 1, 2006 [On-going]	Implementation Teams as appropriate
2	Review and test tracking program.	By April 1, 2007	
3	Compile data and draft the annual report.	Annually beginning	Consultant
4	Review the overall status of implementation of the SWMP to assure compliance with its requirements.	February 1, 2005 [On-going]	MDOT Storm Water Program Manager
5	Review interim milestones and measurable goals for applicability. Revise measurable goals and milestones as needed.		Implementation Teams, Storm Water Program
6	Review annual budget and revise fiscal analysis if necessary.		Manager
7	Review the annual progress report. Provide comments and assure its accuracy.		Implementation Teams. Storm Water Program Manager
8	Conduct the final review of the annual report and issue approval for submitting to MDEQ		MDOT EC
No.	Measurable Goals	Schedule	Responsible
1	Submit annual reports to MDEQ.	By April 1 of each year [On-going]	Storm Water Program Mgr.
2	All tracking information for the previous year will be complete and accessible for inclusion in the annual report.	By January 2 of each year. [On-going]	Consultant, Storm Water Program Mgr.

# **Appendix B**

# **MDOT-Sponsored Education and Outreach**

- 1. Training, Conference, and Event Database (Pages B.1-1 to B.1-4)
- 2. Web Page Tracking Database (Page B.2-1 to B.2-3)
- 3. Storm Water Awareness Survey Report Executive Summary (Pages B.3-1 to B.3-3)

#### Appendix B.1 Training, Conference, and Event Database January 1, 2006 to December 31, 2006

#### PUBLIC EDUCATION

Name or Title of Meeting/Presentation	Date of Presentation	Name of Presenter/Responsible Party						Regio	n								Audie	∍nce				
	/Meeting		No. of Attendees/Number Reached	Education Activity*	Вау	University	Grand	Metro	North	Southwest	Superior	Permits	Executives		Construction Starr	Planning & Development Staff	Contractors - Maintenance	Contractors – Engineers & Traffic	Government (County)	General Public	General Public - Children	Tetra Tech Employees or Road Crew
Career Day Presentations	4/27/2006	Molly Lamrouex, Bethany Matousek	50	СТ																50		ı
Monday Memo - Kalamazoo SW Work Group Praises MDOT	4/17/2006	Department		PEM											1	$\top$	1	$\vdash$				
MDOT SW Display at Kalamazoo Home Expo	3/8/2006-3/11/2006	Kalamazoo Storm Water Work Group	20,000	CT													1			20000	T	
Kids Flyer for Shadow Day	4/27/2006	Department	65	PEM													1				65	
Watertown Township, MI - Web site tip sheets	4/20/2006	General Public		PEM																		
Trash Bags and Brochures for Operation Care 2006 MDOT Career Day Enviroscape Presentation	4/262006-4/29/2006, 7/1/2006-7/4/2006, 9/1/2006-9/4/2006 5/2/2006-5/3/2006	Department Department	100	PEM PEM												<u> </u>	<u></u>			100 X	Х	
Highway Stormwater Management Webcast	5/18/2006, 6/15/2006, 10/26/2006, 12/7/2006	Department	29	PEM										x z	x					х		
MITA Article on MDOT's SESC Program	Spring 2006	Department		PEM										X 2	X		Х			Х		
Storm water trinkets and pamphlets for "Galesburg Days"	Summer 2006	City of Galesburg	100	PEM												T	1			100		
SW general information, trinkets and pamphlets for UP Fair	Summer 2006	Dan Hamlin	250	PEM																200	50	
Career Day Presentations	2006	Coreen Strzalka		CT																X		
MDOT Toolkit and letter to Watershed Groups	2/2/2006	Department	120	PEM															<u> </u>	120	$ldsymbol{ldsymbol{ldsymbol{\sqcup}}}$	
Storm water education materials for MACDC in Howell	6/7/2006	MI. Assn of County Drain Commissioners	25	PEM															25		$ldsymbol{ldsymbol{ldsymbol{\sqcup}}}$	
Storm water education materials for MACDC in Bridgeport	6/8/2006	MI. Assn of County Drain Commissioners	20	PEM												Щ.	Ь.	<u> </u>	20	Ь	igsquare	
Storm water education materials for MACDC in Allegan	6/26/2006	MI. Assn of County Drain Commissioners	27	PEM												Ь	<b>—</b>	<u> </u>	27	Ь—	igspace	
Storm water education materials for MACDC in Big Rapids	6/28/2006	MI. Assn of County Drain Commissioners	16	PEM		<u> </u>											—	<u>↓</u>	16	ـــــ	igspace	
SW handouts at Kalamazoo County Fair	8/7-11/2006	General Public	200-250	PEM											_		—	<u>                                     </u>	╙	200	50	
Universal City, Texas (Brian Siniff)																			1 '	l		
2150 Universal City Blvd. Universal City, Texas 78148	8/28/2006	General Public General Public	450	PEM PEM	<del>                                     </del>	_					-					+	+-	₩	igspace	100		_
SW handouts at Texas Twp (Kzoo County) Fire Dept Open house  Metropolitan Detroit Science Teachers Association	10/1/2006 10/21/2006	Science Teachers	150 1500	PEM	-	1	1								-	+-	+	<u> </u>	-	100 1500	50	-+
MDOT SW small display at Kalamazoo River SWMP public meeting	10/21/2006	General Public	50	PEM	+	+	+						-+		-	+-	+-	-	$\vdash$	50	₩	-+
Community Expo (Lawrence, Michigan)	10/26/2006	Community Expo	60	PEM	+	+	+					-	-	-	+	+	+-	₩	$\vdash$	60	₩	-+
Sodus Township, MI storm water education materials	11/8/2006	General Public (Sodus Township)	50	PEM	$\vdash$		+						-+		-	+	+-	$\vdash$	$\vdash$	50	$\vdash$	-+
GCSI (Cindy)	2/15-17/2006	MDOT	300	PEM	+	1	+				— <del> </del>		-		-	+	+-	H	х	- 50	+	-+
Floodplain Manager Conference - display and brochures	2/13-17/2006	Les Thomas	500	PEM	1		1						-			+	+-	$\vdash$	L^	Х	$\vdash$	-
MWEA Conference - storm water display and brochures	2/6-7/2006	Department	1	PEM	1		1						-+			+	+-	$\vdash$	$\vdash$	X	$\vdash$	-
Kids Flyer and Jeopardy game for Arizona DOT Public Outreach	11/17/2006	Stephanie Brown - Arizona DOT	1	PEM	I	1	1				<u> </u>		_		-	+	+	<del>                                     </del>	$\vdash$	X	Х	
IDEP Brochure adoption by Village of Pickney, MI	12/14/2006	Village of Pickney	1000	PEM	1	1	1	1		-		- +		-+	+	+	+-	-	$\vdash$		+	-
IDEP Brochure adoption by village of Pickney, IVII	12/14/2000	village of Fickriey	1000	PEIVI														1 0		1000		,

2006 New Materials	Date Created	Intended Audience
SESC Pocket Guide	Jan-06	Construction and Maintenance
IDEP Table Top Display	Aug-06	Construction and Maintenance
IDEP Brochure	Aug-06	Construction and Maintenance
SESC 'Dot" Animation	Feb-06	All MDOT Staff

\*Education Activity Key

CT - Conferences and Trainings
PEM - Public Education Materials/News Articles

SW - Storm Water Related Meetings

# Appendix B.1 Training, Conference, and Event Database January 1, 2006 to December 31, 2006

Pollution Prevention/Good Housekeeping

Name or Title of Meeting/Presentation	Date of Presentation	Name of Presenter/Responsible Party		/Good Housek	T		R	egion									Audie	nce					$\neg$
•	/Meeting		No. of Attendees/Number Reached	Education Activity*	Вау	University	Grand	Metro	North	Southwest	Superior	Permits	Executives	taff	Construction Staff	k Development Staff	rs - Maintenance	Contractors – Engineers & Traffic	Government (County)	General Public	General Public - Children	Tetra Tech Employees or Road Crew	Unknown MDOT Department
State Police Truck Inspections at Rest Areas	2006	Department and State Police		ACT	5705	10769	3132	9558	1210	7319	3783										ı	, ,	
Pesticide Training	4/25/2006-4/26/2006	Department	67	CT											-	67							
																					ш	ш	
			-													_	-	-	<b> </b>		$\vdash$	$\vdash$	
				-														+	-		$\vdash$	$\vdash$	
																	-	1			$\vdash$	$\vdash$	
	1	ı			5705	10769	3132	9558	1210	7319	3783	0	0	0	0 6	7 0	0	0	0	0	0	0	0

\*Education Activity Key
CT - Conferences and Trainings
PEM - Public Education Materials/News Articles
SW - Storm Water Related Meetings

ACT- Storm Water Activity

# Appendix B.1 Training, Conference, and Event Database January 1, 2006 to December 31, 2006

Illicit Discharge Elimination Program (IDEP)

	/Meeting																							
			No. of Attendees/Number Reached	Education Activity*	Bay	University	Grand	Metro	North	Southwest	Superior	Permits	Lansing	Design Staff	Construction Staff	O&M Staff	Planning & Development Staff	Contractors - Maintenance	Contractors – Engineers & Traffic	Government (County)	General Public	General Public - Children	Tetra Tech Employees or Road Crew	Unknown MDOT Department
DEP Region Coordinator Training	4/27/2006	Tetra Tech	12	СТ	1	1	1	2	2	2	1	1	1											ı
Maintenance Conference Display & Brochure	8/22/2006	Darwyn Heme	150	CT												150								
Real Estate Conference Display & Brochure		Joe Rios	250	CT													250							ـــــــــــــــــــــــــــــــــــــــ
Itilities Conference Display & Brochure		Joe Rios	250	CT													250							
DEP Construction Advisory	9/20/2006	Construction and Technology	300	PEM											300									ш.
DEP Brochures with Tap-in/Discharge Permits	2006	Joe Rios	25	PEM																	25		_	
									2													0		

\*Education Activity Key CT - Conferences and Trainings PEM - Public Education Materials/News Articles SW - Storm Water Related Meetings

#### Appendix B.1 Training, Conference, and Event Database January 1, 2006 to December 31, 2006

Post Construction Storm Water Management Practices

Name or Title of Meeting/Presentation	Date of Presentation	Name of Presenter/Responsible Party		, ,			R	egion	1			Audience					$\neg$						
	/Meeting		No. of Attendees/Number Reached	Education Activity*	Вау	University	Grand	Metro	North	Southwest	Superior	Permits	Lansing	Design Staff		Planning & Development Staff	Contractors - Maintenance	Contractors – Engineers & Traffic	Government (County)	General Public	General Public - Children	Tetra Tech Employees or Road Crew	Unknown MDOT Department
Design Conference - Stormwater Management Presentation	6/27/2006	Judy Ruszkowski		СТ										х									
															_			Ш			_		
											_			_	_			Щ					=
					-					-	$\dashv$	-	_				<del>                                     </del>	$\vdash \vdash$			$\dashv$	-	$\dashv$
					<del>                                     </del>					_	7	_		<del>-  </del> -	+		<del>                                     </del>	$\vdash$				_	-
											T							$\Box$					$\neg$
					0	0	0	0	0	0	0	0	0	0	0 0	0	0	0	0	0	0	0	0

\*Education Activity Key CT - Conferences and Trainings PEM - Public Education Materials/News Articles SW - Storm Water Related Meetings

## Appendix B.2 Web Page Tracking Database

<u>Pages</u>	Web Link
Home Page	http://www.michigan.gov/stormwatermgt
Why is Managing Storm Water Important	http://www.michigan.gov/stormwatermgt/0,1607,7-20591164,00.html
MDOT's Current Storm Water Management Programs	http://www.michigan.gov/stormwatermgt/0,1607,7-20593182,00.html
EPA Requirements	http://www.michigan.gov/stormwatermgt/0,1607,7-20593313,00.html
Click On DOT For A Storm Water Message	
MDOT Storm Water Web Site Survey	http://www.michigan.gov/stormwatermgt/0,1607,7-20591826,00.html
Jeopardy Game	
Communities	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097,00.html
Phase II Communities Alphabetically	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-93018,00.html
Phase II Communities Sorted By Urbanized Area (UA)	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92922,00.html
Ann Arbor	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92892,00.html
Battle Creek	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92893,00.html
Bay City	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92887,00.html
Benton Harbor/St. Joe	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92894,00.html
Detroit Detroit	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92895,00.html
Elkhart, IN-MI	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92896,00.html
Flint	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92897,00.html
Grand Rapids	http://www.michigan.gov/stormwateringt/0,1607,7-205-30097-92898,00.html
Holland	http://www.michigan.gov/stormwateringt/0,1607,7-205-30097-92899,00.html
Jackson	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92990,00.html
Kalamazoo	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92901,00.html
Lansing	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92902,00.html
Michigan City, IN-MI	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92903,00.html
Monroe	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92904,00.html
Muskegon	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92905,00.html
Port Huron	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92906,00.html
Saginaw	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92907,00.html
South Bend	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92908,00.html
S. Lyon-Howell-Brighton	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92910,00.html
Toledo	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92911,00.html
Metropolitan Planning Organizations	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30097-92943,00.html
Illicit Discharge	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30100,00.html
IDEP Fieldwork Plan for Permit Year One	http://www.michigan.gov/stormwatermgt/0,1607,7-205103745,00.html
Resources	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30101,00.html
Phase II Storm Water Management Plan	http://www.michigan.gov/stormwatermgt/0,1607,7-205114322,00.html
2004 Annual Report	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30101-140191,00.html
Drainage Manual	http://www.michigan.gov/stormwatermgt/0,1607,7-20593193,00.html
Phase I Storm Water Management Plan	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30101-93181,00.html
2003 Annual Report	http://www.michigan.gov/stormwatermgt/0,1607,7-20593101,00.html
2002 Annual Report	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30101-93161,00.html
2005 Annual Report	http://www.michigan.gov/stormwatermgt/0,1607,7-205140179,00.html
Best Management Practices	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30102,00.html
Structural BMPs	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30102-92963,00.html
Vegetative BMPs	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30102-92965,00.html
Operational BMPs	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30102-92975,00.html
Education	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30103,00.html
Public Education	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30103_30478,00.html
MDOT Employee and Contractor Education	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30103_30373,00.html
The MDOT Storm Water Internal Training Modules	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30103_30373-93136,00.html
SESC Poster	/documents/mdot_ms4_2006_sesc_poster_150052_7.pdf
Kids flyer	/documents/mdot_ms4_pubilc_education_kids_flyer_152078_7.pdf
General Education Brochure	/documents/mdot_ms4_general_education_brochure_150054_7.pdf
Litter bag	/documents/mdot_ms4_litter_bag_graphic_150058_7.pdf
Display	/documents/mdot_ms4_storm_waterdisplay_150060_7.pdf
Display for kids	/documents/mdot_ms4_kids_stormwater_display_150056_7.pdf
Litter bag	/documents/mdot_ms4_sw_litterbag_91939_7.pdf
IDEP Brochure	/documents/mdot_ms4_idep_brochure_final_171725_7.pdf
IDEP Display	/documents/mdot_ms4_idepdisplay_final_171723_7.pdf
Links	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30104,00.html
Contacts	1
Full Community Contacts List	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30105,00.html
MS4 Committee Contact List	http://www.michigan.gov/stormwatermgt/0,1607,7-205-30105_31663,00.html
Total Number of Site Downloads Per Month	

Appendix B.2 Web Page Tracking Database

# MDOT Public Web Site Tracking Database January 1, 2005-December 31, 2005

38:	2 4	107	1 <b>/06 - 3/31/06 4/1/2006-4/3</b> 849	356	63		293	29				226		1013		63	263	3 4,6
3		25	39	27		Deleted?		eleted?			Deleted?		Deleted?		Deleted?		eted?	1
5		65	65	44	91		61		51	45		32		104		50	44	
2		29	28	25	22		16	2	21	15		13		35	;	35	17	7 2
	0	0	3	1	1		_		_			_						
Updated	Not Updated	No	t Updated	12	10		5		7	4		3		42	:	26	19	
0	2	10	E4	24	33		20		1.4	35		0		19		1	(	
2: 1:		16 13	51 35	11	33 10		39 14		11 37	25		11 4		87 9		45 14	17 6	
1:		4	35 12	6	4		8		3	25 1		0		3		6	3	
	6	2	4	6	1		3		1	1		0		3		6	(	
	5	0	1	5	2		2		0	0		1		0		5	2	
	4	0	1	4	1		8		2	1		0		0		5	(	
	3	1	4	7	2		6		3	3		3		8		7	(	
	4	1	5	6	2		3		0	0		1		0		7	1	
		0	1	8	1		2		1	2		0		0		4	(	
;	3	1	5	7	1		2		1	2		3		4		7	Ċ	
	7	3	3	2	3		4		5	3		0		2		5	Ċ	) )
	3	1	2	4	2		2		1	1		0		1		5	Ċ	
	4	1	2	5	1		1		1	1		0		0		6	Ċ	
:	2	0	2	4	3		2		3	2		2		3		5	(	
	4	1	6	4	2		3		1	0		1		0		6	1	
;	3	1	2	5	2		3		6	4		2		0		8	(	)
	7	0	5	4	1		2		0	0		0		2		3	(	
	5	2	3	6	1		1		1	1		1		0		2	2	
	3	0	5	4	4		1		1	2		3		4		5	2	
	3	1	3	5	2		3		0	0		0		2		6	(	
(	6	1	2	4	3		2		1	2		3		0		5	3	
	4	2	2	4	1		2		0	0		0		0		4	1	
	7	1	7	6	2		1		3	1		0		1		5	(	
	6	7	3	5	4		8		9	4		5		12		9	5	
10		46	119	145	131		120	10		105		74		238		27	76	
3		7	12	1 Deleted		Deleted?		eleted?			Deleted?		Deleted?		Deleted?		eted?	
41		26	42	26	52		47		23	20		15		66		41	19	
50		51	47	26	42		23		21	16 1		17		50		40	19	
1: 45:		5 101	15 493	431	444	,	4 440	42	0	435		1 385		4 456		10 77	( 379	
	5 <sup>2</sup>	5	493	5	6	2	6		3	435		300		400	3	7	3/8	
	6	1	3	25	3		2		0	2		0		4		7	(	
	6	4	6	9	5		3		0	2		0		0		8	1	
Jpdated	No Updated		Updated No Updated	9	23		14		8	10		11		35		31	13	
3:		31	64	31	46		48		14	35		21		141		55	33	
3		44	65	40	43		38		35	33		31		90		43	40	
1:		21	21	21	16		19		13	12		10		49		19	10	
10		18	21	14	11		18		12	11		7		46		19	13	
3		35	30	25	46		41		34	36		19		92		36	19	
1		75	111	101	91		66		56	52		39		272		81	31	
1:		21	8	14	19		22		3 Dele		Deleted?	1	Deleted?		Deleted?	Del	eted?	1
	7	10	5	14	9		10	1	10	9		8		48		19	10	
(	0	11	45	146	129	1	116	3	33			37		171		54	10	) 7
(	0	0	52	113	24							71		236		41	31	1 5
(	0	17	76	49								49		94		41	38	
(	0	3	34	49								28		69		13	10	) 2
	0	14	31	16								8		98	:	21	13	
(	0	5	15	8								15		29		11	15	
	1	2	4	1								28		69		13	10	
												4		60		9	8	
												7		141		29	16	
19		22	24	20	27		37		11	25		19		46		25	19	
	7	18	31		50		49		32	31		29		32		28	19	
2																		
21		0	11	35	7		5		3	5		8		8		15	6	
	0 3	0 14 192	14	35 25 2001	7 44 1551		5 13 638		10	5 11 1008		15 1270		8 9 1013	19	7	6 5 1253	5 1

Months	1/1/06 - 1/31/06 2/1/0	6 - 2/28/06 3/1/0	6 - 3/31/06 4/1/20	006-4/30/06 5/1/0	6-5/31/06 6/1/0	6-6/30/06 7/1/0	6-7/31/06 8/1/0	6-8/31/06 9/1/0	06-9/30/06 10/1/	06-10/31/06 11/1/	06-11/30/06 12/1/	06-1231/06 To	otal # Visits
Drainage Manual	20	31	18	15	27	19	13	19	25	24	20	16	247.00
/documents/mdot_ms4_app2_dattachment_c_drainage_manual_94976_7.pdf /documents/mdot_ms4_app_5_c_drainage_manual_94993_7.pdf	206	108	147	167	172	173	117	181	155	187	537	144	2,294.00
/documents/mdot_ms4_app_5_c_drainage_manual_94993_7.pdf#search=%22%22box%20inlet%22%22	0	0	0	0 16	0	0	0 26	0 37	1	1 28	0	0 20	2.00 300.00
/documents/mdot_ms4_app_91706_702_a_drainage_manual.pdf /documents/mdot_ms4_app_91709_702_b_drainage_manual.pdf	29 18	30 20	31 28	21	21 24	16 9	26 17	15	29 15	26 27	17 13	10	217.00
/documents/mdot_ms4_app_91710_702_c_drainage_manual.pdf	20	20	22	21	33	9	14	17	10	21	12	10	209.00
/documents/mdot_ms4_app_91710_702_c_drainage_manual.pdf#search=%22%22study%20firm%22%22 /documents/mdot_ms4_app_91711_702_d_drainage_manual.pdf	0 102	0 122	0 87	0 69	0 81	0 67	0 80	0 65	2 74	1 68	0 57	0 47	3.00 919.00
/documents/mdot_ms4_app_91713_702_e_drainage_manual.pdf	40	33	22	19	30	17	24	16	19	26	10	15	271.00
/documents/mdot_ms4_app_91714_7_02_f_drainage_manual.pdf /documents/mdot_ms4_app_91717_7_03_a_drainage_manual.pdf	32 30	19 33	15 40	17 16	19 34	16 26	18 27	16 40	13 25	18 26	9 20	15 23	207.00 340.00
/documents/mdot_ms4_app_91718_703_b_drainage_manual.pdf	127	115	127	80	121	91	113	125	145	112	97	86	1,339.00
/documents/mdot_ms4_app_91719_703_c_drainage_manual.pdf /documents/mdot_ms4_app_91719_703_c_drainage_manual.pdf#search='michigan%20rainfall%20data'	200	137 0	156 1	155 0	65 0	58 0	52 0	65 0	65 0	64 0	34 0	52 0	1,103.00 1.00
/documents/mdot_ms4_app_s1r20_703_d_drainage_manual.pdf	73	61	51	57	50	27	59	42	41	47	29	15	552.00
/documents/mdot_ms4_app_91722_7_04_a_drainage_manual.pdf	19	22	11	16	22	8	16	14	12	18	13	9	180.00
/documents/mdot_ms4_app_91723_704b_drainage_manual.pdf /documents/mdot_ms4_app_91724_704_c_drainage_manual.pdf	65 68	45 88	29 74	18 59	38 65	14 43	34 66	32 49	18 62	28 100	16 53	12 54	349.00 781.00
/documents/mdot_ms4_app_91724_704_c_drainage_manual.pdf#search=%22%22some%20datum%22%22	0	0	0	0	0	0	0	0	1	0	0	0	1.00
/documents/mdot_ms4_app_91726_705_a_drainage_manual.pdf /documents/mdot_ms4_app_91727_705_b_drainage_manual.pdf	38 175	36 215	27 141	21 168	25 170	24 132	19 105	28 131	23 118	22 132	17 94	30 107	310.00 1,688.00
/documents/mdot_ms4_app_91731_706_a_drainage_manual.pdf	15	12	11	9	16	9	9	13	12	11	7	10	134.00
/documents/mdot_ms4_app_91731_706_a_drainage_manual.pdf#search=%22abutment%20filetype%3apdf%22 /documents/mdot_ms4_app_91732_706_b_drainage_manual.pdf	0 20	0 12	0 20	0 11	0 22	0 16	0 15	0 11	3 9	0 14	0	0 8	3.00 167.00
/documents/mdot_ms4_app_91732_706_c_drainage_manual.pdf	24	21	37	23	28	27	21	30	16	34	19	14	294.00
/documents/mdot_ms4_app_91734_706_d_drainage_manual.pdf	67	36	50	34	52	47	26	30	27	27	20	33	449.00
/documents/mdot_ms4_app_91736_707_a_drainage_manual.pdf /documents/mdot_ms4_app_91739_708_a_drainage_manualpdf	40 16	30 17	24 18	19 15	34 27	23 12	19 12	24 11	23 12	25 13	15 10	22 13	298.00 176.00
/documents/mdot_ms4_app_91741_709_a_drainage_manual.pdf	12	19	24	17	17	13	8	10	11	11	13	10	165.00
/documents/mdot_ms4_app_91743_709_b_drainage_manual.pdf /documents/mdot ms4 app 91743 7. 09 b drainage manual.pdf#search=%22%22quarterly%20bid%22%22	35 0	27 0	54 0	25 0	45 0	18 0	13 0	16 0	22 2	21 0	16 0	19 0	311.00 2.00
/documents/mdot_ms4_app_91745_7_10_a_drainage_manual.pdf	11	10	17	16	14	15	11	8	7	10	9	10	138.00
/documents/mdot_ms4_app_91746_7_10_b_drainage_manual.pdf	82	46 105	72 77	54 64	79 91	93 68	96 83	150 107	136 81	113 85	118 66	103 58	1,142.00 964.00
/documents/mdot_ms4_chap_91703_701_drainage_manual.pdf /documents/mdot_ms4_chap_91704_702_drainage_manual.pdf	79 77	56	49	73	70	49	68	53	50	55	52	40	692.00
/documents/mdot_ms4_chap_91704_702_drainage_manual.pdf#search=%22%22row%20purchase%22%22	0	0	0	0	0	0	0	0	1	0	0	0	1.00
/documents/mdot_ms4_chap_91716_703_drainage_manual.pdf /documents/mdot_ms4_chap_91721_704_drainage_manual.pdf	185 169	156 213	102 182	151 123	130 219	111 142	125 161	129 128	100 130	114 178	90 123	116 111	1,509.00 1,879.00
/documents/mdot_ms4_chap_91721_704_drainage_manual.pdf#search=%22willows%20ca%20community%20profile%20reach%22	0	0	0	0	0	0	0	0	1	0	0	0	1.00
/documents/mdot_ms4_chap_91721_704_drainage_manual.pdf#search='hydraulic%20design%20manual' /documents/mdot_ms4_chap_91725_705_drainage_manual.pdf	0 336	0 216	0 221	2 214	0 316	0 270	0 213	0 237	0 171	0 279	0 249	0 300	2.00 3,022.00
/documents/mdot_ms4_chap_91725_7_05_drainage_manual.pdf#search=%22%22use%20inlet%22%22	0	0	0	0	0	0	0	0	1	0	0	0	1.00
/documents/mdot_ms4_chap_91730_706_drainage_manual.pdf /documents/mdot_ms4_chap_91730_706_drainage_manual.pdf#search='design%20details%20of%20hydraulic%20structure'	90 0	59 0	70 0	50 2	75 0	50 0	51 0	47 0	61 0	52 0	44 0	52 0	701.00 2.00
/documents/mdot_ms4_chap_91730_706_drainage_manual.pdu/search=design/accudeatis/accude	0	0	0	2	0	0	0	0	0	0	0	0	2.00
/documents/mdot_ms4_chap_91735_7_07_drainage_manual.pdf	410	279	314	292	472	331	474	344	259	377	281	334	4,167.00
/documents/mdot_ms4_chap_91735_707_drainage_manual.pdf#search=%22%22answer%20spread%22%22 /documents/mdot_ms4_chap_91735_707_drainage_manual.pdf#search=%22%22check%20spread%22%22	0	0	0	0	0	0	0	0	1	0	0	0	1.00 1.00
/documents/mdot_ms4_chap_91735_707_drainage_manual.pdf#search=%22%22find%20spread%22%22	0	0	0	0	0	0	0	Ō	1	0	0	0	1.00
/documents/mdot_ms4_chap_91735_707_drainage_manual.pdf#search=%22%22next%20inlet%22%22 /documents/mdot_ms4_chap_91735_707_drainage_manual.pdf#search=%22%22route%20job%22%22	0	0	0	0	0	0	0	0	0	1	0	0	1.00 1.00
/documents/mdot_ms4_chap_91738_7_08_drainage_manual.pdf	252	140	170	160	151	155	116	192	123	204	149	117	1,929.00
/documents/mdot_ms4_chap_91740_709_drainage_manual.pdf /documents/mdot_ms4_chap_91744_710_drainage_manual.pdf	152 138	57 148	88 189	63 308	76 222	56 179	77 143	60 154	58 121	90 134	41 129	50 128	868.00 1,993.00
/documents/mdot_ms4_cover_acknowledgements_drainage_manual_91702_7.pdf	31	45	44	40	53	36	38	24	40	31	26	18	426.00
/documents/mdot_ms4_glossary_drainage_manual_91747_7.pdf /documents/mdot_ms4_glossary_drainage_manual_91747_7.pdf#search=%22%22next%20inlet%22%22	98 0	77 0	78 0	77 0	98 0	77 0	95 0	67 0	55 0	72	69 0	61 0	924.00 1.00
/documents/mdot_ms4_master_toc_drainage_manual_91748_7.pdf	130	71	66	47	64	73	78	68	70	77	51	55	850.00 0.00
Storm Water Management Plan			•	•						•			0.00
/documents/mdot_ms4_app_91690_7a_phase_i_swmp.pdf /documents/mdot_ms4_app_91692_7b_phase_i_swmp.pdf	0 13	3 20	2 14	6 8	11	2 5	0 2	0 13	1 10	2 7	7	0 1	18.00 111.00
/documents/mdot_ms4_app_91693_7.c_phase_i_swmp.pdf	0	7	5	2	4	2	0	1	0	5	7	0	33.00
/documents/mdot_ms4_app_91695_7.d_phase_i_swmp.pdf /documents/mdot_ms4_app_91697_7a-d_phase_i_swmp.pdf	8 17	12 24	16 27	14 34	20 29	3 22	5 3	12 6	2 8	7 10	8 14	10 0	117.00 194.00
/documents/mdot_ms4_chp_00_phase_i_swmp_91675_7.pdf	18	14	10	0	6	3	4	2	1	10	7	Ö	75.00
/documents/mdot_ms4_chp_01_phase_i_swmp_91677_7.pdf /documents/mdot_ms4_chp_02_phase_i_swmp_91678_7.pdf	7 8	12	8 12	3	7 15	2	10 2	3 2	2	5 10	2	1 0	62.00 64.00
/documents/mdot_ms4_chp_03_phase_i_swmp_91681_7.pdf	11	8	9	9	10	2	4	6	4	6	3	1	73.00
/documents/mdot_ms4_chp_04_phase_i_swmp_91682_7.pdf	8	6	4	1	3	2	0	1	0	2	1	0	28.00
/documents/mdot_ms4_chp_05_phase_i_swmp_91683_7.pdf /documents/mdot_ms4_chp_06_phase_i_swmp_91684_7.pdf	4	10	9	2	3	4	0	1	0	3	8	3	33.00 47.00
/documents/mdot_ms4_chp_07_phase_i_swmp_91685_7.pdf	3	9	2	3	5	2	0	6	1	2	4	0	37.00
/documents/mdot_ms4_chp_08_phase_i_swmp_91686_7.pdf /documents/mdot_ms4_chp_09_phase_i_swmp_91687_7.pdf	11	11 16	27 12	14 5	23 21	3	3	6	3 13	10 10	11 2	3	126.00 105.00
/documents/mdot_ms4_chp_10_phase_i_swmp_91688_7.pdf	4	7	2	4	1	3	5	1	0	2	2	0	31.00
/documents/mdot_ms4_chp_11_phase_i_swmp_91689_7.pdf /documents/mdot_ms4_full_version_phase_i_swmp_91696_7.pdf	15 28	20 60	21 36	10 23	2 16	3 20	0 4	2 11	0 9	3 22	13 3	4 11	93.00 243.00
	25	00	00	20	.0	20	•		ŭ		Ŭ		0.00
Annual Reports /documents/mdot_ms4_july_2001-june_2002appa_annual_report_91630_7.pdf	4	1	4	2	0	6	4	4	4	6	10	2	0.00 47.00
/documents/mdot_ms4_july_2001-june_2002appa_annual_report_91630_7.pdf#search=%22%22way%20workshop%22%22	0	0	0	0	0	0	0	0	0	1	0	0	1.00
/documents/mdot_ms4_july_2001-june_2002_app_b_annual_report_91631_7.pdf /documents/mdot_ms4_july_2001-june_2002_app_c_annual_report_91634_7.pdf	1 a	15 10	12 4	13 0	5 0	6 13	11 2	9	12 19	4	5 6	1 7	94.00 73.00
/documents/mdot_ms4_july_2001-june_2002_appd_annual_report_91635_7.pdf	0	0	2	Ö	Ö	2	0	Ö	0	Ö	1	0	5.00
/documents/mdot_ms4_july_2001-june_2002appe_annual_report_91637_7.pdf /documents/mdot_ms4_july_2001-june_2002appf_annual_report_91639_7.pdf	5	1	5 6	0	1	2	0	1	0 5	4	1	0	20.00 52.00
/documents/mdot_ms4_july_2001-june_2002_appendices_a-f_annual_report_91640_7.pdf	7	0	15	0	1	5	0	0	5	6	3	1	43.00
/documents/mdot_ms4_july_2001-june_2002_appendices_a-f_annual_report_91640_7.pdf#search=%22%22row%20workshop%22%22	0	0	0	0	0	0	0	0	1	0	0	0	1.00
/documents/mdot_ms4_july_2001-june_2002chp_00_annual_report_91641_7.pdf /documents/mdot_ms4_july_2001-june_2002chp_01_annual_report_91643_7.pdf	0	0	6 5	0	1	4	1 0	ნ 1	1 0	4	2 2	3 2	34.00 18.00
/documents/mdot_ms4_july_2001-june_2002chp_03_annual_report_91645_7.pdf	0	0	2	0	0	3	0	1	Ō	0	1	1	8.00
/documents/mdot_ms4_july_2001-june_2002chp_09_annual_report_91653_7.pdf /documents/mdot_ms4_july_2001-june_2002full_version_annual_report_91656_7.pdf	0 18	0 6	2 17	0	0	2 6	0	0	2	0 10	3	0	9.00 65.00
/documents/mdot_ms4_july_2001-june_2002_chp_02_annual_report_91644_7.pdf	1	0	11	ő	18	3	0	2	0	0	1	2	38.00
/documents/mdot_ms4_july_2001-june_2002_chp_04_annual_report_91646_7.pdf	0	1	2	4	0	2	0	2	0	0	1	0	12.00
/documents/mdot_ms4_july_2001-june_2002_chp_05_annual_report_91647_7.pdf /documents/mdot_ms4_july_2001-june_2002_chp_06_annual_report_91649_7.pdf	0	2	6	3	0	2 2	0	0	0	0	1	0	14.00 14.00
/documents/mdot_ms4_july_2001-june_2002_chp_07_annual_report_91650_7.pdf	2	3	6	1	0	2	0	0	0	1	1	0	16.00
/documents/mdot_ms4_july_2001-june_2002_chp_08_annual_report_91651_7.pdf /documents/mdot_ms4_july_2001-june_2002_chp_10_annual_report_91655_7.pdf	4 6	3	2 8	υ 1	0	6 3	0 8	2	1	0 9	1	1 9	19.00 55.00
	-	-				-	-	•		-	-	-	

#### MDOT Public Web Site PDF Document Tracking

/documents/mdot_ms4_july_2001-june_2002_tracking_form_annual_report_91657_7.pdf	22	8	7	2	2	4	4	3	1	1	3	3	60.00
/documents/mdot_ms4_july_2002_june_2003_chp_02_annual_report_91494_7.pdf	2	0	6	3	0	3	5	8	5	4	1	2	39.00
/documents/mdot_ms4_july_2002_june_2003_complete_appendices_double_sided_annual_report_part_1_94558_7.pdf	2	0	40	0	1	42	91	125	133	74	64	125	697.00
/documents/mdot_ms4_july_2002_june_2003_complete_appendices_double_sided_annual_report_part_2_94560_7.pdf	0	18	101	6	131	29	20	86	4	73	2	7	477.00
/documents/mdot_ms4_july_2002-june_2003_app_a_annual_report_91499_7.pdf	11	0	6	9	0	4	0	1	0	7	5	0	43.00
/documents/mdot_ms4_july_2002-june_2003_app_b_annual_report_91501_7.pdf	2	22	7	2	0	3	0	0	0	5	3	0	44.00
/documents/mdot_ms4_july_2002-june_2003_app_c_annual_report_91502_7.pdf	4	5	11	1	3	4	0	3	0	6	7	6	50.00
/documents/mdot_ms4_july_2002-june_2003_app_d_annual_report_91503_7.pdf	22	12	21	21	3	9	/	6	8	11	1	4	125.00
/documents/mdot_ms4_july_2002-june_2003_app_e_annual_report_91505_7.pdf	9 18	10 8	15 43	4 16	12	10 57	2	31	93	50	17	0	104.00 249.00
/documents/mdot_ms4_july_2002-june_2003_app_f_annual_report_part_1_94561_7.pdf	10	12	26	10	Ω	12	0	12	22	53	1	17	196.00
/documents/mdot_ms4_july_2002-june_2003_app_f_annual_report_part_2_94562_7.pdf /documents/mdot_ms4_july_2002-june_2003_chp_00_annual_report_91522_7.pdf	6	1	20	2	1	2	0	1	0	7	2	0	24.00
/documents/mdot_ms4_july_2002-june_2003_chp_01_annual_report_91527_7.pdf	6	1	2	3	4	4	5	0	6	2	1	1	35.00
/documents/mdot_ms4_july_2002-june_2003_chp_03_annual_report_91529_7.pdf	0	2	4	0	2	2	0	ō	1	3	2	0	16.00
/documents/mdot_ms4_july_2002-june_2003_chp_04_annual_report_91532_7.pdf	4	10	12	4	12	3	0	0	3	2	1	0	51.00
/documents/mdot_ms4_july_2002-june_2003_chp_05_annual_report_91534_7.pdf	0	0	2	0	2	2	0	0	0	3	2	0	11.00
/documents/mdot_ms4_july_2002-june_2003_chp_06_annual_report_91536_7.pdf	1	3	9	8	2	6	0	0	2	8	2	2	43.00
/documents/mdot_ms4_july_2002-june_2003_chp_07_annual_report_91538_7.pdf	6	0	5	5	0	4	0	1	2	3	1	0	27.00
/documents/mdot_ms4_july_2002-june_2003_chp_08_annual_report_91539_7.pdf	4	4	4	1	1	2	1	2	3	3	3	1	29.00
/documents/mdot_ms4_july_2002-june_2003_chp_09_annaul_report_91540_7.pdf	0	2	9	2	4	2	0	3	1	2	1	3	29.00
/documents/mdot_ms4_july_2002-june_2003_chp_10_annual_report_91543_7.pdf	5	11	11	4	2	10	7	3	0	14	3	0	70.00
/documents/mdot_ms4_july_2002-june_2003_full_document_double_sidedannual_report_91546_7.pdf	8	4	14	1	8	7	6	6	12	9	3	7	85.00
Public Education Materials													0.00
/documents/mdot_ms4_2006_sesc_poster_150052_7.pdf	0	11	45	146	129	116	33	63	56	185	51	43	878.00
/documents/mdot_ms4_dot_movie_popup_151947_7.html	0	0	411	63	19	21	27	84	14	76	92	28	835.00
/documents/mdot_ms4_general_education_brochure_150054_7.pdf	0	17	76	49	52	39	25	23	49	94	41	38	503.00
/documents/mdot_ms4_idepdisplay_final_171723_7.pdf	0	0	0	0	0	0	0	0	7	141	29	16	193.00
/documents/mdot_ms4_idep_brochure_final_171725_7.pdf	0	0	0	0	0	0	0	0	4	60	9	8	81.00
/documents/mdot_ms4_kids_stormwater_display_150056_7.pdf	0	5	15	8	10	12	7	19	15	29	11	15	146.00
/documents/mdot_ms4_pubilc_education_kids_flyer_152078_7.pdf	0	0	52	113	24	38	21	30	71	236	41	31	657.00
/documents/mdot_ms4_public_education_sesc_pocket_guidel_159655_7.pdf	0	0	0	0	20	73	37	62	37	171	54	10	464.00
/documents/mdot_ms4_storm_waterdisplay_150060_7.pdf	0	14	31	16	16	14	11	6	8	98	21	13	248.00
/documents/mdot_ms4_sw_brochure_91423_7.pdf	18	46	62	56	36	5	3	6	12	13	8	4	269.00
/documents/mdot_ms4_sw_litterbag_91939_7.pdf	1	2	4	1	0	0	0	0	0	0	0	0	8.00
/documents/mdot_ms4_whatisstormwaterrunoff_159349_7.pdf	0	0	0	0	13	14	12	14	18	75	22	20	188.00
/documents/mdot_ms4_what_is_storm_water_runoff_pep_articles91441_7.pdf	,	14	19	31	42	1	0	2	4	3	1	0	124.00 0.00
Other Education Information													0.00
/documents/mdot_ms4_1_training_module_91556_7.pdf	14	9	16	5	3	3	36	8	8	31	17	40	190.00
/documents/mdot_ms4_2_training_module_91557_7.pdf	2	7	19	3	1	3	3	0	0	37	7	14	96.00
/documents/mdot_ms4_3_training_module_91559_7.pdf	12	9	5	10	8	4	2	2	5	8	5	6	76.00
/documents/mdot_ms4_4_training_module_91560_7.pdf	14	13	26	7	12	3	4	8	3	26	10	19	145.00
/documents/mdot_ms4_acknowledgements_rain_intensity_91938_7.pdf	0	3	14	5	4	5	2	1	3	4	1	0	42.00
/documents/mdot_ms4_adopt-a-highway_article_91425_7.pdf	9	5	14	14	6	7	8	3	2	6	7	4	85.00
/documents/mdot_ms4_car_care_article_159344_7.pdf	0	0	0	0	7	10	6	17	3	68	10	4	125.00
/documents/mdot_ms4_car_care_pep_article_91428_7.pdf	13	4	18	8	5	0	0	0	5	0	1	0	54.00
/documents/mdot_ms4_executive_summary_rainfall_intersity_91936_7.pdf	24	34	66	38	33	17	16	4	2	10	56	15	315.00
/documents/mdot_ms4_executive_summary_rainfall_intersity_91936_7.pdf#search='rainfall%20records%20michigan'	0	0	0	0	0	0	0	0	0	0	. 1	0	1.00
/documents/mdot_ms4_final_phase_iipermit_91260_7.pdf	18	26	21	13	12	24	9	11	5	11	13	5	168.00
/documents/mdot_ms4_final_report_rainfall_intensity_91935_7.pdf	45	47 0	31	10	14	31 5	21	39 7	39	26 40	22	24	349.00
/documents/mdot_ms4_home_improvement_article_159345_7.pdf	16	•	0	0	7	5	3	0	7	40	0	4	79.00
/documents/mdot_ms4_home_improvement_pep_article_91430_7.pdf /documents/mdot_ms4_household_hazardous_waste_pep_article_91432_7.pdf	0	12 13	12 24	5	, 5	1	0	7	4	1	0	0	61.00 71.00
/documents/mdot_ms4_household_hazwaste_psyamide_3+bzr.pdf	0	0	0	0	6	7	8	15	9	30	8	5	88.00
/documents/mdot_ms4_introduction_pep_article_91433_7.pdf	2	4	14	11	2	0	0	2	0	2	1	0	38.00
/documents/mdot_ms4_lawn_and_garden_care_pep_article_91435_7.pdf	7	9	30	56	30	3	3	5	1	2	0	Ö	146.00
/documents/mdot_ms4_lawngarden_article_159348_7.pdf	0	0	0	0	14	38	24	25	17	61	5	3	187.00
/documents/mdot_ms4_litter_bag_graphic_150058_7.pdf	0	3	34	49	77	13	19	14	28	69	13	10	329.00
/documents/mdot_ms4_mdot_hwy_sw_runoff_study_91946_7.pdf	33	52	44	40	83	60	55	41	53	50	37	27	575.00
/documents/mdot_ms4_mdot_hwy_sw_runoff_study_91946_7.pdf#search=%22%22quality%20inlet%22%22	0	0	0	0	0	0	0	1	0	0	0	0	1.00
/documents/mdot_ms4_mdot_hwy_sw_runoff_study_91946_7.pdf#search=%22pervious%20pavement%20grand%20rapids%20mi%22	0	0	0	0	0	0	0	0	0	1	0	0	1.00
/documents/mdot_ms4_mdot_sw_management_plan_pep_article_91438_7.pdf	5	9	16	8	11	4	4	4	2	4	0	0	67.00
/documents/mdot_ms4_mdot_today_swarticle_91602_7.pdf	45 27	41	58 1	29	23 7	40	21	33 17	45	54 25	19 12	31	439.00
/documents/mdot_ms4_rainfall_idf_table_rainfall_intensity_91937_7.pdf /documents/mdot_ms4_storm_drain_stenciling_pep_articles_91440_7.pdf	13	20 6	1 29	11	14	23 0	29 2	17 1	24 3	25 5	12	25 0	217.00 87.00
, accounting, mac_mor_atom_atom_atom_gpep_articles_c++to_r.pdf	13	U	23	- "	14	U	2	'	3	3	3	U	0.00
Impairment Maps													0.00
//documents/mdot_ms4_ann_arbor_wb_impairment_map_97908_7.pdf	54	71	7	10	15	4	20	10	16	12	8	4	231.00
/documents/mdot_ms4_battle_creek_wb_impairment_map_97909_7.pdf	4	4	2	3	2	8	0	0	0	3	2	1	29.00
/documents/mdot_ms4_bay_city_wb_impairment_map_97910_7.pdf	12	12	3	5	5	15	6	3	2	5	4	8	80.00
/documents/mdot_ms4_benton_harbor_st_97912_7joseph_wb_impairment_map.pdf	3	23	8	6	5	10	12	20	10	10	3	5	115.00
/documents/mdot_ms4_detroit_wb_impairment_map_97913_7.pdf	23	9	14	8	14	3	5	4	6	23	8	3	120.00
/documents/mdot_ms4_elkhart_wb_impairment_map_97915_7.pdf	1	5	10	3	6	4	8	12	3	0	7	1	60.00
/documents/mdot_ms4_flint_wb_impairment_map_97917_7.pdf	22	10	30	4	12	6	11	5	1	3	1_	4	109.00
/documents/mdot_ms4_grand_rapids_wb_impairment_map_97919_7.pdf	19	45	22	17	29	22	53	25	28	35	7	10	312.00
/documents/mdot_ms4_holland_wb_impairment_map_97921_7.pdf	6	2	7	1	5	6	1	4	1	8	5	3	49.00
/documents/mdot_ms4_jackson_wb_impairment_map_97923_7.pdf	1 11	0 16	2 12	1 11	2	10 6	2	3 8	0 8	1 9	5	0 3	27.00
/documents/mdot_ms4_kalamazoo_wb_impairment_map_97924_7.pdf /documents/mdot_ms4_lansing_wb_impairment_map_97926_7.pdf	11 15	16 3	12 6	11	3	3	3	0	8 27	9 17	5	8	104.00 101.00
/documents/mdot_mis4_tainsing_wb_impairment_map_97926_7.pdi /documents/mdot_ms4_michigan_city_wb_impairment_map_97928_7.pdf	18	4	5	6	10	3 1	0	4	7	5	વ	1	64.00
/documents/mdd_ms4_monroe_wb_impainment_map_97829_7.pdf	7	2	8	9	1	9	1	3	0	1	5	2	48.00
/documents/mdot_ms4_muskegon_wb_impairment_map97931_7.pdf	12	1	18	15	4	10	11	7	3	6	8	3	98.00
/documents/mdot_ms4_port_huron_wb_impairment_map_97933_7.pdf	4	11	11	2	5	2	0	2	1	5	2	1	46.00
/documents/mdot_ms4_saginaw_wb_impairment_map_97935_7.pdf	31	3	14	10	3	6	2	7	7	2	2	1	88.00
/documents/mdot_ms4_south_bend_wb_impairment_map_97936_7.pdf	3	3	1	1	6	3	5	10	4	0	2	0	38.00
/documents/mdot_ms4_south_lyonhowellbrighton_wb_impairment_map_97940_7.pdf	51	37	17	13	14	12	2	26	7	8	5	10	202.00
/documents/mdot_ms4_toledo_wb_impairment_map_97941_7.pdf	8	1	4	1	0	4	0	0	0	0	3	0	21.00
Sub Totals	4,773	4,125	5,106	4,059	4,681	3,786	3,584	3,944	3,480	5,403	3,663	3,127	49,731.00

# Appendix B.3 Storm Water Awareness Survey Report – Executive Summary

### **EXECUTIVE SUMMARY**

In 2005, the Michigan Department of Transportation (MDOT) administered a survey to its employees and the firms it contracts with to determine their level of awareness of various storm water management issues. Survey responses were solicited at MDOT professional development meetings throughout the state and via e-mail. The goals were to: 1) identify groups needing additional training, 2) clarify which issues need to be better conveyed, and 3) determine how best to communicate these issues.

The survey was completed by 302 individuals, including MDOT employees and contractors. All seven MDOT regions as well as those working in the Lansing Central Office were represented. Of particular interest were employees working in the Design, Construction, and Maintenance divisions of MDOT because of their involvement in implementing storm water management practices.

Similar questions were grouped to identify trends in perceptions, knowledge, actions, and learning modes pertinent to storm water management awareness. The following were key findings from the survey:

- Regional differences in how MDOT employees view storm water were apparent with primarily urban regions perceiving storm water to be a more significant water pollution problem than rural regions.
- Job function affects the amount of storm water management training an employee receives with the Construction Division receiving the most training.
- There was an overwhelming preference for the use of structural controls to control

runoff. This would seem to indicate that storm water pollution is perceived to require a technical solution rather than a social solution.

- Among Maintenance Division employees, there is a perception that materials stored outside do not have an impact on water pollution.
- Although training impacted the perception that the survey respondents had about storm water issues, training did not necessarily impact the knowledge the survey respondents had about storm water issues.
- There were no perceived differences in actions between respondents that were trained from those that were not trained. Actions by all MDOT respondents were largely positive.
- A manual was the preferred learning material to help personnel follow proper storm water procedures. Classroom presentations were identified as the most effective learning mode.

The table below captures the above findings in order to better focus recommendations for future training.

		Regio	n		Job D	ivision		
Y = Yes N = No S = Somewhat  1 = Highest Priority/Preference 3 = Lowest Priority/Preference		Rural¹	Urban²	Lansing/Statewide	Construction	Design	Maintenance	All Respondents
Training Are they getting storm water training?		Υ	Υ	N	Υ	S	S	Υ
Perception Are they in-line with the scope of the SWMP?		S	S	S	S	S	N	S
Knowledge Do they understand enough for their job?		s	S	S	Υ	S	S	S
Actions Are they doing what SWMP requires?		Υ	Υ	Υ	Υ	Υ	Υ	Υ
Preferred Learning Mode C = Classroom OL = On-line Tutorials F = Field Trip FM = Field Manual V = Video O = Other	1 2 3	C F V	C F V	F C V	C F V	C F V	C F V	C F V
Preferred Learning Materials E = Email P = Poster M = Manual V = Video N = Newsletter Article W = Web Site	1 2 3	M V E	M V W	P N M	M N V	M E P	M V N/W	M V P
Recommended Ranking for Training (based on survey results)		2	3	1	3	2	1	

- 1. Rural Regions = Bay, North, and Superior
- 2. Urban Regions = Grand, Metro, Southwest, and University

Based on the results of the survey, the following recommendations are offered.

- Training should target groups that have previously received less training, such as those in the Design and Maintenance Divisions.
- 2. Training content should be specific to the target audience and address issues relevant to their region or division, as it pertains to storm water.
- 3. General education on storm water should become a component of job-related training and not a stand-alone part of the curriculum.
- 4. Social solutions to storm water problems (e.g. the proper location to wash vehicles or store materials) should be emphasized more in training along with technical solutions.

- 5. Periodic (e.g. yearly) refresher courses should be conducted on storm water maintenance procedures that should also stress the reasons why following them is important.
- 6. A variety of learning materials should be developed to improve the perception, knowledge, and actions of employees.
- 7. Classroom training, videos and field trips should be the main educational delivery vehicles or learning modes.
- 8. Training should be closely linked to operation manuals highlighting specific actions that employees can practice while on the job.

Since this survey was administered, MDOT has continued to restructure its storm water education program and some of the above

recommendations have already been implemented. For example, the Design Division will be targeted for training in 2007 and the Construction and Maintenance Divisions received a laminated pocket guide on soil erosion and sedimentation control. Out of these observations stem two additional recommendations:

- MDOT should evolve its storm water training into a comprehensive program, developing training manuals and materials which address storm water issues from the initial phases of a project to its on-going maintenance. Job divisions addressing their storm water portion of a project should be aware of their position in the development of a project as it relates to other divisions and storm water.
- MDOT should periodically administer (e.g. every two years) a more detailed survey to training recipients in order to continue to evaluate training effectiveness and make improvements to the program.

# Appendix C

# **Public Involvement and Participation**

1. Early Coordination Office Memorandum and Procedure (Pages C.1-1 to C.1-6)



# OFFICE MEMORANDUM

**DATE:** December 19, 2006

**TO:** Region Engineers

TSC Managers
Delivery Engineers
Development Engineers
Region Resource Staff

FROM: Judy Ruszkowski

Operations Environmental Stewardship Engineer

Storm Water Program Manager

**SUBJECT:** Storm Water Management Plan Activity C-4

Early Coordination Procedure for Post Construction BMPs

The Early Coordination Procedure described in the attached document will be implemented beginning with the scoping process on 2009 non-R&R projects, and 2012 R&R projects rated as categorical exclusions. The MS4 Public Involvement and Participation Sub-Team was charged with implementation of all early coordination related activities contained in the SWMP. MDOT's Environmental Committee has reviewed and approved this procedure. This document is being submitted to the MDEQ Storm Water Unit, as are all components of the department's SWMP.

Beginning January 1, 2007, at scoping, each region will identify the need for post-construction storm water Best Management Practices (BMPs) on individual projects and, using the specific trigger points outlined, determine if the project is subject to the Early Coordination Procedure. By identifying the need for post-construction storm water BMPs early in the process, these items can be included in the budget before projects are selected for inclusion in the Five Year Plan.

Each region should designate a person to coordinate the Early Coordination Procedure with the Aquatic Resource Specialist in the Environmental Section. The region permit coordinators are currently responsible for other early coordination activities (i.e. MDEQ-LWMD and MDNR) for issues pertaining to permits and, therefore, may be best positioned to assume this responsibility as well. The Aquatic Resource Specialist in the Environmental Section (currently Bethany Matousek at 517-241-2311) will provide assistance to the regions in determining when storm water BMPs are necessary for protection of water quality and site specification recommendations for appropriate BMP selection. Recommendations for appropriate BMP selection, as well as information regarding design criteria, appropriate sizing, manufacturer's specifications, and trouble shooting, will be provided by the Drainage Specialist in the Design Division's Hydraulics Unit (currently Coreen Strzalka at 517-373-3397).

Page 2 December 19, 2006

By implementing the Early Coordination Procedure during the 2007 scoping process for 2009/2012 projects, MDOT will have an opportunity to get input from the MDEQ Storm Water Unit on projects that will be constructed beginning in 2009 (safety, capital preventive maintenance, and passing relief projects) and 2012 (R&R projects). The goal is to have the Early Coordination Procedure completed prior to scope verification. The Aquatic Resource Specialist in the Environmental Section is MDOT's single point of contact with the MDEQ Storm Water Unit for coordination of the Early Coordination Procedure. With the assistance of the designated representative from each region, the Aquatic Resource Specialist is responsible for providing project specific information to MDEQ staff and coordinating a site visit, if necessary. The Aquatic Resource Specialist will document and track the results of the Early Coordination Procedure, and organize an annual review of the procedure with the Early Coordination Work Group, as outlined in the procedure itself.

The MS4 Team will evaluate this procedure annually as part of the overall SWMP review. Modifications to this procedure will be made as necessary to ensure MDOT construction and maintenance projects are planned and completed with consideration for the natural resources of the State, as well as project schedule and cost.

As always, I am available to discuss any of the requirements of MDOT's SWMP. Questions about the Early Coordination Procedure can be directed to either me (517-322-5698) or Bethany Matousek, Aquatic Resource Specialist in the Environmental Section (517-241-2311).

Judy Ruszkowski

Attachment

JAR:kar

cc: Environmental Committee

MS4 Team

D. Christian – Tetra Tech A. Thomas – Tetra Tech

# Michigan Department of Transportation SWMP Activity C-4 Early Coordination for Post-Construction BMPs

## 1. Purpose and Scope

Post construction storm water management for new development and redevelopment projects is one of the five elements included in the MDOT Storm Water Management Plan (SWMP). This plan element is supported by several storm water program activities. Activity C-4 of the plan calls for the development and implementation of a process by which roadway design plans will be reviewed for application of post construction best management practices (BMPs). In addition to the MDOT review, MDEQ will be provided the opportunity to review preliminary construction plans and to provide input on placement of drainage and BMPs.

MDOT and MDEQ-Water Bureau have found that this storm water permit requirement can be met by using an early coordination process similar to that required under the National Environmental Policy Act of 1969 (NEPA) to address issues related to storm water management. MDEQ-Water Bureau input earlier in the process of project design will facilitate issue identification and resolution. As a result, project design changes that minimize negative impacts or enhance positive impacts to the state's natural resources can be made more efficiently by MDOT.

Transportation projects conducted by MDOT involving federal funds administered by the Federal Highway Administration (FHWA) must be in compliance with NEPA. Compliance guidance is provided by the United States Department of Transportation (US DOT) in 23 CFR 771 Environmental Impact and Related Procedures. An Environmental Impact Statement (EIS) must be developed for those actions that will have a significant impact on the quality of the human environment. There are many classes of actions that, based on past experience with similar actions, do not involve significant impacts that are categorically excluded from further consideration under NEPA (i.e. Categorical Exclusions (CE)). If an action is not covered by a CE and its potential for significant impact is unknown, an Environmental Assessment (EA) is required to determine if an EIS is needed or if there can be a Finding of No Significant Impact (FONSI).

The existing NEPA process for major action documents (EA and EIS) includes early coordination with other affected agencies. The NEPA process is designed to ensure that all potential impacts, possible alternatives, and affected parties are identified and that the best available science is used to determine the impacts of the proposed action and alternatives. MDOT currently distributes these major action documents to various state regulatory agencies. MDOT will add the MDEQ Stormwater Permits Section MS4 Coordinator to the document distribution list as the single point of contact through which MDOT will distribute all major action documents to the MDEQ-Water Bureau.

Approximately 95% of MDOT's projects are covered by categorical exclusions and are typically exempt from the same NEPA requirements as major action documents. Many actions that are categorically excluded from further NEPA compliance, however, still require MDOT to apply for permits from MDEQ-LWMD. As part of the permitting procedure, MDEQ-LWMD reviews permit applications for unacceptable or avoidable impacts to the state's natural resources. The permit application process for MDOT categorical exclusion projects, however, usually occurs after project plans are nearly complete. At this point in MDOT's process, resource issues identified by MDEQ-Water Bureau are often difficult and costly to incorporate into the project design. In addition to satisfying the conditions of MDOT's statewide NPDES storm water discharge permit, the early coordination procedure with MDEQ-Water Bureau outlined in this document will allow

MDOT to identify issues and minimize impacts to water quality prior to submitting a permit application to MDEQ-LWMD. It is expected that this process will expedite MDEQ-LWMD's permit review process.

### 2. Issues That Will Trigger Early Coordination with MDEQ-Water Bureau

Actions that are categorically excluded from further NEPA compliance will be subject to early coordination between MDOT and MDEQ-Water Bureau for projects that result in an earth disturbance of more than one acre; <u>and</u> meet one or more of the requirements (triggers) listed in section 2.1; **and** meet one or more of the requirements (triggers) listed in section 2.2.

### 2.1 Projects that include one or more of the following:

- **2.1.1** Projects that result in a new storm water outfall to surface waters of the state. Surface waters of the state include all of the following, but do not include drainage ways and ponds used solely for wastewater conveyance, treatment, or control:
  - The Great Lakes and their connecting waters,
  - All inland lakes,
  - Rivers.
  - Streams.
  - Impoundments,
  - Open drains,
  - Other surface bodies of water within the confines of the state; or
- **2.1.2** An increased discharge volume or peak flow rate of 20% or more per storm event as compared to discharges prior to the project.

### 2.2 Projects that include one or more of the following:

- 2.2.1 Discharges to water bodies as designated in PA 451 of 1994 Part 4. Water Quality Standards, Rule 323.1100 (4) and (6-7). This rule references MDNR publications "Coldwater Lakes of Michigan" (Appendix A), "Designated Trout Streams for the State of Michigan" (Appendix B), and "Designated Trout Lakes and Regulations" respectively (Appendix C); or
- 2.2.2 Discharges that may convey pollutants to surface waters of the state that would exceed a Total Maximum Daily Load (TMDL) approved by the U.S. Environmental Protection Agency. Pollutants of concern shall be limited to metals, sediments, oil and grease, fish kills, fish or macroinvertebrate communities rated as poor, and those which would contribute to low dissolved oxygen (Appendix D); or
- 2.2.3 Discharges to Outstanding State Resource Waters as identified in PA 451 of 1994 Part 4. Water Quality Standards, Rule 323.1098 (6) (Appendix E).

### 3. Early Coordination Process for Categorical Exclusion Projects

Early coordination for post construction storm water best management practices on categorical exclusion projects will involve the following process.

- 3.1 Identify Trigger Issue- MIDOT staff will attempt to identify the trigger issue during Scoping. MDOT staff involved in issue identification will include Project Managers, Permit Coordinators, and, if needed, the Aquatic Resource Specialist in the MDOT Environmental Section. MDOT staff will coordinate on relevant issues prior to the MDOT Aquatic Resource Specialist initiating contact with MDEQ-Water Bureau staff.
- 3.2 Provide Information to MDEQ- MDOT will provide the following information to the appropriate MDEQ-Water Bureau District Supervisor for review and will notify the MDEQ-Water Bureau Permits Section MS4 Coordinator.
  - Location map
  - Existing ROW
  - Scope of work
  - Any available preliminary design
  - Digital photos
  - · Early Coordination Project Review Sheet

MDEQ-Water Bureau will have 30 days from the date of transmittal to provide review and comments. If no comments are received during this time period, MDOT will proceed with the project as planned.

- 3.3 Schedule a Site Visit The need for a site visit will be at the discretion of MDOT and MDEQ-Water Bureau staff. Additional staff specialists may be involved in the site evaluation if necessary. MDEQ staff in the Transportation Review Unit will be contacted when appropriate to be given the opportunity to participate in site visits.
- 3.4 Document Results of Early Coordination This will consist of a summary of the results of the Early Coordination process and details needed for process tracking and evaluation. The summary will be provided by the Aquatic Resource Specialist to the Storm Water Program Manager for incorporation into the storm water program annual report.

### 4. Tracking and Measurement

MDOT will develop a database and tracking mechanism to store, analyze, and summarize the necessary information. The following information will be collected by each respective agency and provided to the other agency to allow evaluation of the effectiveness of this early coordination process:

- **4.1** The number of early coordination projects submitted to MDEQ-Water Bureau for review,
- **4.2** The dates on which those projects were submitted,
- **4.3** The dates on which MDEQ-Water Bureau review was completed and provided to MDOT.
- **4.4** The number of projects on which issues required further action to resolve,
- **4.4** Issues that may need to be added or removed from the process,
- **4.5** Issues that were missed but became a permitting issue.

### 5. Annual Process Review.

MiDOT and MDEQ-Water Bureau will establish a workgroup to oversee the early coordination process. Representatives will meet at least annually, and more often if the workgroup finds it necessary, to review the past years' measurements, the effectiveness of the early coordination process, and to make recommendations for any process improvements as they may determine appropriate.

## 5.1 The MDOT members of the workgroup will be as follows:

- Environmental Section Aquatic Resource Specialist
- Hydraulics Engineer
- Region Permit Coordinators
- Storm Water Program Manager

### 5.2 The MDEQ members of the workgroup will be as follows:

- MDEQ-Water Bureau Permits Section MS4 Coordinator
- MDNR Fisheries Division- Designated representative
- MDEQ-LWMD Supervisor of the Transportation Review Unit

# **Appendix D**

# **Illicit Discharge Elimination Program**

- 1. Dry Weather Screening Investigation Maps (Saved on CD-ROM)
- 2. Reported Illicit Discharges (Page D.2-1)
- 3. Construction Advisory (CA) 2006-12, Reporting Illicit Discharges and Illicit Connections (Pages D.3-1 to D.3-2)
- 4. Statewide Outfall Maps (Saved on CD-ROM)
- 5. 2006 Labeled Outfalls (Pages D.5-1 to D.5-3)
- 6. Potential Illicit Discharge Notification Letters (Pages D.6-1 to D.6-33)

See Appendix D.1 Dry Weather Screening Investigation Maps Saved on CD-ROM

# Complaint Summary

Monday, December 04, 2006

Complaint #	Region	Date of Observaion	Route	<i>PSD # PR #</i>	Control Section	Source Nan	ne Source Address	Nature of Problem	Status
1	Southwest	8/21/2006				Hummel	8304 Maple Grove Rd	Two corrugated plastic pipes entering ROW adjacent to headwall. Dark water exiting one of the pipes. Pipe clogged. Once unplugged, water clear.	Resolved
2	Southwest	9/5/2006	M-140	577905	5 80031	unknown	39571 M-140	pipe entering ditchline opposite headwall. Slight odor. Black color.	
3	Southwest	11/2/2006	M-140		80031	Consumers Concrete	13271 M-140	concrete slurry/dust entering drainage ditch	
4	Southwest	2/3/2006	JS-131			choolcraft rm Services	16721 S. US-131 PO Box 326	Secondary containment	Resolved

# Construction Advisory

CA 2006-12

September 20, 2006

From Brenda O'Brien, Engineer of Construction and Technology

MDOT-Construction and Technology Support Area P.O. Box 30049 Lansing, Michigan 48909 Phone/517-322-1087 Fax/517-322-5664 www.michigan.gov/mdot/

Index: Environment

Questions regarding this Construction Advisory should be directed to:

Judy Ruszkowski, Operations Environmental Stewardship Engineer, 517-322-5698 or ruszkowskij@michigan.gov



BJO:JAR

# Reporting Illicit Discharges and Illicit Connections

MDOT's Statewide Storm Water Discharge Permit requires the department to have a process in place to receive and respond to reports of illicit discharges/connections (ID/C) to our storm water drainage system.

Illicit Connections are any physical connection to MDOT's drainage system that 1.) conveys an illicit discharge or 2.) is not authorized or permitted by MDOT where such authorization or permit is required.

Illicit Discharges are any discharge or seepage into MDOT's drainage system that is not composed entirely of storm water, and which is not specifically exempt under MDOT's statewide permit.

MDOT's Illicit Discharge Elimination Program (IDEP) implementation team worked with our storm water consultant, Tetra Tech, to develop a database to record and track the status of all reported ID/Cs. Each region has designated one individual to serve as the IDEP Coordinator to ensure all reported ID/Cs are entered into the database for follow-up. In most regions, this person is also the Storm Water Coordinator.

Construction staff is

reminded to follow BOH-IM 2004-10, *Illicit*Discharge Elimination

Program Procedure,
whenever a possible
ID/C is encountered
during the construction
phase of a project. The
procedure is
summarized here.

- The contractor notifies the MDOT staff when they encounter a suspected ID/C during construction. Examples are an unidentified pipe within a drainage structure or entering a ditch.
- 2. Contact the resource specialist, Storm Water Coordinator or the IDEP Coordinator for the region, if necessary, to assist in determining if an emergency situation exists. Examples of an emergency situation include untreated sewage, or strong chemical or fuel smell from the discharge flowing to our drainage system.
- 3. If an emergency situation does exist, MDOT staff must contact the Pollution Emergency Alert System (PEAS) at 1-800-292-4706 to notify MDEQ of the emergency.
- 4. If no emergency exists, attempt to

- determine the source of the discharge based on the surrounding land use and observable characteristics of the discharge, or direction of the pipe or other conveyance. Examples of nonemergency ID/Cs may include roof drains or sump pump discharges entering our storm water drainage system.
- 5. If you are unable to identify the source in a reasonable amount of time. record all observations about the discharge before continuing with construction in that area. Report this information to your region IDEP Coordinator so it can be entered into the IDEP database for tracking and, if necessary, follow
- 6. The IDEP
  Coordinator will
  then work with the
  TSC to identify the
  source and notify all
  appropriate
  agencies, following
  established
  procedures.

Remember, MDOT is required, as a condition of our storm water discharge permit, to document and follow

### 2 REPORTING ILLICIT DISCHARGES AND ILLICIT CONNECTIONS

up on all ID/Cs that we are made aware of on our right-of-way. Most ID/Cs to our storm water drainage system discovered during construction originates from off our right-of-way. In this case, MDOT will refer the situation to the local health department, MDEQ or other regulatory agency. MDOT will then cooperate in any further investigation by these

agencies where access to our right-of-way may be needed.

If you have any questions on how to report an illicit discharge or illicit connection, or if you would like to receive additional information on our permit requirements contact your region IDEP Coordinator listed here: Superior Region – Dan Hamlin North Region – Mike Rogers or Gary Niemi Grand Region – Steve Houtteman Bay Region – Cary Rouse Southwest Region – Nick VanWoert University Region – Bob Batt Metro Region – Randy McKinney

# See Appendix D.4 Statewide Outfall Maps Saved on CD-ROM

# Appendix D.5 2006 Labeled Outfalls

Project	Outfall Location
1. M-10 Reconstruction near I-696	Southbound M-10, Ramp S. Station 2541+00, 40 feet left of
63081-45715A	centerline, 15 inch RCP.
	Southbound M-10. Station 2518+35, 40 feet right of
	centerline, 18 inch CMP.
	Southbound M-10. Station 2520+72, 85 feet left of
	centerline, 12 inch CMP.
	Southbound M-10. Station 2520+93, 85 feet left of
	centerline, 12 inch CMP.
	Southbound M-10. Station 2520+20, 90 feet right of
	centerline, 12 inch CMP.
	Southbound M-10. Station 2523+00, 90 feet right of
	centerline, 24 inch CMP.
	Northbound M-10, Ramp Q/WB I-696. Station 1375+50. 60
	feet left of off ramp centerline, 12 inch CMP.
	Northbound M-10, Ramp D. Station 311+00, 53 feet right of
	centerline, 18 inch RCP.
	Northbound M-10, Ramp J. Station 1008+75, 95 feet right
	of centerline, 12 inch RCP.
	Northbound M-10, Ramp J. Station 1008+77, 120 feet right
	of centerline, 12 inch RCP.
	Northbound M-10, Ramp J. Station 1008+76, 75 feet left of
	centerline, 18 inch RCP.
	Northbound M-10. Station 1367+25, 80 feet right of
	centerline, 12 inch CMP.
	Northbound M-10. Station 1370+25, 80 feet right of
	centerline, 12 inch CMP.
	Northbound M-10. Station 1370+25, 80 feet left of
	centerline, 12 inch CMP.
	Northbound M-10. Station 1372+51, 80 feet left of
	centerline, 12 inch CMP.
	Northbound M-10. Station 1373+05, 75 feet right of
	centerline, 12 inch CMP
	Northbound M-10, Ramp E. Station 509+45, 55 feet left of
	centerline, 12 inch CMP.
	Northbound M-10, Ramp E. Station 502+30, 23 feet left of
	centerline, 18 inch RCP.
2. I-696 near M-10	Eastbound I-696. Station 1+819, 35 meters right of
63101-54301A	centerline, 300 mm RCP.
	,
	I-696, exit ramp to southbound M-10. Station 7+373, 15
	meters right of centerline, 3000 mm by 1500 mm tee, box.
	·
	I-696, exit ramp to southbound M-10. Station 7+380, 10
	meters right of centerline, 1676 mm RCP.
	I-696, exit ramp to southbound M-10. Station 1+535, 45
0 1 0 0 D1	meters right of centerline, 450 mm RCP.
3. I-96 BL at Rouge River, Farmington Hills	Station 13+72, 30.5 feet right of centerline, 15 inch RCP.
63821-72614A	Station 14+80, 31 feet right of centerline, 48 inch RCP.
	Station 15+75, 36.5 feet right of centerline, 12 inch RCP.

# Appendix D.5 2006 Labeled Outfalls

inch RCP.  Station 56+10, 68 feet right of construction centerline, 48 inch RCP.  5. M-82 in Fremont 62011-79505A Station 1143+88, 74 feet right of centerline, 18 inch RCP. Station 1144+29, 78 feet right of centerline, 24 inch RCP. Station 1144+26, 73 feet left of centerline, 24 inch RCP. Station 1144+26, 73 feet right of centerline, 24 inch RCP.  7. M-37 at M-82, Newaygo 62031-79781A Station 273+35, 32.4 feet left of centerline, 36 inch RCP with galvanized end section.  8. M-78 at the Battle Creek River, Bellevue 23011-78400A Station 588+45, 35 feet north of centerline, 15 inch RCP.  9. I-94 at Lovers Lane Bridge, Portage 39022-76448A  EB I-94 at Portage Creek, Station 1532+04, 105 feet right construction centerline, 30 inch RCP.	Project	Outfall Location
inch RCP. Station 56+10, 68 feet right of construction centerline, 48 inch RCP.  5. M-82 in Fremont 62011-79505A Station 1143+88, 74 feet right of centerline, 18 inch RCP. Station 1144+29, 78 feet right of centerline, 24 inch RCP. Station 1144+29, 78 feet right of centerline, 24 inch RCP. Station 1144+26, 73 feet left of centerline, 24 inch RCP. Station 1144+26, 73 feet left of centerline, 24 inch RCP. T. M-37 at M-82, Newaygo Station 273+35, 32.4 feet left of centerline, 36 inch RCP. With galvanized end section.  Station 588+45, 35 feet north of centerline, 15 inch RCP. Station 588+45, 35 feet north of centerline, 15 inch RCP. WB I-94 at Lovers Lane Bridge, Portage 39022-76448A Station 588+45, 35 feet north of centerline, 15 inch RCP. WB I-94 at Portage Creek, Station 1532+04, 105 feet right construction centerline, 36 inch RCP. WB I-94 at Portage Creek, Station 1528+09, 100 feet left construction centerline, 36 inch RCP. Station 16+85 (storm sewer stationing), 42 inch RCP. Station 259+50, 50 feet left of centerline, 36 inch RCP. Station 260+00, 50 feet left of centerline, 30 inch RCP. Station 260+00, 50 feet left of centerline, 24 inch RCP. Station 260+00, 50 feet left of centerline, 30 inch RCP. Station 260+00, 50 feet left of centerline, 30 inch RCP. Station 260+00, 50 feet left of centerline, 24 inch RCP. Station 39+50, 32 feet right of centerline, 30 inch RCP. Station 89+50, 32 feet right of centerline, 30 inch RCP. Station 89+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 97+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section. Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 91+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 91+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	4. US-24 at Silver Creek, Flat Rock	Station 55+90, 70 feet right of construction centerline, 12
inch RCP.  5. M-82 in Fremont 62011-79505A Station 1143+88, 74 feet right of centerline, 18 inch RCP. Station 1144+29, 78 feet right of centerline, 24 inch RCP. Station 1144+26, 73 feet left of centerline, 24 inch RCP. Station 1144+26, 73 feet left of centerline, 24 inch RCP. Station 1144+26, 73 feet left of centerline, 24 inch RCP. Station 568+00, 30 feet right of centerline, 24 inch RCP. Station 273+35, 32.4 feet left of centerline, 36 inch RCP. with galvanized end section.  Station 588+45, 35 feet north of centerline, 15 inch RCP. WB I-94 at Portage Creek, Station 1532+04, 105 feet right construction centerline, 30 inch RCP. WB I-94 at Portage Creek, Station 1528+09, 100 feet left of construction centerline, 30 inch RCP. Ucated behind the Springport Telephone Company. Station 259+50, 55 feet right of centerline, 36 inch RCP. Station 259+50, 55 feet right of centerline, 36 inch RCP. Station 260+00, 55 feet right of centerline, 24 inch RCP. Station 260+00, 55 feet right of centerline, 24 inch RCP. Station 39+74, 225 feet left of centerline, 24 inch RCP, sloped metal end section. Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	· /	<u> </u>
inch RCP.  5. M-82 in Fremont 62011-79505A Station 1143+88, 74 feet right of centerline, 18 inch RCP. Station 1144+29, 78 feet right of centerline, 24 inch RCP. Station 1144+26, 73 feet left of centerline, 24 inch RCP. Station 1144+26, 73 feet left of centerline, 24 inch RCP. Station 1144+26, 73 feet left of centerline, 24 inch RCP. Station 568+00, 30 feet right of centerline, 24 inch RCP. Station 273+35, 32.4 feet left of centerline, 36 inch RCP. with galvanized end section.  Station 588+45, 35 feet north of centerline, 15 inch RCP. WB I-94 at Portage Creek, Station 1532+04, 105 feet right construction centerline, 30 inch RCP. WB I-94 at Portage Creek, Station 1528+09, 100 feet left of construction centerline, 30 inch RCP. Ucated behind the Springport Telephone Company. Station 259+50, 55 feet right of centerline, 36 inch RCP. Station 259+50, 55 feet right of centerline, 36 inch RCP. Station 260+00, 55 feet right of centerline, 24 inch RCP. Station 260+00, 55 feet right of centerline, 24 inch RCP. Station 39+74, 225 feet left of centerline, 24 inch RCP, sloped metal end section. Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		Station 56+10, 68 feet right of construction centerline, 48
Station 1144+29, 78 feet right of centerline, 24 inch RCP. Station 1144+26, 73 feet left of centerline, 24 inch RCP.  6. M-20 at White River, White Cloud 62015-60572A  Station 568+00, 30 feet right of centerline, 24 inch RCP.  7. M-37 at M-82, Newaygo 62031-79781A  8. M-78 at the Battle Creek River, Bellevue 23011-78400A  9. I-94 at Lovers Lane Bridge, Portage 39022-76448A  Station 588+45, 35 feet north of centerline, 15 inch RCP.  EB I-94 at Portage Creek, Station 1532+04, 105 feet right construction centerline, 30 inch RCP.  10. M-99 in Springport 11. M-51 over Brandywine Creek, Niles 11051-79453A  Station 259+50, 50 feet left of centerline, 30 inch RCP.  Station 259+50, 55 feet right of centerline, 30 inch RCP.  Station 260+00, 50 feet left of centerline, 30 inch RCP.  Station 260+00, 55 feet right of centerline, 24 inch RCP.  Station 1309+74, 225 feet left of centerline, 30 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		inch RCP.
Station 1144+26, 73 feet left of centerline, 24 inch RCP 6. M-20 at White River, White Cloud 62015-60572A 7. M-37 at M-82, Newaygo Station 273+35, 32.4 feet left of centerline, 36 inch RCP 62031-79781A 8. M-78 at the Battle Creek River, Bellevue 23011-78400A 9. I-94 at Lovers Lane Bridge, Portage 39022-76448A Station 588+45, 35 feet north of centerline, 15 inch RCP. WB I-94 at Portage Creek, Station 1532+04, 105 feet right construction centerline, 30 inch RCP. WB I-94 at Portage Creek, Station 1528+09, 100 feet left of construction centerline, 36 inch RCP. Uncated behind the Springport Telephone Company. Station 16+85 (storm sewer stationing), 42 inch RCP. Station 259+50, 55 feet right of centerline, 36 inch RCP. Station 260+00, 50 feet left of centerline, 36 inch RCP. Station 260+00, 55 feet right of centerline, 36 inch RCP. Station 260+00, 55 feet right of centerline, 36 inch RCP. Station 260+00, 55 feet right of centerline, 36 inch RCP. Station 260+00, 55 feet right of centerline, 36 inch RCP. Station 260+00, 55 feet right of centerline, 36 inch RCP. Station 260+00, 55 feet right of centerline, 36 inch RCP. Station 260+00, 55 feet right of centerline, 30 inch RCP. Station 260+00, 55 feet right of centerline, 30 inch RCP. Station 260+00, 55 feet right of centerline, 36 inch RCP. Station 260+00, 55 feet right of centerline, 36 inch RCP. Station 309+74, 225 feet left of centerline, 30 inch RCP. Station 309+74, 225 feet left of centerline, 36 inch RCP, sloped metal end section. Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	5. M-82 in Fremont	Station 1143+88, 74 feet right of centerline, 18 inch RCP.
6. M-20 at White River, White Cloud 62015-60572A  Station 568+00, 30 feet right of centerline, 24 inch RCP.  Station 273+35, 32.4 feet left of centerline, 36 inch RCP with galvanized end section.  8. M-78 at the Battle Creek River, Bellevue 23011-78400A  9. I-94 at Lovers Lane Bridge, Portage 39022-76448A  Station 588+45, 35 feet north of centerline, 15 inch RCP.  EB I-94 at Portage Creek, Station 1532+04, 105 feet right construction centerline, 30 inch RCP.  WB I-94 at Portage Creek, Station 1528+09, 100 feet left construction centerline, 36 inch RCP.  Unough the Springport Station 1528+09, 100 feet left of construction centerline, 36 inch RCP.  10. M-99 in Springport Station 16+85 (storm sewer stationing), 42 inch RCP.  Station 259+50, 50 feet left of centerline, 36 inch RCP.  Station 259+50, 55 feet right of centerline, 36 inch RCP.  Station 260+00, 55 feet right of centerline, 15 inch RCP.  Station 260+00, 55 feet right of centerline, 15 inch RCP.  Station 259+50, 50 feet left of centerline, 36 inch RCP.  Station 259+50, 55 feet right of centerline, 36 inch RCP.  Station 260+00, 55 feet right of centerline, 15 inch RCP.  Station 260+00, 55 feet right of centerline, 24 inch RCP.  Station 1309+74, 225 feet left of centerline, 30 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section.  Station 83+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	62011-79505A	Station 1144+29, 78 feet right of centerline, 24 inch RCP.
Station 568+00, 30 feet right of centerline, 24 inch RCP.  7. M-37 at M-82, Newaygo 62031-79781A  8. M-78 at the Battle Creek River, Bellevue 23011-78400A  9. I-94 at Lovers Lane Bridge, Portage 39022-76448A  Station 588+45, 35 feet north of centerline, 15 inch RCP.  WB I-94 at Portage Creek, Station 1532+04, 105 feet right construction centerline, 30 inch RCP.  WB I-94 at Portage Creek, Station 1528+09, 100 feet left construction centerline, 36 inch RCP.  Located behind the Springport Telephone Company.  Station 16+85 (storm sewer stationing), 42 inch RCP.  Station 259+50, 55 feet right of centerline, 36 inch RCP.  Station 259+50, 55 feet right of centerline, 30 inch RCP.  Station 260+00, 50 feet left of centerline, 30 inch RCP.  Station 1309+74, 225 feet left of centerline, 30 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP.  Station 83+50, 32 feet right of centerline, 30 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP.  Station 83+50, 32 feet right of centerline, 30 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP.  Station 83+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		Station 1144+26, 73 feet left of centerline, 24 inch RCP
7. M-37 at M-82, Newaygo 62031-79781A 8. M-78 at the Battle Creek River, Bellevue 23011-78400A 9. I-94 at Lovers Lane Bridge, Portage 39022-76448A  Station 588+45, 35 feet north of centerline, 15 inch RCP. WB I-94 at Portage Creek, Station 1532+04, 105 feet right construction centerline, 30 inch RCP. WB I-94 at Portage Creek, Station 1528+09, 100 feet left construction centerline, 36 inch RCP. WB I-94 at Portage Creek, Station 1528+09, 100 feet left construction centerline, 36 inch RCP. WB I-94 at Portage Creek, Station 1528+09, 100 feet left construction centerline, 36 inch RCP. Uccated behind the Springport Telephone Company. Station 16+85 (storm sewer stationing), 42 inch RCP. Station 259+50, 55 feet right of centerline, 36 inch RCP. Station 259+50, 55 feet left of centerline, 36 inch RCP. Station 260+00, 50 feet left of centerline, 15 inch RCP. Station 260+00, 50 feet left of centerline, 15 inch RCP. Station 260+00, 55 feet right of centerline, 15 inch RCP. Station 260+00, 55 feet right of centerline, 24 inch RCP. Station 39+74, 225 feet left of centerline, 30 inch RCP. Station 89+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section. Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section. Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	6. M-20 at White River, White Cloud	
Station 259+50, 55 feet right of centerline, 15 inch RCP.	62015-60572A	Station 568+00, 30 feet right of centerline, 24 inch RCP.
8. M-78 at the Battle Creek River, Bellevue 23011-78400A 9. I-94 at Lovers Lane Bridge, Portage 39022-76448A  EB I-94 at Portage Creek, Station 1532+04, 105 feet right construction centerline, 30 inch RCP.  WB I-94 at Portage Creek, Station 1528+09, 100 feet left construction centerline, 36 inch RCP.  10. M-99 in Springport 38011-75184A 11. M-51 over Brandywine Creek, Niles 11051-79453A  Station 16+85 (storm sewer stationing), 42 inch RCP.  Station 259+50, 55 feet right of centerline, 36 inch RCP.  Station 259+50, 55 feet right of centerline, 15 inch RCP. Station 260+00, 55 feet right of centerline, 15 inch RCP.  Station 260+00, 55 feet right of centerline, 15 inch RCP.  Station 2167+15, 45 feet right of centerline, 24 inch CMP.  Station 39+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	7. M-37 at M-82, Newaygo	Station 273+35, 32.4 feet left of centerline, 36 inch RCP
23011-78400A  9. I-94 at Lovers Lane Bridge, Portage 39022-76448A  EB I-94 at Portage Creek, Station 1532+04, 105 feet right construction centerline, 30 inch RCP.  WB I-94 at Portage Creek, Station 1528+09, 100 feet left construction centerline, 36 inch RCP.  10. M-99 in Springport 38011-75184A  11. M-51 over Brandywine Creek, Niles 11051-79453A  Station 259+50, 50 feet left of centerline, 36 inch RCP.  Station 259+50, 55 feet right of centerline, 36 inch RCP.  Station 260+00, 55 feet right of centerline, 30 inch RCP.  12. M-53 over White Creek, Sanilac County 74012-79592A  13. M-26 in South Range 31012-53244A  Station 1309+74, 225 feet left of centerline, 30 inch RCP.  Station 38+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		with galvanized end section.
9. I-94 at Lovers Lane Bridge, Portage 39022-76448A  BEB I-94 at Portage Creek, Station 1532+04, 105 feet right construction centerline, 30 inch RCP.  WB I-94 at Portage Creek, Station 1528+09, 100 feet left or construction centerline, 36 inch RCP.  10. M-99 in Springport 38011-75184A  Located behind the Springport Telephone Company. Station 16+85 (storm sewer stationing), 42 inch RCP.  Station 259+50, 50 feet left of centerline, 36 inch RCP.  Station 259+50, 55 feet right of centerline, 15 inch RCP.  Station 260+00, 50 feet left of centerline, 15 inch RCP.  Station 260+00, 55 feet right of centerline, 15 inch RCP.  Station 260+00, 55 feet right of centerline, 24 inch CMP.  13. M-26 in South Range 31012-53244A  Station 1309+74, 225 feet left of centerline, 30 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	8. M-78 at the Battle Creek River, Bellevue	
39022-76448A  construction centerline, 30 inch RCP.  WB I-94 at Portage Creek, Station 1528+09, 100 feet left of construction centerline, 36 inch RCP.  10. M-99 in Springport 38011-75184A  Station 16+85 (storm sewer stationing), 42 inch RCP.  11. M-51 over Brandywine Creek, Niles 11051-79453A  Station 259+50, 50 feet left of centerline, 36 inch RCP.  Station 259+50, 55 feet right of centerline, 15 inch RCP.  Station 260+00, 50 feet left of centerline, 30 inch RCP.  Station 260+00, 55 feet right of centerline, 15 inch RCP.  Station 260+00, 55 feet right of centerline, 15 inch RCP.  Station 2167+15, 45 feet right of centerline, 24 inch CMP.  13. M-26 in South Range 31012-53244A  Station 1309+74, 225 feet left of centerline, 30 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section.  Station 97+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	23011-78400A	Station 588+45, 35 feet north of centerline, 15 inch RCP.
WB I-94 at Portage Creek, Station 1528+09, 100 feet left of construction centerline, 36 inch RCP.  10. M-99 in Springport  38011-75184A  11. M-51 over Brandywine Creek, Niles 11051-79453A  Station 16+85 (storm sewer stationing), 42 inch RCP.  Station 259+50, 50 feet left of centerline, 36 inch RCP.  Station 259+50, 55 feet right of centerline, 15 inch RCP.  Station 260+00, 50 feet left of centerline, 30 inch RCP.  Station 260+00, 55 feet right of centerline, 15 inch RCP.  Station 260+00, 55 feet right of centerline, 24 inch RCP.  Station 1309+74, 225 feet left of centerline, 30 inch RCP.  Station 1309+74, 225 feet left of centerline, 30 inch RCP.  Station 83+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	9. I-94 at Lovers Lane Bridge, Portage	EB I-94 at Portage Creek, Station 1532+04, 105 feet right of
construction centerline, 36 inch RCP.  10. M-99 in Springport  38011-75184A  Station 16+85 (storm sewer stationing), 42 inch RCP.  11. M-51 over Brandywine Creek, Niles  11051-79453A  Station 259+50, 50 feet left of centerline, 36 inch RCP.  Station 260+00, 50 feet left of centerline, 30 inch RCP.  Station 260+00, 55 feet right of centerline, 30 inch RCP.  Station 260+00, 55 feet right of centerline, 15 inch RCP.  Station 260+00, 55 feet right of centerline, 24 inch CMP.  12. M-53 over White Creek, Sanilac County  74012-79592A  Station 2167+15, 45 feet right of centerline, 24 inch CMP.  Station 339+74, 225 feet left of centerline, 30 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	39022-76448A	· ·
Located behind the Springport Telephone Company. Station 16+85 (storm sewer stationing), 42 inch RCP.		WB I-94 at Portage Creek, Station 1528+09, 100 feet left of
38011-75184A  Station 16+85 (storm sewer stationing), 42 inch RCP.  11. M-51 over Brandywine Creek, Niles 11051-79453A  Station 259+50, 50 feet left of centerline, 36 inch RCP. Station 260+00, 50 feet left of centerline, 30 inch RCP. Station 260+00, 55 feet right of centerline, 15 inch RCP. Station 260+00, 55 feet right of centerline, 15 inch RCP.  12. M-53 over White Creek, Sanilac County 74012-79592A  13. M-26 in South Range 31012-53244A  Station 1309+74, 225 feet left of centerline, 24 inch CMP.  14. M-107 West of Silver City 66061-80207A  Station 83+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		
11. M-51 over Brandywine Creek, Niles 11051-79453A  Station 259+50, 50 feet left of centerline, 36 inch RCP. Station 259+50, 55 feet right of centerline, 15 inch RCP. Station 260+00, 50 feet left of centerline, 30 inch RCP. Station 260+00, 55 feet right of centerline, 15 inch RCP. Station 260+00, 55 feet right of centerline, 15 inch RCP.  12. M-53 over White Creek, Sanilac County 74012-79592A  13. M-26 in South Range 31012-53244A  Station 1309+74, 225 feet left of centerline, 24 inch CMP.  Station 83+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section.  Station 89+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	10. M-99 in Springport	
Station 259+50, 55 feet right of centerline, 15 inch RCP. Station 260+00, 50 feet left of centerline, 30 inch RCP. Station 260+00, 55 feet right of centerline, 15 inch RCP.  12. M-53 over White Creek, Sanilac County 74012-79592A  13. M-26 in South Range 31012-53244A  14. M-107 West of Silver City 66061-80207A  Station 309+74, 225 feet left of centerline, 30 inch RCP. Station 83+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		
Station 260+00, 50 feet left of centerline, 30 inch RCP. Station 260+00, 55 feet right of centerline, 15 inch RCP.  12. M-53 over White Creek, Sanilac County 74012-79592A  13. M-26 in South Range 31012-53244A  14. M-107 West of Silver City 66061-80207A  Station 1309+74, 225 feet left of centerline, 30 inch RCP. Station 83+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	11. M-51 over Brandywine Creek, Niles	
Station 260+00, 55 feet right of centerline, 15 inch RCP.  12. M-53 over White Creek, Sanilac County 74012-79592A  13. M-26 in South Range 31012-53244A  14. M-107 West of Silver City 66061-80207A  Station 309+74, 225 feet left of centerline, 30 inch RCP, sloped metal end section.  Station 89+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	11051-79453A	
12. M-53 over White Creek, Sanilac County 74012-79592A  13. M-26 in South Range 31012-53244A  14. M-107 West of Silver City 66061-80207A  Station 2167+15, 45 feet right of centerline, 24 inch CMP.  Station 1309+74, 225 feet left of centerline, 30 inch RCP. Station 83+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section.  Station 89+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		Station 260+00, 50 feet left of centerline, 30 inch RCP.
74012-79592A  13. M-26 in South Range 31012-53244A  14. M-107 West of Silver City 66061-80207A  Station 2167+15, 45 feet right of centerline, 24 inch CMP.  Station 1309+74, 225 feet left of centerline, 30 inch RCP.  Station 83+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section.  Station 89+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		Station 260+00, 55 feet right of centerline, 15 inch RCP.
13. M-26 in South Range 31012-53244A  Station 1309+74, 225 feet left of centerline, 30 inch RCP.  14. M-107 West of Silver City 66061-80207A  Station 83+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section.  Station 89+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	•	
31012-53244A  Station 1309+74, 225 feet left of centerline, 30 inch RCP.  14. M-107 West of Silver City  66061-80207A  Station 83+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section.  Station 89+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		Station 2167+15, 45 feet right of centerline, 24 inch CMP.
14. M-107 West of Silver City 66061-80207A  Station 83+50, 32 feet right of centerline, 36 inch RCP, sloped metal end section. Station 89+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section. Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section. Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		
sloped metal end section.  Station 89+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		
Station 89+50, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	•	<u> </u>
sloped metal end section.  Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.	66061-80207A	·
Station 94+00, 36 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		<u> </u>
sloped metal end section.  Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		
Station 97+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		
sloped metal end section.  Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		
Station 101+00, 32 feet right of centerline, 24 inch RCP, sloped metal end section.		
sloped metal end section.		
		_
Station 105+50, 24 feet right of centerline, 18 inch RCP,		
I		_
sloped metal end section.		
Station 116+25, 28 feet right of centerline, 24 inch RCP,		_
sloped metal end section.		
Station 130+00, 32 feet right of centerline, 24 inch RCP,		1
sloped metal end section.		'
15. M-61, Airport Road to US-23, Standish Station 239+85, 22.5 feet left of centerline, 24 inch RCP.	l · · · · · · · · · · · · · · · · · · ·	
06021-56940A Station 240+00, 22.5 feet left of centerline, 12 inch RCP.	06021-56940A	Station 240+00, 22.5 feet left of centerline, 12 inch RCP.
16. M-57 at the Shiawassee River, Chesaning		
73021-79615A 25 feet north of centerline on west riverbank.	73021-79615A	25 feet north of centerline on west riverbank.

# Appendix D.5 2006 Labeled Outfalls

Project	Outfall Location
17. I-94 at I-94BL, Port Huron	I-94 Eastbound, Station 1878+25, 37 feet right of edge of
77111-45758A, 72406A	concrete shoulder, 14 foot by 6 foot box culvert
·	I-94 Westbound, Station 2199+10, 10 feet left of edge of
	concrete shoulder, 14 foot by 6 foot box culvert
	I-94 Eastbound, Station 1842+00, 25.5 feet right of edge of
	concrete shoulder, 66 inch RCP.
	I-94 Westbound, Station 2162+85, 35 feet left of edge of
	concrete shoulder, 66 inch RCP.
	I-94 Eastbound, Station 1816+40, 33.5 feet right of edge of
	concrete shoulder, 42 inch RCP.
	I-94 Westbound, Station 2136+45, 34 feet left of edge of
	concrete shoulder, 42 inch RCP.
	I-94 Eastbound, Station 1806+15, 36 feet right of edge of
	concrete shoulder, 66 inch RCP.
	I-94 Westbound, Station 2125+41, 25 feet left of edge of
	concrete shoulder, 66 inch RCP.
	I-94 Eastbound, Station 1786+40, 40 feet right of edge of
	concrete shoulder, 58 inch by 91 inch RCP.
	I-94 Westbound, Station 2106+40, 28 feet left of edge of
	concrete shoulder, 58 inch by 91 inch RCP.
	I-94 Eastbound, Station 1764+00, 40 feet right of edge of
	concrete shoulder, 48 inch RCP.
	I-94 Westbound, Station 2084+00, 23 feet left of edge of
	concrete shoulder, 48 inch RCP.
	I-94 Eastbound, Station 1738+00, 44 feet right of edge of
	concrete shoulder, 60 inch RCP.
	I-94 Westbound, Station 2058+00, 40 feet left of edge of
	concrete shoulder, 60 inch RCP.
	I-94 Eastbound, Station 1653+00, 44 feet right of edge of
	concrete shoulder, 48 inch RCP.
	Range Road, Station 1+00, 14 feet left of edge of HMA
	shoulder, 48 inch RCP.
	Range Road Ramp A, Station 26+00, 40 feet left of edge of
	HMA shoulder, 66 inch RCP.
	Range Road Ramp A, Station 26+00, 43 feet right of edge
	of HMA shoulder, 66 inch RCP.
	Range Road Ramp E, Station 14+00, 33.5 feet left of edge
	of HMA shoulder, 66 inch RCP.
	Range Road Ramp E, Station 14+00, 46 feet right of edge
	of HMA shoulder, 66 inch RCP.
18. M-32 in East Jordan	Station 7+64, 60 feet right of centerline, concrete headwall,
15051-56932A	36 inch CPE.
	Station 7+64, 34 feet right of centerline, concrete headwall,
	12 inch RCP.
19. M-125 over Little Sandy Creek Drain	12
58071-53258A	Station 8+97, 65 feet left, 15 inch RCP.
00071 002001	Station 9+16, 63 feet left, 12 inch RCP.
	Station 8+80, 55 feet right, 12 inch RCP.
20. M-125 over Sandy Creek	Station 6100, 55 leet right, 12 mon ton.
58071-53258A	Station 110+04.5, 60 feet right, 12 inch RCP.
0001 1 00200A	Totation 110104.0, 00 lock right, 12 mon Nor.



STATE OF MICHIGAN

JENNIFER M. GRANHOLM
GOVERNOR

# DEPARTMENT OF TRANSPORTATION KALAMAZOO TRANSPORTATION SERVICE CENTER

GLORIA J. JEFF

February 7, 2006

Schoolcraft Farm Services Inc. Wilbur-Ellis Company 16721 South US-131 P.O. Box 326 Schoolcraft, Michigan 49087

Dear Property Owner:

The Michigan Department of Transportation (MDOT) is currently investigating its drainage system within Schoolcraft Township. During a field investigation on February 3, 2006, MDOT staff identified a pump emptying water from the secondary containment lagoons surrounding your storage tanks into MDOT's drainage system along US-131. This discharge constitutes an illicit discharge and connection.

The Federal Clean Water Act and Part 31, Water Resources Protection of the Natural Resources and Environmental Protection Act, 1994 PA 451, as amended and regulations promulgated pursuant to these statutes mandate that only clean storm water or potable water can be discharged to a system that discharges to the waters of the State. Your property could be discharging pollutants to MDOT's drainage system in violation of these laws and in violation of the Highways Obstructions and Encroachments Act, 1925 PA 368.

Please remove this illicit discharge and connection immediately. By March 31, 2006 you must provide documentation to this office describing what actions you have taken to resolve this matter. By copy of this letter we are notifying the Michigan Department of Environmental Quality, Schoolcraft Township, and Kalamazoo County Health and Human Services of this information.

Please contact Nicholaus VanWoert at 269-337-3936 if you have any questions.

Sincerely,

Mark S. Geib

Manager

Kalamazoo Transportation Service Center

MSG:NV:dae



5372 SOUTH 9TH STREET • KALAMAZOO, MICHIGAN 49009 www.michigan.gov • (269) 375-8900 Tolf Free: (877) 320-6368

Printed by members of:



Schoolcraft Farm Services Inc. Page 2 February 7, 2006

cc: Kalamazoo County Health and Human Services
Schoolcraft Township
Kalamazoo District Supervisor, MDEQ Water Division
Tetra Tech MPS, MDOT MS4 Consultant
Judy Ruszkowski, MDOT Storm Water Program Manager
Bobbi Welke, MDOT Southwest Region Engineer
Nicholaus VanWoert, MDOT Southwest Region Storm Water Representative



JENNIFER M. GRANHOLM
GOVERNOR

# STATE OF MICHIGAN DEPARTMENT OF TRANSPORTATION BAY CITY TRANSPORTATION SERVICE CENTER

June 27, 2006

Plaza Hotel 501 Saginaw Street Bay City, Michigan 48708

Dear Property Owner:

The Michigan Department of Transportation (MDOT) is currently investigating its storm sewer system within the Bay City urbanized area. Information gathered during the course of this investigation indicates that a potential illicit discharge/connection is originating from your property and entering into MDOT's storm sewer system as evidenced by presence of chlorine.

The Federal Clean Water Act and Part 31, Water Resources Protection of the Natural Resources and Environmental Protection Act, 1994 PA 451, as amended and regulations promulgated pursuant to these statutes mandate that only clean storm water or potable water can be discharged to a system that discharges to the waters of the State. Your property could be discharging pollutants to MDOT's storm sewer system in violation of these laws and in violation of the Highways Obstructions and Encroachments Act, 1925 PA 368. Non-residential swimming pool water, if in fact that is the source of the discharge, must be dechlorinated and any filter backwash water must be treated before MDOT can issue a permit to allow this discharge. Please let me know what steps you plan to take to ensure that your system does not discharge to our storm sewer in violation of the public acts cited.

If you have any questions, please contact me at 989-671-1535 extension 305 or Cary Rouse, MDOT Bay Region Resource Specialist, at 989-754-0878 extension 244.

Sincerely,

Robert A. Ranck, Jr., P.E.

Manager

Bay City Transportation Service Center

RAR:CR:md

Cc: Valerie Sanglier, Tetra Tech (MDOT MS4 Consultant)

Judy Ruszkowski, MDOT Storm Water Program Manager Cary Rouse, MDOT Bay Region Storm Water Coordinator

> 2590 EAST WILDER ROAD • BAY CITY, MICHIGAN 48706 www.michigan.gov • (989) 671-1555 Printed by members of:



STATE OF MICHIGAN

DEPARTMENT OF TRANSPORTATION

MARSHALL TRANSPORTATION SERVICE CENTER

JENNIFER M. GRANHOLM

KIRK T. STEUDLE

September 6, 2006

Mr. Brett Hummel 8304 Maple Grove Road Nashville, Michigan 49073

Dear Mr. Hummel:

The Michigan Department of Transportation (MDOT) is currently performing construction activities adjacent to your property at 8304 Maple Grove Road in Maple Grove Township, Barry County. During these activities, construction staff noticed two corrugated plastic pipes entering into MDOT's drainage system. Additional information was gathered indicating that a wash machine drain is connected to these pipes. This constitutes an illicit discharge and connection.

The Federal Clean Water Act and the Water Resources Protection of the Natural Resources and Environmental Protection Act, Part 31, 1994 PA 451, as amended, and regulations promulgated pursuant to these statutes mandate that only clean storm water or potable water can be discharged to a system that discharges to the waters of the State. Your property could be discharging pollutants to MDOT's drainage system in violation of these laws and in violation of the Highways Obstructions and Encroachments Act, 1925 PA 368.

Please take steps to have the wash machine drain and any other illicit discharges rerouted out of MDOT's drainage system within 30 days of receipt of this letter. You must provide documentation to the Marshall Transportation Service Center (TSC) by October 11, 2006, describing what actions you have taken to resolve this matter. If you are unable to remove the encroachment by this date, you must provide information to the TSC by October 4, 2006, describing the specific steps and schedule by which you will remove the encroachment.

The Marshall TSC address is:

MDOT – Marshall TSC 15300 West Michigan Avenue Marshall, Michigan 49068

In addition, improvements to the intersection of M-66 and Maple Grove Road may have affected the drainage of the pipes in question. It shall be your responsibility to make the necessary adjustments to allow for the proper drainage of any legal discharges.

By copy of this letter we are notifying the Michigan Department of Environmental Quality, Maple Grove Township, and the Barry-Eaton District Health Department of this information.

Mr. Brett Hummel Page 2 September 6, 2006

Please contact Nicholaus VanWoert, MDOT Southwest Region Resource Specialist, at (269) 337-3936 if you have questions on the illicit discharge. Please contact Jon Kolbasa, MDOT Marshall Transportation Service Center Utility/Permit Engineer at (269) 789-0592 if you have questions on performing any construction activities within MDOT right of way.

Sincerely.

Brad Wieferich

Marshall TSC Manager

By Certified Mail

cc: Barry-Eaton District Health Department Maple Grove Township Grand Rapids District Supervisor, MDEQ Water Bureau cc: Barry-Eaton District Health Department
Maple Grove Township

Grand Rapids District Supervisor, MDEQ Water Bureau

bc: Tetra Tech MPS, MDOT MS4 Consultant
Judy Ruszkowski, MDOT Storm Water Program Manager
Bobbi Welke, MDOT Southwest Region Engineer
Nicholaus VanWoert, MDOT Southwest Region Storm Water Representative
Jon Kolbasa, Marshall TSC Utilities and Permits Engineer



JENNIFER M. GRANHOLM GOVERNOR

# STATE OF MICHIGAN DEPARTMENT OF TRANSPORTATION LANSING

KIRK T. STEUDLE

### METRO REGION OFFICE

October 10, 2006

Thomas Biasell, Public Services Director City of Farmington Hills 31555 W. Eleven Mile Road Farmington Hills, MI 48336-1165

Dear Mr. Biasell:

RE: MDOT's IDEP Crossing 'e'; Outfall No. 63022-001-A000N

Illicit Discharge Farmington Auto Wash; MH 63022-001-C015N

HRC Job No. 20030263.20

Hubbell, Roth & Clark, Inc. is working on behalf of the Michigan Department of Transportation (MDOT), implementing their Illicit Discharge Elimination Plan (IDEP) required under their NPDES Storm Water Discharge Permit. We are currently investigating a MDOT storm sewer system within the City of Farmington Hills. Information gathered during the course of this investigation indicates an illicit discharge is originating from property adjacent to MDOT's right-of-way and entering into MDOT's storm sewer system.

On September 8, 2006, a soapy surface discharge was observed entering the MDOT right-of-way from the Farmington Auto Wash located on Grand River Avenue between Springbrook and Haynes. We have attached a sample location map along with several photos showing the discharge. MDOT is requesting that the City of Farmington Hills work with the property owner of the above mentioned business to eliminate this illicit discharge. Please provide documentation to this office, within the next 30-days, describing what actions you have taken to resolve this matter.

We are willing to meet with you and your staff to discuss this matter should you feel it is necessary.

Mr. Thomas Biasell HRC Job Number 20030263.20 October 10, 2006 Page 2

Please contact the undersigned should you have any questions or require additional information.

Sincerely,

Randy McKinney/P.E.,

Metro Region Maintenance Engineer

248-483-5144


RM:dvd

Enclosures:

Sample Location Map Laboratory Test Results

cc: MDEQ Water Bureau District Supervisor; Hae-Jin Yoon MDOT Storm Water Program Manager; Judy Ruszkowski Tetra Tech; Dan Christian HRC; William Davis File

9-1 104 MOST Phase 2 Storm Water IDEP Crossing "e" Grand River at Tuck City of Farming ton Hills GRAND RIVER Page D.6-9 Appendix D.6 Potential Illicit Discharge Notifications



# FOUCH FREE AUTOMATIC



JENNIFER M. GRANHOLM GOVERNOR

# STATE OF MICHIGAN DEPARTMENT OF TRANSPORTATION LANSING

KIRK T. STEUDLE

#### METRO REGION OFFICE

October 10, 2006

Thomas Biasell, Public Services Director City of Farmington Hills 31555 W. Eleven Mile Road Farmington Hills, MI 48336-1165

Dear Mr. Biasell:

RE:

MDOT's IDEP Crossing 'e'; Outfall No. 63022-001-A000N Potential Illicit Connection 30400 Block Grand River MH 63022-001-C010N HRC Job No. 20030263.20

Hubbell, Roth & Clark, Inc. is working on behalf of the Michigan Department of Transportation (MDOT), implementing their Illicit Discharge Elimination Plan (IDEP) required under their NPDES Storm Water Discharge Permit. We are currently investigating a MDOT storm sewer system within the City of Farmington Hills. Information gathered during the course of this investigation indicates a possible illicit connection is originating from property adjacent to MDOT's right-of-way and entering into MDOT's storm sewer system.

On September 8, 2006, dry weather samples were collected and found to have high levels of bacteria and detergents. This appears isolated to the 30400 block of Grand River Avenue between Tuck and Springbrook. There are two businesses located on this block:

- 1. HI-Tech Transmission 30400 Grand River (248)473-5800
- AG Black Veterinary Hospital 30470 Grand River (248) 478-5400

Mr. Thomas Biasell HRC Job No. 20030263.20 October 10, 2006 Page 2

We have attached a sample location map and test results. MDOT is requesting that the City of Farmington Hills work with the property owner's of the above mentioned businesses to verify the existence of an illicit connection(s) via dye testing and eliminate all confirmed illicit connections. Please provide documentation to this office, within the next 30-days, describing what actions you have taken to resolve this matter.

We are willing to meet with you and your staff to discuss this matter should you feel it is necessary. Please contact the undersigned should you have any questions or require additional information.

Sincerely,

Randy McKinney, P.E.,

Metro Region Maintenance Engineer

248-483-5144

RM:dvd

Enclosures:

Sample Location Map Laboratory Test Results

cc: MDEQ Water Bureau District Supervisor; Hae-Jin Yoon MDOT Storm Water Program Manager; Judy Ruszkowski Tetra Tech; Dan Christian HRC; William Davis File

9-1 04 MOOT Phase 2 Storm Water IDEP Crossing "e" Grand River at Tuck City of Farmington Hills 2.0030243 GRAND RIVER Potential Illicit Discharge Notifications Page D.6-14



31628 Glendale St. Livonia, Michigan 48150 TEL: 734.422.8000 FAX: 734.422.5342 Website: <u>www.rtilab.com</u>

**Analytical Report** 

(consolidated)

WO#: 0609178

Date Reported:

9/11/2006

CLIENT:

Hubbell, Roth & Clark, Inc.

Project:

MDOT Ph II - 20030263

Lab ID:

0609178-001

C005N

Client Sample ID 63022-001 (C050N)

Matrix: WATER

Collection Date: 9/8/2006 1:15:00 PM

Analyses	Result	RL (	Qual	Units	DF	Date Analyzed
E. COLI				E1103.	1	Analyst: JS5
Escherichia Coli	69,000	10		CFU/100ml	10	9/8/2006 3:00:00 PM
METHYLENE BLUE ACTIVE	SUBSTANCES			E425.1		Analyst: JE
MBAS	1.6	0.25	Н	mg/L	5	9/11/2006 8:30:00 AM

Qualifiers:

\*/X Value exceeds Maximum Contaminant Level

E Value above quantitation range

J Analyte detected below quantitation limits

ND Not Detected at the Reporting Limit

S Spike Recovery outside accepted recovery limits

B Analyte detected in the associated Method Blank

H Holding times for preparation or analysis exceeded

M Manual Integration used to determine area response

RL Reporting Detection Limit

Page 2 of 8



31628 Glendale St. Livonia, Michigan 48150 TEL: 734.422.8000 FAX: 734.422.5342 Website: www.rtilab.com

**Analytical Report** 

(consolidated)

0609178

Date Reported:

WO#:

9/11/2006

Analyst: JE

CLIENT:

Hubbell, Roth & Clark, Inc

Project:

MDOT Ph II - 20030263

Lab ID:

0609178-002

Client Sample ID 63022-001-C010N

Matrix: WATER

E425.1

Collection Date: 9/8/2006 1:20:00 PM

Analyses Result RL Qual Units DF Date Analyzed E. COLI E1103.1 Analyst: JS5 Escherichia Coli 66,000 10 CFU/100ml 10 9/8/2006 3:00:00 PM **METHYLENE BLUE ACTIVE SUBSTANCES** 

**MBAS** 2.1 0.25 9/11/2006 8:30:00 AM mg/L

Qualifiers:

\*/X Value exceeds Maximum Contaminant Level

Ë Value above quantitation range

Analyte detected below quantitation limits

Not Detected at the Reporting Limit

Spike Recovery outside accepted recovery limits

В Analyte detected in the associated Method Blank

Н Holding times for preparation or analysis exceeded

M Manual Integration used to determine area response

Reporting Detection Limit

Page 3 of 8



31628 Glendale St. Livonia, Michigan 48150 TEL: 734.422.8000 FAX: 734.422.5342 Website: venou rillah com

**Analytical Report** 

(consolidated)

WO#: 0609

Date Reported:

0609178 9/11/2006

Website: www.rtilab.com Date

CLIENT:

Hubbell, Roth & Clark, Inc

Project:

MDOT Ph II - 20030263

Lab ID:

0609178-003

Client Sample ID 63022-001-C015N

Collection Date: 9/8/2006 1:30:00 PM

Matrix: WATER

Analyses	Result	RL (	)ual	Units	DF	Date Analyzed
E. COLI				E1103.	1	Analyst: JS5
Escherichia Coli	1,400	10		CFU/100ml	10	9/8/2006 3:00:00 PM
METHYLENE BLUE ACTIVE	SUBSTANCES			E425.1		Analyst: JE
MBAS	0.21	0.050	н	mg/L	1	9/11/2006 8:30:00 AM

Qualifiers:

\*/X Value exceeds Maximum Contaminant Level

E Value above quantitation range

J Analyte detected below quantitation limits

ND Not Detected at the Reporting Limit

S Spike Recovery outside accepted recovery limits

B Analyte detected in the associated Method Blank

H Holding times for preparation or analysis exceeded

M Manual Integration used to determine area response

RL Reporting Detection Limit

Page 4 of 8



31628 Glendale St. Livonia, Michigan 48150 TEL: 734.422.8000 FAX: 734.422.5342 Website: www.rtilab.com

**Analytical Report** 

(consolidated)

WO#:

0609178

Date Reported:

9/11/2006

CLIENT:

Hubbell, Roth & Clark, Inc

Project:

MDOT Ph II - 20030263

Lab ID:

0609178-004

Client Sample ID 63022-001-C020N

Collection Date: 9/8/2006 2:00:00 PM

Matrix: WATER

Analyses	Result	RL (	Qual	Units	DF	Date Analyzed
E. COLI				E1103.	1	Analyst: J\$5
Escherichia Coli	210	10		CFU/100ml	10	9/8/2006 3:00:00 PM
METHYLENE BLUE ACTIVE S	UBSTANCES			E425.1		Analyst: JE
MBAS	0.25	0.050	н	mg/L	1	9/11/2006 8:30:00 AM

Qualifiers:

\*/X Value exceeds Maximum Contaminant Level

E Value above quantitation range

J Analyte detected below quantitation limits

ND Not Detected at the Reporting Limit

S Spike Recovery outside accepted recovery limits

B Analyte detected in the associated Method Blank

H Holding times for preparation or analysis exceeded

M Manual Integration used to determine area response

RL Reporting Detection Limit

Page 5 of 8



31628 Glendale St. Livonia, Michigan 48150 TEL: 734.422.8000 FAX: 734.422.5342 Website: www.rtilab.com

**Analytical Report** 

(consolidated)

WO#: 0609178

Date Reported: 9/11/2006

CLIENT:

Hubbell, Roth & Clark, Inc.

.

MDOT Ph II - 20030263

Project: Lab ID:

0609178-005

Client Sample ID 63022-001-D000N

Collection Date: 9/8/2006 2:10:00 PM

Matrix: WATER

Analyses	Result	RL Qı	ıal	Units	DF	Date Analyzed
E. COLI				E1103.1		Analyst: JS5
Escherichia Coli	60	10		CFU/100ml	10	9/8/2006 3:00:00 PM
METHYLENE BLUE ACTIVE	SUBSTANCES			E425.1		Analyst: JE
MBAS	0.19	0.050 i	4	mg/L	1	9/11/2006 8:30:00 AM

Qualifiers:

\*/X Value exceeds Maximum Contaminant Level

E Value above quantitation range

J Analyte detected below quantitation limits

ND Not Detected at the Reporting Limit

S Spike Recovery outside accepted recovery limits


B Analyte detected in the associated Method Blank

H Holding times for preparation or analysis exceeded

M Manual Integration used to determine area response

RL Reporting Detection Limit

Page 6 of 8





# BOARD OF COUNTY ROAD COMMISSIONERS OF MACOMB COUNTY

Administration Building 117 S. Groesbeck Highway Mount Clemens, Michigan 48043 (586) 463-8671

December 18, 2006

Mr. Randy McKinney, P.E. Michigan Department of Transportation 18101 West Nine Mile Road Southfield, MI 48075

RE: MDOT's IDEP Crossing 51 Outfall #50021-005-A000N

Potential Illicit Connection M-59 & Mound Road MH 50021-005-7015N&7040N

HRC Job #20030263.20

Dear Mr. McKinney:

The Road Commission of Macomb County has been involved in a thorough investigation of the above-references IDEP Crossing. Enclosed please find several letters from various agencies indicating no illicit connections found at the Classic Shine Car Wash.

A full investigation was facilitated by the Road Commission of Macomb County, and we believe no further action is warranted at this time.

We appreciate the opportunity to continue our partnership with MDOT on this IDEP program. If you have any questions regarding this issue, please feel free to contact me.

Sincerely,

ROAD COMMISSION OF MACOMB COUNTY

Robert P. Hoepfner, P.E. County Highway Engineer

RH/sf

enclosures

cc: H. Yoon, MDEQ; A. Marrocco, MCOPW;

T. Schoenherr, Shelby Twp DPW; J. Ruszkowski, MDOT;

D. Christian, TetraTech; W. Davis, HRC;

K. Andre, Classic Shine Car Wash



### Environmental Consulting & Technology, Inc.

December 14, 2006

Mr. Joe Pacella Macomb County Road Commission 117 S. Groesbeck Hwy Mt. Clemens, MI 48043

RE: Dye Test Findings - 45275 Mound Rd. Utica, Michigan

On behalf of Kevin Andre owner of the Classic Shine Car Wash, Environmental Consulting & Technology, Inc. (ECT) is responding to your letter dated November 21, 2006 regarding the potential illicit connection of the car wash to the Road Commission's storm sewer system.

Eventhough, the concentrations of surfactants found by MDOT's contractor are commonly found in watercourses and storm drains throughout southeast Michigan, Mr. Andre had the wash dye tested to conclusively determine that it is properly connected to the sanitary sewer system.

The results of the dye test conducted by the MCHD indicate that the car wash is indeed properly discharging to the sanitary sewer system (see attached report) and not the storm sewer. Mr. Andre appreciates the County's assistance in resolving this matter.

If you should have any questions regarding this information please contact Mr. Andre at 248-342-6478 or myself at 586-465-2583.

Sincerely,

ENVIRONMENTAL CONSULTING & TECHNOLOGY, INC.

Annette DeMaria Staff Engineer

\_\_\_\_

Cc: Kevin Andre, Classic Shine Car Wash

Groesbeck Hwy Clinton Township, Mi 48036

> (586) 465-2583

FAX (586)

		·
Inspectors:	8m195	Investigation No.: <u>06-344</u>
mapeowra		Investigation Date: 11/21/06
	**************************************	

# MACOMB COUNTY HEALTH DEPARTMENT ENVIRONMENTAL HEALTH SERVICES DIVISION

### 8.W.L.M. SITE INVESTIGATION REPORT FOR CENTER LINE & WARREN FACILITIES


Facility Name: Classic Shine Auto Wash Phone No .:
Facility Address: 45275 Mound Rd, Shelby
Facility Type:
Property Owner: Kevin Andre Phone No.: 248-342-6478
Property Owner Address: 856 Majestic, Rochestin Hills, M1 48306
Person Interviewed: Kevin Andre Standard Industrial Classification Code (SIC):
☐ Basement ☐ Crawl Space Slab Sump Pump? ☐ Yes ☐ No Not Applicable
Sump Connected to Sanitary Lead Inside Building Other
Pump Discharge: Ground Surface Storm Drain - Location
DYE APPLICATION INFORMATION  Please provide specific information for the categories "Fixture Location" (ex: Northwest comer of 2 <sup>nd</sup> Floor) and "Location where dye was observed" (ex: discharging from South pipe in Manhole No. 0).
Application No. 1 Time Dye Applied: 9:07 Time Dye Observed: 9:12
Dye applied to: Toilet Sink Laundry Tub Floor Drain Other:
No. of Fixtures Per Lead: 7 /Lead Fixture Location: Both room in office - South and of Bldy 5FD
Color: Red Green Other Dye observed At: Storm Sanitary Not Found
Location where dye was observed: Sanitary sever on west side of bullding near
autonatic car wash drive in.
Application No. 2 Time Dye Applied: 9:13 Time Dye Observed: 9:53
Dye applied to: Toilet Sink Laundry Tub Floor Drain Other: Pit Basin in car wash bay
No. of Fixtures Per Lead: 9 /Lead Fixture Location: Auto wash - South and of building
Color: Red Green Other Dye observed At: Storm Sanitary Not Found
Location where due was observed: Sanitary on west side of building near
Application No. 3 Time Dye Applied: Time Dye Observed:
Dye applied to:  Toilet Sink Laundry Tub Floor Drain Other:
No. of Fixtures Per Lead:/Lead Fixture Location;
Color: Rcd Green Other Dye observed At: Storm Sanitary Not Found
Location where dye was observed:

1 of 4

It\Swim Programs\Forms\Wenten-Center Line Inspection.dec 02/05

Inspectors:	Investigation No.:  Investigation Date:
CENTER LINE &	WARREN FACILITY INVESTIGATION REPORT
FACILITY NAME:	
Investigation completed with the ass	sistance of: Warren Center Line None
RESULTS/ACTION REQUIRED	MCPWO
☐ IDEP Correction Required ☐ Sanitary Connection to Storm	IDEP Correction Not Required  Sump Connected to Sanitary
Comments: Santar	, manhole had heavy sedement
accumulation.	
	Site Drawing
(N	Mound
	A. C.

141 17



3 of 4

ti/Swim Programe\Forme\Warren-Center Line Inspection.doc 02/95



### HEALTH DEPARTMENT

### Mount Clemens Health Center

43525 Elizabeth Road Mount Clemens, Michigan 48043 586-469-5235 FAX 586-469-5885 macombcountymi.gov/publichealth

Thomas J. Kalkofen Director/Health Officer

Kevin P. Lokar, M.D. Medical Director Robert Hoepfner, P.E. Road Commission of Macomb County Administration Building 117 S. Groesbeck Highway

Dear Mr. Hoepfner:

Mt. Clemens, MI 48043

November 28, 2006

SUBJECT: CLASSIC SHINE AUTO WASH - 45275 MOUND ROAD

On November 21, 2006 the Macomb County Health Department, at the request of the Macomb County Public Works Office, inspected and dye tested the facility at the above address to determine if the sanitary waste lines are connected to the appropriate sewer systems.

During our investigation, dye was introduced to the bathroom plumbing and the drains in the automatic wash bay. The investigation revealed that the waste lines are connected to the sanitary sewer located in the driveway on the west side of the building. Additionally, we observed a large quantity of sediment in the sanitary sewer. The owner of the property was advised to have the sediment removed from the manhole to prevent a potential sewage back-up.

If you have any questions regarding this matter, please contact me at (586) 469-5236.

Sincerely.

Cole Shoemaker, M.P.H., R.S.

Coughlin

Supervisor

Environmental Health Services Division

#### Attachments

CC:

Lynne Seymore, MCPWO

Kevin Andre, Classic Shine Acquistions LLC Ted Schoenherr, Shelby Township DPW

J. Pacella, Road Commission of Macomb County

H. Yoon, MDEQ R. McKinney, MDOT

MACOMB COUNTY BOARD OF COMMISSIONERS

Nancy M. White District 20 Chair

Joan Flynn District 6 Vice-Chair

Leonard Haggerty District 21 Sergeant-At-Arms

William J. Revoir - District 16

Betty Slinde - District 22

ispectors:	8m195	Investigation No.: 06-344
**		Investigation Date: 11/21/06

### MACOMB COUNTY HEALTH DEPARTMENT

### ENVIRONMENTAL HEALTH SERVICES DIVISION

S.W.I.M. SITE INVESTIGATION REPORT FOR CENTER LINE & WARREN FACILITIES


Facility Name: Classic Shine Auto Wash Phone No.:
Facility Address: 45275 Mound Rd, Shelby
Facility Type: Industrial Commercial Institution
Property Owner: Kevin Andre Phone No.: 248-342-6478
Property Owner Address: 856 Majestic, Rochester, Hills, M1 48306
Person Interviewed: Kwin Andu Standard Industrial Classification Code (SIC):
Basement Crawl Space Slab Sump Pump? Yes No Not Applicable
Sump Connected to Sanitary Lead Inside Building Other
Pump Discharge: Ground Surface Storm Drain - Location
<b>DYE APPLICATION INFORMATION</b> Please provide specific information for the categories "Fixture Location" (ex: Northwest corner of 2 <sup>nd</sup> Floor) and "Location where dye was observed" (ex: discharging from South pipe in Manhole No. 0).
Application No. 1 Time Dye Applied: 9:07 Time Dye Observed: 9:12
Dye applied to: Toilet Sink Laundry Tub Floor Drain Other:
No. of Fixtures Per Lead: 7 /Lead Fixture Location: Bathroom in office - South and of Bldg 5 FD
Color: Red Green Other Dye observed At: Storm Sanitary Not Found
Location where dye was observed: Sanitary sever on west side of bullding near automatic car wash drive-in.
Application No. 2 Time Dye Applied: 9:13 Time Dye Observed: 9:53
Dye applied to: Toilet Sink Laundry Tub Floor Drain Other: Pt Basin in car wash bay
No. of Fixtures Per Lead: 9 /Lead Fixture Location: Auto wash - South and of building
Color: Red Green Other Dye observed At: Storm Sanitary Not Found
Location where dye was observed: Sanitary on west side of building near
Application No. 3 Time Dye Applied: Time Dye Observed:
Dye applied to: Toilet Sink Laundry Tub Floor Drain Other:
No. of Fixtures Per Lead:/Lead Fixture Location:
Color: Red Green Other Dye observed At: Storm Sanitary Not Found
Location where dye was observed:

nspectors:	Investigation No.:
•	Investigation Date: 1/2/106

### CENTER LINE & WARREN FACILITY INVESTIGATION REPORT

FACILITY NAME:	
Investigation completed with the assist	ance of: Warren Center Line None  MCPWO
☐ IDEP Correction Required ☐ Sanitary Connection to Storm	IDEP Correction Not Required Sump Connected to Sanitary
Comments: Santay	manhole had heavy sediment

### Site Drawing



# Garter Township of Shelby

### Theodore P. Schoenherr, Director

Department of Public Works, Water and Sewer

Phone: (586) 726-7272

Fax: (586) 726-7221

E-mail: dpw@shelbytwp.org

6333 23 Mile Road Shelby Township, MI 48316-4405

November 2, 2006

Mr. Bob Hoepfner County Highway Engineer Macomb County Road Commission 117 S. Groesbeck Highway Mount Clemens, MI 48043-2183

RE: Potential Illicit Connection at Classic Shine Auto Wash, 45275 Mound Road, Shelby Township 586-726-8203

Dear Bob:

Please be advised that we have inspected the above-referenced site, and to the best of our knowledge, the wash bay runoff outlets into the Shelby Township sanitary sewer system, as per design. I have no reason to believe otherwise, as the auto wash is paying a substantial water and sewer bill for this service.

If I can be of further assistance, please to not hesitate to contact me.

Very truly yours,

CHARTER TOWNSHIP OF SHELBY

Ted Schrenbenn

Theodore P. Schoenherr Director of Public Works

Director of Fabric wo

TPS/pac

Enclosure



JENNIFER M. GRANHOLM GOVERNOR

### STATE OF MICHIGAN **DEPARTMENT OF TRANSPORTATION** LANSING

KIRK T. STEUDLE DIRECTOR

#### METRO REGION OFFICE

October 10, 2006

Bob Hoepfner, County Highway Engineer Macomb County Road Commission 117 S. Groesbeck Highway Mount Clemens, MI 48043-2183

Dear Mr. Hoepfner:

RE: MDOT's IDEP Crossing 51 Outfall No. 50021-005-A000N

Nay metro and Potential Illicit Connection M-59 & Mound Road MH 50021-005-J015N & J040N

HRC Job No. 20030263.20

Hubbell, Roth & Clark, Inc. is working on behalf of the Michigan Department of Transportation (MDOT), implementing their Illicit Discharge Elimination Plan (IDEP) required under their NPDES Storm Water Discharge Permit. We are currently investigating a MDOT storm sewer system within Macomb County. Information gathered during the course of this investigation indicates a potential illicit connection is originating from the Mound Road storm sewer system and entering into MDOT's storm sewer system. The Auto Wash at 45275 Mound Road, located just north of M-59 in Shelby Township, is a potential source of the detergents found in dry weather samples. We have attached a sample location map and test results.

MDOT is requesting that the Macomb County Road Commission investigate the source of the detergents and eliminate all confirmed illicit connections. Please provide documentation to this office, within the next 30-days, describing what actions you have taken to resolve this matter.

We are willing to meet with you and your staff to discuss this matter should you feel it is necessary.

Mr. Bob Hoepfner HRC Job Number 20030268.20 October 10, 2006 Page 2

Please contact the undersigned should you have any questions or require additional information.

Sincerely,

Randy McKinney, F

Metro Region Maintenance Engineer


248-483-5144

RM:dvd

Enclosures:

Sample Location Map Laboratory Test Results

cc: MDEQ Water Bureau District Supervisor; Hae-Jin Yoon Macomb County Public Works Commissioner; Anthony Marrocco Shelby Twp. Department of Public Works; Theodore Schoenherr MDOT Storm Water Program Manager; Judy Ruszkowski Tetra Tech; Dan Christian HRC; William Davis File





31628 Glendale St. Livonia, Michigan 48150 TEL: 734.422.8000 FAX: 734.422.5342

Analytical Report

WO#:

0608700

Website: www.rtilab.com

Date Reported: 8/29/2006

CLIENT:

Hubbell, Roth & Clark, Inc

Project:

MDOT IDEP - 20030263.20

Lab ID:

0608700-001

Client Sample ID 50021-005-A000N

Matrix: WATER

Collection Date: 8/23/2006 11:30:00 AM

Analyses	Result	RL Q	ual Units	DF	Date Analyzed
INORGANIC ANIONS			E300.0		Analyst: <b>MW</b>
Fluoride	0.13	0.010	mg/L	1	8/28/2006 11:03:00 AM
HARDNESS			A2340E	3	Analyst: AB2
Total Hardness (As CaCo3)	390	20	mg/L CaCO3	20	8/27/2006 11:32:28 AM
E. COLI			E1103.1		Analyst: JS5
Escherichia Coli	220	10	CFU/100ml	10	8/23/2006 3:00:00 PM
AMMONIA			E350.3		Analyst: PG
Nitrogen,A mmonia	ND	0.10	mg/L	1	8/24/2006 11:00:00 AM
METHYLENE BLUE ACTIVE SUBS	STANCES		E425.1		Analyst: <b>JE</b>
MBAS	0.094	0.050	mg/L	1	8/24/2006 7:45:00 AM

Qualifiers:

- \*/X Value exceeds Maximum Contaminant Level
- E Value above quantitation range
- Analyte detected below quantitation limits
- ND Not Detected at the Reporting Limit
- S Spike Recovery outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- M Manual Integration used to determine area response
- RL Reporting Detection Limit

Page 2 of 8

# #51



31628 Glendale St. Livonia, Michigan 48150 TEL: 734.422.8000 FAX: 734.422.5342 Website: www.rtilab.com

**Analytical Report** 

WO#:

(consolidated) 0608700

Date Reported:

8/29/2006

CLIENT:

Hubbell, Roth & Clark, Inc

Project:

MDOT IDEP - 20030263.20

Lab ID:

0608700-002

Client Sample ID 50021-005-J015N

Matrix: WATER

Collection Date: 8/23/2006 10:45:00 AM

Analyses	Result	RL Qua	al Units	DF	Date Analyzed
INORGANIC ANIONS			E300.0	)	Analyst: <b>MW</b>
Fluoride	0.18	0.010	mg/L	1	8/28/2006 11:03:00 AM
HARDNESS			A2340E	3	Analyst: AB2
Total Hardness (As CaCo3)	630	20	mg/L CaCO3	20	8/27/2006 11:34:55 AM
E. COLI			E1103.	1	Analyst: <b>JS5</b>
Escherichia Coli	100	10	CFU/100ml	10	8/23/2006 3:00:00 PM
AMMONIA			E350.3		Analyst: <b>PG</b>
Nitrogen,A mmonia	0.64	0,10	mg/L	1	8/24/2006 11:00:00 AM
METHYLENE BLUE ACTIVE SUBSTAI	NCES		E425.1		Analyst: <b>JE</b>
MBAS	0.17	0.050	mg/L	1	8/24/2006 7;45:00 AM

Qualifiers:

- \*/X Value exceeds Maximum Contaminant Level
- E Value above quantitation range
- J Analyte detected below quantitation limits
- ND Not Detected at the Reporting Limit
- S Spike Recovery outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- M Manual Integration used to determine area response
- RL Reporting Detection Limit

Page 3 of 8

RTI LABORATORIES, INC.

31628 Glendale St. Livonia, Michigan 48150 TEL: 734.422.8000 FAX: 734.422.5342 Website: <u>www.rtilab.com</u>

Analytical Report

WO#:

0608700

Date Reported:

8/29/2006

CLIENT:

Hubbell, Roth & Clark, Inc.

Project:

MDOT IDEP - 20030263.20

Lab ID:

0608700-003

Client Sample ID 50021-005-J040N

Matrix: WATER

Collection Date: 8/23/2006 11:15:00 AM

Analyses	Result	RL Qual	Units	DF	Date Analyzed
INORGANIC ANIONS			E300.0		Analyst: <b>MW</b>
Fluoride	0.17	0.010	mg/L	1	8/28/2006 11:03:00 AM
HARDNESS			A2340B	•	Analyst: AB2
Total Hardness (As CaCo3)	760	20	mg/L CaCO3	20	8/27/2006 11:37:23 AM
E. COLI			E1103.1		Analyst: JS5
Escherichia Coli	ND	1.0	CFU/100ml	1	8/23/2006 3:00:00 PM
AMMONIA			E350.3		Analyst: <b>PG</b>
Nitrogen,A mmonia	2.6	0.10	mg/L	1	8/24/2006 11:00:00 AM
METHYLENE BLUE ACTIVE SUBSTANCE	S		E425.1		Analyst: <b>JE</b>
MBAS	0.17	0.050	mg/L	1	8/24/2006 7:45:00 AM

Qualifiers:

- \*/X Value exceeds Maximum Contaminant Level
- E Value above quantitation range
- J Analyte detected below quantitation limits
- ND Not Detected at the Reporting Limit
- S Spike Recovery outside accepted recovery limits
- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- M Manual Integration used to determine area response
- RL Reporting Detection Limit

Page 4 of 8

## Appendix E

## **Post Construction Storm Water Management**

1. List of Post-Construction Storm Water Best Management Practices (Pages E.1-1 to E.1-3)

### Appendix E.1 List of Post-Construction Storm Water Best Management Practices

Control Section	Job Number	County	Route	Job Description	Impact Issues	BMP/Mitigation	Recommended Maintenance
		·	US-31, Median, South of	•			
			Washington Ave. in				
3033		Allegan	Holland	Detention Basin			
4031	32335	Alpena	US-23	Detention Basin			
11012		Berrien	US-131, St. Joe River	Detention pond in Ramp			
			I-94, over St. Joe River -				
11016		Berrien	SE quadrant	Detention Pond			
11016	38208	Berrien	I-94 at Napier Ave.	Detention Basin			Berrien County Drain
11018		Berrien	I-94 @ Mill Race Creek	Drop Structure			
			Old US-33, Woodlawn				
11051		Berrien	and Church Street	Detention Basin			MDOT Maintenance
			M-63 - NE quadrant of	Detention Basin at Lake			
11054	99282	Berrien	Maple Lane	Michigan			
			US-31, Station 354, Niles				
11056		Berrien	Buchanan Road	Detention Basin			
11056		Berrien	US-31, Station 507, NB	Detention Basin			
11056		Berrien	US-31, Station 539, NB	Detention Basin			
11056		Berrien	US-31, Station 616, SB	Detention Basin			Private Property
11000		Bomon	US-31, Station 740, Lake				1 iivato i Toporty
11056		Berrien	Chapin Rd.	Detention Basin			
11000		Bernen	US- 31, Station 753, NB,	Beterition Basin			
			South side of Lake				
11056		Berrien	Chapin	Detention Basin			
11030		Demen	US-31, Station 767, NB,	Determon Basin			+
			North side of Lake				
11056		Berrien	Chapin	Detention Basin			
11030		Demen	US-31, Station 780, NB,	Determon Basin			
11056		Berrien	South of Snow Rd.	Detention Basin			
11030		Demen	US-31, Station 789, NB,	Determon Basin			
11056		Dorrion	Snow Rd.	Detention Regin			
11000		Berrien	US-31, Station 862, NB,	Detention Basin			
44050		Damian		Tue Detection Besies			
11056		Berrien	North of Shawnee Rd.	Two Detention Basins			
			US-31 NB Lemon Creek				
44057	00540 04544	Damian	Tributary, Walton and	Data atia a / Ca dias a statia a			
11057	29512, 34511	Berrien	Maths Rd.	Detention/ Sedimentation			
44440	0.4544	D	US-31 @ Old US-31 (S08				
11112	34511	Berrien	of 11112)	Detention Pond			
40004	00000	0-11	M-66 @ B Drive, Battle	Malara Bararia Baria			
13031	99289	Calhoun	Creek	Walmart Detention Basin			
40000	0005	0 "		Co. Drain to Infiltration			
13032	39654	Calhoun	M-66 @ Pennifield	Basin			
			M-75, Boyne Industrial				
15071		Charlevoix	Park	Infiltration Trench			
15091	32322	Charlevoix	US-131, BR	Retention Basin, 2 cell			
			110 40455	Harrison Infiltration			
18032		Clare	US-131BR	System			
23062		Eaton	I-69	Detention Basin			
25032	33289	Genesee	I-75/ US-23 Parker Drive	Stilling Basin			

Appendix E.1 Storm Water BMP Database

### Appendix E.1 List of Post-Construction Storm Water Best Management Practices

Control Section	Job Number	County	Route	Job Description	Impact Issues	BMP/Mitigation	Recommended Maintenance
			US-31, M-37, Chums				
28012		Grand Traverse	Corner	Two cell Detention Basin			
28051		Grand Traverse	US-31/ M-37	Detention Basin			
30062		Hilldale	US-12, Jonesville	Retention Basin			
33084		Ingham	I-96	Detention Basin			
			M-20,US-127, NE	Pump Station and			
37022		Isabella	quadrant of Ramp	Retention			
39011		Kalamazoo	US-131, Station 163, SB	Detention Basin			Private Property
			I-94 WB at Galesburg				
39022		Kalamazoo	Rest area	Detention Basin			MDOT Maintenance
39024	54230	Kalamazoo	I-94 at Sprinkle Road	Detention Basins			
39032	28617	Kalamazoo	M-43	Detention Basin			
39081		Kalamazoo	M-43 at 8th St.	Two Detention Basins			
39082		Kalamazoo	M-43	Infiltration Basin			
			M-37, Plaster Creek				
			Tributary, NW of 44th				
41031	30147	'Kent	Street	Detention Basin			
41031	34694	Kent	M-37 @ 44th to 60th	Retention Basin			
41051		Kent	M-44	Detention Basin			
				County Drain - Knapps			
41057	•	Kent	M-44	Drain - Infiltration			County will maintain
				Bridge Reconstruction		Bank stablization to	
41131	51903	Kent	US-131	over Plaster Creek	Scupper Drain Runoff	correct gully erosion	
	0.000	110111	M-37 @ Lake Street,	ever i laeter eveet	Coupper Brain Harren	contest gaily creaters	
43555		Lake	Baldwin	Vortech, outlet weir			
10000		Lano	M-22, Glenn Arbor Pump				
45012		LeeLanau	station	Retention Basin			City jurisdiction
					Extensive groundwater	Minimize utility cuts,	, j
				Ramp Reconstruction,	contamination at all 4	Dewatering, non-porous	
47014	34519	Livingston	M-59	Widen Approaches	quadrants	backfill	
	0.0.0		M-59 @ Elizabeth Rd. / I-	· · · · · · · · · · · · · · · · · · ·	quadramo		
50022	28460	Macomb	94	Detention Basin			
50022		Macomb	M-59	Detention Basin			
50022	II.	Macomb	M-59, Snover Road	Infiltration Basin			
30022	20400	IVIACOTTID	W-59, Shover Road	3 Detention Basins, First			
50023		Macomb	M-59,	flush in Median			
50023		Macomb	I-696, Lake Street	Oli/gas separator		+	
51011	74005	Manistee	US-31, Manistee	Vortech		+	MDOT Maintain
31011	14000	ividiliolee	UU-U1, Mailistee	Detention and Leachate		+	IVIDO I IVIAII ILAIII
53022	44413	Mason	US-10	Basin			
59045		Montcalm	M-46 East of Edmore	2 ponds		+	
63012	32341	Oakland	I-696, River Rouge	Pump Station		+	
63022	£1000	Oakland	I-96 @ Beck Road	Pond			
03022	31000	Variallu	1-30 @ Deck Koad	FUIIU			
			US-10 and Northwestern				
63081		Oakland		Dotontion Bosin			
63081		Oakianu	Hwy., McKinley Drain I-696, Minnow Pond	Detention Basin Swale retrofit		1	
00404	0040	Coldond	T				
63101	9219	Oakland	Drain	demostration project			

Appendix E.1 Storm Water BMP Database

### Appendix E.1 List of Post-Construction Storm Water Best Management Practices

							Recommended
Control Section	Job Number	County	Route	Job Description	Impact Issues	BMP/Mitigation	Maintenance
				B B			
				Detention Basin with			
				Pump Station discaharge			
63102	22140	Oakland	Hwy.	into Rouge River			
63112		Oakland	M-24, Lake Orion	Retention Study by MSU			
67022	38464	Osceola	US-10 in Evart	Detention Basin			
69000		Otsego	Gaylord	Detention Basin			
			M-45, west of Sand				
70041		Ottawa	Creek	Retention Basin			
77023		St. Clair	M-21	Detention Basin			
80071	48547	Van Buren	M-51 in Decatur	Infiltration Basin			
80071	48547	Van Buren	M-51 in Decatur	Infiltration Basin			
			I-94 Beech Daly to				
82022	45686	Wayne	Pelham Road	Detention Basin			
			US-131BR, Cadillac,				
83031	48538	Wexford	Mackinaw Trail	Detention Basin			
83033		Wexford	US-131	Bog/Fen Bridge Approach	Infiltration	Minimize salt to bog	
				Basin - Infiltration and			
83033	43613	Wexford	US-131 at S04 of 83033	Retention	Litigation		
FR11112	38605		US-31 (Relocation)	Detention Basin	Ğ		
	74149		I-69	Rest area reconstruction	parking lot runoff	oil/water separators	
			US-12 and I-69	Detention Basin			MDOT Maintenance

Appendix E.1 Storm Water BMP Database Page E.1-3

### Appendix F

## **Pollution Prevention/Good Housekeeping**

- 1. Salt and Sand Usage (Page F.1-1)
- 2. Maintenance Activity Costs for MDOT Direct Forces (Page F.2-1)
- 3. Maintenance Activity Costs for Contracted Agencies (Page F.3-1)

### Appendix F.1 Salt and Sand Usage

### **MDOT Salt and Sand Usage**

### Winter 2005-2006

Municipal Salt Oct 2005-April 2006

Region	LANE MILES	TONS/DATE	TONS/LANE MILE
Superior	206.74	4674.25	22.61
North	147.13	5822.00	39.57
Grand	100.24	1523.90	15.20
Bay	296.71	6131.60	20.67
Southwest	299.52	3876.30	12.94
University	387.73	9496.72	24.49
Metro	251.69	4217.40	16.76
TOTAL	1689.76	35742.17	21.75

**County and Direct Forces Salt & Sand** 

Oct 2005-April 2006

Region	LANE MILES	SALT/TONS	TONS/LANE MILE	SAND/TONS	TONS/LANE MILE
Superior	4015.9	96389.9	24.0	39871.4	9.9
North	4808.5	119610.9	24.9	35953.5	7.5
Grand	3368.4	85388	25.3	14288.8	4.2
Bay	4356.2	68744.5	15.8	58.0	0.0
Southwest	3743.5	53938.1	14.4	67.9	0.0
University	4301.4	60028.3	14.0	10980.1	2.6
Metro	4778.6	99469	20.8	0.0	0.0
TOTAL	29372.5	583568.7	19.9	101219.7	3.5

Combined Total (municipal, county, direct)

Oct 2005-April 2006

Region	LANE MILES	SALT/TONS	TONS/LANE MILE	SAND/TONS	TONS/LANE MILE
Superior	4222.6	101064.2	23.9	39871.4	9.4
North	4955.6	125432.9	25.3	35953.5	7.3
Grand	3468.6	86911.9	25.1	14288.8	4.1
Bay	4652.9	74876.1	16.1	58.0	0.0
Southwest	4043.0	57814.4	14.3	67.9	0.0
University	4689.1	69525.0	14.8	10980.1	2.3
Metro	5030.3	103686.4	20.6	0.0	0.0
TOTAL	31062.3	619310.9	20.0	101219.7	3.3

### Appendix F.2 Maintenance Activity Costs for MDOT Direct Forces

**MDOT PCA Costs and Details FY 2006** 

Region	Activity		# Hours	Cost	# Units Cost/unit	
Superior	Roadside Maintenance	Catch Basin Cleanout	2,312	\$251,974	3,539	\$71
•	General Maintenance	Approach Sweeping	61	\$2,141	45	\$48
		Curb Sweeping	1,069	\$54,942	Not available	Not available
		Total	3,442	\$309,057	=	-
North	Roadside Maintenance	Catch Basin Cleanout	1,477	\$123,357	2,447	\$50
	General Maintenance Approach Sweepin		468	\$25,350	1,117	\$23
		Curb Sweeping	30	\$10,239	Not available	Not available
		Total	1,975	\$158,946	=	-
Grand	This region does not have	egion does not have any direct forces garages. Maintenance is done by local agencies.				
Bay	Roadside Maintenance	Catch Basin Cleanout	211	\$13,700	5	\$2,740
Ť	General Maintenance	Approach Sweeping	365	\$19,679	610	\$32
		Curb Sweeping	1,140	\$366,335	320.5 curb miles	\$1,143
		Total	1,716	\$399,714	-	-
Southwest	Roadside Maintenance	Catch Basin Cleanout	413	\$185,418	2,582	\$72
	General Maintenance Approach Sweeping		1,018	\$42,458	2,245	\$19
		Curb Sweeping	8	\$82,491	175 curb miles	\$471
		Total	1,439	\$310,367	=	-
University	Roadside Maintenance	Catch Basin Cleanout	129	\$4,504	234	\$19
	General Maintenance Approach Sweeping		1,580	\$62,963	4,559	\$14
		Curb Sweeping	0	\$51,535	0	-
		Total	1,709	\$119,002	ı	-
Metro	Roadside Maintenance	Catch Basin Cleanout	38	\$95,871	Not available	Not available
	General Maintenance	Approach Sweeping	0	\$1,006,008	0	-
		Curb Sweeping	16	\$296,584	Not available	Not available
		Total	54	\$1,398,463	ı	-
Total*	Roadside Maintenance	Catch Basin Cleanout	4,542	\$578,953	8,807	\$66
	General Maintenance Approach Sweeping		3,492	\$152,591	6,710	\$23
		Curb Sweeping	2,273	\$565,568	=	-
		Total	10,307	\$1,297,112	-	-

<sup>\*</sup> Hourly and unit totals for Catch Basin Cleanout and Approach and Curb Sweeping do not include complete data from the regions. Cost information is assumed to be correct.

### Appendix F.3 Maintenance Activity Costs for Contracted Agencies

### Local Agency Payment System (LAPS) Report Summary for Maintenance Activities

Region	Activity	Cost	Lane Miles	Cost per Lane Mile	Average Cost per Hour	Approximate Total Hours <sup>1</sup>
Superior	Street Sweeping and Flushing	\$36,507	3,301	\$11.06	\$97	376
	Culvert/Underdrain Maintenance	\$88,779	3,300	\$26.90	\$81	1,096
	Ditch Clean-out	\$103,334	3,300	\$31.31	\$68	1,520
	Total	\$228,620	9,901	\$23.09	\$82	2,992
North	Street Sweeping and Flushing	\$98,727	4,048	\$24.39	\$76	1,299
	Culvert/Underdrain Maintenance	\$161,764	4,048	\$39.96	\$74	2,186
	Ditch Clean-out	\$14,379	4,050	\$3.55	\$75	192
	Total	\$274,870	12,146	\$22.63	\$75	3,677
Grand	Street Sweeping and Flushing	\$275,097	3,368	\$81.67	\$239	1,151
	Culvert/Underdrain Maintenance	\$36,574	3,368	\$10.86	\$226	162
	Ditch Clean-out	\$19,609	3,369	\$5.82	\$56	350
	Total	\$331,280	10,105	\$32.78	\$174	1,663
Bay	Street Sweeping and Flushing	\$235,587	3,341	\$70.51	\$123	1,915
	Culvert/Underdrain Maintenance	\$181,342	3,341	\$54.27	\$88	2,061
	Ditch Clean-out	\$2,087	3,366	\$0.62	\$58	36
	Total	\$419,016	10,049	\$41.70	\$90	4,012
Southwest	Street Sweeping and Flushing	\$53,115	748	\$71.05	\$100	531
	Culvert/Underdrain Maintenance	\$77,967	748	\$104.29	\$382	204
	Ditch Clean-out	-	0	-	-	0
	Total	\$131,082	1,495	\$87.67	\$241	735
University	Street Sweeping and Flushing	\$254,501	2,489	\$102.24	\$433	588
	Culvert/Underdrain Maintenance	\$72,451	2,489	\$29.11	\$44	1,647
	Ditch Clean-out	\$17,904	2,490	\$7.19	\$70	256
	Total	\$344,856	7,468	\$46.18	\$182	2,490
Metro	Street Sweeping and Flushing	\$2,898,490	4,385	\$660.99	\$72	40,257
	Culvert/Underdrain Maintenance	-	0	-	-	0
	Ditch Clean-out	-	0	-	-	0
	Total	\$2,898,490	4,385	\$660.99	\$72	40,257
Total	Street Sweeping and Flushing	\$3,852,024	21,680	\$177.68	\$163	46,117
	Culvert/Underdrain Maintenance	\$618,877	17,294	\$35.79	\$149	7,355
	Ditch Clean-out	\$157,313	16,576	\$9.49	\$65	2,353
	Total	\$4,628,214		\$83.32	\$141	55,826

<sup>&</sup>lt;sup>1</sup>Wayne County and many cities do not report labor hours in LAPS. The number of hours listed in italics is based the average "cost per hour" obtained from local agencies which had reported the number of their hours spent on the activity.

### **Appendix G**

### **Soil Erosion and Sedimentation Control**

- 1. SESC QA/QC Review Locations (Page G.1-1)
- 2. SESC Program Review Process and Memorandum (Page G.2-1 to G.2-8)
- 3. Construction Advisory (CA) 2006-15, Slope Restoration (Pages G.3-1 to G.3-2)

## 2006 Construction Reviews MDOT Stormwater Program

		No. of
Region	Projects Reviewed	Inspections
Bay	M-84 reconstruction in Bay County	1
	M-84/I-75 Interchange reconstruction in Saginaw County	1
	M-46 from M-24 to M-53 reconstruction in Tuscola County	2
	US-23 reconstruction in Genesee County	1
Grand	M-20 in Newago County	1
	I-96/36th Street near Grand Rapids	3
	I-96 in Walker in Kent County	1
North	M-27 bridge over Mullett Creek	1
	I-75 south of Mackinac Bridge	1
	M-115/M-55 near Cadillac	1
	M-32 in Alpena County	1
Southwest	I-69 near Marshall	1
	M-66/M-79 near Nashville	1
	M-51 at Brandywine Creek near Niles	1
Superior	M-28 in Luce County	1
	M-26 in Houghton County	1
	M-203 in Calumet	1
Metro	M-153 over Fellow Creek - three visits	3
	M-14 Wayne/Washtenaw County Line to Sheldon Road	3
	I-75	3
	US-24 over Silver Creek	3
	I-96 BL in Oakland County	3
	M-1/M-102 in Oakland County	3
	US-24 in Wayne County	3
	M-39 in Detroit	3
	M-29 over Crepeau Drain	3
	I-94 in St. Clair County	3
	M-85 over I-75 south of Detroit	3



### OFFICE MEMORANDUM

**DATE:** May 26, 2006

**TO:** Region Engineers

TSC Managers
Delivery Engineers
Development Engineers
Region Resource Staff

FROM: Judy Ruszkowski

Operations Environmental Stewardship Engineer

Storm Water Program Manager

SUBJECT: Storm Water Management Plan Activity C-7

Soil Erosion and Sedimentation Control (SESC) Program Review Process

As part of the department's Storm Water Management Plan (SWMP), we will implement the SESC Program Review Process, described in the attached document, beginning with the 2006 construction season. MDOT's Environmental Committee approved the review process developed by the Municipal Separate Storm Sewer Systems (MS4) sub-team charged with implementation of SESC related activities contained in the SWMP. This procedure is being submitted to the MDEQ's Storm Water Unit, as all components of the department's SWMP are.

This review process relies on quality control and quality assurance measures currently in place under which the need for SESC is evaluated during project planning, development and delivery phases. The added component is an internal project-level review, with a feedback mechanism to evaluate the effectiveness of existing procedures and identify opportunities for improvement. This program review does not replace project design considerations and field inspections required by our MDEQ-approved SESC procedures; instead it provides an added quality assurance check to make sure those procedures are effective in anticipating, identifying and correcting erosion and sedimentation control problems before waters of the State are impacted.

The SESC program review will be phased in over the remaining life of the five-year statewide Storm Water Discharge Permit, with the frequency and timing of the reviews ultimately tied to the Engineer Certification Program schedule. Tying the SESC program review to the three-year engineer certification schedule creates a built-in trigger within existing MDOT business rules to ensure the SESC reviews are completed. This allows the reviews to be completed in the most efficient manner, as many of the region staff involved in the engineer certification reviews will also be involved in the SESC program reviews. In addition, since the engineer certifications are staggered over the three-year cycle, SESC program review activity will generally occur each construction season in each region, reinforcing the importance of good soil erosion and sedimentation control.

SESC Program Review Process Page 2 May 26, 2006

During the 2006-2008 construction seasons, C&T SESC staff will work with the regions to schedule program reviews. Once the process is fully implemented, region staff with SESC oversight responsibility will schedule the reviews using the engineer certification list, which is available on C&T's Web page. The MS4 Team will evaluate the outcome of this review process annually as part of the overall storm water management program review. Modifications will be made, as necessary, to ensure that MDOT construction and maintenance projects are planned and completed with Michigan's natural resources in mind.

Region SESC Coordinators are asked to contact Tom Killingworth (517-322-6450) to schedule reviews. If you have general program review questions, please contact Tom or Dave Gauthier (517-322-5710). I am always available to discuss the requirements of MDOT's Storm Water Management Program. You can reach me at 517-322-5698 or <a href="mailto:ruszkowskij@michigan.gov">ruszkowskij@michigan.gov</a>.

#### Attachment

#### JAR:kar

cc: Environmental Committee
A. Thomas, Tetra Tech
D. Christian, Tetra Tech
MS4 Team

#### Michigan Department of Transportation SWMP Activity C-7 SESC Program Review Process

#### 1. Purpose and Scope

Construction Storm Water Runoff Control is one of the five elements included in the MDOT Storm Water Management Plan (SWMP). This plan element is supported in large part by the existing MDOT Soil Erosion and Sedimentation Control (SESC) program. In addition to the continued enforcement of the department's MDEQ-approved SESC program as required to maintain Authorized Public Agency (APA) status, Activity C-7 of the SWMP calls for the development and implementation of an internal program review process. The process outlined herein fulfills this SWMP requirement by detailing the business rules under which appropriate SESC measures are evaluated during the project planning, development and delivery phases (quality control) and by implementing an internal project-level review component (quality assurance). The purpose of the project level review is to ensure compliance with MDOT's approved SESC procedures thereby ensuring that all applicable SESC laws, administrative rules and requirements are being met.

The objective of the program review process is to provide the checks and balances necessary to document the adequacy of the department's SESC program and to identify opportunities for continued improvement through training of new staff or adoption of new methods and technologies. The outcome of this review process will be evaluated annually by the Municipal Separate Storm Sewer System (MS4) team at MDOT as part of the overall storm water management program review. Modifications will be made as necessary to improve compliance with the statewide storm water discharge permit.

#### 2. Project Development QC/QA

2.1 Development Quality Control - During project development, soil erosion and sedimentation control (SESC) measures are incorporated into the contract documents in accordance with the procedures detailed in the Road and/or Bridge Design Manual and the Drainage Manual. The project manager follows the plan review checklists as a guide during the development of road and bridge projects to ensure all necessary components for a given project are included.

SESC measures are considered several times as the project manager uses the check lists to assure the completeness of the project documents. During preliminary plan development, prior to the Plan Review meeting, areas with high erosion potential and sensitive areas such as wetlands, lakes, and streams are identified and appropriate temporary or permanent SESC measures are specified to ensure adequate protection during construction. Depending on the nature of the project area and extent of earth disturbance, the project manager may consult with region soils engineer, Lansing Construction & Technology (C&T) and/or the Michigan Department of Environmental Quality (MDEQ) at this stage of project development for input on specific erosion control measures.

Once selected, these measures are detailed on the plans at the approximate location they will be needed in the field. Pay items and quantities for the erosion control measures are listed on the respective plan sheets. Miscellaneous quantities of typical erosion control pay items are included on the note sheet to be used "as needed" to account for extreme weather conditions and unforeseen changing field conditions during construction.

Under certain circumstances, specialized erosion control measures not included in the SESC manual may be necessary to provide adequate protection to sensitive areas. These

SWMP Activity C-7 SESC Program Review Process May 1, 2006

situations often require additional design and detailing efforts on the plans and will be handled on a case by case basis with input from the appropriate design staff.

2.1 Development Quality Assurance - Inclusion of SESC measures is one of many items verified during the Plan Review for a project. The plan review meeting and corresponding field review is conducted by the Quality Assurance and Lettings Unit of the Design Support Area to assure the completeness of the contract documents for a project. Under unusual circumstances, such as an expedited project schedule or when a Quality Assurance Engineer is not available, a Design Engineer-Road or Region System Manager may conduct the plan review. If SESC measures are incomplete or inadequate, corrections are made on the plans to assure sufficient coverage is afforded for implementation during construction.

A post-construction meeting may also be held on projects. At the post-construction meeting, the project is reviewed with discussions focusing on problems encountered during the construction phase, solutions applied and possible methods to avoid similar issues in the future. At this meeting, recurring issues with the inclusion of adequate SESC measures during project development will be discussed with the project Development and Delivery staff, the prime and/or sub-contractor, Lansing C&T SESC staff and the Operations Environmental Stewardship Engineer (OESE) so that program improvements can be implemented.

#### 3. Project Delivery QC/QA

- 3.1 Delivery Quality Control Construction SESC quality control for construction projects is provided through a combination of enforcement of the contract documents and field inspections. SESC quality control on construction projects begin at the preconstruction meeting. Preconstruction meetings are conducted by the delivery engineer, or designated staff, and must cover a range of topics, one of which is erosion and sedimentation control. The format for this meeting typically follows the Guide for Conducting Preconstruction Meetings as detailed in Section 102 of the MDOT Construction Manual. The following excerpt, taken from Item 20 of the guide, lists various SESC-related issues that may be discussed during project delivery:
  - 20 Soil Erosion and Sedimentation Control (SESC) and National Pollutant Discharge Elimination System (NPDES).
    - Review DEQ permit requirements and discuss impact to sensitive areas.
    - Install temporary SESC measures prior to all earth change activities.
    - Maintain SESC measures throughout the life of the project until the site is stabilized and accepted.
    - Review effectiveness of SESC measures at progress meetings.
    - Stabilization/Restoration completed in accordance with subsection 208.03B of the standard specifications.
    - Identify SESC inspector(s) and verify valid training certificates.
    - Earth Change Plan required for work outside limits of earth disturbance but within ROW.

Once the contract is awarded and construction begins, consideration of SESC measures continues throughout the life of the project. At progress meetings with the contractor, the effectiveness of the in-place SESC measures is reviewed to determine what measures are working well and providing adequate protection and what measures and/or locations need improvement or maintenance.

Until the site is stabilized and accepted, inspections are conducted by certified staff once per week and within 24 hours of a precipitation event that results in discharge from the right-of way. These inspections are documented on MDOT form 1126. If corrective actions are necessary, the contractor is directed to complete them in the time frame consistent with that specified in the SESC manual. A log of these inspections is maintained throughout the construction phase. Upon project completion and acceptance, the inspection reports are placed in the project files and retained for at least three years.

If a post-construction meeting is scheduled, problems encountered during the construction phase, solutions applied and possible methods to avoid similar issues in the future are discussed. At this meeting, recurring issues with the inclusion of adequate SESC measures during project development will be discussed with the project Development and Delivery staff, the prime and/or sub-contractor, Lansing C&T SESC staff and the Operations Environmental Stewardship Engineer (OESE) so that program improvements can be implemented.

3.2 Delivery Quality Control – Maintenance - SESC quality control for maintenance activities is provided through a combination of training and field inspections. Training is provided to department maintenance staff as necessary to ensure compliance with the department's SESC program. Supervisory staff responsible for conducting SESC inspections are required to attend training sponsored by the MDEQ. Non-supervisory staff attends in-house training provided by C&T and/or region staff as necessary. Region resource staff periodically attend regularly scheduled garage meetings to discuss the selection, implementation and maintenance of SESC measures.

During the execution of maintenance activities involving earth disturbances other than ditch clean out operations, department and contract maintenance staff follow the directions for completing an earth change plan that are included in the Maintenance Operations Manual and/or the SESC Manual. These manuals also include an example of an acceptable plan along with specific direction on when the plan is required. Ditch clean out operations do not require preparation of an earth change plan provided they are conducted according to the MDOT-approved work methods that accompany the Maintenance Performance Guide for Activity #12300.

Regular inspections are conducted by certified staff once per week and within 24 hours of a precipitation event that results in discharge from the right-of-way until the site is stabilized. These inspections are documented using MDOT form 1126. If corrective actions are necessary, maintenance staff is directed to complete them in the time frame consistent with that specified in the SESC manual. A log of these inspections is kept throughout the performance of the maintenance activity. The inspection reports are kept on file by designated maintenance staff and retained for at least three years.

3.3 Delivery Quality Assurance Review Frequency - In order to ensure that this program review process continues to receive the appropriate level of attention across the department, a phased approach will be taken that ultimately ties the internal SESC review process to the schedule for the federally required Engineer Certification Program. MDOT delivery engineers are reviewed on a three year cycle to ensure that they are following all construction project administration and documentation requirements as prescribed by the Federal Highway Administration. Tying the SESC program review to the three year engineer certification schedule creates a built-in trigger within the existing business rules at MDOT to ensure that the SESC reviews are completed. This also allows the reviews to be completed in the most efficient manner as many of the individuals involved in the engineer

certification reviews will also be involved in the SESC program reviews. Since the engineer certifications are staggered over the three year cycle, annual SESC program review activity will occur in each region, but not in each TSC.

The first phase of this SESC quality assurance review process will cover the 2006-2008 construction seasons to coincide with the initial 2004-2009 storm water discharge permit cycle. During this time SESC review activities will take place in each of the seven MDOT regions on an annual basis. A minimum of two reviews will be completed in each Transportation Service Center (TSC) during this time. Beginning in 2009 the SESC reviews will be scheduled to take place at the same time the engineer certification reviews are scheduled. The frequency of these reviews will be increased as necessary to ensure compliance.

3.4 Delivery Quality Assurance Review - The projects selected for program evaluation will target those that involve large earth disturbances or that are located adjacent to sensitive areas such as lakes, streams and wetlands. The review will include verification that appropriate enforcement agencies were notified of earth change activities; a review of training records for all Part 91 SESC inspectors assigned to the projects; regular project inspection reports; and earth change plans. Program quality assurance reviews may include a review of field conditions to determine if the measures included in the projects plans were sufficient and are being fully enforced to prevent excessive erosion or off-site sedimentation. If any corrective actions have been identified in the regular project inspection reports, the review team will check whether a time frame for completion consistent with that specified in the SESC Manual was included in the inspection report and whether there was adequate follow up documented to ensure the actions were completed in that time frame.

The results of the SESC Program Review will be documented using the SESC Program Review Form and will be filed with the appropriate maintenance staff or placed in the construction project file. At a minimum, copies will be sent to the TSC Manager and the OESE.

#### 4. Delivery Quality Assurance Review Team

The review team for maintenance activities will include TSC maintenance staff, Region staff responsible for SESC compliance, and Lansing C&T SESC staff. TSC maintenance staff can include the Maintenance Superintendent, Maintenance Supervisor, Maintenance Coordinator or Maintenance Engineer. The review team for construction will include the Delivery Engineer, Region staff responsible for SESC compliance, and Lansing C&T SESC staff. The Delivery Engineer may delegate attendance at the review to the Assistant Delivery Engineer or senior technician. It is recommended that other individuals, including the Part 91 SESC inspector, region soils engineer, project development staff, the environmental permit coordinator and the OESE, participate in the review. Construction and maintenance reviews may be conducted together or may be scheduled separately depending on the staffing and preferences of a particular TSC.

## SESC Program Field Review MAINTENANCE

Original: Maintenance Staff; Copy: TSC Manager & Operations Environmental Stewardship Engineer						
Route:		Date:				
Control Section:		Job Number (if available):				
Maintenance Representative:		Review Conducted by: 1.				
TSC and/or Garage:		2. 3.				
No.	SESC Review Items		Yes	No	Date Corrected	
1.	Inspector training certificates up to date?					
2.	Inspections up to date? (MDOT Form 1126)					
3.	Corrective actions completed in appropriate time frame?					
4.	Sediment leaving ROW or entering waters of the s	state?				
5.	Construction sediment tracking onto public roadw	ay?				
6.	Specific SESC measures					
	a. Silt fence properly installed? (trenched in, orientated, etc.)					
	b. Sediment traps maintained and functioning?					
	c. Checkdams properly constructed?					
	d. Inlet protection installed and maintained?					
	e. Filter bags used properly?					
	f. Other SESC measures? (list below)					
	Earth Change Plan for work outside grading limits	within ROW?				
7.	7. a. Earth Change Plan in compliance with R 323.1703?					
Commen	ts and/or Corrective Actions:					
					<u> </u>	
			<u></u>		maketen in the second s	
			······································	· · · · · · · · · · · · · · · · · · ·		

## SESC Program Field Review CONSTRUCTION

Route:	Original: Project file; Copy: TSC Manager & Operations Environmental Stewardship Engineer  Oute:  Date:				
Control Section:					
	Control Section:		Job Number:		
Delivery	r Engineer:	Review Condu	ucted by:		
Contrac	Contractor:		1. 2.		
		3.			
No.	SESC Review Items	Yes No Date Corrected			Date Corrected
1.	Inspector training certificates up to date?				
2.	Inspections up to date? (MDOT Form 1126)				
3.	Corrective actions completed in appropriate time	frame?			
4.	Sediment leaving ROW or entering waters of the	state?			
5.	Construction sediment tracking onto public roadw				
6.	Specific SESC measures				
	a. Silt fence properly installed? (trenched in, orie	entated, etc.)			
	b. Sediment traps maintained and functioning?				***************************************
	c. Checkdams properly constructed?				
	d. Inlet protection installed and maintained?				
	e. Filter bags used properly?				
	f. Other SESC measures? (list below)				
7.	Earth Change Plan for work outside grading limits	within ROW?			
	a. Earth Change Plan in compliance with R 323.1703?				
Commen	ts and/or Corrective Actions:				
		······································	<del></del>		
<del></del>					· · · · · · · · · · · · · · · · · · ·
			······································		
		William Committee Committe			
***************************************		**************************************	***************************************		
····		***************************************			
***************************************		<u></u>			
****					
		4-2-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-	······································	<del></del>	MANAGARIA MANAGARIA ANAGARIA

# Construction Advisory

CA 2006-15

From Brenda O'Brien, Engineer of Construction and Technology

MDOT-Construction and Technology Support Area P.O. Box 30049 Lansing, Michigan 48909 Phone/517-322-1087 Fax/517-322-5664 www.michigan.gov/mdot/

Index: Earthwork

Questions regarding this Construction Advisory should be directed to:

Dave Gauthier, Grading and Drainage Engineer, 517-322-5710 or gauthierd@michigan.gov



BJO:DMG

#### **Slope Restoration**

Timely slope restoration is critical during the construction phase to establish vegetation as soon as possible, and to minimize soil erosion and subsequent off-site sedimentation. The primary components of slope restoration include topsoil, fertilizer, seed and mulch. Per specification subsection 208.03B, slope restoration is to be completed within 5 calendar days after final grading or within 24 hours after final grading if the earth disturbance is within 150 feet of a lake, stream or wetland. Final grade is not explicitly defined in the standard specifications, but implied to be the time when all grading activities are completed prior to slope restoration. Once final grade is achieved, the contractor should be directed to complete slope restoration in accordance with the standard specifications. The contractor is also subject to a limit of maximum area of bare soil permissible, as detailed in subsection 208.03C. If this area requirement is exceeded, the contractor should be directed to stabilize that area necessary to be in compliance with the limitations outlined in the specifications before

Topsoil quality, quantity and placement are important factors to establish adequate vegetation in a timely manner. Quality topsoil should consist of natural loam, sandy loam, silty loam or clay loam humus bearing soil to support plant growth. Topsoil that is too sandy will not retain moisture and will inhibit the germination and establishment of vegetation and should be avoided. The topsoil should be placed at a minimum thickness of three inches and be loose, friable, free of lumps, roots, rocks, litter and foreign matter. Final shaping of topsoil should be evenly graded and free of ruts to enable mulching material to be placed in direct contact with the soil.

Chemical fertilizer nutrient (typically Class A on MDOT projects) utilized for slope restoration is comprised of both water soluble and non-water soluble ingredients, and is intended for placement with one application. The water soluble component of the fertilizer provides a quick boost to generate initial germination, while the non-water soluble component provides a slow release of fertilizer in approximately 4 to 6

weeks. Review fertilizer packages to verify proper ingredients to ensure the fertilizer meets the minimum requirements, as outlined in Section 917 of the standard specifications.

The variety of seed specified for a project should be selected from the Qualified Products List (QPL) and tagged, identifying the supplier and all other pertinent details about the seed type. Seed placement, application rates and seasonal limitations should be in accordance with the standard specifications and verified during construction to ensure the potential for well established vegetation. If permanent seeding is permitted outside of the seasonal limitations, the contractor should be required to certify in writing that if the vegetation fails to establish they will correct all deficiencies at their cost the following spring. If necessary, acceptance of the project may be delayed until adequate vegetation is established and the potential for erosion is eliminated.

Mulch materials should be placed on a given area within 1 day after seeding and fertilizing. If mulch is not placed

disturbing more soil.

#### 2 SLOPE RESTORATION

within 1 day, the area should be inspected for proper seed coverage and reseeded as necessary. Mulch materials may include straw or hay mulch utilizing tackifier from the QPL, mulch blankets, high velocity mulch blankets, turf reinforcing mats or any other approved technique for stabilizing the exposed ground surface. To ensure effectiveness, install mulch blankets and turf reinforcing mats in accordance with the manufacturer's published guidelines.

Please share this information with consultants and local agencies within your area.