CMB Drawings

PETRO-CHEM ENGINEERING DRAWINGS - CONTAINER MANAGEMENT BUILDING

DRAWING NUMBER	DRAWING DESCRIPTION							
ARCHITECTURAL AND STRUCTURAL								
A-1	A-1 Container Management Bldg Floor Plan							
A-2	Container Management Bldg Exterior Elevations							
A-3	Container Management Bldg Exterior Elevations and Sections							
A-4	Container Management Bldg Floor Plan, Schedules and Details							
A-9	Details							
ELECTRICAL								
E-1	Legend							
E-2	Site Plan							
E-3	Container Management Bldg. and Heel Management Buildings - One-Lines							
E-4	Container Management Bldg Lighting Floor Plan							
E-5	Container Management Bldg Power Floor Plan							
E-7	Details							
FIRE PROTEC	CTION							
F-1	Container Management Bldg Fire Protection Flow Diagram							
F-2	Container Management Bldg Fire Protection Floor Plan							
GENERAL								
G-1	Existing Site Plan							
G-2	Proposed Site Plan							
G-3	Site Details & Schedules							
G-4	Details							
G-5	Container Management Bldg Containment Areas							
MECHANICAL								
M-1	Container Management Bldg Heating and Ventilating Flow Diagram							
M-2	Container Management Bldg. and Heel Management Building - Flow Diagram							

CMB Drawing Index.xlsx Page 1 of 2

PETRO-CHEM ENGINEERING DRAWINGS - CONTAINER MANAGEMENT BUILDING

DRAWING NUMBER	DRAWING DESCRIPTION
M-3	Container Management Bldg Floor Plan
M-3A	Pump Room Enlarged Plan
M-4	Container Management Bldg Details and Schedules
STRUCTURAL	
S-1	Container Management Bldg Partial Foundation Plan
S-2	Container Management Bldg Partial Foundation Plan
S-4	Container Management Bldg Detail Sheet
S-5	Container Management Bldg. & Heel Management - Detail Sheet
S-6	Container Management Bldg. & Heel Management - Detail Sheet
71	BB Inspection
72	BB Inspection
73	BB Inspection
TK001	Asbuilt Drawing Clawson Tank TK001
TK002	Asbuilt Drawing Clawson Tank TK002
SUPA1	Lab/Office Drawings
SUPA2	Lab/Office Drawings
SUPA3	Lab/Office Drawings
SUPA4	Lab/Office Drawings

CMB Drawing Index.xlsx Page 2 of 2

PSC ENVIRONMENTAL SERVICES DIVISION DETROIT FACILITY REBUILD

515 LYCASTE AVE., DETROIT, MICHIGAN 142-17450-07-01

SHEET IN	DEX:							
SHEET NO. SHEET TITLE								
GENERAL	The state of the s							
G-1	EXISTING SITE PLAN							
G-2	PROPOSED SITE PLAN							
G-3	SITE DETAILS & SCHEDULES							
G-4	DETAILS							
G-5	CONTAINER MANAGEMENT BLDG. — CONTAINMENT AREAS							
ARCHITECTU	ral and structural							
A-1	CONTAINER MANAGEMENT BLDG. — FLOOR PLAN							
A-2	CONTAINER MANAGEMENT BLDG. — EXTERIOR ELEVATIONS							
A-3	CONTAINER MANAGEMENT BLDG. — EXTERIOR ELEVATIONS AND SECTIONS							
A-4	CONTAINER MANAGEMENT BLDG FLOOR PLANS, SCHEDULES AND DETAILS							
A-5	HEEL MANAGEMENT BLDG - PLAN AND SECTION							
A-6	HEEL MANAGEMENT BLDG — EXTERIOR ELEVATIONS							
A-7	SDG/ELECTRICAL BLDG - FLOOR & ROOF PLAN							
A-8	SDG/ELECTRICAL BLDG — ELEVATIONS							
A-9	DETAILS							
STRUCTURAL								
S-1	CONTAINER MANAGEMENT BLDG. — PARTIAL FOUNDATION PLAN							
S-2	CONTAINER MANAGEMENT BLDG. — PARTIAL FOUNDATION PLAN							
S-3	HEEL MANAGEMENT BLDG - FOUNDATION PLAN							
S-4	CONTAINER MANAGEMENT BLDG. — DETAIL SHEET							
S-5	CONTAINER MANAGEMENT BLDG. & HEEL MANAGEMENT — DETAIL SHEET							
S-6	CONTAINER MANAGEMENT BLDG. & HEEL MANAGEMENT - DETAIL SHEET							
MECHANICAL								
M-1	CONTAINER MANAGEMENT BLDG. — HEATING AND VENTILATING FLOW DIAGRAM							
M-2	CONTAINER MANAGEMENT BLDG. AND HEEL MANAGEMENT BUILDING - FLOW DIAGRAM							
M-3	CONTAINER MANAGEMENT BLDG. — FLOOR PLAN							
M-4	HEEL MANAGEMENT BUILDING - FLOOR PLAN AND SECTION							
M-5	CONTAINER MANAGEMENT BLDG. — DETAILS AND SCHEDULES							
M-6	CONTAINER MANAGEMENT BLDG. & HEEL BLDG. PROCESS FLOW DIAGRAMS							
FIRE PROTE	CTION							
F-1	CONTAINER MANAGEMENT BLDG FIRE PROTECTION FLOW DIAGRAM							
F-2	CONTAINER MANAGEMENT BLDG FIRE PROTECTION FLOOR PLAN							
ELECTRICAL								
E-1	LEGEND							
E-2	SITE PLAN							
E-3	CONTAINER MANAGEMENT BLDG. AND HEEL MANAGEMENT BUILDINGS — ONE-LINES							
E-4	CONTAINER MANAGEMENT BLDG LIGHTING FLOOR PLAN							
E-5	CONTAINER MANAGEMENT BLDG POWER FLOOR PLAN							
E-6	HEEL MANAGEMENT BUILDING - FLOOR PLAN							






Ann Arbor, Michigan Office 710 Avis Drive Ann Arbor, Michigan 48108 . 734.665.6000 Fax: 734.665.2570

ISSUED: 2/13/2007


FOR BID (NOT FOR CONSTRUCTION)





SIGNATURE OF LICENSEE





PLOT DATE 2/19/2007 9:29 AM | LAST EDITED BY: RICK,BUSHAW | PLOT DENKE: XES 8630 - P





























MARK	~~~	ND	STRUC				-	DOOR						RAM	E				
	OM NA		EN'GS					DOOK	SIZE		IGLASS		-	CHIN	SIZE			- 0	
	NUMB	and the second second second second	T & IN)					(FT. &	OR INC	HES)	(IN.)			(1)	NCHE	ES)			
SEE PLANS	KEY	FROM	w	н	MATERIAL	TYPE	QUANTITY	w	н	Ť	NOMINAL SIZE	TYPE	MATERIAL	TYPE	w	D	U.L. LABEL (HR)	HARD WARE SET NO./ STOP	BEMARKS
CONTA	INER \	WAREH	OUSE																
100	EXT	102	3-4	7-4	HM	N1	1	3-0	7-0	1.75	6×24	SAF	HM	2	2	5.75	-	3.10	2
101	EXT	102	10-0	12-0 12-0	GST	SOH	1	10-0	12-0 12-0	1.75	3.0	- 4	STL	-	1000	1.0			2
103	EXT	100	3-4	7-4	HM	NT	1	3-0	7-0	1.75	6×24	SAF	HM	2	2	5.75	_	3.10	
104	EXT	100	3-4	7-4	НМ	N1	1	3-0	7-0	1.75	6×24	SAF	НМ	2	2	5,75		3.10	
105	EXT	104	3-4	7-4	HM	N1	1	3-0	7-0	1.75	6×24	SAF	НМ	2	2	5.75	-	3.00	
106	104	105	3-4	7-4	HM	N1	1	3-0	7-0 7-0	1.75	6x24	SAF	HM	2	2	5.75 5.75	-	1.00	
108	104	100	3-4	7-4	HM	NT	1	3-0	7-0	1.75	6x24	SAF	НМ	2	2	5.75	1.5	1.20	
109	105	101	3-4	7-4	HM	NT	1	3-0	7-0	1.75	6×24	SAF	НМ	2	2	5.75	1.5	1.20	
110	EXT	107	6-4	8-0	НМ	N1	2	3-0	7-10	1.75	6×24	SAF	НМ	2	2	5.75	-	4.10	
111	EXT	101	8-0	8-0	HM	SOH	1	8-0	8-0	1.75	C-01	- CAE	STL	-	- 0	-	-	210	
112	100	101	3-4 3-4	7-4	HM	N1 N2	1	3-0 3-0	7-0 7-0	1.75	6×24 5×20	SAF	HM	2	2	5.75	9	3.10 3.10	2
114	100	101	12-0	12-0	GST	COH	1	12-0	12-0	1.75	5X20	~	STL	-	-	5.75	-	- 3.10	5
115	102	101	6-0	7-4	НМ	N2	2	2-10	7-0	1.75	5×20	W	НМ	2	2	5.75		2.00	
200	200	201	3-4	7-4	HM	N1	1	3-0	7-0	1.75	6x24	SAF	HM	2	2	5.75	-	1.00	
201	202	201 100	3-4 5-4	7-4	HM	N1	1	3-0	7-0	1,75	6×24	SAF	HM	9	2	5.75 5.75	1.5	1.00	4
203	202	101	5-4	4-0	-		-			-	60 x 44	W	HM	9	2	5.75	1.5		4
		EMENT									2-2011		a.w.u			200.0			
300	EXT	200	3-4	7-4	НМ	N1	1	3-0	7-0	1.75	6x24	SAF	НМ	2	2	5.75		3.10	
301	EXT	200	16-0	14-0	GST	SOH	1	16-0	14-0	1.75	-	-	STL	-	-	-	-	-	
302	EXT	200	3-4	7-4	НМ	N1	1	3-0	7-0	1,75	6×24	SAF	НМ	2	2	5.75	-	3.10	
303	EXT	200	16-0	14-0	GST	SOH	1	16-0	14-0	1.75	~	-	STL	•		-	-1		-
SDG BL					200	4.400	-	6.75								2		200	
400	EXT	405 405	6-0 3-4	7-4	HM	N1 N1	2	2-10	7-0 7-0	1.75	6×24	SAF	HM	2	2	5.75 5.75	-	3.10	
402	EXT	403	3-4	7-4	HM	N1	1	3-0	7-0	1.75	6×24	SAF	НМ	2	2	5.75	-	3.10	
403	EXT	403	8-0	12-0	GST	COH	1	8-0	12-0	1.75	-	9	STL	-		-	-	-	
404	403	404	8-0	12-0	GST	and the second second	1	8-0	12-0	1.75	-	-	STL	-	-		1.5		5
405	404 EXT	403 404	3-4 3-4	7-4 7-4	HM	N1 N1	1	3-0 3-0	7-0 7-0	1.75	5×20 6×24	SAF	HM	2	2	5.75	1.5	3.10	
406	403	403	8-0	12-0	GST	COH	1	8-0	12-0	1.75	bx24	SAF	STL	2	-	5.75	-	3.00	5
408	EXT	402	3-4	7-4	HM	N1	1	3-0	7-0	1.75	6×24	SAF	HM	2	2	5.75		3.10	
409	401	402	8-0	12-0	GST	COH	1	8-0	12-0	1.75		19	STL	-	-	-			5
410	402	401	6-8	7-5	GST	COH	1	6-8	7-5	1.75	C-01	CAE	STL	9	- 0	- E 7E	-	210	
411	EXT	402	3-4 8-11	7-4	HM	N1 COH	1	3-0 8-11	7-0 10-9	1.75	6×24	SAF	HM STL	2	2	5.75		3.10	
413	EXT	401	3-4	7-4	НМ	N1	1	3-0	7-0	1.75	6×24	SAF	НМ	2	2	5.75	-	3.10	
LAB/O	FFICE											3 4							
500	EXT	500	3-4	7-4	НМ	N1	1	3-0	7-2	1.75	6×24	SAF	НМ	1	2	5.75		3.10	
501	504	500	3-4	7-4	HM	HG	1	3-0	7-2	1,75	24×30		НМ	1	2	5.75	•	1.2/B	
502 503	504 504	501 502	3-4	7-4	HM	N1 N1	1	3-0 3-0	7-2 7-2	1.75	6×24 6×24	SAF	HM	1	2	5.75		1.1/B 1.1/B	
503	504	503	3-4	7-4	HM	NT	1	3-0	7-2	1.75	6x24	SAF	НМ	1	2	5.75		1.1/B	
505	EXT	504	3-4	7-4	НМ	N1	1	3-0	7-2	1.75	6x24	SAF	НМ	1	2	5.75	(-)	3.00	
506	504	505	3-4	7-4	НМ	F	1	3-0	7-2	1.75				1	2	5.75	-RI	1.00	
507 508	504 504	506 507	3-4 3-4	7-4	HM	F	1	3-0 3-0	7-2 7-2	1.75 1.75				1	2	5.75		1.30	
ang	Puc	7.00	3-4	(-4	UM	Г		3-11	1-6	1.75	-	*		:1:		0.75	-	1.30	
DOOR	SCHED	OULE LE	GEND					REMAR	RKS										
сон	COILING	OVERHE	AD					1. HI-LI	FT										
EXT	EXTERIO	OR						2. VER	TICAL LIFT										
	Company of the State of the Sta	V METAL						3. SLID											
	GALV. S SAFETY								SHUTTER	0/1		-							
	SAFETY							a. WITH	FUSIBLE	LINK				\vdash					
	- mar 10 11 11 10 1																		








DOOR & WINDOW ELEVATIONS SCALE: NONE

LINTEL	SCHE	DULE	
WALL THICKNESS	OPENING LENGTH	DESCRIPTION (INCHES & POUNDS)	REMARKS
8"	UP TO 3'-6"	(2) L'S 3 1/2"X3 1/2"X5/16"	SEE NOTES 2 & 3

1. FOR OPENINGS LARGER THAN 12'-6", SEE STRUCTURAL DRAWINGS FOR SIZE AND SHAPE.

- 2. SEE SPECIFICATIONS FOR COPING REQUIREMENTS.
- 3. PROVIDE 5/16" X (WALL THICKNESS 1 1/2") PLATE, WHEN SEAM IS EXPOSED TO VIEW.
- 4. SLH = SHORT LEG HORIZONTAL
- 5. LLH = LONG LEG HORIZONTAL

6. LOADING CONDITION IMPOSED ON LINTELS FROM ROOF AND/OR ELEVATED STRUCTURES ARE NOT INCLUDED IN THE LINTEL SIZE CALCULATION.



STRIPING OF PALLET ROWS
9 - CTG IN SHOWER ONLY

STEEL GUARD POST DETAIL
SCALE: NONE

			V	/
\triangle				100
\triangle				
Δ				
Δ				
A	ISSUED FOR BID		02/13/07	DEN
REV	DESCRIPTION	BY	DATE	CHK'D

DESIGNED B. CLARK CHECKED .

SCALE 1/8" = 1'-0" CADD DATE 3/2/2007 1:58 PM

PART P:\142-17450-07-001\CAD\142-17450-07-001\A\FLOORPLAN.DWG


PSC ENVIROMENTAL SERVICES 515 LYCASLE DETROIT, MI DETROIT FACILITY REBUILD


ARCHITECTURAL

CONTAINER MANAGEMENT BLDG FLOOR PLANS, SCHEDULES & DETAILS

DMISION CONTRACT

CONTRACT SHEET A-4





- EXPANDED POLYETHYLENE

-MULTI-PART POLYURETHANE

CLASS A, SEALANT, 20 YEAR

US-TT-S-00227D TYPE 2

FOAM BACK-UP

BUILDING PAPER

BOND BREAKER

IN BLOCK @

SHEAR KEY


BLOCK —


NOTES:

OR BRICK

 'X' DIMENSION TO EQUAL TYPICAL MASONRY JOINT
 'Y' DIMENSION TO EQUAL 'X'

EXTERIOR CONTROL JOINT





12" CONC. BLOCK

NO SCALE

LINTEL FLASHING DETAIL

JURED CONCRETE OOT'G. SEE STRUCTURAL SUBBASE RIGID INSULATION

INSULATED 12" CONC. BLOCK WEEP HOLE & FLASHING DETAIL

UP TO 3'-6" (3) L'S 4"X3 1/2"X5/16" SEE NOTES 2 & 3

12" WALL THICKNESS OPENING LENGTH (INCHES & POUNDS) REMARKS

UP TO 3'-6" (3) L'S 3 1/2"X5/16" SEE NOTES 2 & 3

3'-6" TO 6'-6" (3) L'S 4"X3 1/2"X5/16" SEE NOTES 2 & 3

W8X10
6'-6" TO 12'-6" (1) 5/16"X10 1/2" PLATE SEE NOTES 2 & 3

8" UP TO 3'-6" (2) L'S 3 1/2"X3 1/2"X5/16" SEE NOTES 2 & 3

TES: 1. FOR OPENINGS LARGER THAN 12'-6", SEE STRUCTURAL DRAWINGS FOR SIZE AND SHAPE.

2. SEE SPECIFICATIONS FOR COPING REQUIREMENTS.


3. PROVIDE 5/16" X (WALL THICKNESS - 1 1/2") PLATE, WHEN SEAM IS

EXPOSED TO VIEW.


4. SLH = SHORT LEG HORIZONTAL

5. LLH = LONG LEG HORIZONTAL

6. LOADING CONDITION IMPOSED ON LINTELS FROM ROOF AND/OR ELEVATED STRUCTURES ARE NOT INCLUDED IN THE LINTEL SIZE CALCULATION.




TYPICAL SINGLE WYTHE CONTROL JOINT DETAIL




NO SCALE


TYP. FLASHING END DAM DETAIL




TYP. REINFORCING



INTER-SECTION OF EXTERIOR LOAD BEARING WALL W/ INTERIOR NON-LOAD BEARING WALL



12" CONC. BLOCK
LINTEL FLASHING DETAIL
NO SCALE



	BACKGROUND PLAN AND	ONE LINE	SYMBOLS
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
•	CONTROL SWITCH (SEL. OR P.B.) SEE CIRCUITS FOR SPECIFIC TYPE	· > 0	LOW VOLTAGE DISCONNECT SWITCH
F FL	SEE CIRCUITS FOR SPECIFIC TYPE FLOAT SWITCH - FLOW SWITCH		LOW VOLTAGE FUSE (BELOW 600V)
T M	TEMPERATURE — HUMIDISTAT SWITCH (SUBSCRIPT = NO. OF STAGES)	T 1 RV	ALL STARTERS SHALL BE FULL VOLTAGE NON—REVERSING UNLESS
L P V	LIMIT - PRESSURE - VACUUM SWITCH	FVR 2	OTHERWISE INDICATED (FVR) FULL VOLTAGE REVERSING (RV) REDUCED VOLTAGE
ALT	ELECTRICAL OR MECHANICAL ALTERNATOR (SEE WIRING)	2S,2W	(2S,2W) TWO SPEED, TWO WINDING
os	OVERLOAD SWITCH OR DEVICE	00	600V, 3 POLE MOLDED CASE CIRCUIT BREAKER, FRAME & RATING AS SHOWN
ТВ	TERMINAL BOX	1/2 A-3	SINGLE PHASE, FRACTIONAL HP MOTOR TO LOCATION INDICATED (SEE GEN. NOTE 4)
\otimes	SOLENOID VALVE	A ₁	THREE PHASE LOAD WITH IDENTIFICATION
PC	PHOTOCELL LINE VOLTAGE		HIGH VOLTAGE FUSE (ABOVE 600 V)
□ 304 >	ITEM NO. INTERCOM EQUIPMENT		TAG NO. (BALLOON) FOR DEVICE INDICATED
A WS LB	INTERCOMMUNICATION SYSTEM AMPLIFIER — WALL STATION — LINE BALANCE	A-3	FOR POWER (SEE GEN. NOTE 4) 3/4"C(2/C#18 SHLD.)CONDUIT AND WIRE RUN FROM DEVICE INDICATED TO
DS	INTERCOMMUNICATION DESK SET	FT MCP OR CP-1	LOCATION INDICATED
\vee	INTERCOM. SPEAKER (SURFACE MTD.)	沬	CAPACITOR, 3 PHASE, SIZE AS INDICATED
\otimes	INTERCOM. SPEAKER (CEILING LAY-IN)		DISCONNECT SWITCH (F) = FUSED (C) = CIRCUIT BREAKER
▼	TELEPHONE OUTLET OR JUNCTION BOX	\boxtimes	MAGNETIC STARTER (BACKGROUND DRAWINGS ONLY)
	WELDING RECEPTACLE - NEMA L9-50R 600V, 2P, 3W, SIMPLEX	SIZE 2	COMBINATION MAGNETIC STARTER FUSED UNLESS NOTED (CIRCUIT BREAKER)
HS	INTERCOM HANDSET — SURFACE MOUNTED WITH REMOTE SPEAKER AMPLIFIER	Ę	COMBINATION LIGHTING CONTACTOR WITH HAND-OFF-AUTO SWITCH
VC	INTERCOM VOLUME CONTROL		MANUAL STARTER (R) = REVERSING
\square	INTERCOM SPEAKER - SURFACE MOUNTED	CP	CONTROL PANEL
HS	INTERCOM HANDSET — FLUSH MOUNTED WITH REMOTE SPEAKER AMPLIFIER	TCP	TEMPERATURE CONTROL PANEL
	AS NOTED (LIGHTING PANEL, CONTROL PANEL, DISTRIBUTION PANEL ETC.) WALL MOUNTED	1/8 _{UH-19}	UNIT HEATER, 1/8 HORSEPOWER
JB	JUNCTION BOX	BUS DUCT	600 VOLT FEEDER BUS DUCT (AMPERAGE AS INDICATED)
	HEATER	⊕ <u>¯</u>	LIGHTNING ARRESTOR
38	TRANSFORMER	A-3	LOW VOLTAGE HOME RUNS 120/208 V 120/240 V (SEE GEN. NOTE 4)
	CONDUIT WITH CONDUIT SEAL FITTING	NEMA 4	WATERTIGHT
	CONDUIT EXPOSED	NEMA 4X	WATERTIGHT AND CORROSION PROOF
	CONDUIT CONCEALED	NEMA 7	EXPLOSION PROOF — CLASS I, DIVISION I, GROUP D
——Е——	DIRECT BURIED CONDUIT	NEMA 9	EXPLOSION PROOF — CLASS II, DIVISION 1
—— UG ——	DIRECT BURIED CABLE	⟨K⟩	KEYLOCK
—— он ——	OVERHEAD LINE	SD	SMOKE DETECTOR
—— DB ——	UNDERGROUND DUCT BANK	₹	EXIT LIGHT
023	CONCRETE ENCASED DUCT BANK, WITH CABLE LOCATIONS AND SPARE DUCTS AS		FLUORESCENT LUMINAIRE
<u>456</u>	INDICATED ON DRAWINGS	X	INCANDESCENT LUMINAIRE
	CABLE REEL		HIGH INTENSITY DISCHARGE LIGHT
		EM	EMERGENCY BATTERY PACK

FUSE SIZE	WIRES TO CONTROL NO. 1 FIELD MOUNTED PILOT DEVICES	
60A 20A	2#14 (1) 3/4"C(4#14) DENTIFICATION PLATE INFORMATION (1) (1) (1) (1) (1) (1) (1) (1) (1) (1)	
	CONDUIT SIZE 60A 1 3/4"C(4#12) SAMPLE PUMI	Þ
SWITCH SIZE STARTER AND TYPE	DISCONNECT LOAD IDENT. THESE ITEMS SHOWN ON PLAN VIEW AS	
	M.C.C. LEGEND EXAMPLE	

GENERAL NOTES:

- 1. ELECTRICAL MATERIALS AND EQUIPMENT ITEMS SHOWN IN LIGHT LINE WEIGHTS ON THE DRAWINGS ARE EXISTING ITEMS TO REMAIN. ELECTRICAL MATERIALS AND EQUIPMENT ITEMS SHOWN IN HEAVY LINE WEIGHTS ARE NEW THIS CONTRACT.
- 2. ITEMS SHOWN CROSSHATCHED ON THE DRAWINGS ARE EXISTING ITEMS TO BE REMOVED.
- 3. FOR ITEMS INDICATED AS "FIELD LOCATE" CHECK DRAWINGS OF OTHER TRADES (IN PARTICULAR PIPING AND STRUCTURAL) FOR INTERFERENCE AND FOR LOCATIONS OF MOUNTING FLANGES, CONNECTION POINTS, ETC.
- 4. INSTALL A SINGLE CONDUCTOR INSULATED (RHW, THHN, OR XHHW) COPPER GROUND WIRE IN EACH CONDUIT, SIZE AS SHOWN ON DRAWINGS OR AS A MINIMUM PER THE NATIONAL ELECTRICAL CODE. THIS GROUND WIRE SHALL BE CONNECTED AT EACH END TO THE EQUIPMENT GROUND. CONDUIT SHALL BE 3/4" MIN.
- 5. THE FOLLOWING COMPONENT IDENTIFICATION SHALL BE USED AS APPROPRIATE:

 (F) FIELD MOUNTED, NOT AT STARTER OR OTHER CONTROL PANELS.

 (S) STARTER PANEL MOUNTED.

 (MCP) AT MAIN CONTROL PANEL.


 (1) AT CONTROL PANEL NO. 1

 (2) AT CONTROL PANEL NO. 2

 (TCP) AT TEMPERATURE CONTROL PANEL.

CONTR	OL CIRCUIT & PI	IL	LOT DEVIC	CE LEGEND
SYMBOL	DESCRIPTION		SYMBOL	DESCRIPTION
2 P	PRESS. ACTUATED SWITCH		H O O O O	SELECTOR SWITCH OPERATOR WITH FUNCTION SHOWN
7° C	FLOW ACTUATED SWITCH		0 0	MOMENTARY PUSHBUTTON OPERATOR—NORMALLY OPEN
2	TEMP. ACTUATED SWITCH		ه ا ه	MOMENTARY PUSHBUTTON OPERATOR—NORMALLY CLOSED
∞ °	LIMIT SWITCH— NORMALLY OPEN		оТо	PUSHBUTTON OPERATOR WITH MUSHROOM HEAD
0-70	LIMIT SWITCH- NORMALLY CLOSED		<u>O O</u> (F)	FIELD LOCATED STOP BUTTON
00	LIMIT SWITCH-NORMALLY CLOSED-HELD OPEN		0 0	MAINTAINED PUSH-PULL OPERATOR
9	LIMIT SWITCH-NORMALLY OPEN-HELD CLOSED		0,0	MAINTAINED STOP—START PUSHBUTTON OPERATOR
9	LATCHING CABLE SWITCH		0 0	FUSHBUTTON OF ENATOR
	TIME-DELAY FUSE			SOLENOID OR CLUTCH
	CONTROL RELAY COIL		0 R 1 4 0	PUSH-TO-TEST INDICATING LIGHT
11	CONTROL RELAY CONTACT—NORMALLY OPEN CONTROL RELAY CONTACT—NORMALLY CLOSED		0 0 0	MAINTAINED STOP— MOMENTARY START PUSHBUTTON (JOG)
-CR-L	TWO COIL LATCHING DELAY		O	ZERO SPEED OR ANTI— PLUGGING SWITCH
-CR-	TWO COIL LATCHING RELAY		0	LOCAL TERMINALS WITH EXTERNAL WIRING
	TIMING RELAY COIL		—(ETI)—	ELAPSED TIME INDICATOR
~°	TIMED CLOSED CONTACT ON ENERGIZATION		—	TIMING RELAY
To	TIMED OPEN CONTACT ON ENERGIZATION		Inst.	INSTANTANEOUS CONTACTS
→	TIMED OPEN CONTACT ON DE-ENERGIZATION			
T°	TIMED CLOSED CONTACT ON DE-ENERGIZATION			
o ^{X1}	120 VAC TRANSFORMER			


	WIRING DEVICE SCHEDULE					
SYMBOL	DESCRIPTION	NEMA TYPE				
6	125V, 2P, SIMPLEX, CLOCK HANGER	1-15 R				
Ф	125V, 2P, SIMPLEX, 3W	5-20 R				
Ь	125V, 2P, DUPLEX, 3W	5-20 R				
b	125/250V, 3P, SIMPLEX, 3W, RANGE TYPE	10-50 R				
Ş	20A, 120/277 V SWITCH	SPST				
S _{2P}	20A, 120/277 V SWITCH	2PDT				
S ₃	20A, 120/277 V SWITCH	3 WAY				
<u>S</u> 4	20A, 120/277 V SWITCH	4 WAY				
S _D	20A, 120/277 V DIMMER SWITCH					
SXP	20A, 120/277 V EXPLOSION-PROOF SWITCH	7				
•	250V, 2P, SIMPLEX, 3W, 50A	6-50R				
ΦΦΦ	125V, 2P, MULTI-RECEPTACLE	5-15R				
0	250V, 2P, SIMPLEX, 3W, 20A					
	600V, 2P, 3W, SIMPLEX WELDING					
\triangle	208V, 3P, SIMPLEX, 4W, LOCKING	L14-20R				
•	277V, 2P, DUPLEX, 3W	7-15R				



NOTES

- THE FOLLOWING COMPONENT IDENTIFICATION SHALL BE USED AS APPROPRIATE:

 (F) FIELD MOUNTED NOT AT STARTER OR OTHER CONTROL PANELS.
 (S) STARTER PANEL MOUNTED.
 (TCP) AT TEMPERATURE CONTROL PANEL.
 (MCP) AT MAIN CONTROL PANEL.
 (1) AT CONTROL PANEL NO. 1.
 (2) AT CONTROL PANEL NO. 2.
- WIRE NUMBERS (1,3 & 5) ETC. SHALL BE PREFIXED WITH STARTER TAG NUMBERS. THE WIRE NUMBER AFTER THE PREFIX, MAY BE THE MANUFACTURERS WIRE NUMBERING SYSTEM. WIRE MARKERS MAY BE USED AT EACH WIRE TERMINATION POINT.





CONTRACT


DIVISION

 $MPS \setminus E \setminus FRM \setminus 5 - 1M$

E-1







A B C 100A SUH-1 1-0 0-DOOR OPERATOR 5 0-6 LIGHTING-EXTERIOR -0-8 LIGHTING-EXTERIOR DOOR OPERATOR 9-0 -0 0-10 LIGHTING-INTERIOR 0 0 12 LIGHTING-INTERIOR 0 14 RECEPTS-ROOF EYEWASH 13 0 0-HEAT TRACE 15 0 0-0 0 16 SPARE HEAT TRACE 17 0 0 O O SPARE SPARE 19 0 0 SPARE 2100 O 022 SPARE SPARE 23 0 0-

30KVA, 3Ø, 480-120/208V, POLE-MOUNTED TRANSFORMER

- (3#4, 1#8), SPLICE TO EXISTING OVERHEAD FEEDERS


PANELBOARD 'L-2'

LOCATION: HEEL

VOLTAGE: 120/208V

BUS RATING: 225A

PANEL L-2 ONE-LINE



OVERHEAD ELECTRICAL LINES SHALL

1-1/2°C WITH WEATHERHEAD

CONNECTION SECURED TO HEEL BUILDING

NEW HEEL BUILDING

NEMA 3R ENCLOSURE

BE WRAPPED AROUND A SUSPENSION CABLE FOR SUPPORT

TETRA TECH

DESIGNED FWY снескер WAP CA00 DATE 2/12/2007 2:19 PM FILE P:\142-17450-07-001\CAD\142-17450-07-001\E\E-3 ONE-LINE.


энел Е−3


CONTAINER AND HEEL MANAGEMENT BLDG ONE-LINES


NOTES:


1. MAIN POWER FEED CONDUIT IS ONLY FROM THE EXISTING PANEL UP TO THE CABLE TRAY AND FROM THE CABLE TRAY DOWN TO MCC-Y. SEAL CONDUIT UPON ENTERING AND EXITING THE CABLE TRAY, FULL-LENGTH OF CONDUCTORS FROM EXISTING PANEL TO MCC-Y SHALL BE CABLE TRAY RATED.


2. FIELD VERIEY AND COORDINATE WITH OWNER FOR LOCATION OF POWER PANEL WITHIN MAINTENANCE OFFICE LOCKER ROOM AND WAREHOUSE AREA.











































NOTES:

1. CONCRETE CLASS DESIGNATIONS ON DWSD DETAILS REFER TO DWSD STANDARD CONCRETE CLASSES AND ARE NOT NECESSARILY THE SAME AS THE CONCRETE CLASS DESIGNATIONS IN THE PROJECT SPECIFICATIONS






	CONTAIN	MENT AREA LEGEND						
		TOTAL AVAILIBLE	REQUIF	RED CONTAINMENT	TOTAL REQUIRED	RE'Q CONTAINMENT		
AREA	HATCHING	CONTAINMENT VOLUME BY AREAS +(GAL)	10% STORAGE VOLUME -(GAL)	FIRE WATER VOLUME -(GAL)	PALLATS / DRUMS VOLUME -(GAL)	VOLUME —(GAL) SEE NOTE 1	VOLUME IN AREA 10 (GAL)	
-		6,537	1,452	10,944	1,878	14,272	-7,737	
2		5,161	968	7,296	1,252	9,516	-4,355	
3	/////////	7,225	1,452	10,032	1,878	13,362	-6,137	
4	ZZZZZ	4,443	2,112	23,712	0	25,824	-21,381	
5	ZZZZZ	800	517	14,504	0	15,021	-14,221	
6		8,602	1,936	13,680	2,504	18,120	-9,518	
7	77777777	11,698	2,420	15,960	3,130	21,510	-9,812	
88	7777777	15,139	3,388	22,344	4,382	30,114	-14,975	
9	ZZZZZZ	800	627	18,720	0	19,347	-18,547	
10	ZZZZZ	34,819	1,408	20,000	0	21,408	13,411	
11	ZZZZ	6,881	0	10,736	0	10,736	-3,855	
12	ZZZZZ	5,834	5,000	3,120	0	8,120	-2,286	
13	ZZZZ	748	615	1,920	0	2,535	-1,9787	


- NOTES:

 1. TOTAL REQUIRED VOLUME = 10% VOLUME OF DRUM STORAGE + FIRE WATER VOLUME (BASED ON SQUARE FOOTAGE OF CONTAINMENT AREA TIMES 0.40 GPM/FT² x 20 MIN) + PALLATS/DRUMS DISPLACEMENT VOLUME.

 2. FIRE WATER VOLUME FOR CONTAINMENT AREA 10 IS BASED ON 2500 SQUARE FEET x 0.40 GPM/FT² x 20 MIN.



BUILDING PROFILE CONTAINMENT AREAS SCALE: NONE




DESIGNED D. WALZER CHECKED DEN

SCALE 3/32" = 1'-0" CADO DATE 2/12/2007 3:14 PM

GENERAL

CONTAINER MANAGEMENT BLDG CONTAINMENT AREAS

94EET **G-5** 9F 5



NEW CONTAINER WAREHOUSE & PROCESS BUILDING

	RETURN GRILLE (RG) AND SUPPLY REGISTER (SR) SCHEDULE									
MAK	LOCKRON	CFN RMME	MECK	STALE	REMINS					
SR-1	CONTAIER WAREHOUSE	1610	24X14	TITUS 300FS	Suppliedbycontractor Installedbyconstractor					
SR-2	PUMP ROOM	3000	35X18	TITUS 300FS	Suppliedbycontractor Installedbyconstractor					
SR-3	ELECTRICAL ROOM	180	8X6	TITUS 300FS	Suppliedbycontractor Installedbyconstractor					
SR-4	DECON ROOM	500	12X10	TITUS 300FS	Supplied by contractor installed by constractor					
SR-5	KMNO4 ROOM	315	1206	TITUS 300FS	Supplied by contractor installed by constractor					
RG-1	Contaier Warehouse	500	12X12	TITUS 350ZFL	Suppliedbycontractor Installedbyconstractor					
RG-2	STAIRWELL Room	340	10X10	TITUS 350ZFL	Suppliedbycontractor Installedbycontractor					
RG-3	KMNO4 ROOM	180	8X8	TITUS 350ZFL	SUPPLIEDBYCONTRACTOR INSTALLEDBYCONTRACTOR					

STEAM UNIT HEATERS (120 PSI STEAM) (DH) SUPPLIED BY CONTRACTOR INSTALLED BY CONTRACTOR

NOTES:

1. INTERLOCK DH-1 THRU 6 WITH AUTOMATIC DOOR OPENERS. DH-1 THRU 6 SHALL ENERGIZE WHEN DOOR OPENER ENERGIZES AND STAY ENERGIZED WHILE DOOR IS OPEN AND DENERGIZE WHEN DOOR CLOSER IS DENERGIZED.

			1	STEAM TRAP S	SCHEDULE (ST)		
WEK	LECUPION (EQUIP. OR DIRE. NO.)	TIPE OF THIP	WORK PRESS. (PSK)	CUPICEY (FFH)	1869 1877, PRESS. (750)	COL NOWS	REMINS
ST-1	ERU-1 Container Building	INVERTED BUCKET 215SS 11/32	150	6843	120	N/A	SUPPLIED BY CONTRACTOR INSTALLED BY CONTRACTOR
ST-2	DH-1 THRU 6 CONTAINER BUILDING	INVERTED BUCKET 212SS 5/32	150	1735	120	N/A	SUPPLIED BY CONTRACTOR INSTALLED BY CONTRACTOR
\$1-3	• •	:					:

	EXHAUST FANS													
				_	VOLTS /			REMINES						
WAK	LOCKHOM	8	8		PHASE	ROUGH OPENING	GREEN-ECK NCCEL NO.	PUNNESH ALL FINES WITH DISCOMBECT SMITCHES						
EF-1	HOOD EXHAUST FAN DEPACK ROOM	1000	0.5	0.5	115 -	1	TCB-1-13	SUPPLIED BY CONTRACTOR INSTALLED BY CONTRACTOR						
EF-2	HOOD EXHAUST FAN DEPACK ROOM	1600	0.5*	0.5	115 -	1	1CB-1-13	SUPPLIED BY CONTRACTOR INSTALLED BY CONTRACTOR						
EF-3	SCRUBBER FAN PUMP ROOM	8000	6.0*	15	480 3	1	NEW YORK BLOWER AFC/PLR 22 CW	SUPPLIED BY OWNER INSTALLED BY CONTRACTOR						
EF-4	VACUUM BLOWER DEPACK ROOM	250	30*	5	480 3	-	NEW YORK BLOWER	SUPPLIED BY OWNER INSTALLED BY CONTRACTOR						

	PUMP SCHEDULE (P)													
MAK	GUNNINY	LOCKRON	THE	(SER) CENTRY	189	DESIGN TEMP.	9	MOTOR DESCRIPTION	SEMCE	REWINS				
P-1 - 4	4	CONTAINER PUMP OUT PUMP ROOM	AIR Diaphram	80	60	70	N /A	Plant air (100 psi)	LIQUID WASTE	Supplied by owner Installed by owner				
P-5	1	AIR SCRUBBER PUMP ROOM	CENTRIFUGAL PUMP	320	70	70	15	480V 3/60	RECIRCULATION SCRUBBER	SUPPLIED BY OWNER INSTALLED BY OWNER				
P-6	1	TW CIRCULATING PUMP DECON ROOM	CENTRIFUGAL PUMP	20	60	120	1.5	460V 3-PH	RECIRCULATION TW	SUPPLIED BY CONTRACTOR INSTALLED BY CONTRACTOR				
P-7 & 8	2	TK-001 AND TK-002 PUMP ROOM	CENTRIFUGAL PUMP	200	80	70	15	480V 3/60	Liquid Waste	SUPPLIED BY OWNER INSTALLED BY OWNER				

- NOTES:

 1. PUMPS P-1 THRU 4 SHALL BE ALL-FLO MODEL ST-20E, 2*x 2* FLANGED, 316SS W/ SANTOPRENE.

 2. PUMP P-5 SHALL BE PEERLESS MODELB196 MTP, 316SS, 3x4-10 WTH 15HP 1800R 254TEXPPRF.

 3. PUMP P-6 SHALL BE GRUNDFOS MODEL TP40-240/2, 1-1/2*x 1 1/2* FLANGED, CAST IRON WITH 1 1/2HP TEFC, 3/60/208-230-460V MOTOR.
- A PUMP P-7 & B SHALL BE GORMAN RUPP SUPER T SERIES SELF-PRIMING CENTRIFUCAL PUMP, MODEL T3A61S-B/F, SIZE 3"x 3", TRASH PUMP W/ GRAY IRON CASING AND SS FITTED INTERNALS. BELT DRIVEN @ APPROX. 1900 RPM W/ 1750 RPM, 254T FRAME, 3/60/230-460V, EXPLOSION PROOF MOTOR, MOUNTED ON A STEEL VERTICAL FABRICATED V-BELT BASEPLATE ASSEMBLY WI/BELT GUARD.

	ehergy recovery unit (eru) — plate hx																
		SUPF		SUPPLY		DOWNST		HK		STEW				VOLES /			
MAK	LOCHRON	2	8	9	68	a	9	4	粧	ENT	ğ	Ē			PHOE	MODEL NO.	REMAIS
ERU-1	Outside Container Bldg	19,875	3.46	20	15,840	2.47	15	60		40	1534	1768			460 3	see notes Below	SEE NOTES BELOW

- NOTES:


 1. PLATE TYPE COUNTER FLOW HEAT EXCHANGER FOR SENSIBLE HEAT RECOVERY.

 2. PROVIDE HX FACE AND BYPASS DAMPERS ON FRESH AIR SIDE FOR FROST PREVENTION AND SUMMER OPERATION

 3. ERU-1 EXHAUST PLENUM TO BE CLASS 1, DIVISION 2, GROUP D AREA.

 4. PROVIDE FLANGED CONNECTION AT EXHAUST DISCHARGE FROM ERU-1
- 5. ERU-1 MANUFACTURE: INNOVENT AIR HANDLING EQUIPMENT, MODEL: RHXC-1F-1010-19000-ST/FR-A-1
 6. ERU-1 SHALL BE SUPPLIED BY OWNER, INSTALLED BY CONTRACTOR.

REV	DESCRIPTION	BY	DATE	снк'о
҈	ISSUED TO MDEQ	DCW	01/09/07	DEN
Æ	ISSUED FOR BID	DCW	02/13/07	DEN
Δ				
4				



DESIGNED D. WALZER	CHECKED DEN
SCALE ,	CADO DATE 2/14/2007 4:51 PM
EN F PA 142-17450-07-001\040\141	17450-07-00(\IAU-1 EBU SOUED A

CONTAINER MANAGEMENT BLDG HEATING AND VENTILATING FLOW DIAGRAM

SHEET M-1 of 6


NOTES:


1. SEE DRAWING M-4 FOR EQUIPMENT AND PUMP SCHEDULE.


2. SEE MECHANICAL SPECIFICATIONS 15050 THROUGH 15905 FOR MATERIAL AND INSTALLATION REQUIREMENTS OF MECHANICAL EQUIPMENT.


3. SEE SCHEDULES FOR MATERIALS AND EQUIPMENT SUPPLIED BY OWNER/CONTRACTOR

SEE SCHEDULES FOR MATERIALS AND EQUIPMENT SUPPLIED BY OWNER/CONTRACTOR
AND INSTALLED BY OWNER/CONTRACTOR.
 CONTRACTOR SHALL SUPPLY ALL PIPING MATERIALS, VALVES, FITTINGS, HANGERS, ETC.
FOR ALL PIPING SYSTEMS SHOWN ON THE DESIGN DRAWINGS.
 COORDINATE FINAL LOCATION OF EQUIPMENT AND PIPING WITH OWNER.
 AIR COMPRESSOR, DRYER, AND FILTERS SHALL BE INSTALLED IN THE MANAGEMENT
OFFICE, LOCKER RM, WAREHOUSE BUILDING. SEE OWNER FOR LOCATION.
 THE CONTRACTOR IS ALSO RESPONSIBLE FOR ANY ADDED VALUE REVIEWS/CHANGES
TO THE DESIGN DRAWINGS TO MEET ALL CODES AND REQUIREMENTS, AND PROVIDE
THE OWNER WITH ANY POTENTIAL COST SAVINGS. THE CONTRACTOR IS ENCOURAGED
TO FURTHER EXPLORE OTHER OPTIONS THAT MAY MEET PROJECT OBJECTIVES WHILE
REDUCING COST.









			(EQUIPMENT SCI	EDULE		
Mex	CLUMMITY	CESCRIPTION	COMECTORS	CHICITY	ELECTRICAL	NODEL NO.	REMIS
MX-1	1	MIXER/ AGITATOR	ELECTRICAL	3 HP MOTOR	480V 3-PH	mm	Supplied by Owner Installed by Contractor
MX-2	1	MIXER/ AGITATOR	ELECTRICAL.	3 HP MOTOR	480V 3-PH	7777 7777	SUPPLIED BY OWNER INSTALLED BY CONTRACTOR
TK-001	1	liquid waste Storage tank	2" WW ELECTICAL	6,000 GALLON	120V 1-PH	m	SUPPLIED BY OWNER INSTALLED BY CONTRACTOR
TK-002	1	liquid waste Storage tank	2" WW Electical	6,000 GALLON	120V 1-PH	11111 11111	SUPPLIED BY OWNER INSTALLED BY CONTRACTOR
SCR-1	1	AIR SCRUBBER PUMP ROOM	exhaust duct wake-up water	8,000 CFM	15 HP 480V 3-PH	m	Supplied by Owner Installed by Contractor
VC-1	1	VERNICULITE COLLECTION DEPACK ROOM	ELECTRICAL			m	Supplied by Owner Installed by Contractor
AC-1	1	AIR COMPRESSOR MAINTENANCE BUILDING	2*	200 SCFM	50 HP 48V 3-PH	QUINCY QSB50	SUPPLIED BY OWNER INSTALLED BY CONTRACTOR
AC-DRYER	1	DESICCANT HEATLESS DRYER MAINTENANCE BUILDING	INLET 2". OUTLET 2"	240 SCFM	110V 1-PH	QUINCY MXA102c	SUPPLIED BY OWNER INSTALLED BY CONTRACTOR
AC-COND1	1	CONDENSATE REMOVER MAINTENANCE BUILDING	INLET 2" OUTLET 2"	200 SCFM	115V 1-PH	QUINCY QMAT-1	SUPPLIED BY OWNER INSTALLED BY CONTRACTOR
AC-COND2	1	CONDENSATE REMOVER MAINTENANCE BUILDING	INLET 2. OUTLET 2	200 SCFM	115V 1-PH	QUINCY QMAT-2	SUPPLIED BY OWNER INSTALLED BY CONTRACTOR
AC-FILTER1	1	0,1 Micron 5PPM Filter Maintenance Building	INLET 2". OUTLET 2"	200 SCFM	N/A	QUINCY AAO40HNFX	Supplied by Owner Installed by Contractor
AC-FILTER2	1	0.01 MICRON 1PPM FILTER MAINTENANCE BUILDING	INLET 2". OUTLET 2"	200 SCFM	N/A	QUINCY AAO40HNFX	Supplied by Owner Installed by Contractor
CRP-30	1	WATER/OIL SEPARATOR MAINTENANCE BUILDING	INLET 2". OUTLET 2"	200 SCFM	N/A	QUINCY CRP-30	SUPPLIED BY OWNER INSTALLED BY CONTRACTOR
RT-1	1	CA RECEIVER DEPACK ROOM	1" CA	500 GALLON	N/A	ASME SEC-V111 DIV-1	SUPPLIED BY OWNER INSTALLED BY CONTRACTOR
WH-1	1	ELECTRIC WATER HEATER DECON ROOM	1 1/2	52 GALLON	115V 1-PH	AMERICAN STANDARD CE-52-AS	SUPPLIED BY CONTRACTOR INSTALLED BY CONTRACTOR
WH-2	1	ELECTRIC WATER HEATER DECON ROOM	1 1/2	52 GALLON	115V 1-PH	AMERICAN STANDARD CE-52-AS	SUPPLIED BY CONTRACTOR INSTALLED BY CONTRACTOR
EWSS-1	1	EYEWASH/SAFETY SHOWER OUTSIDE TRUCK DOCK	1 1/4" TW	23 GPM	120V AC 1-PH	HAWS 8317CTFP	SUPPLIED BY CONTRACTOR INSTALLED BY CONTRACTOR
EWSS-2	1	EYEWASH/SAFETY SHOWER CONT/DEPACK/PUMP/DECON	1 1/4" TW	23 GPM	120V AC 1-PH	HAWS 8309WC	SUPPLIED BY CONTRACTOR INSTALLED BY CONTRACTOR
RC-1&2	2	NOTOR DRIVEN ROLLER CONVEYOR PUMP ROOM	:		480V 3-PH 1HP	REVERSING STARTER	Supplied by owner Installed by owner

LEGEND

HOSE BIB GATE VALVE

BALL VALVE ELBOW UP ELBOW DOWN REDUCER

AIR FLOW AIR SET FLOW ARROW STEAM TRAP METER

BACK FLOW PREVENTER EYEWASH/SAFETY SHOWER TIE-IN POINT

SUPPLY DEFUSER

RETURN GRILLE

THERMOSTATE DOOR UNIT HEATER

7				
7				
7				
7	ISSUED FOR BID		02/13/07	
7	ISSUED TO MDEQ	DCW	01/09/07	DEN
,	DESCRIPTION	BY	DATE	СНКО




DESIGNED D. WALZER	CHECKED DEN
SCALE AS NOTED	CADO DATE 2/12/2007 2:26 PM
FILE P:\142-17450-07-001\CAD\142	2-17450-07-001\M\N-4_DETALS_2.DWG

PSC ENVIRONMENTAL SERVICES DMS 515 LYCASTE DETROIT, MICHIGAN DETROIT FACILITY REBUILD

CONTAINER MANAGEMENT DLDG DETAILS AND SCHEDULES

SHEET M-4 of 6



. GENERAL

- A. THESE GENERAL NOTES PRESENT AND/OR SUMMARIZE KEY PROJECT INFORMATION FOR THE PLANS READER'S CONVENIENCE. SEE ALSO INDIVIDUAL PLAN NOTES AND PROJECT SPECIFICATIONS FOR FURTHER DETAILS AND REQUIREMENTS.
- B. ALL REFERENCES TO REFERENCE STANDARDS HEREIN ARE TO MOST RECENT ISSUE IN 3. FOUNDATIONS EFFECT AS OF THE DATE OF THESE DOCUMENTS, UNLESS NOTED OTHERWISE IN PROJECT SPECIFICATIONS OR ON THE PLANS.
- C. ELEVATIONS. ALL ELEVATIONS ARE REFERENCED TO EL. 100'-0"=____ ALL ELEVATIONS SHOWN ON PLANS ARE REFERENCED TO THIS DATUM UNLESS NOTED.
- D. ABBREVIATIONS:
- B/ BOTTOM OF CONC CONCRETE CMU CONCRETE MASONRY UNIT
- DEMO DEMOLITION . EACH FACE . ELEVATION
- EMBED EMBEDMENT . EACH WAY
- EXT. EXISTING GAUGE
- GRADE BEAM . NEAR FACE
- N.W. NORMAL WEIGHT .. ON CENTER
- T/ TOP OF TOS TOP OF STEEL
- TYP TYPICAL UNO UNLESS NOTED OTHERWISE WWF WELDED WIRE FABRIC
- E. SUBMIT SHOP DRAWINGS, PROJECT DATA AND SAMPLES AS SPECIFIED IN PROJECT SPECIFICATIONS.
- F. SPECIAL IDENTIFICATION: TINDICATES CONTRACT/CONSTRUCTION REQUIREMENTS THAT IN THE EXPERIENCE OF THE DESIGNER ARE (A) ESPECIALLY CRITICAL TO SAFE OR SATISFACTORY PERFORMANCE; AND/OR (B) FREQUENTLY NOT GIVEN ADEQUATE CONSTRUCTION QUALITY CONTROL BY THE CONTRACTOR OR SUBCONTRACTORS; AND/OR (C) NOT "STANDARD" OR COMMON CONSTRUCTION REQUIREMENTS AND THEREFORE MAY BE SUBJECT TO CONTRACTOR OVERSIGHT IN COSTING AND/OR CONSTRUCTION.

2. DESIGN CRITERIA

- A. BUILDING CODE: 2003 MICHIGAN BUILDING CODE
- B. BULDING CLASSIFICATION IN ACCORDANCE WITH IBC 2003, TABLE 1604.4. METAL BUILDING MFR'R TO APPLY APPROPRIATE IMPORTANCE FACTORS FOR SNOW, WIND, AND SEISMIC.
 - HEEL MANAGEMENT BUILDING: III CONTAINER WAREHOUSE: IV

- A. FOUNDATIONS SHALL BE A DEEP FOUNDATION SYSTEM UTILIZING TITAN MICROPILES (UNITED DYNAMICS (812)-282-2222, ERIC MINZENBERGER) OR APPROVED EQUAL. SEE PLANS FOR REQUIRED CAPÁCITIES. A MINIMUM OF 2 TEST PILES WILL BE REQUIRED. PROVISIONS SHALL BE MADE FOR ADDITIONAL TEST PILES IF SITE CONDITIONS WARRANT.
- B. GEOTECHNICAL ENGINEER SHALL BE RETAINED TO PROVIDE OBSERVATION AND TESTING SERVICES DURING THE GRADING AND FOUNDATION PHASE OF CONSTRUCTION PER SOIL REPORT RECOMMENDATIONS. INSPECTION AND TESTING REPORTS SHALL BE SUBMITTED TO THE STRUCTURAL
- . SUBGRADE FOR ALL SHALLOW BEARING CONTINUOUS WALL FOUNDATIONS SHALL BE OVEREXCAVATED A MINIMUM OF 2'-0", COMPACTED, AND FILLED WITH CRUSHED STONE. THIS IS NOT REQUIRED AT THE PERIMETER GRADE BEAMS.
- D. PROVIDE PROTECTION OF ALL EXISTING AND ADJOINING PUBLIC AND PRIVATE PROPERTY FROM DAMAGE DUE TO EXCAVATIONS.
- E. DESIGN AND PROVIDE SHEETING AND SHORING AS REQUIRED TO CONTAIN BANKS AND SIDES OF EXCAVATIONS.
- F. FURNISH AND INSTALL UNDERPINNING REQUIRED TO SUPPORT EXISTING STRUCTURES.
- G. PREVENT HEAVY VEHICULAR TRAFFIC WITHIN 10 FEET OF SHORING BULKHEAD OR TOP OF EMBANKMENTS.
- H. EMERGENCY TELEPHONE NUMBERS (FIRE, POLICE, TRAFFIC, UTILITY, SEWER MAINTENANCE, ETC.) SHALL BE POSTED AT THE JOB SITE AND ALL OTHER NECESSARY PRECAUTIONS SHALL BE TAKEN TO PROVIDE FOR EMERGENCIES.

4. CAST-IN-PLACE REINFORCED CONCRETE

- A. REFERENCE STANDARD: ACI 301. COLD WEATHER PLACEMENT: ACI 306-1. HOT WEATHER PLACEMENT: ACI 305R. CONTRACTOR TO MAINTAIN COPIES OF THESE SPECIFICATIONS AT JOB SITE.
- B. MIX DESIGN SHALL BE DOCUMENTED IN ACCORDANCE WITH SECTION 03300 OF THE SPECS AND ACI 301, CHAPTER 3 "PROPORTIONING". MIX DESIGNS WHICH ARE SUBMITTED WITHOUT THE REQUIRED DOCUMENTATION WILL BE REJECTED. FIELD SLUMPS RECORDED AT JOB SITE SHALL NOT EXCEED THE SLUMP ESTABLISHED FOR THE MIX DESIGN.
- C. TYPE CONCRETE. SEE CONCRETE SPECIFICAITON 03310 1. PILE CAPS, CONTINUOUS WALL FOUNDATIONS: CLASS A
- 2. ALL REMAINING CONCRETE STRUCTURES SHOWN: CLASS S
- 3. ALL CONCRETE EXPOSED TO THE ELEMENTS SHALL BE AIR-ENTRAINED 5 1/2% (± 1 1/2%). SEE SPECS.
- 4. ALL CONCRETE IN 8" WALLS OR COLUMNS WITH TWO PLANES OF REINFORCEMENT SHALL HAVE MAXIMUM 3/4 INCH AGGREGATE. IT IS RECOMMENDED THAT THE CONTRACTOR
- CONSIDER SUPER-PLASTICIZED CONCRETE PER SPECS. 5. TYPICAL REINFORCING BARS LAP: TENSION "B" UNLESS NOTED OTHERWISE.

- 1. REINFORCING BARS: DEFORMED, GRADE 60, ASTM A615, A616, A617 OR A706 A. FABRICATION: ACI 315-60 "DETAILS AND DETAILING OF CONCRETE REINFORCEMENT OR CRSI "REINFORCING BAR DETAILING" (MANUAL OF STANDARD PRACTICE).
- 2. WELDED SMOOTH WIRE FABRIC ASTM A185 (SHEETS ONLY, ROLL FABRIC NOT ALLOWED) 3. WELDING - ACI 301, SECTION 5.3 4. ACCESSORIES: PROVIDE PROTECTED BAR SUPPORTS CLASS 1, MAXIMUM PROTECTION (CRSI MANUAL OF STANDARD PRACTICE) FOR ALL SLABS AND BEAMS WITH SOFFITS EXPOSED TO VIEW, INCLUDING PAINTED OR SPRAY-ON FINISHED SURFACES. MINIMUM BAR CLEARANCES/
- ACCESSORIES ARE NOT ACCEPTABLE. USE MOLDED PLASTIC LEGS, 1/4" MINIMUM LENGTH. 5. CORNER BARS: PROVIDE CORNER BARS SAME SIZE AND SPACING AS HORIZONTAL REINFORCEMENT AT INTERSECTIONS OF ALL WALLS, UPTURNED BEAMS AND GRADE BEAMS.

COVERAGE MUST BE MAINTAINED. IF SOFFIT IS TO BE GROUND, PLASTIC DIPPED/COATED

- 6. BEAMS: PROVIDE (2) #4 CARRYING BARS CONTINUOUS IN TOP OF ALL BEAMS, UNO 7. SPLICES: CONTINUOUS REINFORCING BARS SHALL BE PROVIDED WITH TENSION LAPS AT ALL
- SPLICES, U.N.O., INCLUDING CORNER BARS. 8. COVER FOR PROTECTION TYPICAL, U.N.O.:
- A. UNFORMED SURFACE IN CONTACT WITH GROUND 3" B. FORMED SURFACE IN CONTACT WITH GROUND OR EXPOSED TO THE ELEMENTS - 2.5"
- C. BEAMS & GIRDERS 2 1/2"
- D. COLUMN TIES, BEAM TIES & STIRRUPS 2 1/2" E. IN ALL CASES NOT LESS THAN THE DIAMETER OF THE BAR.
- F. HOOKS INDICATED ARE ACI/CRSI STANDARD 90° OR 180° HOOKS. BAR LENGTHS SHOWN ARE OUT-TO-OUT AND DO NOT INCLUDE HOOK LENGTH. G. PROVIDE HOOKS ON ALL TOP BARS IN SLABS AND BEAMS TYPICAL AT DISCONTINUOUS ENDS.
- E. EMBEDDED PIPES OR CONDUIT. MAXIMUM DIAMETER -1/3 X SLAB OR WALL THICKNESS, SPACED MINIMUM OF 3 TIMES DIAMETER ON CENTER.

F. CURING AND PROTECTION: SEE SPECS.

- 1. STRIP CAST WITH CONTROL/CONSTRUCTION JOINTS TO ALIGN WITH COLUMN CENTERLINES AND/OR AT 15' O.C. MAX.
- 2. CONTROL JOINTS MADE BY ZIPSTRIP BY GREENSTREAK OR EQUAL. CONSTRUCTION JOINTS DETAILS SEE PLANS. (JOINTS MAY BE SAWED WITH ENGINEER'S APPROVAL AFTER REVIEW OF CONCRETE MIX DESIGN POUR SEQUENCE AND SAWING SCHEDULE.)
- G. SHOP DRAWINGS: SUBMIT REBAR SHOP DRAWINGS. SEE SPECS.

SPECIAL INSPECTIONS

- THE FOLLOWING ARE REQUIRED PER THE 2003 MICHIGAN BUILDING CODE, SECTION 1704. CONCRETE CONSTRUCTION:
- 1. PERIODIC INSPECTION OF REINFORCING STEEL IN FOOTINGS, GRADE BEAMS, WALLS
- 2. CONTINUOUS INSPECTION OF BOLTS TO BE INSTALLED IN CONCRETE (PRIOR TO AND DURING PLACEMENT OF CONCRETE).
- 3. PERIODIC VERIFICATION OF DESIGN MIX.
- 4. CONTINUOUS SAMPLING FOR STRENGTH TESTS, SLUMP AND AIR CONTENT AND TEMPERATURE TESTS FOR CAST-IN-PLACE CONCRETE.
- 5. PERIODIC INSPECTION FOR MAINTENANCE OF SPECIFIED CURING TEMPERATURES AND TECHNIQUES.

STEEL CONSTRUCTION:

- 1. PERIODIC VERIFICATION OF HIGH-STRENGTH BOLTS, NUTS AND MANUFACTURER'S CERTIFICATE OF COMPLIANCE.
- 2. PERIODIC INSPECTION OF BEARING TYPE BOLTED CONNECTIONS. CONTINUOUS INSPECTION OF SLIP-CRITICAL BOLTED CONNECTIONS.
- 3. CONTINUOUS INSPECTION OF COMPLETE AND PARTIAL PENETRATIONS GROOVE WELDS, MULTI-PASS FILLET WELDS, AND SINGLE-PASS FILLET WELDS > \(\frac{1}{6} \).
- 4. PERIODIC INSPECTION OF SINGLE-PASS FILLET WELDS < 1/3/6", AND FLOOR AND
- DECK WELDS. 5. PERIODIC INSPECTION OF STEEL FRAME JOINT DETAILS FOR COMPLIANCE WITH
- APPROVED CONSTRUCTION DOCUMENTS. MASONRY CONSTRUCTION:
- 1. LEVEL 2 SPECIAL INSPECTION AS DELINEATED IN TABLE 1704.5.3 OF THE INTERNATIONAL BUILDING CODE.

\triangle				
\triangle				
A	ISSUED FOR BID		02/13/07	DEN
\triangle	ISSUED TO MDEQ		1/09/07	DEN
REV	DESCRIPTION	BY	DATE	CHK'D





CHECKED CDC SCALE 1/8" = 1'-0" | CADD DATE 1/17/2007 10:36 AM PART P:\142-17450-07-001\CAD\142-17450-07-001\A\FLOORPLAN.DWG


PSC ENVIRONMENTAL SERVICES 515 LYCASTE DETROIT, MI DETROIT FACILITY REBUILD


STRUCTURAL CONTAINER MANAGEMENT BLDG. PARTIAL FOUNDATION PLAN


S**-**1















JOB PSC ENVIRONMENTAL SERVICES SHEET NO. SUP AT SUBJECT LAB/OFF SUPPLEMENTAL DWGS FILE NO.

COMPUTED BY BTC DATE 2/13/07 CHK BY DATE






JOB_PSC_ENVIRONMETVTAL SETZULCES SHEET NO. SUP A 2 SUBJECT_LAB/OFF SUPPLEMENTAL DWS FILE NO. COMPUTED BY BTC DATE 2/13/07 CHK. BY DATE



WALL SECTION SCALE: 3/4"=1'-0"









JOB	85C	BNVI	RONIN	イミンドバし	SERVIA	SHEET NO.	SUP	A4
				LONGONT				
СОМРИТ	TED BY 📙	<i>10</i> d	ATE 2/	13/07 CHI	K. BY	DATE		

SOME: 18" -1-02






Confidential Material Redacted


CT	AWSON Tank	CLAV	ISON	TANE	< C(MPANY
	PHILIP SERVICE DETROIT, MI LIP SERVICE ROIT, MI				2004	CATE:
SCALD Y	/P* = 12* 8-07	APPROVED BY	DRAWN MY	J GROH		PROSET &
	DESCRIPTION:	6,000 GAL VE				09507


CMB2 and QAQC Drawings 2022


CMB2 and QAQC Drawings 2022

DRAWING NUMBER	DRAWING DESCRIPTION
GA-01	General Arrangement - Site Layout
GA-02	General Arrangement -QA/QC PEMB Building Addition
GA-03	General Arrangement - QA/QC PEMB Building Addition Elevations
GA-04	QA/QC PEMB Building Addition Elevations
GA-05	General Arrangement - Proposed TS4/CMB2 PEMB Building
GA-06	General Arrangement - Proposed TS4/CMB2 PEMB Building Elevations
GA-07	Proposed TS4/CMB2 PEMB Building Elevations
GA-08	Rendering - North West
GA-09	Rendering - North
GA-10	Rendering - South East
GA-11	Rendering - North East










FILE NAM 46:56 PM	D DMH2 MBI XXX 6/8/22 ISSUE FOR CLIENT REVIEW	CLIENT	1/24/22 2/18/22 3/16/22 6/8/22	DADD	Project Office: BARR ENGINEERING COMPANY 4300 MARKETPOINTE DRIVE	Scale Date Drawn	AS SHOWN 1/12/2022 DMH2	CLEAN EARTH, LLC	CLEAN EARTH, LLC DETRIOT, MICHIGAN	BARR PROJECT NO. 22821113. CLIENT PROJECT NO.	
NTRAL 022 3:	C DMH2 MBI XXX 3/16/22 ISSUE FOR CLIENT REVIEW B DMH2 MBI XXX 2/18/22 ISSUE FOR CLIENT REVIEW			DARK Composeto Hondayustare:	MINNEAPOLIS, MN 55435	Checked	MBI MBI/DMH2	DETROIT, MICHIGAN	GENERAL ARRANGEMENT	DWG NO.	REV NO
<cen< td=""><td>A DMH2 MBI XXX 1/21/22 ISSUE FOR CLIENT REVIEW NO. BY CHK APP DATE REVISION DESCRIPTION</td><td>RELEASE TO/FOR</td><td>DATE RELEASED</td><td>Minneapolis, Minnesota Ph: 1-800-632-2277</td><td>Fax: (952) 832-2601 www.barr.com</td><td>Approved</td><td>MBI</td><td></td><td>SITE LAYOUT</td><td>GA-01</td><td>D</td></cen<>	A DMH2 MBI XXX 1/21/22 ISSUE FOR CLIENT REVIEW NO. BY CHK APP DATE REVISION DESCRIPTION	RELEASE TO/FOR	DATE RELEASED	Minneapolis, Minnesota Ph: 1-800-632-2277	Fax: (952) 832-2601 www.barr.com	Approved	MBI		SITE LAYOUT	GA-01	D



C DMH2 MBI XXX 3/16/22 ISSUE FOR CLIENT REVIEW B DMH2 MBI XXX 2/18/22 ISSUE FOR CLIENT REVIEW A DMH2 MBI XXX 1/21/22 ISSUE FOR CLIENT REVIEW NO. BY CHK APP DATE REVISION DESCRIPTION RELEASED linneapolis, Minnesota TO/FOR DATE RELEASED Ph: 1-800-632-2277


SUITE 200 Ph: 1-800-632-2277

Fax: (952) 832-2601

MBI MBI/DMH2 MBI


DETROIT, MICHIGAN


GENERAL ARRANGEMENT QA/QC PEMB BUILDING ADDTION **GA-02**





PRELIMINARY DRAFT- NOT FOR CONSTRUCTION

AS SHOWN CLEAN EARTH, LLC 22821113.00 BARR ENGINEERING COMPANY
4300 MARKETPOINTE DRIVE
SUITE 200
MINNEAPOLIS, MN 55435 1/12/2022 CLEAN EARTH, LLC DETRIOT, MICHIGAN D DMH2 MBI XXX 6/8/22 ISSUE FOR CLIENT REVIEW
C DMH2 MBI XXX 3/16/22 ISSUE FOR CLIENT REVIEW
B DMH2 MBI XXX 2/18/22 ISSUE FOR CLIENT REVIEW
A DMH2 MBI XXX 1/21/22 ISSUE FOR CLIENT REVIEW CLIENT PROJECT NO. DMH2 MBI DETROIT, MICHIGAN GENERAL ARRANGEMENT Ph: 1-800-632-2277 Fax: (952) 832-2601 www.barr.com MBI/DMH2 RELEASED TO/FOR QA/QC PEMB BUILDING ADDITION ELEVATIONS Minneapolis, Minnesota Ph: 1-800-632-2277 GA-03 NO. BY CHK APP DATE REVISION DESCRIPTION MBI DATE RELEASED









3 ELEVATION: QA/QC PEMB BUILDING - FROM SOUTH

0 1 5 10 15 20

SCALE

Jedi-cad\Cad\Design\22821113 00\

	D14110	ME	1007	0/0/00	LOCALE FOR ALLENT RELATION
0	DMH2 DMH2		XXX	6/8/22 3/16/22	ISSUE FOR CLIENT REVIEW ISSUE FOR CLIENT REVIEW
	DMH2		XXX	2/18/22	ISSUE FOR CLIENT REVIEW
	DMH2		XXX	1/21/22	ISSUE FOR CLIENT REVIEW
NO.	BY	CHK	APP	DATE	REVISION DESCRIPTION


CLIENT	1/21/22	2/18/22	3/16/22	6/8/22		
					E	
						BARF
						-0 -0 00
RELEASED	Α	В	C	D		Corporate Headquarters: Minneapolis, Minnesota
TO/FOR			DATE	RELE	Ph: 1-800-632-2277	

	Project Office:	4
	BARR ENGINEERING COMPANY	I
	4300 MARKETPOINTE DRIVE SUITE 200	I
Z	MINNEAPOLIS, MN 55435	(
I.	Ph: 1-800-632-2277	[
	Fax: (952) 832-2601 www.barr.com	1

	Scale	
ANY	Date	1/12/2022
	Drawn	DMH2
	Checked	MBI
	Designed	MBI/DMH2
	Approved	MBI

CLEAN EARTH, LLC	
DETROIT, MICHIGAN	

	03/1	7/22		
CLEAN EARTH, LLC	BARR PROJECT NO 2282111			
DETRIOT, MICHIGAN	CLIENT PROJECT NO.			
QA/QC PEMB BUILDING ADDITION ELEVATIONS	DWG NO. GA-04	REV NO		



MINNEAPOLIS, MN 55435

Ph: 1-800-632-2277

Fax: (952) 832-2601

www.barr.com

linneapolis, Minnesota

Ph: 1-800-632-2277

RELEASED

TO/FOR

DATE RELEASED

MBI

MBI/DMH2

MBI

DETROIT, MICHIGAN

GENERAL ARRANGEMENT

PROPOSED TS4/CMB2 PEMB BUILDING


GA-05


B DMH2 MBI XXX 2/18/22 ISSUE FOR CLIENT REVIEW


A DMH2 MBI XXX 1/21/22 ISSUE FOR CLIENT REVIEW


REVISION DESCRIPTION

NO. BY CHK APP DATE











03/17/22

	CLIENT 1/21/22 2/18/22 3/16/22 6/8/22	Project Office: Scale BARR ENGINEERING COMPANY Date	1/12/2022		CLEAN EARTH, LLC	BARR PROJECT NO. 22821113.00
D DMH2 MBI XXX 6/8/22 ISSUE FOR CLIENT REVIEW		RAPP 4300 MARKETPOINTE DRIVE Drawn	DMH2	CLEAN EARTH, LLC	DETRIOT, MICHIGAN	CLIENT PROJECT NO.
C DMH2 MBI XXX 3/16/22 ISSUE FOR CLIENT REVIEW B DMH2 MBI XXX 2/18/22 ISSUE FOR CLIENT REVIEW		MINNEAPOLIS, MN 55435 Checked	MBI	DETROIT, MICHIGAN		DWG NO I PEV
A DMH2 MBI XXX 1/21/22 ISSUE FOR CLIENT REVIEW NO BY CHK APP DATE REVISION DESCRIPTION	RELEASED A B C D TO/FOR DATE RELEASED	Corporate Headquarters: Ph: 1-800-632-2277 Designed Minneapolis, Minnesota Fax: (952) 832-2601 Ph: 1-800-632-2277 www.barr.com Approved	MBI/DMH2 MBI		TS4/CMB2 PEMB BUILDING ELEVATIONS	GA-07





BARR ENGINEERING COMPANY
4300 MARKETPOINTE DRIVE
SUITE 200
MINNEAPOLIS, MN 55435 Ph: 1-800-632-2277 Fax: (952) 832-2601 www.barr.com


	Scale	AS SHOWN	1
۱Y	Date	1/12/2022	
	Drawn	KMK	
	Checked	MBI	
	Designed	MBI/DMH2	
	Approved	MBI	

CLEAN EARTH, LLC DETROIT, MICHIGAN

BARR PROJECT NO. 22821113.00 CLEAN EARTH, LLC DETRIOT, MICHIGAN

RENDERING - NORTH WEST

CLIENT PROJECT N	0.
DWG NO. GA-08	REV NO.



Project Office:

BARR ENGINEERING COMPANY
4300 MARKETPOINTE DRIVE
SUITE 200
MINNEAPOLIS, MN 55435

Corporate Headquarters:
Minneapolis, Minnesota
Ph: 1-800-632-2277
Fax: (952) 832-2601
www.barr.com

Scale AS SHOWN

Date 1/12/2022

Drawn KMK

Checked MBI

Designed MBI/DMH2

Approved MBI

CLEAN EARTH, LLC
DETROIT, MICHIGAN

CLEAN EARTH, LLC
DETRIOT, MICHIGAN

RENDERING - NORTH

BARR PROJECT NO.
22821113.00
CLIENT PROJECT NO.

DWG NO.
GA-09
D

_						
	D	DMH2	MBI	XXX	6/8/22	ISSUE FOR CLIENT REVIEW
	С	DMH2	MBI	XXX	3/16/22	ISSUE FOR CLIENT REVIEW
	В	DMH2	MBI	XXX	2/18/22	ISSUE FOR CLIENT REVIEW
	Α	DMH2	MBI	XXX	1/21/22	ISSUE FOR CLIENT REVIEW
N	10.	BY	CHK	APP	DATE	REVISION DESCRIPTION


Corporate Headquarters: Minneapolis, Minnesota Ph: 1-800-632-2277 RELEASED TO/FOR DATE RELEASED

BARR ENGINEERING COMPANY
4300 MARKETPOINTE DRIVE
SUITE 200
MINNEAPOLIS, MN 55435 Ph: 1-800-632-2277 Fax: (952) 832-2601 www.barr.com

	Scale	AS SHOWN	1
IY	Date	1/12/2022	1
	Drawn	KMK	1
	Checked	MBI	
	Designed	MBI/DMH2	1
	Approved	MBI	1

CLEAN EARTH, LLC DETROIT, MICHIGAN

CLEAN EARTH, LLC	BARR PROJECT NO. 22821113.00		
DETRIOT, MICHIGAN	CLIENT PROJECT NO.		
RENDERING - SOUTH EAST	DWG NO. GA-10	REV I	



Project Office:

BARR ENGINEERING COMPANY
4300 MARKETPOINTE DRIVE
SUITE 200
MINNEAPOLIS, MN 55435

Corporate Headquarters:
Minneapolis, Minnesota
Ph: 1-800-632-2277
Fax: (952) 832-2601
www.barr.com

Date 1/12/2022

Drawn Author

Checked Checker

Designed Designer

Approved Approver

CLEAN EARTH, LLC
DETROIT, MICHIGAN

CLEAN EARTH, LLC
DETRIOT, MICHIGAN

RENDERING - NORTH EAST

CLIENT PROJECT NO.
CLIENT PROJECT NO.

DWG NO.
REV N
GA-11
D

Volume II - Photos & Drawings, Volume III - Hydrogeologic

Hazardous Waste Management Facility Operating License Renewal Application

Petro-Chem Processing Group of Nortru, LLC (Petro-Chem) MID 980 615 298; Waste Data Systems Number 399102 421 Lycaste Street, Detroit, Michigan

Prepared for Petro-Chem Processing Group of Nortru, LLC (Petro-Chem)

June 2022

Proj. no. 22821113.05

Section 1

Hydrogeological Report (B3)

FORM EQP 5111 ATTACHMENT TEMPLATE B3 HYDROGEOLOGIC REPORT

The administrative rules promulgated pursuant to Part 111, Hazardous Waste Management, of Michigan's Natural Resources and Environmental Protection Act, 1994 PA 451, as amended (Act 451), R 299.9506, R 299.9508, and R 299.9612 and Title 40 of the Code of Federal Regulations (CFR) §§264.94, 264.95, 264.97, 264.98, 270.13(10)(I), and 270.14(b)(19) establish requirements for hydrogeologic reports for hazardous waste management facilities. All references to 40 CFR citations specified herein are adopted by reference in R 299.11003.

This license application template addresses requirements for a hydrogeologic report for the hazardous waste management units and the hazardous waste management facility for the Petro-Chem facility in Detroit, Michigan. This template includes hydrogeologic report requirements, waiver demonstrations, and alternative information requests for operating license applications. This hydrogeologic report supplies information to support the groundwater monitoring program, or groundwater monitoring waiver request, proposed and included in Template B5, Environmental Monitoring Programs.

Applicant for Operating License for Existing Facility: \boxtimes R 299.9506 hydrogeologic report A waiver for the hydrogeologic report is requested for one or more units Alternative information is proposed for information required in the hydrogeologic report for one or more units A waiver is requested for groundwater monitoring requirements for one or more units, and is included in Template B5 More than one box may be checked, if waivers or alternative information apply to some of the units at the facility. Applicant for Operating License for New, Altered, Enlarged, or Expanded Facility: R 299.9506 hydrogeologic report A waiver is requested for groundwater monitoring requirements for one or more units, and is included in Template B5 (B) Both boxes may be checked, if appropriate

(Check as appropriate)

This template is organized as follows:

B3.A B3.B	HYDROGEOI SITE HYDRO B3.B.1 B3.B.2 B3.B.3	GEOLOGY Summary of Eldentification Topographic B3.B.3(a) NB3.B.3(b) EB3.B.3(c) EB3.B.3(d)	Existing Information of Aquifers and Their Uses Map Waste Management Areas Property Boundaries Point of Compliance Groundwater Monitoring Wells Aquifer Information
			Extent of Contaminant Plume
	B3.B.4	Wells and Bo	rings within One Mile
	B3.B.5		Plume Description
B3.C			OR PROPOSED GROUNDWATER MONITORING PROGRAM
	B3.C.1		ernate Information
	B3.C.2		Sampling, and Testing
			Number and Location of Soil Borings
			Soil Sampling and Testing
			Soil Layer Evaluations
			Boring Log Information
		` '	Borehole Completion
	B3.C.3		Wells and Well Clusters
			Static Water Levels and Construction Details
			Groundwater Maps
		` '	Justification for Observation Well Locations
			Logs for Borings Completed as Observation Wells
B3.D			RING PROGRAM
			Groundwater Monitoring Program
B3.E			N REQUIREMENTS
	B3.E.1		il Boring Tests
	B3.E.2	•	o Define Bedrock
	B3.E.3		eotechnical Characteristics
	B3.E.4	Geologic Cro	
	B3.E.5	Water Budge	t Calculations

EPA 1992. *RCRA Groundwater Monitoring Draft Technical Guidance Document*. Document Number 530-R-93-001. November.

The original Hydrogeological Report was submitted in support of Petro-Chem's original RCRA Part B Permit Application with MDEQ, dated September 24, 1996. Additional information is provided in the 2007 Part 201 exposure pathways determination related to the 2006 fire and the 2016 Corrective Measures Study, prepared by Bureau Veritas North America, Inc and submitted to EGEL. Petro-Chem continually monitors groundwater and the most recent 2021 Petro-Chem Processing Group of Nortru, LLC Annual Groundwater Report was submitted to EGLE on February 28, 2022. Petro-Chem will provide an electronic copy of the 463-page 2021 annual groundwater monitoring report, other historic groundwater monitoring reports, the 201exposure pathway evaluation or the 2019 upon request.

B3.A HYDROGEOLOGIC REPORT WAIVER REQUEST

[R 299.9508(2)]

Historically, transfer areas into the tank systems and some container management activities occur outside. Therefore, the facility is not requesting a waiver from the hydrogeologic reporting requirements.

With the new proposed container management building and enclosure of the QAQC area, the container storage areas will be located inside a building that provides protection from precipitation and run-on/runoff and is designed and operated in accordance with R 299.9604. Tanks used to store hazardous waste are located outside in secondary containment areas. These tanks are designed and operated in accordance with R 299.9604. Precipitation which falls on the tanks is collected in the secondary treatment system and inspected/tested before being discharged under the facilities indirect NPDES discharge permit. If the water is impacted, it is managed as a hazardous waste. The facility does not operate any landfills, surface impoundments, waste piles or land treatment units.

The facility does not operate a landfill, surface impoundment, waste pile, or land treatment unit, all hazardous waste management activities take place inside or under a structure that provides protection from precipitation and run-on/run-off, and the unit is in compliance with the facility design and operating standards found in R 299.9604.

B3.B SITE HYDROGEOLOGY

[R 299.9506 (1)(a) through (g) and 40 CFR, Part 265, Subpart F, and §§270.13(l), 270.14(b)(19), and 264.97]

This section presents a summary of the Petro-Chem facility's unit-specific preapplication groundwater monitoring data, an identification of all aquifers, hydrogeologic information on topographic maps, and identification of any plumes of contamination.

B3.B.1 Summary of Existing Information

[R 299.9506(1)(a)]

The original Hydrogeological Report dated September 24, 1996 was submitted in support of Petro-Chem's original RCRA Part B Permit Application. The most recent 2021 Petro-Chem Processing Group of Nortru, LLC Annual Groundwater Report was submitted to EGLE on February 28, 2022 and is not included in this application. Petro-Chem will provide another copy of the 463-page 2021 annual groundwater monitoring report and other historic groundwater monitoring reports upon request. Additional information has been provided in the 2007 Part 201 exposure pathways determination related to the 2006 fire and the 2016 Corrective Measures Study, prepared by Bureau Veritas North America, Inc and submitted to EGEL November 17, 2016. Petro-Chem will provide electronic copies of these reports upon request.

B3.B.2 Identification of Aguifers and Their Uses

[R 299.9506(1)(b), (c), and (d)]

Section I. D thru K of the 1996 hydrogeologic report contain information on the aquifers and their uses. More current information is provided in the most recent 2021 Petro-Chem Processing Group of Nortru, LLC Annual Groundwater Report, which was submitted to EGLE on February 28, 2022.

Petro-Chem will provide another electronic copy of the 463-page 2021 annual groundwater monitoring report and other historic groundwater monitoring reports upon request.

B3.B.3 Topographic Map

[R 299.9506(1)(e)(i) through (v)]

Topographic maps, in accordance with 40 CFR §270.14(b)(19), are located in the Part A application in Volume I, Section 1. A topographic map is also included as a figure in Volume IV, Section 1 Figure B4.1 and Figure B4.2. This topographic map is at a scale of one inch equal to no more than 200 feet, showing a distance of 1000 feet around the facility perimeter. Additional topographical maps and maps with the information specified in B3.B.3 subsections are included in the groundwater monitoring reports. The most recent 2021 Petro-Chem Processing Group of Nortru, LLC Annual Groundwater Report was submitted to EGLE on February 28, 2022 and is not included in this application. Petro-Chem will provide another copy of the 463-page 2021 annual groundwater monitoring report and other historic groundwater monitoring reports upon request.

B3.B.3(a) Waste Management Area

[R 299.9506(1)(e)(i)]

A facility layout map, Figure 01, showing the locations of the waste management areas, property boundaries, points of compliance, and the location of groundwater monitoring wells has been included with the Part A application forms in Volume I, Section 1.

B3.B.3(b) Property Boundaries

[R 299.9506(1)(e)(ii)]

A facility layout map, Figure 01, showing the locations of the waste management areas, property boundaries, points of compliance, and the location of groundwater monitoring wells has been included with the Part A application forms in Volume I, Section 1.

B3.B.3(c) Point of Compliance

[R 299.9506(1)(e)(iii)]

A facility layout map, Figure 01, showing the locations of the waste management areas, property boundaries, points of compliance, and the location of groundwater monitoring wells has been included with the Part A application forms in Volume I, Section 1.

B3.B.3(d) Groundwater Monitoring Wells

[R 299.9506(1)(e)(iv)]

A facility layout map, Figure 01, showing the locations of the waste management areas, property boundaries, points of compliance, and the location of groundwater monitoring wells has been included with the Part A application forms in Volume I, Section 1.

B3.B.3(e) Aquifer Information

[R 299.9506(1)(e)(v)]

A topo map and maps with the information specified in B3.B.3(e) is included with the most recent 2021 Petro-Chem Processing Group of Nortru, LLC Annual Groundwater Report submitted to EGLE on February 28, 2022. Petro-Chem will provide a copy of the 463-page 2021 annual groundwater monitoring report and other historic groundwater monitoring reports upon request. A

monitoring well location and groundwater contour map has been provided in Volume IV, Section 2 Appendix B5.1 of this application. Additional information is located in the 1996 hydrogeologic report Sections I and II.

B3.B.3(f) Extent of Contaminant Plume

[R 299.9506(1)(g)(i)]

Information on the extent of contaminant plume is located in the 1996 hydrogeologic report Sections I. L. Information is provided in the most recent 2021 Petro-Chem Processing Group of Nortru, LLC Annual Groundwater Report was submitted to EGLE on February 28, 2022 application. Additional information has been provided in the 2007 Part 201 exposure pathways determination related to the 2006 fire and the 2016 Corrective Measures Study, prepared by Bureau Veritas North America, Inc and submitted to EGEL November 17, 2016. Petro-Chem will provide electronic copies of these reports upon request.

Wells and Borings Within One Mile [R 299.9506(1)(f)]

Data on wells located within a one-mile radius of the facility has been provided in Section I. B and C. in the 1996 hydrogeological report and as Figure I.1 in that report. Additional soil boring information is included in the most recent 2021 Petro-Chem Processing Group of Nortru, LLC Annual Groundwater Report submitted to EGLE on February 28, 2022. Petro-Chem will provide an electronic copy of the 463-page 2021 annual groundwater monitoring report and other historic groundwater monitoring reports upon request.

B3.B.5 Contaminant Plume Description

[R 299.9506(1)(g)]

Information on the extent of contaminant plume is located in the 1996 hydrogeologic report Sections I. L. The most recent 2021 Petro-Chem Processing Group of Nortru, LLC Annual Groundwater Report was submitted to EGLE on February 28, 2022. Additional information has been provided in the 2007 Part 201 exposure pathways determination related to the 2006 fire and the 2016 Corrective Measures Study, prepared by Bureau Veritas North America, Inc and submitted to EGEL November 17, 2016. Petro-Chem will provide electronic copies of these reports upon request.

B3.C ENGINEERING REPORT FOR PROPOSED GROUNDWATER MONITORING PROGRAM [R 299.9506(2) and (7)]

The groundwater monitoring program engineering report is included in Section III of the 1996 hydrogeological report. Additional information has been provided Volume I, Section 8 Form B2 and Volume III, Section 2, Form B5 as well as in the 2007 Part 201 exposure pathways determination related to the 2006 fire and the 2016 Corrective Measures Study, prepared by Bureau Veritas North America, Inc and submitted to EGEL November 17, 2016. Petro-Chem will provide electronic copies of these reports upon request.

B3.C.1 Waiver or Alternate Information Request [R 299.9506(7)]

	facility is not requesting a waiver for information required by R 299.9506(2) nor is the facility osing to provide alternative information.
	Waiver is requested for R 299.9506(2)
	Alternate information is substituted for information requirements in R 299.9506(2)
B3.C	S.2 Soil Borings, Sampling, and Testing [R 299.9506(2)(a)(i) through (vi)]

Soil boring, sampling, and testing information is discussed in Section II of the 1996 hydrogeological report. Boring, sampling and testing data and logs are located in the figures, tables and attachments to the 1996 report and are also provided in Volume IV, Section 1 Appendix B4.2 - 1.2 and 1.3.

The facility has also submitted the following reports to EGLE which contain information on soil borings, sampling and testing:

- RFI Report, Philip Environmental Services Division, Petro-Chem Processing Group Facility,
 421 Lycaste Street, Detroit, Michigan, dated February 16, 2011
- Amended Corrective Action Investigation Report, Petro-Chem Processing Group of Nortru, LLC, 421 Lycaste Street, Detroit, Michigan, dated November 20, 2015
- Corrective Measures Study Investigation Report, Stericycle Environmental Solutions, Inc., Petro-Chem Processing Group Facility, 421 Lycaste Street, Detroit, Michigan, dated May 13, 2016
- Corrective Measures Study, Stericycle Environmental Solutions, Inc., Petro-Chem Processing Group Facility, 421 Lycaste Street, Detroit 48214, Michigan, dated November 17, 2016

Copies of these reports will be provided upon request.

B3.C.2(a) Number and Location of Soil Borings [R 299.9506(2)(a)(i)]

Soil boring, sampling, and testing information is discussed in Section II of the 1996 hydrogeological report. Boring, sampling and testing data and logs are located in the figures, tables and attachments to the 1996 report and are also provided in Volume IV, Section 1 Appendix B4.2, Appendix 1.2 and 1.3. See section B3.C2 above for a list of additional reports with information on soil borings.

B3.C.2(b) Soil Sampling and Testing

[R 299.9506(2)(a)(ii) and R 299.9506(6)(a)}

Soil boring, sampling, and testing information is discussed in Section II of the 1996 hydrogeological report. Boring, sampling and testing data and logs are located in the figures, tables and attachments to the 1996 report and are also provided in Volume IV, Section 1 Appendix

B4.2, Appendix 1.2 and 1.3. See section B3.C2 above for a list of additional reports with information on soil borings.

The facility does not operate a landfill, surface impoundment, waste pile, or land treatment area. Soil sampling and testing information to meet requirements of R 299.9506(2)(a)(ii) is included in this section.

B3.C.2(c) Soil Layer Evaluations

[R 299.9506(2)(a)(iii) and R 299.9506(6)(b)]

Soil boring, sampling, and testing information is discussed in Section II of the 1996 hydrogeological report and report attachments. Additional reports are provided in Volume IV, Section 1 Appendix B4.2, Appendix 1.2 and 1.3. Section B3.C2 above lists additional more recent reports with information on soil borings.

The facility does not operate a landfill, surface impoundment, waste pile, or land treatment area. Soil layer evaluations are included to meet the requirements of R 299.9506(2)(a)(iii).
The <u>facility operates a</u> unit that is a landfill, surface impoundment, waste pile, or land treatment area. Soil layer evaluations have been included to meet the requirements of R 299.9506(2)(a)(iii) and R 299.9506(6)(b). (The facility is not required to conduct soil evaluates at the minimum 10-foot intervals.)

B3.C.2(d) Boring Log Information

[R 299.9506(2)(a)(iv) and (vi)]

Soil boring, sampling, and testing information is discussed in Section II of the 1996 hydrogeological report and report attachments. Additional reports are provided in Volume IV, Section 1 Appendix B4.2, Appendix 1.2 and 1.3. Section B3.C2 above lists additional more recent reports with information on soil borings.

B3.C.2(e) Borehole Completion

[R 299.9506(a)(2)(v)]

Soil boring, sampling, and testing information is discussed in Section II of the 1996 hydrogeological report and report attachments. Additional reports are provided in Volume IV, Section 1 Appendix B4.2, Appendix 1.2 and 1.3. Section B3.C2 above lists additional more recent reports with information on soil borings.

B3.C.3 Observation Wells, and Well Clusters

[R 299.9506(2)(b) through (f)]

Observation wells and well cluster information is discussed in Section II of the 1996 hydrogeological report.

The facility has also submitted the following reports to EGLE which contain information on observation wells:

RFI Report, Philip Environmental Services Division, Petro-Chem Processing Group Facility,
 421 Lycaste Street, Detroit, Michigan, dated February 16, 2011

- Amended Corrective Action Investigation Report, Petro-Chem Processing Group of Nortru, LLC, 421 Lycaste Street, Detroit, Michigan, dated November 20, 2015
- Corrective Measures Study Investigation Report, Stericycle Environmental Solutions, Inc., Petro-Chem Processing Group Facility, 421 Lycaste Street, Detroit, Michigan, dated May 13, 2016
- Corrective Measures Study, Stericycle Environmental Solutions, Inc., Petro-Chem Processing Group Facility, 421 Lycaste Street, Detroit 48214, Michigan, dated November 17, 2016

B3.C.3(a) Static Water Levels, and Construction Details [R 299.9506(2)(b)]

Soil boring, sampling, and testing information is discussed in Section II of the 1996 hydrogeological report and report attachments. Additional reports are provided in Volume IV, Section 1 Appendix B4.2, Appendix 1.2 and 1.3. Section B3.C2 above lists additional more recent reports with information on soil borings.

B3.C.3(b) Groundwater Maps

[R 299.9506(2)(c) and (d)]

Soil boring, sampling, and testing information is discussed in Section II of the 1996 hydrogeological report. Ground water data is provided in the figures, tables and attachments to the 1996 report and the annual monitoring reports. The most recent 2021 Petro-Chem Processing Group of Nortru, LLC Annual Groundwater Report was submitted to EGLE on February 28, 2022. Petro-Chem will provide a copy of the 2021 annual groundwater monitoring report and other historic groundwater monitoring reports upon request. A groundwater contour map has been provided in Volume IV, Section 2, Appendix B5.1. See Section B3.C3 above for a list of additional reports with well information.

B3.C.3(c) Justification for Observation Well Locations [R 299.9506(2)(e)]

Observation wells, sampling, and testing information is discussed in Section II of the 1996 hydrogeological report. Ground water data is provided in the figures, tables and attachments to the 1996 report and the annual monitoring reports. The most recent 2021 Petro-Chem Processing Group of Nortru, LLC Annual Groundwater Report was submitted to EGLE on February 28, 2022. Petro-Chem will provide a copy of the 2021 annual groundwater monitoring report and other historic groundwater monitoring reports upon request. A ground water contour map has been provided in Volume IV, Section 2, Appendix B5.1 and a monitoring well location map has been provided in Volume IV, Section 1, Appendix B4.2, Figure B4.2. See section B3.C3 above for a list of additional reports with well information.

B3.C.3(d) Logs for Borings Completed as Observation Wells [R 299.9506(2)(f)]

Boring logs, sampling, and testing information for the observation wells is discussed in Section II of the 1996 hydrogeological report. Ground water data is provided in the figures, tables and attachments to the 1996 report and the annual monitoring reports. The most recent 2021 Petro-Chem Processing Group of Nortru, LLC Annual Groundwater Report was submitted to EGLE on February 28, 2022. Petro-Chem will provide a copy of the 2021 annual groundwater monitoring report and other historic groundwater monitoring reports upon request. A ground water contour

map has been provided in Volume IV, Section 2, Appendix B5.1 and a monitoring well location map has been provided in Volume IV, Section 1, Figure B4.2. See section B3.C3 above for a list of additional reports with well information.

B3.D GROUNDWATER MONITORING PROGRAM

[R 299.9506(3) through (5), R 299.9611(2)(b) and (3), R 299.9612, R 299.9629, and 40 CFR, Part 264, Subpart F, except 40 CFR §§264.94(a)(2) and (3), 264.94(b) and (c), 264.100, and 264.101]

The groundwater monitoring program is described in Section III of the 1996 hydrogeological report. Information on the current groundwater monitoring program has been provided in EGLE form B5 located Volume IV, Section 2 of this permit application. The most recent 2021 Petro-Chem Processing Group of Nortru, LLC Annual Groundwater Report was submitted to EGLE on February 28, 2022. Petro-Chem will provide a copy of the 2021 annual groundwater monitoring report and other historic groundwater monitoring reports upon request.

B3.E ADDITIONAL INFORMATION REQUIREMENTS

[R 299.9506(6)]

The facility units will not include a landfill, surface impoundment, waste pile, or land treatment unit. The requirements of R 299.9506(6) do not apply.
The [Hazardous Waste Unit] unit is a landfill, surface impoundment, waste pile, or land treatment unit. Additional information has been included to address requirements necessary to determine site suitability and facility design.

B3.E.1 Additional Soil Boring Tests

[R 299.9506(6)(a) and (b)]

The facility units will not include a landfill, surface impoundment, waste pile, or land treatment units. The requirements of R 299.9506(6) do not apply.

B3.E.2 Soil Borings to Define Bedrock

[R 299.9506(6)(c)]

The facility units will not include a landfill, surface impoundment, waste pile, or land treatment units. The requirements of R 299.9506(6) do not apply.

B3.E.3 Additional Geotechnical Characteristics

[R 299.9506(6)(d)]

The facility units will not include a landfill, surface impoundment, waste pile, or land treatment units. The requirements of R 299.9506(6) do not apply.

B3.E.4 Geologic Cross Sections

[R 299.9506(6)(e)]

The facility units will not include a landfill, surface impoundment, waste pile, or land treatment units. The requirements of R 299.9506(6) do not apply.

B3.E.5 Water Budget Calculations

[R 299.9506(6)(f)]

The facility units will not include a landfill, surface impoundment, waste pile, or land treatment units. The requirements of R 299.9506(6) do not apply.