MATERIALS SOURCE GUIDE

January 2027



CONSTRUCTION FIELD SERVICES
DIVISION

If you require assistance accessing this information or require it in an alternative format, contact the Michigan Department of Transportation's (MDOT) Americans with Disabilities Act (ADA) coordinator at Michigan.gov/MDOT-ADA.

Foreword

This manual has been prepared to give information and guidance to personnel associated with sampling, testing and inspection of materials used in Michigan Department of Transportation projects. Its purpose is to supplement the Materials Quality Assurance Procedures (MQAP) Manual, Hot Mix Asphalt (HMA) Production Manual, Procedures for Aggregate Inspection, Density Testing and Inspection Manual, and the Michigan Construction Manual to standardize procedures and assure adequate, uniform quality control.

Buy America certification is required for all iron/steel, manufactured products, and construction materials as defined in the contract. Please review the Special Provision for Domestic Materials, 20SP105(C) or Special Provision for Domestic Materials, Multiple Contracts Under National Environmental Policy Act Decision, 20SP105(D) available under the heading Supplemental Specifications and Special Provisions, Special Provisions – Frequently Used 2020 here.

For copies of the most recent Materials Source Guide you can:

Download from the internet at web address:

https://www.michigan.gov/mdot/Business/Construction/Materials-Source-Guide

Or Navigate by:

www.michigan.gov/mdot
\
Business
\
Construction
\
2020 Standard Specifications and Reference Publications
\
Materials Source Guide

Periodically check the website for updates to the Materials Source Guide. Updated guides can be downloaded and printed.

Table of Contents

Title	Page
Definitions	5
Index (In reference to the Materials Acceptance Requirements Table)	12
Materials Acceptance Requirements, including Special Instructions, copied from the MDOT Materials Quality Assurance Procedures Manual Chapter 6	29
Approved Suppliers List	76
Approved Manufacturers List	80
Qualified Products List	93
Selecting and Shipping Samples	128
Appendix	
Visual Inspection Items by Quantity - Alphabetical	130
Visual Inspection Items by Quantity - by Specification Number	132

This manual is in accordance with the 2020 Standard Specifications for Construction.

Definitions
(References to the Materials Quality Assurance Procedures Manual-MQAP)

Basis of Acceptance: Refers to the method by which materials incorporated into MDOT projects are accepted. Below is a list of all the current Basis of Acceptance methods used by MDOT for acceptance of materials.

- Visual Inspection (VI): (See MQAP Section 1.06) Materials which may be visually inspected by MDOT personnel for acceptance or rejection. When a maximum VI limit is given for materials with another specified basis of acceptance, materials may be accepted by VI up to maximum VI quantities as indicated for that material, per item, per contract. (NOTE: All materials should be visually inspected prior to incorporation into the job without quantity limit, and may be rejected on that basis even though material may be acceptable on another basis.)

    - Qualified Product List (QPL): (See MQAP Section 5.01) Products that have been tested and/or evaluated by MDOT and found to meet performance and/or other specification requirements. A Qualified Products List (QPL) of these products is maintained within this document. All QPL materials must be documented per Section 5.01 of the MQAP.

- General Certification (Gen Cert): (See MQAP Section 2.01) When this certification is specified as the basis of acceptance in the contract documents, it must be provided in accordance with Section 2.01 of the MQAP. A general certification must include a general description of the material(s), a list of the applicable specifications (ASTM, AASHTO, MDOT or other designations as appropriate), and a statement that the material(s) conforms to these specifications.

- Test Data Certification (Test Data Cert): (See MQAP Section 2.01) When this certification is specified as the basis of acceptance in the Materials Acceptance Requirements Table, in addition to the requirements of a General Certification, the certification must also include laboratory test report(s) for samples obtained from the same lot(s), batch, heat, etc. of material represented by the certification and tested according to applicable specifications (ASTM, AASHTO, MDOT).

- Approved Manufacturer (Appr Mfr): (See MQAP Section 2.02) A manufacturer who has submitted quality control documentation and/or material samples, and has been given approval status to certify specific material(s). General Certification per the requirements of Section 2.01 of the MQAP must accompany all Approved Manufacturer shipments to either an Approved Supplier location or the MDOT project site. Strict adherence to the requirements for Certification Documentation and Distribution is required of all Approved Manufacturers.

    - Approved Supplier: (See MQAP Section 2.02) When Approved Manufacturer is specified as the basis of acceptance in the contract documents, the material must be supplied by the manufacturer or, without modification to the material, by an Approved Supplier. An Approved Supplier must recertify Approved Manufacturer material(s). Strict adherence to the requirements for Certification Documentation and Distribution is required of all Approved Suppliers for the recertification of material(s). All original Approved Manufacturer General Certification(s) must accompany the material(s) shipment to the MDOT project site. When Approved Manufacturer is specified, a supplier may not distribute or recertify material(s) unless they have been granted Approved Supplier status.

- Special Provision: Revisions and additions to the Standard and Supplemental Specifications applicable to an individual project. Special Provisions have been reviewed and approved for use by MDOT. Materials acceptance may be defined by these documents included in the project proposals.

- Fabrication Inspection (Fabrication Inspection): Materials subjected to Fabrication Inspection are those that are typically manufactured offsite and shipped to the project. Refer to the proper subsection of the Structural Fabrication Quality Manual (SFQM) to find the requirements of the various Fabrication Inspections currently performed by MDOT.

- Acceptance Testing (Test): Sampling and testing of a material to determine compliance with specification requirements prior to incorporation into the project. Acceptance testing is the required basis of acceptance for some materials, as indicated in the contract documents, but may be applied to all materials regardless of the basis of acceptance.

Other Definitions

Manufacturer: A producer or fabricator of materials with control over the quality, workmanship and handling of material.

Supplier: A supplier has no control, other than through careful handling, over the quality and workmanship of material.

Certification Documentation
(See MQAP Section 2.01)

Where more than one piece of paper is included in the certification document, all pages must be numbered (__ of __)and include Contract I.D. in order to reunite them should they become separated.

Stencil, stamp, or otherwise mark all certified material prior to delivery to a supplier or project. This mark must identify the AASHTO, ASTM, or MDOT specification that the material meets, to allow the material to be recognized and checked against the certification document.

General Certification – This documentation must consist of all of the following:

- Company name, address and contact information.
- Date the certification was produced.
- Contract number (Control Section/Job Number).
- Name of contractor.
- If material is certified by a supplier or Contractor, the manufacturer's name must be included on the certification.
- A list of all applicable specifications (ASTM, AASHTO, MDOT or other designations as appropriate) which the material is certified to meet.
- Any applicable specification modifier such as class, grade, type, etc.
- Name of material (MDOT designation and Spec Number).
- Identification markings on shipment as required by the General Materials Certification Procedures, in the Quality Assurance Procedures Manual, Section 2.01.03.B.

- A statement, signed by a responsible representative of the manufacturer, supplier, or Contractor that the material represented by the certification meets all MDOT listed specification requirements.

Test Data Certification - When this certification is specified as the basis of acceptance in the Materials Acceptance Requirements Table, in addition to the requirements of a General Certification, the following information must also be included:

- Laboratory test report(s) for samples obtained from the lot(s) of material represented by the certification and tested according to applicable specifications (ASTM, AASHTO, MDOT).

Certification Distribution

All certification documents except those issued by Approved Manufacturers/Approved Suppliers must be distributed as follows: Submit to the Construction/Project Engineer. The Contractor is ultimately responsible for all materials documentation distribution to the Project Engineer's office.

Approved Manufacturer/Approved Supplier Certifications must follow the above distribution requirements with the addition of one a copy being mailed or emailed on the date of shipment to:

Michigan Department of Transportation
Construction Field Services Division
Materials Control
P.O. Box 30049
Lansing, Michigan 48909
Facsimile: (517) 322-5664
Email: MDOT-MaterialsControl@michigan.gov

Certifications and Recertification

Information required on certifications may vary from one material to the next. The following examples of certification documents are only provided for reference.

Materials Source List
(See MQAP Section 1.04)

A completed and signed Materials Source List (Form 501) is required project documentation, and required for payment of associated items of work. The Materials Source List is not a substitute for other required material quality control and quality assurance documentation. Prime contractors are responsible for accurate submission of the Materials Source Lists for all materials including their subcontractors.

If you require assistance accessing this information or require it in an alternative format, contact the Michigan Department of Transportation's (MDOT) Americans with Disabilities Act (ADA) coordinator at www.Michigan.gov/MDOT-ADA.

Michigan Department
of Transportation
0501 (03/2026)

Clear Form

MATERIALS SOURCE LIST

INSTRUCTIONS: Use the "Materials Source Guide" for material name and specification number. Enter "SP" for MDOT SPEC NUMBER for materials specified by special provision. To avoid delays, submit as soon as possible. No testing of materials will be conducted until the Engineer has been notified. Contractor to submit form to Engineer in ProjectWise Contractor Inbox. The Engineer will populate the remaining fields and distribute to Region/Transportation Service Center (TSC) Materials Supervisor.

Specification (SPEC), Certifications (CERTS), Visual Inspection (VI), Special Provision (SP), Fabrication Inspection (FI)

CONSTRUCTION/PROJECT ENGINEER:	CONTRACTOR:	CONTRACT ID:
PROJECT LOCATION:	FOR OFFICE USE ONLY (Owner Agency)	

MDOT SPEC NUMBER	MDOT MATERIAL/ PRODUCT NAME	TYPE/SIZE or CLASS	APPROX QUANTITY	SOURCE OF MATERIAL (NAME, ADDRESS, LOCATION, AGGREGATE SOURCE INVENTORY (ASI) NUMBER)	BASIS OF ACCEPTANCE					REMARKS/OTHER
					TEST	CERTS	VI	SP	FI	
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here
										Select one from list OR type here

☐ Check here if there are any revisions. Mark any revisions with an asterisk.

Additional Page

CONTRACTOR CONTACT NAME	CONTRACTOR CONTACT E-MAIL ADDRESS	PHONE NUMBER	DATE SUBMITTED
ENGINEER REPRESENTATIVE NAME	ENGINEER REPRESENTATIVE E-MAIL ADDRESS	PHONE NUMBER	DATE PROCESSED

Enter Your Company Letterhead/Logo Here
(Name, Address, Contact Info)

General Certification

Date: _____ Name of Contractor: _____

Control Section/Project #: _____ Project/Job Location: _____

We certify that the following described materials/products meet the specification requirements of the Michigan Department of Transportation, ASTM, or AASHTO.

MDOT Material Name: As described in the MDOT Materials Source Guide

MDOT Spec #: As described in the MDOT Materials Source Guide

Lot #, Heat OR Identification:

Class, Grade OR Type:

Size or Weight:

EXAMPLE

Signature of Company Representative

Printed Name of Company Representative

Title of Company Representative

Distribution: Submit to the Construction/Project Engineer

Enter Your Company Letterhead/Logo Here
(Name, Address, Contact Info)

Approved Supplier Recertification

Contract ID:
Control Section/Job #: _____ Date: _____

Contractor: _____

We certify that the following described material meets the specification requirements of the Michigan Department of Transportation for the above project and this material is certified by the manufacturers indicated below.

MDOT Material Name: As described in the MDOT Materials Source Guide
MDOT Spec #: As described in the MDOT Materials Source Guide
Manufacturer:
Lot, Heat or Identification:
Quantity:

MDOT Material Name: As described in the MDOT Materials Source Guide
MDOT Spec #: As described in the MDOT Materials Source Guide
Manufacturer:
Lot, Heat or Identification:
Quantity:

MDOT Material Name: As described in the MDOT Materials Source Guide
MDOT Spec #: As described in the MDOT Materials Source Guide
Manufacturer:
Lot, Heat or Identification:
Quantity:

All materials furnished on this certification are of domestic origin and are in compliance with the project Domestic Materials provisions.

Signature of Company Representative

Printed Name of Company Representative

Title of Company Representative

Distribution: Submit to the Construction/Project Engineer. Submit one additional Copy mailed or emailed to Construction Field Services Division, MDOT, P.O. BOX 30049, LANSING, MI 48909, or via email to MDOT-MaterialsControl@michigan.gov , complete on date of material Shipment.

EXAMPLE

Sampling Frequency: (If Required) Amount of material or number of items, as defined in the Materials Acceptance Requirements Table or other contract documents, which require a sample when submitting material to the Construction Field Services Division for testing.

Size of Sample: Minimum size of sample required for testing as defined in the Materials Acceptance Requirements Table or other contract documents.

Maximum VI Quantity: Maximum amount of material which can be accepted by visual inspection for each material, per item, per project.

Remarks: Special notes pertaining to individual materials.

Special Instructions: More detailed information pertaining to particular types of materials, and referenced in "Remarks" or listed in the Materials Source Guide.

Note: When the Basis of Acceptance is not “Test”, the sampling criteria provided may be used as guidance if the Project/Construction Engineer determines there may be a problem with the material and requests sampling and testing.

Alphabetical Index
To 2020 Material Specification Numbers
In The Material Acceptance Requirement Table

-A-

ABS Pipe....909.07A1
Abrasive, Low Dusting Blasting....715.02 & 716.02
Abutment Backfill....902
Adhesive Systems for Structural Anchors and Lane Ties....712.03J
Adhesive Systems for Dowel Bars & Tie Bars....603.03B2
Adjusting Rings for Manholes and Drainage Structures (Recycled Rubber)....909.01
Adjusting Rings for Manholes and Drainage Structures (Precast Concrete)....913.06
Admixture, Air Entraining....903.01
Admixture, Latex Emulsion for Concrete....903.03
Admixture, Mineral Filler, Bituminous Mixtures....902
Admixture, Pozzolanic (Fly Ash) for Concrete....901.07
Admixture, Water Reducing, Retarding, and/or Liquid Accelerators....903.02
Admixture for Expansive Grout Type E-1....1005.02C
Aggregates....902
Air Entraining Admixture....903.01
Aluminum Alloy Pipe (Corrugated)....909.05B
Aluminum Alloy Sheets, Corrugated....909.05B
Aluminum Alloy Structural Plate....Misc. #9
Aluminum Sheets for Signs....919.02A3
Anchor Bolts, Studs, Rods....908.14
Anchor Bolts and Nuts, Other Purposes....908.14D
Anchors, Concrete Adhesive Bonded (Resin)....712.03J
Anchors, Expansion....712.03K
Approved Manufacturers....Page 58
Approved Suppliers....Page 54
Arrow Bars, Lighted....922.07
Arrow Boards, Type C Solar Assist....922.07
Asphalt Binder....904.03A
Asphalt Emulsion, Bond Coat....904.03C
Asphalt Release Agents....501.02
Asphalt Rubber, Overband....914.04C
Assemblies, Load Transfer....914.07

-B-

Back-up Plates for Guardrail 908.11C
Backer Rod, Foam 914.04B
Backfill, Abutment 902
Band Clamps, Strain Pole 921.05A
Bar Chairs 905.03D
Barbed Wire 907.03B
Barricades 922.03E
Barrier Reflectors 922.04A
Barrier Reflectors, Temporary 922.04A
Bases, Precast Concrete 913.07
Baskets, Dowel, Load Transfer 914.07
Beam Guardrail 908.11A
Beam Plates, Sealant for Perimeter 713.02B
Bearings, Elastomeric 914.12A
Bent Tie Bars, Lane Ties 914.09
Biaxial Geogrid, Road Grade 910.06
Bituminized Fiber Joint Filler 914.03
Bituminized Fiberglass and Cotton Fabric ..... Misc. #14
Bituminous Materials (Asphalt Binder) 904.03A
Blasting Abrasive, Low Dusting ..... 715.02 & 716.02
Blasting Abrasive, Steel Grit 715.02
Block, Concrete 913.05
Bolts, Mechanical Expansion Anchors 914.10
Bolts, Adhesive Anchor Systems 914.10
Bolts, Anchor, Studs, Rods 908.14
Bolts, Anchor, Other Purposes 908.14D
Bolts, High Strength 906.07
Bond Release Agent, Concrete (Dowel Bars) 914.07A3
Bonded Anchors, Concrete Adhesive 712.03J
Brick, Clay and Sand Lime 913.03
Brick, Concrete 913.03C
Bridge Deck Drain Extensions, Fiberglass 909.08C
Bridge Railing, Base Plate and Post Elements 908.09A
Bridge Railing, Hardware 908.09C
Bridge Railing, Tube, Parapet 908.09B

Bridge Railing, Tube, Rectangle (Galvanized) 908.09A
Bridge Sign Connections 810.03O
Bushings for Pins and Link Plates 707.02

-C-
Cable, Electrical 918.03
Cable, Prestress Strand 905.07
Calcium Chloride 922.12A
Calcium Chloride Concrete Accelerators 903.04
Cantilever, Sign Support 919.07
Caps, Expansion for Dowel Bars 914.07C
Casing, Steel Pipe 909.05D
Casing, Foundation 919.10
Cast Iron Pipe ..... Misc. #2
Castings, Miscellaneous Metals (Manhole) 908
Catch Basins 908
Cedar Posts (Wood Fence) 912.07B
Cement 901
Certification Verification of Cement 901
Certification Verification of Expansive Grout 1005.02C
Chain Link Fence Fabric 907.04A
Chairs, Steel Reinforcement 905.03D
Chemical Fertilizer for Grass Seeding 917.09
Chemical Weed Sprays 917.15
Class A, B and F Bury Plastic Pipe 909.06
Clay Brick 913.03
Clay Pipe ..... Misc. #3
Closed-Cell Polyproylene Foam Joint Filler 914.03C
Coarse Aggregate 902
Coating for Dowel Bars 914.07A2
Coating for Rebar, Epoxy 905.03
Coating Systems for Steel Structures, Hangers Assemblies and End Diaphragms (Prime, Intermediate, Top) 915
Cobblestone 916.01A
Cold Applied Pipe Joint Sealer (Mastic) 909.09
Cold Plastic Pavement Marking, Permanent 811.03D4

Cold Plastic Pavement Marking, Temporary (Tape) 922.06A
Column Break-Away Sign Support 919.06
Compost 917.07
Compression Gasket 909.03
Concrete Adhesive System for Bonded Anchors (Resin) 712.03J
Concrete Barriers, Temporary 922.04
Concrete Barrier Reflectors 922.04A
Concrete Bases, Precast 913.07
Concrete Block 913.05
Concrete Brick 913.03C
Concrete End Sections, Precast 909.04E
Concrete Expansion Anchors 712.03K
Concrete Pipe, Reinforced and Non-Reinforced ..... 909.04A - C
Conduit, Electrical ..... 918.01, 918.01A, B, D, F
Conduit, Electrical (Polyethylene) ..... 918.01D & E
Cones, Traffic 922.03A
Contraction Baskets 914.07
Copper Sheet (Waterstop) 908.08
Corrugated Aluminum Alloy Pipe 909.05B
Corrugated Aluminum Alloy Sheets 909.05B
Corrugated Poly-Pipe, Culverts and Sewers 909.06
Corrugated Poly-Tubing, Underdrains 909.07B
Corrugated Plate, Structural ..... Misc. #8
Corrugated Steel Pipe 909.05A
Corrugated Steel Pipe (Polymer Coated) 909.05A1
Corrugated Steel Sheets 909.05A1
Cotton Fabric, Bituminized ..... Misc. #14
Coupling Bands 909.05A3
Cover, Sign 922.02D
Covers and Lids, Manholes 908
Crack Injection 914.06
Crack Treatment, HMA and Overband 914.04C
Culvert, Cast Iron ..... Misc. #2
Culverts, Class B 909.06
Curing Compound 903.06
Curtain, Turbidity 916.07

Cut-offs for Piling 906.05

-D-
Deck Drain Extensions, Bridge 909.08C
Deformed Steel Bars for End-of Pour Joint Devices 914.08
Delineator Posts, Flexible 919.03D
Delineator Posts, Steel 919.03D
Delineator Reflectors ..... 919.03A, B
Dense Graded Aggregate 902
Detectable Warning Surfaces 803.02B
Dimension (Sawed) Posts, Wood 912.08
Ditch Lining (Geotextile Blanket) 910.03A
Dowel Bar Grouting Systems 603.03B2
Dowel Bars for Load Transfer (Steel) 914.07
Dowel Baskets, Load Transfer 914.07
Downspouts, Bridge Deck 909.08A
Downspouts, Culvert 909.08B
Drain Pipe (Underdrain) ..... 909.07A, B
Drainage Marker Post 909.10
Drainage Casting, Misc. Metals 908
Drainage Structures, Precast Reinforced Concrete 913.06
Drainage Structure Adjusting Rings, Precast Concrete 913.06
Ductile Iron Castings 908.05
Ductile Iron Pipe ..... Misc. #2
Dust Palliative, Calcium Chloride 922.12A

-E-
Edge Drain (Tubing) 909.07B
Elastomeric Bearings 914.12A
Elastomeric Leveling Pads 914.12B
Electrical Cable 918.03
Electrical Conduit (Galvanized Steel and Non-Metallic) 918.01A
Electrical Conduit (Polyethylene) 918.01D
Electrical Conduit (Polyvinyl Chloride) 918.01B
Electrical Traffic Control Devices 921.03
Embedded, Galvanic Anodes 712.03Y

Emulsified Asphalt 904.03C
Emulsion, Latex Admixture for Concrete 903.03
End Sections, Grate, for Culverts 401.03E
End Sections, Slope, Steel 909.05C
End Sections, Steel 909.05C
End Sections, Precast Concrete 909.04E
End Sections, Guardrail 908.11A
End-of-Pour Joint Devices/Deformed Steel Bars 914.08
Epoxies for Adhesive Systems 712.03J
Epoxy Binder, Joint Spall Repair 914.05
Epoxy Coated Dowel Bars 914.07A
Epoxy Coated Steel Reinforcing Bars 905.03
Epoxy Coating for Bar Reinforcement 905.03
Epoxy Coating for Dowel Bars 914.07A2
Epoxy Mastic 712.03D
Epoxy Resin Adhesive for Crack Injection 914.06
Excelsior Mulch Blankets 917.14B
Expansion Anchors, Structure 712.03K
Expansion Baskets 914.07
Expansion Caps for Dowel Bars 914.07C
Expansion Joint Devices, Bridge 706.03K4
Expansive Grout Type E-1, Admixture 1005.02C
External Type Gasket for Pipe 909.03
Extruded Aluminum Sections for Sign Panels 919.02A1

-F-

Fabric, Bituminous, Cotton, Fiberglass ..... Misc. #14
Fabric, Filter, for Underdrain (Geotextile Blanket) 910.03A
Fabric for Chain Link Fence 907.04A
Fabric for Woven Wire Fence 907.03A
Fabric Reinforcement, Welded Steel Wire (Mesh) 905.06
Fast Set Patching, Hydraulic Mortar 1006
Fence, High Tensile Wire 907.05A
Fence, Horizontal Rail 907.04C
Fence Fabric, Chain Link 907.04A
Fence Fabric, Woven Wire 907.03A

Fence Gates, Chain Link 907.04D
Fence Gates, Woven Wire 907.03F
Fence Pedestrian, Posts and Rail 907.04C
Fence Protective 907.06
Fence Posts, Steel 907.04C
Fence Posts, Wood ..... (907.03E & 907.05B) 912.07B
Fertilizer 917.09
Fiber Joint Filler, Bituminized 914.03
Fiberglass Fabric ..... Misc. #14
Filter Bags, Geotextile Blanket 910.03A
Filter Fabric for Wrapped Underdrain (Knitted Sock) 910.03A
Fine Aggregate 902
Flexible Metal Conduit 918.01
Fly Ash, Mineral Filler for Bituminous Mixtures 902
Fly Ash, Pozzolanic Admixture for Concrete 901.07
Foam Backer Rod 914.04B
Foundation Piling 906.05

-G-

Galvanic Anodes, Embedded 712.03Y
Galvanized Bridge Tube Railing 908.09B
Galvanized Conduit, Electrical 918.01A
Galvanized Slotted Drain Pipe ..... Misc. #5
Galvanized Steel Sheets, Corrugated 909.05A1
Gasket, Compression 909.03
Gasket, External Type for Pipe 909.03
Geocomposite Wall Joint Drain 910.05B
Geogrid, Biaxial Road Grade 910.06
Geotextile Blanket 910.03A
Geotextile Pipe Wrap Liner 910.03A
Geotextile Rip Rap Liner 910.03B
Geotextile Separator 910.03C
Geotextile, Stabilization 910.03D
Glare Screen 804.01
Glass Beads, Standard 920.02B
Granular Material 902

Grass Seed 917.11
Gray Iron Castings 908.05
Grit, Steel, Blasting Abrasive 715.02
Grounding Rods 918.02C
Grounding System 918.02
Grout Under Masonry Plates 712.03X
Grout, For Full-Depth Concrete Pavement Repairs 603.03B2
Grouting Cracks by Pressure Injection, Intrusion 914.06
Grouts and Mortars ..... 1005.02A, B, C
Guar Gum Base Adhesive, Mulch Binder 917.14C
Guardrail Anchorage, Bridge, Beam Elements, End Sections, Shoes and Departing End Terminals 908.11A
Guardrail Approach Terminals 908.11A
Guardrail Hardware 908.11B
Guardrail Offset Blocks, Recycled Plastic or Rubber 912.08Q
Guardrail Posts and Blocks, Wood (Dimension Sawed) 912.08
Guardrail Posts for Beam Guardrail, Steel 908.12
Guardrail Reflectorized Washer 908.13
Guardrail Steel Beam Elements 908.11A
Guide Posts 912.07B
Guy Wire, Electrical 918.11A

-H-

H Piling 906.05
Handholes, Precast 918.06
Hanger Assemblies, Coating Systems 915
Hardware, Fence 907.04E
Hardware, Guardrail 908.11B
Hardware, Sign 919.02C
Headwall, Precast Concrete 401.03E
Herbicide, Spray 917.15
High Strength Steel Bolts, Nuts and Washers 906.07
High Tensile Fence Wire 907.05A
Highway Lighting Materials (Luminaires) 918.09
Hollow Load and Non-Load Bearing Block (Concrete) 913.05
Hot Mixed Asphalt (HMA) Crack Treatment and Overband 914.04C

Hot-Poured Joint and Crack Sealant 914.04A
Hydraulic Anchor Systems 712.03J

-I-

Insulation, Blankets and Polystyrene ..... 903.07C & D
Interim Linseed Oil Curing Compound 903.07A
Iron Pipe, Cast and Ductile Iron and Fittings ..... Misc. #2

-J-

Jacked-In-Place Steel Pipe 909.05D
Joint Filler 914.03, 914.03B, 914.03C
Joint Filler, Fiber (Bituminized) 914.03
Joint and Crack Sealant, Hot-Poured 914.04A
Joint Sealer, Pipe Gaskets (O-Ring) 909.03
Joint Sealer for Pipe, Cold Applied (Mastic) 909.09
Joint Spall Repair Materials 914.05
Joint Wall Drain, Geocomposite 910.05B

-K-

-L-

Lane Ties 914.09
Latex Base Adhesive for Mulch 917.14C
Latex Emulsion Admixture for Concrete 903.03
Lead Sheet (Waterstop) 908.07
Light Standards 918.08
Lighted Arrows 922.07A
Limestone Dust, Bituminous Mineral Filler 902
Liner for Riprap 910.03B
Link Plates for Steel Bridge Construction 906.08
Linseed Oil Interim Curing Compound 903.07A
Liquid Asphalt, MC & RC-250 ..... 904.03B
Load Transfer, Dowel Bars (Steel) 914.07
Load Transfer Assemblies, Dowel Baskets 914.07
Load-Bearing Block (Concrete) 913.05
Loop Sealant, Traffic 921.08B

Low Dusting Blasting Abrasive ..... 715.02 & 716.02
Lumber, Structural 912.05
Luminaires 918.09

-M-
Mail Box Posts 912.07B
Malleable Iron Castings 908.03
Manhole, Block 913.05
Manhole, Brick 913.03C
Manhole Castings 908
Manhole Covers and Lids 908
Marking Tape, Cold Plastic, Permanent 811.03D4
Marking Tape, Temporary Lane 922.06A
Masonry Plate, Grout 712.03X
Masonry Units, Precast Drainage 913.06
Mastic (Cold Applied Joint Sealer for Pipe) 909.09
Mechanical Reinforcement Splicing 712.03L
Membrane, Preformed Waterproofing 914.11
Membrane Curing Compound 903.06
Mesh Reinforcement (Pavement) 905.06
Metal End Sections 909.05C
Metallic Waterstop, Sheet Copper 908.08
Metallic Waterstop, Sheet Lead 908.07
Mineral Filler for Bituminous Mixtures 902
Mortars and Grouts ..... 1005.02A, B, C
Mulch Anchoring 917.14C
Mulch Binder, Tackifiers, Non-Asphalt Emulsion 917.14C
Mulch Blanket, Excelsior and Straw 917.14B2
Mulch Blanket, High Velocity 917.14B1
Mulch Blanket, Straw 917.14B2
Mulching Materials for Nursery Stock 917.13

-N-
Non-Load Bearing Block 913.05
Non-Reinforced Concrete Pipe 909.04C
Non-Shrink Mortars and Grouts, Type H1 (Non-Metallic) 1005.02B

Nursery Stock (Trees, Bushes) 917.03

-O-

O-Ring, Compression Gasket..... 909.03
Open-Graded Aggregate..... 902
Outlet, Drainage Pipe (Underdrain) ..... 909.07C1, 2, & 3
Outlet Ending (Underdrain) 404.02C
Overband 914.04C

-P-

PVC Sanitary Sewer Pipe 909.06
Paint for Coating Existing Steel Structures (Prime, Intermediate, Top)..... 915
Paint for Pavement Marking 811.03D
Patching, Fast Set Hydraulic Mortar 1006
Pavement Lane Ties 914.09
Pavement Marking Cover (Temporary)..... 922.06C
Pavement Marking, Standard Glass Beads 920.02B
Pavement Marking, Modified Epoxy 811.03D8
Pavement Marking, Polyurea 811.03D7
Pavement Marking, Thermoplastic, Liquid..... 811.03D5
Pavement Marking, Thermoplastic, Sprayable 811.03D6
Pavement Marking, Thermoplastic, Preformed..... 811.03D9
Pavement Marking, Waterborne, Liquid, Paint..... 811.03D1
Pavement Marking Regular Dry Paint 811.03D3
Pavement Marking Tape, Cold Plastic..... 811.03D4
Pavement Marking Tape, Type R/NR..... 922.06A
Pavement Markers, Raised (Temporary)..... 922.06B
Pavement Reinforcement (Mesh)..... 905.06
Pavement Tie Bars..... 914.09
Penetrating Water Repellents..... 706.03S
Perforated Poly-Tubing, Underdrain 909.07B
Pile Points 906.05
Piling, H Piling and Special Sections 906.05
Piling, Steel Sheet..... 906.06
Piling, Steel Shells 906.05
Piling, Timber 912.06

Pipe, Cast and Ductile Iron ..... Misc. #2
Pipe, Clay ..... Misc. #3
Pipe, Concrete ..... 909.04A - C
Pipe, Corrugated Aluminum Alloy 909.05B
Pipe, Corrugated Polyethylene (CPE/HDPE) 909.06
Pipe, Corrugated Steel 909.05A
Pipe, Downspouts ..... 909.08A, B
Pipe, Gasket 909.03
Pipe, Plastic, Class A, B and F Bury 909.06
Pipe Joint Sealers 909.09
Pipe, Steel Casing 909.05D
Pipe, Steel Casing, Foundation 919.10
Pipe Wrap, Geotextile 910.03A
Plastic Drums 922.03
Plastic Guardrail Blocks 912.08Q
Plywood for Signs 919.02A2
Poles, Tower Lighting 918.10A
Polyethylene Pipe for Culverts and Sewers(CPE/HDPE) 909.06
Polyethylene Tubing for Underdrain 909.07B
Polymer Coated Corrugated Steel Pipe 909.05A1
Polystyrene, Insulation 903.07D
Polyvinyl Chloride Pipe (CPV/PVC) 909.06
Portable Signs 922.07C
Post Tensioning, Tendons 905.08
Posts, Delineator, Flexible 919.03D
Posts, Delineator, Steel 919.03D
Posts, Dimension Sawed (Wood) 912.08
Posts, Drainage Marker 909.10
Posts, Mailbox 912.07B
Posts, Signs, Steel 919.04
Posts, Wood for Fencing 912.07B
Posts, Wood Sign 912.08, 919.05
Posts for Chain Link Fence (Steel) 907.04C
Posts for Woven Wire Fence (Steel) 907.03D
Pozzolanic Admixture for Concrete (Fly Ash) 901.07
Precast Concrete Bases 913.07

Precast Concrete Box Sections 909.04D
Precast Concrete End Sections 909.04E
Precast Concrete 3 Sided or Arch Sections 909.04G
Precast Concrete Handholes 918.06
Precast Concrete Headwalls 401.03E
Precast Reinforced Concrete Drainage Structures 913.06
Precast Sumps 913.07
Preformed Waterproofing Membrane 914.11
Premixed Grouts and Mortars, Type H1 (Non-Metallic) 1005.02B
Prestress Strand for Concrete 905.07
Prestressed Concrete Beams 708.01
Protective Coating for Concrete, Water Repellent 706.03S
Protective Fence 907.06

-Q-

Qualified Products List ..... Page 68

-R-

R C 250, Liquid Asphalt Waterproofing Primer 904.03B
Railing, Bridge Tube Element (Galvanized) 908.09B
Raised Pavement Markers (Temporary) 922.06B
Recertifiers ..... Page 54
Recycled Plastic or Rubber Guardrail Offset Block 912.08Q
Recycled Rubber Adjusting Rings 909.01
Recycled Rubber Joint Filler 914.03B
Reflective Sheeting 919.02B1
Reflective Sheeting, Temporary Signs 922.02B
Reflectorized Washers, Guardrail 908.13
Reflectors, Delineator 919.03A, 919.03B
Reflectors, Concrete Barriers 922.04A
Reflectors, Concrete Barriers, Temporary 922.04A
Regular Dry Pavement Marking Paint 811.03D3
Reinforced Concrete Pipe 909.04A
Reinforcing Steel Bars 905.03
Release Agents, Asphalt 501.02
Retarding Admixtures 903.02

Rip Rap 916.01C
Road Grade Biaxial Geogrid 910.06
Rubber, Recycled, Joint Filler 914.03B
Rumble Strips, Temporary (Orange) 922.06D
Rustic Construction, Timber 912.09

-S-

Sand Lime Brick 913.03
Sawn Wood Posts and Blocks 912.08
Sealant for Perimeter of Beam Plates 713.02B
Sealer for Pipe Joints, Cold Applied (Mastic) 909.09
Seeding Mixtures 917.11
Selecting and Shipping Samples ..... Page 91
Separator, Geotextile 910.03C
Sewer Pipe, Concrete ..... 909.04A - C
Sewer Pipe, PVC Sanitary 909.06
Shear Developers (Studs) 906.09
Sheet Copper (Waterstop) 908.08
Sheet Lead (Waterstop) 908.07
Sheeting, Reflective 919.02B1
Sheeting, Reflective, Temporary Signs 922.02B
Shelf Life, Curing Compound (Linseed Oil Base) 903.07A
Shipping and Selecting Samples ..... Page 91
Shotcrete, Waterproofing 710.03D
Shredded Bark, Mulching Materials 917.13
Sign Hardware 919.02C
Sign Paddles 922.11
Sign Posts 919.04, 919.05
Sign Support, Cantilever 919.07
Sign Support, Truss 919.08
Signals, Electrical Traffic Control 921.03
Signs, Permanent 919.02
Signs, Portable 922.07C
Signs, Temporary, Prismatic 922.02
Signs, Temporary, Cover 922.02D
Signs, Temporary, Reflective Sheeting 922.02B

Silt Fence (full assembly) 916.02
Silt Fence Geotextile (fabric only) 910.04
Slag Cement 901.06
Sleeves, Steel for Guardrail 908.11C
Sleeves, Steel for Wood Sign Posts 919
Slope Paving Block 913.09
Slotted Drain Pipe, Galvanized ..... Misc. #5
Sod 917.12
Span Wire, Electrical 921.02
Splicing, Reinforcement (Mechanical) 712.03L
Sprays, Chemical (Weed Control) 917.15
Stabilization Geotextile 910.03D
Standard Mortars and Grouts 1005.02A
Steel Barbed Wire 907.03B
Steel Beam Guardrail Elements 908.11A
Steel Castings 908.04
Steel Grit Blasting Abrasive 715.02
Steel H Piling 906.05
Steel Pipe, Jacked-In-Place 909.05D
Steel Posts for Beam Guardrail 908.12
Steel Posts for Fence 907.03D, 907.04C
Steel Posts for Signs 919.04
Steel Reinforcing Bars 905.03
Steel Sheet, Corrugated Galvanized 909.05A1
Steel Sheet Piling 906.06
Steel Sleeves for Guardrail 908.11C
Steel Sleeves for Wood Sign Posts 919
Straight Tie Bars, Lane Ties 914.09
Strain Poles (Traffic Signal) 921.05
Strain Pole Band Clamps 921.05A
Strand for Prestressed Concrete 905.07
Straw Mulch Blankets 917.14B
Structural Plate for Pipe (Corrugated) ..... Misc. #8
Structural Steel 906.04
Structural Tile 913.08
Structural Timber and Lumber 912.05

Structure Expansion Anchors 712.03K
Stud Shear Developers 906.09
Subbase 902
Sumps, Precast 913.07

-T-

Tackifiers for Mulch 917.14C
Tape, Lane Marking, Temporary 922.06A
Temporary Concrete Barriers 922.04
Temporary Overlay and Chip Seal Markers 922.06B
Temporary Rumble Strips (Orange) 922.06D
Temporary Seal for Cracks Injection 914.06
Temporary Signs 922.02
Tendons for Post Tensioning 905.08
Tension Wire 907.04B
Thermoplastic Pavement Marking 811.03D5, 811.03D6
Tie Bar Grouting Systems 603.03B2
Tie Bars for Longitudinal Sawed Joints 914.09
Tile, Structural 913.08
Timber and Lumber, Structural 912.05
Timber Piling 912.06
Tower Lighting Units 918.10A
Traffic Cones 922.03A
Traffic Loop Sealant 921.08B
Treated Wood 912.05
Truss, Sign Support 919.08
Tube Railing, Galvanized 908.09B
Turbidity Curtain 916.07

-U-

Underdrain Outlet Endings 404.02C
Underdrain Pipe ..... 909.07A, B, C

-V-

Vests 922.11

-W-

Wall Joint Drain, Geocomposite 910.05A
Warning Flashers and Lights 922.07B
Washers, Reflectorized 908.13
Water 911
Water Main Materials 923
Water Reducing/Retarding Admixture 903.02
Water Repellent, Penetrating Sealer 706.03S
Waterproofing Membrane, Preformed 914.11
Waterproofing Primer, Liquid Asphalt, RC 250 ..... 904.03B
Waterstop (Metallic) 908.07, 908.08
Watertight Joints 909.03
Weed Spray (Herbicides) 917.15
Welded Wire Reinforcement (Mesh) 905.06
Wet Reflective Optics..... 920.02C
Wire, Electrical Cable 918.03
Wire, High Tensile Fence 907.05A
Wire, Rope 908.11B
Wire Mesh 905.06
Wood Fence Posts 912.07B
Wood Mulch/Chips 917.13
Wood Posts and Lath for Silt Fence 916.02
Wood Posts for Guardrail (Dimensioned Sawed) 912.08
Wood Posts for Signs 912.08, 919.05
Woven Wire Fence Materials 907.03
Wrap, Filter Fabric 910.03A

-X- -Y- -Z-

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
401.03E End Section Grate for Culverts	VI	-	-	-	See Standard Plans for Sizes.
401.03E Precast Concrete Headwalls	Gen Cert	-	-	-	24” or less. For larger than 24” construct per Section 706 of Standard Specifications.
404.02C Underdrain Outlet Endings	VI	-	-	-	See Standard Plans.
501.02 Asphalt, Release Agents	VI	-	-	-	
NOTE: Must be approved by the project engineer. No fuel or oil-based agents.					
603.03B2 Adhesive Systems for Grouting Dowel Bars and Tie Bars for Full-Depth Concrete Pavement Repairs	VI See Remark	-	-	-	Must be a Qualified Product (603.03B2).
Note: Use for grouting to existing concrete in the same direction of traffic in the same lane as the repair. For grouting lane ties (deformed bars positioned transverse to the direction of traffic located between traffic lanes) select from Adhesive Anchor Systems for Structural Anchors and Lane Ties (712.03J).					
706.03K4 Expansion Joint Devices for Bridges	See Remark	-	-	-	See project plans for list of approved devices and details.
706.03S Penetrating Water Repellent (Protective Coating for Concrete)	VI See Remark	-	-	-	Must be a Qualified Product (706.03S).

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
707.02 Bushings for Pins and Link Plates	VI See Remark	-	-	-	Must be a Qualified Product (707.02).
708.01 Structural Prestressed Concrete Construction	Fabrication Inspection	-	-	-	See Chapter 5 of the SFQM for Precast Concrete Beam Approved Supplier List. See subsection 2.2. of the SFQM for fabrication inspection procedure. See Special Instructions.
710.03D Waterproofing Shotcrete	VI	-	-	-	
712.03A1c Abrasive, Low Dusting	Gen Cert	-	-	-	See Section 715.02.
712.03D Epoxy Mastic	VI	-	-	-	
712.03J Adhesive Anchor Systems for Structural Anchors and Lane Ties	VI See Remark	-	-	-	Must be a Qualified Product (712.03J). Pull-out testing is required see MQAP Manual Section 3.03.
712.03K Structure Expansion Anchors (Mechanical Expansion Anchors)	VI See Remark	-	-	-	Must be a Qualified Product (712.03K). Pull-out testing is required see MQAP Manual Section 3.03.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
712.03L Mechanical Reinforcement Splicing	VI See Remark	1 per project	2 splices	-	See Special Instructions. Must be a Qualified Product (712.03L).
712.03X Grout Under Masonry Plates	VI	-	-	-	
712.03Y Embedded Galvanic Anodes	VI See Remark	-	-	-	Must be a Qualified Product (712.03Y).
713.02B Sealant for Perimeter of Beam Repairs	VI See Remark	-	-	-	Must be a Qualified Product (713.02B).
715.02 Coating Systems for New Hanger Assemblies	VI See Remark	-	-	-	Must be a Qualified Product (915).
715.02 Abrasive, Low Dusting	VI See Remark	-	-	-	Must be a Qualified Product (715.02).
715.02 Abrasive, Steel Grit	VI	-	-	-	Verify uniform profile after blasting of 1 to 2.8 mils per SSPC.
716.02 Abrasive, Low Dusting	VI See Remark	-	-	-	See Section 715.02.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
803.02B Detectable Warning Surfaces	VI See Remark	-	-	-	Must be a Qualified Product (803.02B).
804.01 Glare Screen	VI	-	-	-	Included in Concrete Spec.
808.03C Temporary Fence Materials	VI	-	-	-	
810.03O Bridge Sign Connections	Fabrication Inspection	-	-	-	See Chapter 5 of the SFQM for Steel Highway Structure Approved Suppliers List. See subsection 2.4 of the SFQM for fabrication inspection procedure.
811.03D1 Waterborne, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D1).
811.03D2 Low Temperature Waterborne, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D2).
811.03D3 Regular Dry Paint, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D3).

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.
* Must be tested unless provided by an Approved Manufacturer.
** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
811.03D4 Cold Plastic Tape, Preformed Pavement Marking Material	VI See Remark	-	-	-	MQAP Manual Section 5.14. Must be a Qualified Product (811.03D4).
811.03D5 Thermoplastic Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D5).
811.03D5 Thermoplastic, Blocks Rumble Strips and Snowmobile Crossings	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D5).
811.03D6 Thermoplastic, Sprayable, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D6).
811.03D7 Polyurea, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D7).
811.03D8 Modified Epoxy, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 5.13. Must be a Qualified Product (811.03D8).
811.03D9 Preformed Thermoplastic, Preformed Pavement Marking Material	VI See Remark				MQAP Manual Section 5.14. Must be a Qualified Product (811.03D9).
901 Cement	Appr Mfr	See Remark	10 lb	45 ton	See Special Instructions, see MQAP Manual Section 2.06.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
901.06 Slag Cement	Appr Mfr	-	10 lb	-	See Special Instructions for Cement.
901.07 Fly Ash, Pozzolanic Admixtures for Concrete	Appr Mfr	-	10 lb	-	See Special Instructions for Cement, see MQAP Manual Section 2.07

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
902 Coarse Aggregates	Test	See Remark	See Remark	See Remark	See Special Instructions Refer to Chapter 3 of the Procedures for Aggregate Inspection Manual for sampling and maximum visual inspection information. See Current List of all Prequalified Aggregate Suppliers at Construction Field Services Web Page.
902 Dense-Graded Aggregates	Test	See Remark	See Remark	See Remark	
902 Open-Graded Aggregates	Test	See Remark	See Remark	See Remark	
902 Granular Material Class I	Test	See Remark	See Remark	See Remark	
902 Granular Material Class II (Subbase), Class IIA and Class IIAA	Test	See Remark	See Remark	See Remark	
902 Class II (Abutment B. F.)	Test	See Remark	See Remark	See Remark	
902 Granular Material Class III	Test	See Remark	See Remark	See Remark	
902 Granular Material Class IIIA	Test	See Remark	See Remark	See Remark	
902 Fine Aggregate	Test	See Remark	See Remark	See Remark	
902 Mineral Filler for HMA Mixtures	Test See Remark	1 per project	1 qt	10 ton	Refer to Section 902.11 of the 2020 Standard Specifications.
903.01 Air Entraining Admixtures	VI See Remark	-	-	-	Must be a Qualified Product (903.01).

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.
* Must be tested unless provided by an Approved Manufacturer.
** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
903.02 Liquid Chemical Admixtures	VI See Remark	-	-	-	Must be a Qualified Product (903.02).
903.03 Latex Admixture for Concrete	Appr Mfr	1 per lot	1 qt	-	
903.04 Calcium Chloride Concrete Accelerators	VI See Remark	-	-	-	Note the chemical composition.
903.06 Membrane Curing Compound	Test Data Cert	1 per lot or batch	1 qt	200 gal	
NOTE: Curing compounds must not be used after ONE year from manufacture. Date of manufacture must be clearly printed on the outside of containers.					
903.07A Interim Curing (Linseed Oil Based)	Test Data Cert	1 per lot or batch	1 qt	50 gal	See Note for 903.06 above.
903.07C Insulating Blanket	Test Data Cert	-	-	10 sheets	
903.07D Polystyrene Insulation	Test Data Cert	-	-	-	
904.03A Asphalt Binder for HMA Mixtures	See Remark	See Remark	See Remark	-	See Special Instructions.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
904.03B Liquid Asphalt (MC)	Gen Cert	1 per batch	See Remark	-	1 gal from the top and 1 gal from the bottom of tank.
904.03B Liquid Asphalt (RC-250)	Gen Cert	1 per batch	2 qt	5 gal	
904.03C Emulsified Asphalt	Appr Mfr * See Remark	See Remark	See Remark	-	See Special Instructions.
905.03 Bar Reinforcement (Uncoated)	Appr Mfr *	1 per project per mfr per size	See Remark	500 lb	See Special Instructions.
905.03 Bar Reinforcement (Epoxy Coated) 1. Bar 2. Epoxy Coating Companies 3. Epoxy Coating Material (905.03C)	 Appr Mfr * Appr Mfr * VI See Remark	 1 per project per mfr per size	See Note	500 lb	 See Special Instructions. Epoxy Coating must be a Qualified Product (905.03C).
905.03D Bar Chairs and Wire Ties for Epoxy Coated Steel Reinforcement	VI	-	-	-	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
905.06 Welded Steel Wire Reinforcement (Mesh)	Appr Mfr *	1 per project per mfr	See Remark	500 syd	See Special Instructions.
905.07 Strand for Prestressed Concrete	Appr Mfr *	1 per heat	2 pcs each 60 in long	-	See Special Instructions.
905.08 Tendons for Post Tensioning of Box Beams (Prestressing Strand)	Appr Mfr * See Remark	1 per heat	2 pcs each 60 in long	-	See Special Instructions.
905.08 Tendons for Post Tensioning of Box Beams (Post Tensioning Bar)	Test	1 per heat per project	2 pcs each 30 in long	-	
906.04 Structural Steel	Fabrication Inspection	-	-	-	See subsections 2.3 and 2.4 of the SFQM for bridge steel and structural steel fabrication inspection procedures, respectively. See Special Instructions.
906.05 Foundation Piles (Steel H Piling and Special Sections, Steel Shells for Cast-in-Place Concrete Piles and Pile Points)	Test Data Cert	-	-	-	
906.05 Pile Cutoffs	Gen Cert	-	-	-	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
906.06 Steel Piles (Temporary and Permanent Steel Sheet Piling)	Gen Cert	-	-	-	
906.07 High Strength Steel Bolts, Nuts, and Washers for Structural Joints	Test	1 per dia per length per lot per project	3 assemblies	-	See Special Instructions.
906.09 Shear Developers (Studs)	VI See Remark	-	-	-	Must be a Qualified Product (906.09).
907.03A – C Woven Wire Fence (Woven Wire Fabric, Barbed Wire, Smooth Line Wire)	Test Data Cert	1 per project per mfr	Full width of roll 5 ft 6 ft 4 ft	400 ft	
907.03D Woven Wire Fence (Steel Posts)	Test Data Cert	1 per project per mfr	1 post	25 posts	
907.03E Woven Wire Fence (Treated Wood Posts)	See Remark	-	-	-	See Section 912.07B.
907.03F Woven Wire Fence (Gates)	VI	-	-	-	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
907.04A Steel Chain Link Fence (Fabric)	Test Data Cert	See Remark	5 ft full width of roll	250 ft	1 per height and/or mesh size, per project and 1 per mfr per project.
907.04B Steel Chain Link Fence (Tension Wire)	Gen Cert	1 per project per mfr	3 ft	500 ft	
907.04C Steel Chain Link Fence (Post for Fence and Gates), (Pedestrian Fence and Structure Fencing (Steel))	Test Data Cert	1 per project per mfr	1 post	25 posts	See Special Instructions.
Note: An alternative zinc/clear coat system will be allowed for pipe sections only. This alternative coating system shall comply with subsection 907.03D of the Standard Specifications for Construction.					
907.04C Steel Chain Link Fence (Top Rail), ((Horz. Rail) (Pedestrian Fence))	Test Data Cert	1 per project per mfr See Remark	5 ft	250 ft	See Special Instructions.
907.04D & E Steel Chain Link Fence (Gates, Fence Fittings and Hardware)	VI	-	-	-	
907.05A High Tensile Wire Fence (Wire)	Test	1 per project per mfr	3 ft	250 ft	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
907.05B High Tensile Wire Fence (Treated Wood Posts)	See Remark	-	-	-	See Section 912.07B.
907.05C High Tensile Wire Fence (Hardware)	VI	-	-	-	
907.06 Protective Fence	VI	-	-	-	
908 Castings, Manhole 908.03 Malleable Iron 908.04 Steel 908.05 Gray/Ductile Iron	VI	-	-	-	
908.07 Sheet Lead	Gen Cert	-	-	25 sft	
908.08 Sheet Copper	Gen Cert	1 per consignment	13 in square or equivalent area	25 sft	May be accepted in field if weight requirements can be documented.
908.09A Tubing, Steel Railings (Base Plate, Angle, and Non-Tubular Post Elements)	Fabrication Inspection	-	-	-	See subsection 2.4 of the SFQM for fabrication inspection procedure.
908.09B Tubing, Steel Railings (Rail Elements and Tubular Post Elements)	Fabrication Inspection	-	-	-	See subsection 2.4 of the SFQM for fabrication inspection procedure.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
908.09C Tubing, Steel Railings (Hardware)	Test	1 per lot per diameter per project	1 assembly	-	See Special Instructions.
908.10 Hardware for Timber Construction	VI	-	-	-	
908.11A Guardrail, Steel Beam Elements, End Sections	Appr Mfr *	1 per project per mfr	1 piece at least 1 ft length	125 ft	Including Anchorage, Bridge, Shoes, Departing End Terminals.
908.11A Guardrail Approach Terminals	See Remark	-	-	-	See contract documents.
908.11B & C B. Hardware C. Steel Sleeves, Soil Plates, Bearing Plates, Backup Plates	VI	-	-	-	Item supplied by guardrail supplier.
908.11B Wire Rope	Gen Cert	-	-	-	
908.12 Steel Posts for Beam Guardrail	Appr Mfr *	1 per 1000 posts or fraction thereof	1 post	25 posts	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
908.13 Reflective Washers	VI See Remark	-	-	-	Inspect galvanizing, dimensions and type of sheeting.
908.14 Anchor Bolts, Nuts, and Washers	Test	1 per lot per diameter per project	1 assembly	-	See Special Instructions.
908.14D Anchor Bolts and Nuts for Other Purposes	Gen Cert	1 per lot per diameter per project	1 assembly	-	See Special Instructions.
909.01 Recycled Rubber Adjusting Rings for Manholes and Drainage Castings	VI See Remark	-	-	-	Must be a Qualified Product (909.01).
909.03 Watertight Joint Systems	VI See Remark	-	-	-	Must be a Qualified Product (909.03).
909.03 Gasket, Compression (O-Rings)	VI	-	-	-	Part of Watertight Joint System.
909.03 Gasket, External Rubber Type	VI	1 per lot or shipment	18 in length full width of gasket	-	Part of Watertight Joint System.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.04A Reinforced Concrete Pipe	Appr Mfr *	1 percent of number of pcs of each size	See Remark	5 pieces of 42 in or smaller	See Special Instructions.
909.04B Reinforced Concrete Elliptical Pipe	Appr Mfr *	1 percent of number of pcs of each size	See Remark	5 pieces of 42 in or smaller	See Special Instructions.
909.04C Non-Reinforced Concrete Pipe	Appr Mfr *	See Remark	See Remark	10 pcs	See Special Instructions.
909.04D Precast Concrete Box Sections	Appr Mfr * See Remark	-	-	-	Spans 20 ft. and greater (measured from inside of exterior walls, parallel to the roadway centerline) require QA inspection. QA inspection may be required for spans from 10-20 ft. Box = 4 sided. See subsection 2.1 of the SFQM for fabrication inspection procedure. See Special Instructions.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.04E Precast Concrete End Section for Culverts and Sewers	Appr Mfr *	1 percent of number of pcs	Full size units	10 pcs	Strength test by coring or cylinders, VI dimensions and conditions. Test for air content. .
909.04G Precast Concrete Three-Sided or Arch Culverts	Appr Mfr See Remark	-	-	-	Spans 20 ft. and greater (measured from inside of exterior walls, parallel to the roadway centerline) require QA inspection. QA inspection may be required for spans from 10-20 ft. See subsection 2.1 of the SFQM for fabrication inspection procedure. See Special Instructions.
909.05A Corrugated Steel Pipe	Appr Mfr *	See Remark	See Remark	-	See Special Instructions.
909.05A1 Corrugated Steel Sheets (Galvanized)	Gen Cert	See Remark	See Remark	-	See Special Instructions.
909.05A1 Polymer Coating, Galvanized Corrugated Steel Pipe	VI See Remark	-	-	-	Coating must be from Qualified Products List (909.05A1).
909.05A3 Coupling Bands	Gen Cert	-	-	5 pcs	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.05B Corrugated Aluminum Alloy Sheet	Gen Cert	See Remark	See Remark	25 sheets	See Special Instructions.
909.05B Corrugated Aluminum Alloy Pipe	Gen Cert	1 per 1000 ft	See Remark	250 ft	Sample Size: A 6 in by 3 in (minimum) section cut from the end of the pipe avoiding the seams. Do not damage coating.
909.05C Steel End Section	Gen Cert	-	-	4 pcs	
909.05D 1. Steel Pipe (Jacked-in-Place)	Gen Cert	-	-	-	For drainage applications.
909.05D 2. Casing, Steel Pipe	VI	-	-	-	For drainage applications.
909.06 1. Corrugated Polyethylene Pipe (CPE/HDPE), (Smooth Lined Type S)	Appr. Mfr*	See Remark	See Remark	100 ft	See MQAP Chapter 3.10.
909.06 2. Corrugated Polyvinyl Chloride (CPV) Pipe	Test	1 per 1000 ft	See Remark	12 in. dia and over, 100 ft	Over 12 in. dia- one 10 ft and one 6 ft. length plus coupling.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.06 3. Plastic Pipe Class A, B and F Bury (CPE/HDPE & CPV)	VI See Remark	-	-	-	Must be a Qualified Product (909.06).
909.06 4. Smooth Polyvinyl Chloride (PVC) Pipe and Fittings for Sanitary Sewer	VI	1 per 6000 ft	1 piece, 5 ft in length	-	Sample must include bell end of pipe.
909.07A Pipe for Underdrains Smooth Perforated Plastic Pipe (PVC)	Test	1 per 2500 ft or fraction thereof	5 ft length	250 ft	Sample must include bell end of pipe.
909.07A1 Pipe for Underdrains Acrylonitrile-Butadiene-Styrene (ABS)	Test	1 per 6000 ft	1 piece, 6 ft in length	600 ft	If bell and spigot joint, sample from bell end.
909.07B Pipe for Underdrains Corrugated Plastic Tubing (Perforated and Non-Perforated) (Wrapped and Non-Wrapped)	Appr Mfr * 4-, 6-, or 8-in dia	1 per 5000 ft sample from coils	See Remark	250 ft	Sample Size, one 12 ft length plus coupling. For perforated tubing wrapped in fabric, tie fabric securely in place before cutting sample. Do not disturb fabric after cutting.
909.07C Outlet Pipe for Underdrains 1. Polyvinyl Chloride (PVC) Pipe	Test	1 per 2500 ft or fraction thereof	5 ft length	250 ft	See 404.02C for Underdrain Outlet Endings. Sample must include bell end of pipe.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.07C Outlet Pipe for Underdrains 2. Corrugated Steel Pipe	Appr Mfr *	See Remark	See Remark	-	See Special Instructions for 909.05A,. See 404.02C for Underdrain Outlet Endings.
909.07C Outlet Pipe for Underdrains 3. Corrugated Aluminum Alloy Pipe	Gen Cert	1 per 1000 ft	6 in x 3 in	250 ft	See 404.02C for Underdrain Outlet Endings. See 909.05B.
909.08A Bridge Deck Downspouts	VI	-	-	-	
909.08B Culvert, Downspouts 1. Corrugated Steel Pipe	Appr Mfr *	See Remark	See Remark	-	See 909.05A Corrugated Steel Pipe.
909.08B Culvert, Downspouts 2. Corrugated Aluminum Alloy Pipe	Gen Cert	1 per 1000 ft	6 in x 3 in	250 ft	See 909.05B.
909.08B Culvert, Downspouts 3. Corrugated Polyethylene Pipe (Corrugated Type C) (CPE/HDPE)	Test	1 per 1000 ft	See Remark	<12 in. dia up to 250 ft ≥12 in. dia up to 100 ft	A sample consists of one 10-foot-long piece, one 6-foot-long piece, and one coupling.
909.08C Bridge Deck Drain Extensions (Polyethylene)	Gen Cert	-	-	-	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.09 Cold Applied Pipe Joint Sealer (Mastic)	VI	1 per shipment from a single container	1 qt	-	
909.10 Drainage Marker Post	See Delineator Posts	-	-	-	
910.03A Geotextile Blanket (incl. Filter Bags)	Test	See Remark	See Remark	500 syd	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.
910.03A Knitted Sock Pipe Wrap	See Remark	-	-	-	See 909.07B Certified with Corrugated Plastic Tubing.
910.03B Geotextile Liner (Rip-Rap, etc.)	Test	See Remark	See Remark	500 syd	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.
910.03B Heavy Geotextile Liner (Rip-Rap, etc.)	Test	See Remark	See Remark	500 syd	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
910.03C Geotextile Separator (Woven, Non-woven)	Test	See Remark	See Remark	500 syd	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.
910.03D Stabilization Geotextile (Woven, Non-woven)	Test	See Remark	See Remark	500 syd	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.
910.04 Silt Fence Geotextile (fabric only)	VI See Remark	-	-	-	Must be a Qualified Product (910.04). See 916.02 for sampling and acceptance instructions for Silt Fence (full assembly).
910.05A Wall Drain	Test	1 per 2000 ft or less	See Remark	250 sft	See Special Instruction 910.05. Suppliers must provide separate samples of filter wrap geotextile and polymer core.
910.06 Road Grade Biaxial Geogrid	Test	1 per lot per shipment	1 pc 6 ft long full roll width	-	Sample must be rolled not folded. Include lot number and/or roll number, name of manufacturer, and the product or style number. Anticipate up to 28 calendar days for the testing of geogrid samples.

Materials Acceptance Requirements

See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction.
* Must be tested unless provided by an Approved Manufacturer.
** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
911 Water	Test See Remark	1 per source	1 qt	-	Water approved for drinking by the Michigan Dept of Public Health may be used without sampling and testing.
912.05 Structural Timber and Lumber	Appr Mfr *	Each Charge	22 cores See Remark	-	48 cores if treatment is creosote.
912.06 Timber Piles	VI	-	-	-	
912.07B Treated Wood; Fence Posts, Guide Posts, Guard Posts and Mail Box Posts	VI	-	-	-	
912.08 Wood Posts and Blocks for Guardrail and Highway Signs (Dimension Sawed)	Appr Mfr *	Each Charge	22 cores	-	Cedar post need not be treated.
912.08Q Recycled Plastic or Rubber Guardrail Offset Blocks	VI See Remark	-	-	-	Must be a Qualified Product. May only be used on Steel Posts (912.08Q).
912.09 Timber for Rustic Construction	Gen Cert	-	-	-	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
913.03 Clay and Sand Lime Brick and Block	Test	1 per 250,000 or fraction thereof	6 pcs	1000 pcs	
913.03C Concrete Brick	Test Data Cert	See Remark	6 pcs	1000 pcs	1 from each 10,000 bricks or fraction thereof; 2 from lots more than 10,000 to 100,000; 3 from each lot over 100,000.
913.05 Concrete Block	Test Data Cert	See Remark	4 pcs	1000 pcs	One from lot of 10,000 or fraction thereof; 2 from lots more than 10,000.
913.06 Precast Reinforced Concrete Units for Drainage Structures (Tops, Risers and Sump Bases)	Appr Mfr *	1 percent per size	See Remark	10 pcs total	Submit QA cylinder test results and core samples. Submit sample 1-3 sq.in. from wall of unit if absorption is required.
913.06 Precast Drainage Structure Adjusting Rings	Gen Cert	-	-	-	
913.07 Precast Concrete Bases, for Drainage Structures	Appr Mfr *	5 percent of total	-	10 pcs total	
913.08 Structural Tile	Test	1 per proj.	6 tiles	1000 tiles	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
913.09 Slope Pavement Blocks	Appr Mfr *	1 per 25,000	6 blocks	1000 pcs	
914.03 Bituminized Fiber Joint Filler	Test Data Cert	1 per 1000 sft or fraction thereof	2 ft See Remark	150 sft	Sample for structure to be at least 5 in. wide. ¼ in. filler need not be sampled.
914.03B Recycled Rubber Joint Filler	VI	-	-	-	
914.03C Closed-Cell Polypropylene Foam	Test Data Cert	1 per 1000 sft or fraction thereof	2 ft See Remark	150 sft	Sample for structure to be at least 5 in. wide. ¼ in. filler need not be sampled.
914.04A Hot-Poured Joint and Crack Sealant	VI See Remark	-	-	-	Must be a Qualified Product (914.04A).
914.04B Backer Rod for Use with Hot-Poured Joint Sealant	VI	-	-	-	
914.04C HMA Crack Treatment and Overband	VI See Remark	-	-	-	Must be a Qualified Product (914.04C).
914.05 Joint Spall Repair Materials	See Remark	-	-	-	See contract documents as applicable.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
914.06 Epoxy Resin Adhesive (Crack Injection)	VI See Remark	-	-	-	Must be a Qualified Product (914.06).
914.07 Transverse Pavement Joints 1. Dowel Bars	Appr Mfr	-	1 bar	1200 bars	Bond Release Agent must be a Qualified Product (914.07A). See Special Instructions 914.07.
2. Dowel Baskets (Load Transfer Assemblies)	Appr Mfr	-	Full size unit	100 assemblies	Field Inspection required, MQAP Manual Section 3.04. See Special Instructions 914.07.
914.07A Coatings for Dowel Bars 1. Epoxy Coating Companies	Appr Mfr *	1 per project per mfr	1 bar	240 bars	
2. Epoxy Coating Material	VI See Remark	-	-	-	Epoxy Coating must be a Qualified Product (914.07A2).
3. Bond Release				20 gal max	
a. Bituminous Material	Gen Cert	-	-		
b. Alternate Bond Release Agents	VI See Remark	-	-	-	Must be a Qualified Product (914.07A3).

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
914.07C Dowel Bar Expansion Caps	VI	-	-	-	Caps must conform to Standard Plan R-40 Series.
914.08 End-of-Pour Joint Devices	VI	-	-	-	
914.08 Deformed Bars 1. Bars 2. Epoxy Coating	Appr Mfr * VI See Remark	1 per project per mfr	-	500 lb	Epoxy Coating must be Qualified Product (905.03C).
914.09 Straight and Bent Tie Bars for Longitudinal Pavement Joints (Lane Ties) 1. Bars 2. Epoxy Coating	Appr Mfr * VI See Remark	1 per project per mfr	2 bar	500 lb	Epoxy Coating must be a Qualified Product (905.03C).
914.10 Bolts for Structure Expansion Anchors	Gen Cert	-	-	-	
914.11 Preformed Waterproofing Membrane and Joint Waterproofing Membrane	VI See Remark	-	-	-	Must be a Qualified Product (914.11). Do not use on Treated Wood Materials.
914.12A Elastomeric Bearings	Gen Cert	-	-	-	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
914.12B Elastomeric Leveling Pads	Gen Cert	-	-	-	
915 Bridge Coating Systems	VI See Remark	-	-	-	Must be a Qualified Product (915).
916.01A Cobblestone	VI	-	-	-	
916.01C Riprap	VI	-	-	-	
916.02 Silt Fence (full assembly) Note: Sample to include identifying markings of fabricator. Indicate on sample ID description of markings. Note where markings were found.	Appr Mfr *	See Remark	See Remark	500 ft	See Special Instructions 916.02. See 910.04 for acceptance instructions for Silt Fence Geotextile (fabric only).
916.07 Turbidity Curtain	VI				
917.03 Nursery Stock	VI	-	-	-	
917.04 Balling Material	VI	-	-	-	
917.05A Wire for Bracing and Guying	VI	-	-	-	
917.05B Hose for Bracing and Guying	VI	-	-	-	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
917.05C Stakes for Bracing and Guying	VI	-	-	-	
917.07 Compost	VI	-	-	-	
917.09 Chemical Fertilizer for Grass Seed	VI See Remark	-	-	-	Provide the bag label, showing the guaranteed analysis.
917.11 Grass Seeding Mixtures Grass Seed Varieties	VI See Remarks VI See Remark	1 per lot per shipment	1/2 lb	1100 lbs	For projects that include more than 5 acres of seeding, see Grass Seed Testing Special Provision in contract. Varieties of seed must be Qualified Product (917.11).
917.12 Sod	VI	-	-	-	
917.12A Pegs for Sodding	VI	-	-	-	
917.13 Mulching Materials for Nursery Stock	VI	-	-	-	Only shredded hardwood, wood chips or wood products not allowed.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
917.14B1 & 2 High Velocity Mulch Blankets and Standard Mulch Blanket	VI See Remark	-	-	-	Must be a Qualified Product (917.14B 1 & 2). High velocity - netting 2 sides. Standard - netting 1 side.
917.14C Mulch Anchoring - Latex, Recycled Newsprint, Wood Fiber, Guar Gum, Other Tackifiers	VI See Remark	-	-	-	Must be a Qualified Product (917.14C).
917.15 Weed Control (Herbicides)	Test Data Cert	-	-	-	
918.01 Flexible Metal Conduit	VI	-	-	-	
918.01A Electrical Conduit, Rigid (Galvanized Steel)	Gen Cert	See Remark	6 ft, include coupling, if applicable	400 ft	1 sample for 2500 ft or fraction thereof; 2 samples over 2500 to 10,000 ft; 1 sample for each additional 10,000 ft.
918.01B & C Electrical Conduit (Polyvinyl Chloride) Schedule 40 and 80	Gen Cert	See Remark	6 ft sample w/ bell end incl coupling	400 ft	1 sample for 2500 ft or fraction thereof; 2 samples over 2500 to 10,000 ft; 1 sample for each additional 10,000 ft.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
918.01D & E Electrical Conduit (Polyethylene/HDPE) Schedule 40 and 80	Gen Cert	See Remark	See Remark	400 ft	1 sample for 2500 ft or fraction thereof; 2 samples over 2500 to 10,000 ft; 1 sample for each addi-tional 10,000 ft; 6 ft plus a sepa-rate section consisting of 2-18 in. long pcs. connected by the joint.
918.01F Electrical Conduit (Rigid Fiberglass)	Gen Cert	See Remark	6 ft sample w/ bell end incl. coupling	400 ft	1 sample for 2500 ft or fraction thereof; 2 samples over 2500 to 10,000 ft; 1 sample for each additional 10,000 ft.
918.02 Grounding System	VI	-	-	-	
918.02C Grounding Rods	VI	-	-	-	
918.03 Electrical Cable	Gen Cert	-	-	-	
918.06 Precast Concrete Handholes and Manholes for Electrical and Telephone Connections	Appr Mfr *	1 percent per size	-	10 pcs	
918.08 Light Standards (Steel and Aluminum Light Standards)	Gen Cert	-	-	-	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
918.08C Light Standards, Frangible Transformer Bases	VI See Remark	-	-	-	Must be a Qualified Product (918.08C).
918.09 Luminaries	Gen Cert	-	-	-	
918.10A Tower Lighting Units	Fabrication Inspection	-	-	-	See Chapter 5 of the SFQM for Steel Highway Structure Approved Supplier List. See subsection 2.4 of the SFQM for fabrication inspection procedure.
918.11A Guy Wire	Gen Cert	1 per size	3 ft	-	
919 Steel Sleeves for Wood Posts	Gen Cert	-	-	-	
919.02 Signs (Permanent)	See Remark	-	-	-	General Cert must be attached and inspected at project site.
919.02A1 Metal Sections (Extruded Aluminum)	VI See Remark	-	12 in. long and full width of section	-	Mill Cert must be submitted to the Project Engineer.
919.02A2 Plywood	Gen Cert See Remark	-	-	-	Grade mark on materials serves as certification.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
919.02A3 Aluminum Sheet	VI See Remark	-	Min. of 12 in. square	-	Mill Cert must be submitted to the Project Engineer.
919.02B1 Reflective Sheeting	VI See Remark	1 per run or lot	See Remark	1 roll, for less than 3 in. in width	Must be a Qualified Product (919.02B1) 4 pcs each 12 in. square. For rolls less than 12 in. width, at least 7.5 ft.
919.02C Sign Hardware	Gen Cert See Remark	-	-	-	Identifying marks on items may serve as certification.
919.03A Delineators, Aluminum Reflectors	Gen Cert	1 per shipment per color	21 pcs	25 pcs each color	
919.03B Delineators, Reflective Sheeting Reflectors	Gen Cert	1 per shipment per color	2 pcs each color	25 pcs each color	
919.03D Delineator Posts, Steel	Gen Cert	1 per project per mfr	1 post	80 post	
919.03D Delineator Posts, Flexible	VI See Remark	-	-	-	Must be a Qualified Product (919.03D).

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
919.04 Steel, Galvanized Sign Posts	Test Data Cert	1 per project per mfr	See Remark	20 posts	Sample 30 in. length min. length. Posts for temporary signs may be painted.
919.05 Wood Sign Posts	Appr Mfr *	Each charge	22 cores	20 posts	See 912.08.
919.06 Steel Column Breakaway Sign Supports	VI	-	-	-	Mill Cert must be submitted to the Project Engineer.
919.07 Cantilever Sign Supports	Fabrication Inspection	-	-	-	See Chapter 5 of the SFQM for Steel Highway Structure Approved Supplier List. See subsection 2.4 of the SFQM for fabrication inspection procedure.
919.08 Truss Sign Supports	Fabrication Inspection	-	-	-	See Chapter 5 of the SFQM for Steel Highway Structure Approved Supplier List. See subsection 2.4 of the SFQM for fabrication inspection procedure.
919.10 Casings for Cantilever Drilled Piles	Gen Cert	-	-	-	For Cantilever, Drilled Shaft, Strain Pole, etc. Foundations.
920.02B Standard Glass Beads	Gen Cert	1 from each lot	2 lb	500 lbs	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
920.02C Wet Reflective Optics	VI See Remark	-	-	-	Must be a Qualified Product (920.02C).
921.02 Messenger Wire and Span Wire	Gen Cert	1 per size	3 ft	-	
921.03 Traffic Signals and Mounting Assemblies	Gen Cert	-	-	-	
921.05 Traffic Signal Strain Pole	Gen Cert	-	-	-	
921.05A Strain Pole Band Clamps	VI See Remark	-	-	-	Must be a Qualified Product (921.05A).
921.08B Traffic Loop Sealant	Gen Cert	2 from each lot	Tubes	-	
922.02 Temporary Traffic Control Temporary Signs	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.02B Temporary Traffic Control Reflective Sheeting (Signs)	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.02D Temporary Traffic Control Sign Covers	See Remark	-	-	-	See MQAP Manual Section 3.07.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
922.03 Temporary Traffic Control A. Cones B. Drums	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.03E Temporary Traffic Control Type III Barricade, Reflective Sheeting	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.04 Temporary Traffic Control Temporary Concrete Barriers (TCB)	Test Data Cert See Remark	Each project	-	-	Contractor must provide certifications and documentation confirming the TCB provided meets the requirements of subsection 922.04.A of the Standard Specifications for Construction.
922.04A Barrier Reflectors Temporary	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.04A Barrier Reflectors Permanent	VI	-	-	-	
922.06A Temporary Traffic Control Temporary Pavement Markings; Type R and NR Tape	VI See Remark	-	-	-	Must be a Qualified Product (922.06A).

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
922.06A2 Temporary Traffic Control Temporary Pavement Markings; Paint	VI See Remark	-	-	-	Must be a Qualified Product (811.03D).
922.06B Temporary Traffic Control Temporary Raised Pavement Markers	VI See Remark	-	-	-	Must be a Qualified Product (922.06B).
922.06C Temporary Traffic Control Pavement Marking Cover	VI See Remark	-	-	-	Must be a Qualified Product (922.06C).
922.06D Temporary Rumble Strips (Orange)	VI See Remark	-	-	-	See MQAP Manual Section 3.07.
922.07A Temporary Traffic Control Lighted Arrows; Type B and C (Solar Assist)	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.07B Temporary Traffic Control Warning Flashers and Lights; Type A, B, C	See Remark	Each project	3 each type	-	See MQAP Manual Section 3.07.
922.07C Temporary Traffic Control Portable Changeable Message Signs	See Remark	-	-	-	See MQAP Manual Section 3.07.
922.11 Temporary Traffic Control Sign Paddles and Vests	See Remark	-	-	-	See MQAP Manual Section 3.07.

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
922.12A Temporary Traffic Control Dust Palliative 1. Calcium Chloride Solids	Test Data Cert	1 per project	5 lb	5000 lb	
922.12A Temporary Traffic Control Dust Palliative 2. Calcium Chloride Solutions	Test Data Cert	1 per project	1 qt	1000 gal	
923 Watermain Materials	Gen Cert	-	-	250 ft of pipe	See contract documents as applicable.
1005.02A Standard Mortar and Grout Mixtures	VI	-	-	-	
1005.02B Non-Shrinking Mortar and Grout, Type H-1(Non-Metallic) Pre-Mixed	VI See Remark	-	-	-	Must be a Qualified Product (1005.02B).
1005.02C Admixture for Expansive Grout, Type E-1	Test Data Cert	-	-	-	
Note: Certification to include manufacturers recommended dosage per sack of cement.					
1006 Prepackaged Hydraulic Fast Set Mortar	VI See Remark	-	-	-	Must be a Qualified Product (1006).
Misc. #2 Culvert, Cast and Ductile Iron	Gen Cert	-	-	250 ft	

Materials Acceptance Requirements					
See Miscellaneous area at the end of table for materials deleted from the 2020 Standard Specifications for Construction. * Must be tested unless provided by an Approved Manufacturer. ** When the Basis of Acceptance is not “Test”, the sampling criteria below may be used when there are concerns with material quality.					
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
Misc. #3 Clay Pipe	Gen Cert	See Remark	See Remark	10 pieces	See Special Instructions.
Misc. #5 Galvanized Slotted Drain Pipe	VI See Remark	-	-	-	MDOT approval of Design is required. Coating thickness checked at project site.
Misc. #8 Corrugated Galvanized Steel Structural Plated	Gen Cert	1 per 100 plates or fraction thereof	1 piece at least 3 in. by 3 in.	10 plates	
Misc. #9 Aluminum Alloy Structural Plates	Gen Cert	-	-	-	
Misc. #13 Pavement Warning Strips	VI	-	-	-	
Misc. #14 Bituminized Cotton Fabric and Fiberglass Fabric	Gen Cert	See Remark	1 piece full width of roll, min of 3 ft	5 rolls	1 per 100 rolls (50 sft per roll) or fraction thereof; for lots of more than 100 rolls - 1 sample plus 1 for each 500 rolls or fraction thereof. Do not sample from first 3-4 ft of roll.

********** See following pages for Special Instructions **********

Special Instructions

708.01 Prestressed Concrete

Fabrication inspection is required for all prestressed miscellaneous bridge products, prestressed straight-strand bridge beams, and prestressed deflected-strand bridge beams. The following steel components incorporated into prestressed concrete beams do not require fabrication inspection: dowel bars and sole plates.

712.03L Mechanical Reinforcement Splicing

The contractor must make test splices, witnessed by the Engineer, on the largest bar sizes that are to be spliced. Test splice consists of 2 pieces of reinforcing bar joined by the coupler with 20 inches of bar exposed on each end of the coupler.

901 Cements and Fly Ash

Samples of fly ash and slag cement must be accompanied by a sample of the Portland cement with which it is being used. The plastic lined cement sample bags furnished by the laboratory will hold 10 pounds when full.

902 Prequalified Aggregate Suppliers

Quality Assurance tests will be conducted by Department personnel at the frequencies stated in Chapter 3 of the MDOT Aggregate Supplier Program, found in the Procedures for Aggregate Inspection Manual.

904.03A Asphalt Binder for HMA Mixtures

If the Asphalt Binder is supplied from a source currently on the Approved Asphalt Binder Certifier List, a certification meeting the requirements of Section 2.04.05 of the Materials Quality Assurance Procedures Manual is required. See the contract documents for sampling, acceptance, and daily monitoring requirements.

If the binder is supplied from a source that is not currently shown in the Approved Asphalt Binder Certifier List, the asphalt binder must be sampled, tested, and approved for use prior to incorporation into the project. See contract documents for sampling, acceptance, and monitoring requirements.

See Current List of Asphalt Binder Certifiers at Construction Field Services Web Page.

Instructions to MDOT Construction web page: From MDOT home page (michigan.gov/mdot), click on Business (top), then click on Construction (left side), and then click Go to Construction. The Approved Asphalt Binder Certifier List is under Resources heading.

904.03C Emulsified Asphalt

Size of Sample – For CV Sampling see Section 2.05.06 of the Materials Quality Assurance Procedures Manual. For all other sampling see contract documents for criteria. Submit the samples in plastic containers only.

905.03 Bar Reinforcement (Uncoated)

Sample size must be 2 pieces, one 24 in. and one 36 in. Sample ID must include the name of the bar manufacturer, lot number, and heat number. Mill Cert must be attached to the Sample ID form.

905.03C Bar Reinforcement (Epoxy Coated)

Sample size must be 2 pieces, one 24 in. and one 36 in. Sample ID must include the name of the epoxy coating company, epoxy resin trade name, name of bar manufacturer, lot number, and heat number. Mill Cert must be attached to the Sample ID form. Epoxy coating must be a Qualified Product (905.03C).

905.06 Welded Steel Wire Reinforcement

Sample size must be one-piece, full width of fabric with two transverse wires. Longitudinal wires must extend 6 in. to 8 in. either side of transverse wires. Sampling not required when larger wire is less than 0.13 in. (w1.5) in dia. Include on sample ID the size that the wires are supposed to be. Sample may be folded or cut into approx. 3 ft. sections. If cut, pieces should be wired together and identified. Mill Cert must be attached to the Sample ID form.

905.07 Strand for Prestressed Concrete

Do not obtain sample from within 5 feet of the end of the reel. Mill Cert must be attached to the Sample ID form.

905.08 Tendons for Post Tensioning of Box Beams – Prestressing Strand

Do not obtain sample from within 5 feet of the end of the reel. Mill Cert must be attached to the Sample ID form.

906.04 Structural Steel

Fabrication inspection is required for all main and secondary bridge member pay items listed in 707.04.

Fabrication inspection is required for structural steel and pipe bridge railing pay items listed in 711.04.

Fabrication inspection is required for the following structural steel bridge rehabilitation pay items listed in 713.04: pin and hanger replacement, bearing stiffeners at temporary supports, retrofit structural steel, and structural steel welded repairs.

The following structural steel components do not require fabrication inspection: plate washers and pier nosing.

906.07 High Strength Steel Bolts

An assembly is typically a combination of a bolt, nut, and washer but may be any combination of a bolt, nut, washer, lock washer, etc. depending on the project specifications. Mill Certs must be included for each component of the assembly and be attached to the Sample ID form. Plate washers are not required to be sampled and tested.

907.04C Steel Chain Link Fence-Posts for Fence and Gates

An alternative zinc/clear coat system will be allowed for pipe sections only. This alternative coating system shall comply with subsection 907.03D of the Standard Specifications for Construction.

907.04C Steel Chain Link Fence-Top Rail, Horizontal Rail

An alternative zinc/clear coat system will be allowed for pipe sections only. This alternative coating system shall comply with subsection 907.03D of the Standard Specifications for Construction.

908.09C Tubing, Steel Railings (Hardware)

An assembly is typically a combination of a bolt, nut, and washer but may be any combination of a bolt, nut, washer, lock washer, etc. depending on the project specifications. Plate washers are not required to be sampled and tested.

908.14 Anchor Bolts, Nuts, and Washers

An assembly is typically a combination of a bolt, nut, and washer but may be any combination of a bolt, nut, washer, lock washer, etc. depending on the project specifications. For Type C, D, E and J cantilevers, the sampling frequency is 1 assembly per heat, per diameter, per foundation, for a max of 3 per project. Full length bolts are required for testing but if the total length is less than 20”, a second sample must be submitted for testing. Non MDOT

standard plan bolts require shop drawings along with a Mill Cert attached to the Sample ID form. Stainless steel anchors bolts are not required to be sample and tested. Plate washers are not required to be sampled and tested.

908.14D Anchor Bolts and Nuts for Other Purposes

A General Cert is acceptable for stainless steel anchor bolts, pedestal foundations for pedestrian signals, push buttons, controller cabinets, Hawks signals and repeaters and pedestrian fencing. Anchor bolts for all other purposes require testing. An assembly is typically a combination of a bolt, nut, and washer but may be any combination of a bolt, nut, washer, lock washer, etc. depending on the project specifications. Plate washers are not required to be sampled and tested.

909.04A Reinforced Concrete Pipe
909.04B

Size of Sample - Full size units for strength test. For absorption tests, 26-inch square to 81-inch square in area from the wall of each piece of pipe tested.

Number of Samples - One percent of the number of pieces of each size.

Reinforced concrete pipe 42-inch diameter and larger may be tested by coring. Size of core will be 4-inch nominal diameter (but not less than 3 ¼ inches actual). Up to 1 percent of the number of pieces of pipe for each size, but not less than 3 pieces, will be selected for coring. One core will be drilled and tested from each of these test pieces. Reinforcement will be inspected prior to incorporation in the pipe.

909.04C Nonreinforced Concrete Pipe

Size of Sample - Same as reinforced concrete pipe.

Number of Samples - One percent of the number of pieces, but not less than 2 pieces of each size except that at the option of the department the following sampling schedule will apply for 4 inches through 24 inches in diameter sewer pipe for quantities of 500 or more:

Sampling Schedule - Per the following:

Concrete Pipe	Number of Samples
500 to 1,000 pieces	6
1,001 to 2,000 pieces	8
2,001 to 5,000 pieces	11
Over 5,000 pieces	2 samples per 1,000 or fraction thereof

909.04D Precast Concrete Box Sections

The following structural steel components do not require fabrication inspection: plate washers, connection plates, and connection angles used to connect culvert segment, headwall, and wingwall.

909.04G Precast Concrete Three-Sided or Arch Culverts

The following structural steel components do not require fabrication inspection: plate washers, connection plates, and connection angles used to connect culvert segment, headwall, and wingwall.

909.05A Corrugated Steel Pipe

Size of Sample - A 6-inch by 3-inch (minimum) section cut from the pipe. The sample should be taken from the end of the pipe avoiding the seams. Care should be taken to assure the coating is not damaged during sampling. Mill Cert must be attached to the Sample ID form.

Number of Samples - Per the following:

Diameter of Pipe	Quantity Represented (maximum)
12 inches or less	2500 ft
15 inches through 54 inches	1000 ft
60 inches and over	500 ft

Less than 5 percent of the quantity in the above table may be visually inspected.

909.05A1 Corrugated Galvanized Steel Sheets

Size of Sample - One strip the full width of the sheet and 3 ½ inches in the direction of the length of the sheet. The strip may be cut from the end of the sheet for material coated in coils. If the sheets were individually coated after being cut to length, as indicated by heavy accumulations of zinc at one end, the sample strip shall be cut from the end opposite the heavy accumulation and after cutting 4 inches from the end of the sheet. Mill Cert must be attached to the Sample ID form.

Number of Samples - Per the following:

Diameter of Pipe Represented (max)	Length of Sheet	Quantity
12 inches or less	44 inches or less	2500 ft
15 through 54 inches	50 to 175 inches, approx*	1000 ft
60 inches and over	190 inches and over*	500 ft

*Larger pipe may be made from combination of shorter sheets. Less than 5 percent of the quantity in the table above may be visually inspected.

Note: Normally each heat and thickness is to be sampled. Exception may be made where quantities are limited and/or mixtures of heat numbers are excessive.

909.05B Corrugated Aluminum Alloy Sheets

Size of Sample - A transverse strip full width of the sheet and at least 3 inches in length cut from the end of the sheet.

Number of Samples - A sample shall be taken from each of 3 different sheets for lots weighing 5 tons or less, from 4 sheets for lots weighing more than 5 tons and less than 10 tons, and from 5 sheets for lots weighing 10 tons or more.

910.03 Geotextiles

Sampling Frequency - Obtain samples to represent the required quantity of geotextile according to the following schedule:

Geotextile	First Sample	Additional Samples
Blanket	500 to 1500 syd	7,500 syd or less
Liner for Riprap	500 to 1500 syd	5,000 syd or less
Separator/Stabilization	500 to 1500 syd	25,000 syd or less
Liner for Heavy Riprap	500 to 1500 syd	4,000 syd or less

Maximum for VI - 500 syd (4500 sq ft)

Size of Sample - Sample must be a minimum of 75 sft, taken across the full roll width. For rolls over 15 ft wide, sample must be a minimum of 5 ft long, taken across the full roll width.

Geotextile samples submitted for testing must be identified with the lot number and/or roll number, the name of the manufacturer, and the product or style number.

Notes:

Geotextiles must be unwrapped one full roll circumference prior to sampling.

Geotextiles must be rolled, not folded, and shipped in a manner to prevent creases in the fabric.

910.05 Drainage Geocomposites

Size of Sample –

Filter wrap geotextile sample must be a minimum of 75 sft, taken across the full roll width.

Polymer core sample must be a minimum of 6 ft long, taken across the full roll width.
Coupon of the assembled drainage geocomposite must be a minimum of 1 ft long, taken across the full roll width.

Notes:

Manufacturers and suppliers must provide separate samples of filter wrap geotextile and polymer core for testing. These samples must be taken from the same production lot as the assembled drainage geocomposite intended for use on the project.

Include a coupon of the assembled drainage geocomposite when the separate components are submitted for testing.

Assembled coupon and component samples of the drainage geocomposite submitted for testing must be identified with the lot number and/or roll number, the name of the manufacturer, and the product or style number.

914.07 Load Transfer Assemblies; Dowel Baskets

Field Inspection required per Chapter 3.04 of the Materials Quality Assurance Procedures Manual. A Powerpoint in Division 602 of the Construction Manual has been created to assist with the field inspections. Form #0553 is to be used to document the inspections.

Assemblies must meet the requirements of Standard Plan, R-40-I.
All shipments of load transfer assemblies will be accompanied by proper certification documentation.

- Certification from steel (dowel bar) manufacturer.
- Certification from epoxy coating company.
- Documentation of epoxy coating.
- Certification from assembly manufacturer.
- Documentation of bond release.

When shipment is made to a project, each bundle will bear a legible tag with the following information:

- Assembly manufacturer name and plant location.
- Control section/project number.
- Lot number or other identification that will also be shown on the accompanying certification.
- Supplier and/or contractor’s name.

916.02 Silt Fence (full assembly)

Sampling Frequency - Obtain a sample for the first 3,000 ft or fraction thereof. Obtain subsequent samples for each additional 10,000 ft or fraction thereof.

Maximum for VI - 500 ft

Size of Sample - Sample must be a minimum of 25 ft long, taken across the full roll width. Must include at least 3 attached posts and laths.

Notes:

Silt fence must be unwrapped one full roll circumference prior to sampling. Samples must be clean and free of binding tape.

Silt fence must be tested unless provided by an Approved Manufacturer.

Misc. #3 Clay Pipe

Normal Sampling Frequency - One percent of the number of pieces, but not less than 2 pieces of each size except that at the option of the department the following sampling schedule will apply for 4-inch through 24-inch diameter sewer pipe for quantities of 500 or more:

Sampling Schedule - Per the following:

Clay Pipe	Number of Samples
500 to 1,000 pieces	6
1,001 to 2,000 pieces	8
2,001 to 5,000 pieces	11
Over 5,000 pieces	2 samples per 1,000 or fraction thereof

Size of Sample - Full size units for strength test. For absorption tests, 26 inches square to 82 inches square in area from the wall of each piece of pipe tested.

Approved Suppliers

The firms listed in this section have received written permission from the Construction Field Services Division to recertify material for use on Michigan Department of Transportation projects. Supplying materials is also allowed by manufacturers listed in the Approved Manufacturers List.

When recertification of any materials is made by any firm not found on this list, please notify the Construction Field Services Division, Materials Control, immediately.

See also Section 2.02 of the Materials Quality Assurance Procedures Manual.

Approved Suppliers

A.J. Rehmus & Son, Inc., Bay City, MI
ABC Coating Co. of Illinois, Inc., Manteno, IL
ABC Coating Co. of Michigan, Inc., Wyoming, MI
ABC Coating Co. of Minnesota, Inc., Minneapolis, MN
ABC Coating Co. of Oklahoma, Inc., Tulsa, OK
Action Traffic & Maintenance Co., Flint, MI
ADL Systems, Inc., Portland, MI
Allied Seed, L.L.C., Nampa, ID
Alro Steel Corporation, Alpena, MI
Anlaan Corporation, Grand Haven, MI
Art Thureson, Inc., Waterford, MI
Austin Morgan Companies, Clarkston, MI
B&R Reinforcing, Columbus, OH
BARNSCO, Detroit, MI
Bella Concrete Construction, LLC, Houghton Lake, MI
Boomer Construction Materials, Detroit, MI
Brandt Technologies LLC, Bensenville, IL
Burt Forest Products Co., Ann Arbor, MI
C & D Hughes, Inc., Charlotte, MI
C.A. Hull Co., Inc., Walled Lake, MI
Cadillac Culvert, Cadillac, MI
Carroll Distributing and Construction Supply, Inc. (Store 16), Wyoming, MI
Causie Contracting, Inc., Mason, MI
Central Michigan Contracting, Inc., Houghton Lake, MI
Chiles Michigan, Inc., Flat Rock, MI
Cipparrone Contracting, Inc., Southfield, MI
CMA Supply, South Bend, IN
Concrete Central Inc., Grand Rapids and Traverse City, MI
Core and Main LP, Canton, Mason, Shelby Twp. and Wayland, MI
Crawford Contracting, Inc., Mt. Pleasant, MI
D.J. McQuestion & Sons, Inc., LeRoy, MI
Dale Dukes & Sons, Inc., Big Rapids, MI
Davis Construction, Lansing, MI
Dayton Superior Corporation, Miamisburg, OH, Oregon, IL, Valparaiso, IN
Diane Dukes, Inc., Big Rapids, MI
Doan Construction, Ypsilanti, MI
Dornbos Sign & Safety Inc., Charlotte, MI
Eastlund Concrete Construction, Holt, MI
East Jordan Iron Works, Inc., Wyoming, MI
Edward R. White Contractor, Inc., Waterford, MI
Elsey Construction Products, Harper Woods, MI
Environmental Protection Products, Williamsburg, MI
ETNA Supply Co., Chesterfield, Flint, Grand Ledge, Grand Rapids and Holland, MI
ETNA Supply Co., Jackson, Kalamazoo, Mt. Pleasant and Muskegon, MI
ETNA Supply Co., Saginaw, Sault Ste. Marie, Springfield, Traverse City and Wixom, MI
ETNA Supply Co., South Bend, IN and Toledo, OH
Evergreen Seed Supply, Lambertville, MI
F and M Concrete Construction, LLC, Dimondale, MI
Ferguson Enterprises, Inc., Flushing, Kalamazoo, Kentwood, Lansing, and Warren, MI

Firelands Supply Co., Norwalk, OH
Fort Wayne Contracting, Inc., Detroit, MI
Frederick Steel Company, Cincinnati, OH
Future Fence Co., Sterling Heights, MI
G3 Steel Group, Troy, MI
Geo Products, Birmingham, MI
Give 'Em-A-Brake Safety, Grandville, MI
Grant Welding Service, Grant, MI
Green Infrastructure Partners, Inc., Taylor, MI
Great Lakes Concrete Supply, Flint, MI
Harbor Pipe and Supply, Traverse City, MI
Harris Supply Solutions, Inc., Kokomo, IN
Hunt Brothers Concrete Contractors, Inc., Whittemore, MI
Hymmco, Saginaw, MI
Indiana Material Handling, IMH Products, Inc., Indianapolis, IN
InteRebar Fabricators/InteRebar Epoxy, Schererville, IN
J & J Contracting, Ithaca, MI
J & N Construction, LLC, Gaylord, MI
J.D. Russell Co., Utica, MI
JISI Group, LLC, Sterling Heights, MI
Jacklin Steel Supply Co., Escanaba, MI
Jensen Bridge and Supply Co., Grand Rapids and Sandusky, MI
John Deere Landscapes, Ann Arbor, and Grand Blanc, MI
John Deere Landscapes, Clinton and Commerce Townships, MI
John Deere Landscapes, Grand Rapids, Holland, and Kalamazoo, MI
John Deere Landscapes, Dimondale, Livonia, Madison Heights, and Saginaw, MI
John Deere Landscapes, Shelby Township
John Deere Landscapes, Taylor, and Traverse City, MI
Kalamazoo Forest Products, Inc., Otsego, MI
Kamminga & Roodvoets, Inc., Grand Rapids, MI
Kenmark, Inc., Buckley, MI
Klein Brothers Hardwood, Inc., Milford, MI
L.J. Construction, Inc., Clifford, MI
L.W. Lamb, Inc., Saugatuck, MI
Lane Enterprises, Inc., Carlisle, PA
Mack Industries, Inc., White Lake, MI
Manthei Development Corp., Charlevoix, MI
Martin J. Concrete, Inc., Coopersville, MI
Meadow Burke, Palisades Park, NJ
Metro Rebar, West Bloomfield, MI
Michigan Highway Signs, Flint, MI
Michigan Pipe and Valve, Grand Rapids, Holland, Jackson, Kalamazoo, Saginaw, MI
Michigan Pipe & Valve, Traverse City, MI
Midway Contractor Supply, Negaunee, MI
Midwest Pipe Coatings, Schererville, IN
Milbocker & Sons, Inc., Allegan, MI
Miller Bridge Construction, LLC, Portland, MI
Miller Development, Inc., Weidman, MI
Miller Products & Supply Company, Iron Mountain, MI

Nashville Construction Company, Nashville, MI
Nationwide Fence & Supply Co., Chesterfield, MI
North Coast Roofing Systems, Grand Rapids, MI
Northern Concrete Pipe, Bay City, Charlotte, Clarkston, and Wyoming, MI; Sylvania, OH
Northern Construction Services Corp., Niles, MI
NuTek Steel, Toledo, OH
Nucor Rebar Fabrication Midwest, LLC, Bourbonnais, IL; Lansing, MI
OEM Distribution, LLC, Detroit, MI
Oglesby Construction, Inc., Norwalk, OH
Oldcastle Infrastructure, Kalamazoo, MI
One Supply Group, Auburn Hills, MI
P.K. Contracting, Inc., Lake City, MI
Power Line Supply Company, Reed City, MI
Prestress Services Industries, LLC, Decatur, IN and Mount Vernon, OH
Rathco Safety Supply, Inc., Portage, MI
Remington Construction Company, Inc., Mattawan, MI
Rhino Seed and Landscape Supply, Bradley and Brighton, MI
Rightway Fence Co., Sterling Heights, MI
Sanches Construction Company, Lansing, MI
Simcote, Inc., Saint Paul, MN and Marion, OH
Snowden, Inc., Escanaba, MI
Standale Lumber, Grandville, MI
StressCrete Group, Atchison, KS
Striker Supply, Traverse City, MI
Sweeney Construction Materials, Novi, MI
T & D Concrete Construction LLC, Mason, MI
Titusville Fabricators, Inc., Franklin, PA
Tri-Valley Landscaping, Inc., Saginaw, MI
Upper Peninsula Concrete Pipe Co., Escanaba, MI
Van Laan Construction Supply, Dutton, MI
Wady Industries, Maqouketa, IA
Watson Bowman Acme Corp., Amherst, NY
Weyand Bros. Inc., Saginaw, MI
White Cap, LP, Byron Center, Detroit, Grand Rapids, Highland, Lansing, MI
White Cap, LP, Madison Heights, Northville, Traverse City, and Wyoming, MI

Approved Manufacturers

The materials in this section may be accepted for use on Michigan Department of Transportation projects on the basis of certification from the suppliers listed under specific materials.

This Approved Manufacturers List is in accordance with the 2020 Standard Specifications for Construction.

See also Section 2.02 of the Materials Quality Assurance Procedures Manual.

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Approved Distribution Facilities (not manufacturer specific)
901 Cement	Amrize Cement Inc. - Alpena, MI; Paulding, OH; and Bloomsdale, MO; Bath, Ontario, Canada Ash Grove - Foreman, AR; Chanute, KS; Mississauga, Ontario, Canada Buzzi Unicem USA - Chattanooga, TN; Festus MO; Greencastle, IN Central Plains Cement - Sugar Creek, MO Dai Doung Cement Company - Thanh Hoa Province, Vietnam Fairborn Cement Company - Fairborn (Xenia), OH Goltas Cement Company - Isparta, Turkey Heidelberg Materials - Logansport and Mitchell, IN; Union Bridge, Maryland; Fleetwood, PA; Picton, Ontario, Canada Holcim - Hammam, Dalaa, and Oggaz, Mascara, Algeria; Lykovrissi, Greece; Fujariah, United Arab Emirates Illinois Cement Co. - LaSalle, IL Kosmos Cement Co. - Louisville, KY Long Son Cement Company - Thanh Hoa Province, Vietnam McInnis Cement - Port Daniel-Gascons, Quebec, Canada Quikrete Cement - Hannibal, MO; Martinsburg, WV St-Lawrence Cement - Joliette, Quebec, Canada St. Mary's Cement, Inc. (US) - Detroit and Charlevoix, MI; Bowmanville and St. Mary's, Ontario, Canada	Amrize Cement Inc.- Detroit, Essexville, Muskegon, St. Joseph, Wixom and Zilwaukee, MI; Chicago, Lemont and Summit, IL; Toledo, OH; Green Bay, WI Ash Grove - Detroit, and Dundee, MI; Duluth, MN Buzzi Unicem USA - Elmira and Grandville, MI; Elkhart, IN; Joliet, IL High Grade Materials - Grand Rapids, MI Hollingshead Cement - Savannah, GA; Jacksonville, FL; Middletown, OH Ozinga - Chicago, IL; Muskegon, MI St. Mary's Cement, Inc. (US) - Cleveland 1, Cleveland 2, Marysville, Newcomerstown and Toledo, OH; Ferrysburg, MI Stubbe's Cement - Princeton, Ontario, Canada Sultan Cement, LLC - Detroit, MI

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Approved Distribution Facilities (not manufacturer specific)
901.06 Slag Cement	Amrize Cement Inc. - South Chicago, IL; Beachville and Stoney Creek, Ontario, Canada Anshan Iron and Steel - Liaoning, China Ash Grove - Foreman, AR; Detroit, MI; Mississauga, Ontario, Canada Heidelberg Materials - Speed, IN Lehigh Cement Company, LLC - Middlebranch, OH National Cement Company - Beni Suef, Egypt Skyway Cement Company, LLC - Chicago, IL St. Mary's Cement, Inc. (US) - Charlevoix and Detroit, MI; Milwaukee, WI	Amrize Cement Inc. - Detroit, Essexville, Muskegon, St. Joseph, Wixom and Zilwaukee, MI; Chicago, Lemont and Summit, IL; Toledo, OH; Green Bay, WI Ash Grove - Dundee, MI High Grade Materials - Grand Rapids, MI Ozinga - Chicago, IL; Muskegon, MI St. Mary's Cement, Inc. (US) - Cleveland 1, Cleveland 2, Marysville and Newcomewrstown OH; Ferrysburg, MI Sultan Cement, LLC - Detroit, MI
901.07 Pozzolanic Admixtures (Fly Ash) for Concrete	Amrize Cement Inc. - Will Co. Plant, Romeoville, IL; Elm Road Generating Station, Oak Creek, IL; Columbia, Portage, WI; Edgewater Sta. Unit 5, Sheboygan, WI; Pleasant Prairie, Kenosha, WI; Weston #3, Wausau, WI Charah, Inc. - Zimmer Power Station, Moscow, OH; Miami Fort Unit 7 & 8, North Bend, OH EM Resources LLC - Monroe Power Plant, Monroe, MI; Scherer Plant, Juliette, GA; Cayuga Power Plant, Cayuga, IN; Schahfer Station, Unit 17 & Unit 18, Wheatfield, IN; Labadie Power Station, Labadie, MO; Coal Creek Steam Generating Plant, Underwood, ND; Miller Power Plant, Quinton, AL Ozinga - Belle River Power Plant, East China, MI; Dallman Station, Springfield, IL Separation Technologies, LLC - Cardinal Power Plant, Brilliant, OH; Clifty Creek Power Station, Madison, IN; Longview Power Plant, Maidsville, WV Waste Mgmt./FlyAsh Direct - Zimmer Power Plant, Moscow, OH; Miami Fort Unit 7 & 8, North Bend, OH; Avon Lake Unit 9, Cleveland, OH; Joppa Generating Station, Joppa, IL	Amrize Cement Inc. - Wixom, MI Ash Grove - Dundee, MI High Grade Materials - Grand Rapids, MI

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
903.03 Latex Admixture For Concrete	Trinseo BASF Corporation Polytherm Systems, Inc., General Tires	
904.03C Emulsified Asphalt	See Current List of Emulsified Asphalts at Construction Field Services Web Page. Instructions to Construction Field Services web page: From MDOT home page (michigan.gov/mdot), click on about MDOT (left side), then click on Highway Field Services, and then click Construction Field Services. The Approved Emulsified Asphalt Suppliers List is under Resources & Publications.	

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location

905.03
Bar Reinforcement (Uncoated)
	ABC Coating Co. of MI, Inc.
	ABC Coating Co. of IL, Inc.
	ASI Alton Steel, Inc.
	BARNSCO
	Byer Steel (formerly A.B. Steel)
	CMC Rebar
	CMC Steel
	  CMC Steel Florida
	  CMC New Jersey
	  CMC Steel Oklahoma
	  CMC Tennessee
	  CMC Steel Texas
	  CMC Steel
	Cascade Steel Rolling Mills
	EVRAZ Rocky Mountain Steel
	Great Lakes Concrete Supply
	Gerdau Ameristeel Corporation
	  Charlotte Steel Mill Div.
	  Jackson Steel Mill Div.
	  Midlothian Steel Mill Div.
	  St. Paul Steel Mill Div.
	HYBAR LLC
	HYMMCO, LLC
	Nucor Steel
	  Nucor Steel Auburn, Inc.
	  Nucor Steel Birmingham, Inc.
	  Nucor Steel Connecticut, Inc
	  Nucor Steel Jackson, Inc.
	  Nucor Steel Kankakee, Inc.
	  Nucor Steel Marion, Inc.
	  Nucor Steel Seattle, Inc
	  Nucor Steel Sedalia, LLC
	  Nucor Steel Texas, Inc.
	  Nucor Steel Utah, LLC
	Optimus Steel, LLC
	Steel Dynamics Inc.
	
	White Cap, LP
		Wyoming, MI
		Manteno, IL
		Alton, IL
		Detroit, MI
		Cincinnati, OH
		Kankakee, IL
		
		Baldwin, FL
		Sayreville, NJ
		Durant, OK
		Knoxville, TN
		Seguin, TX
		Cayce, Columbia, SC
		McMinnville, OR
		Pueblo, CO
		Flint, MI
		
		Charlotte, NC
		Jackson, TN
		Midlothian, TX
		St. Paul, MN
		Osceola, AR
		Saginaw, MI
		
		Auburn, NY
		Birmingham, AL
		Wallingford, CT
		Flowood, MS
		Bourbonnais, IL
		Marion, OH
		Seattle, WA
		Sedalia, MO
		Jewett, TX
		Plymouth, UT
		Vidor, TX
		Pittsboro, Columbia City, IN; Roanoke, VA
		Lansing and Wyoming, MI

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
905.03C Bar Reinforcement (Epoxy Coated)	Great Lakes Concrete Supply HYMMCO, LLC Pacific Highway Products, LLC White Cap, LP <u>Epoxy Coating Companies</u> ABC Coating Co. ABC Coating Co. of OK, Inc. ABC Coating Co. of MI, Inc. ABC Coating Co. of IL, Inc. ABC Coating Co. of MN, Inc., American Highway CMC Rebar Corrosion Control, Inc. (CCI) Lane Enterprise, Epoxy Coating Div. Midwest Pipe Coatings Nucor Rebar Fabrication Midwest, LLC Simcote Simcote Simcote Titusville Fabricators, Inc. Wady Industries, Inc.	Flint, MI Saginaw, MI Marion, OH Lansing and Wyoming, MI Tulsa, OK Wyoming, MI Manteno, IL Roseville, MN Kankakee, IL Kankakee, IL; Knoxville, TN; Waxahachie, TX Auburn, NY Carlisle, PA Schereville, IN Bourbonnais, IL Saint Paul, MN Marion, OH Franklin, PA Maquoketa, IA
905.06 Welded Steel Wire Reinforcement (Mesh)	Hallett Wire Products Co. Insteel Wire Products Iowa Steel & Wire National Wire, LLC Numesh Nucor Steel Connecticut, Inc. Oklahoma Steel & Wire Co. Inc. Structural Reinforcement Products Inc. Tatano Wire Products LLC Wire Mesh Corporation (WMC) - Nelson Wire and Steel, LLC	 Kingman, AZ; Jacksonville, FL; Hickman, KY; St Joseph, MO; Mt Airy, NC; Upper Sandusky, OH; Hazelton, PA; Gallatin, TN; Dayton, TX Centerville, IA Conroe, TX Glen Falls, NY Wallingford, CT Madill, OK Hazelton, PA Lemont Furnace, PA Oglesby, IL; Jacksonville, FL New Salem, PA

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
905.07 Strand for Prestressed Concrete	Bekaert Corporation Insteel Wire Products Kiswire, Inc. Liberty Strand Tech Manufacturing, Inc. RettCo Steel, LLC Sumiden Wire Products Corporation Wire Mesh Corporation (WMC)	Van Buren, AR Sanderson, FL; Gallatin, TN; Houston, TX Newberry, SC Summerville, SC Newnan, GA Stockton, CA; Dickson, TN St. Matthews, SC; Conroe, TX
905.08 Tendons for Lateral Post Tensioning		
908.11A Guardrail, Steel Beam Elements, Anchorage, Bridge, Shoes, Departing End Terminals (End Sections)	Contech Engineered Solutions, LLC Gregory Highway Products Highway Safety Corporation IMH Products, Inc. R.G. Steel Corporation SPIG Industry LLC Valtir, LLC	 Glastonbury, CT Indianapolis, IN Pulaski, PA Abingdon, VA Lima, OH
908.12 Steel Posts for Beam Guardrail	Contech Engineered Solutions, LLC Gregory Highway Products Highway Safety Corporation IMH Products, Inc. R.G. Steel Corporation SPIG Industry LLC Valtir, LLC	 Glastonbury, CT Indianapolis, IN Pulaski, PA Abingdon, VA Lima, OH
909.04A Reinforced Concrete Pipe	County Materials Corporation Green Infrastructure Partners, Inc. Northern Concrete Pipe Oldcastle Infrastructure Upper Peninsula Concrete Pipe Co.	Marathon, WI Taylor, MI Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Elgin and Romeoville, IL Escanaba, MI
909.04C Non-Reinforced Concrete Pipe	Green Infrastructure Partners, Inc. Northern Concrete Pipe Upper Peninsula Concrete Pipe Co.	Taylor, MI Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Escanaba, MI

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
909.04D Precast Concrete Box Sections	ADL Systems, Inc. Mack Industries Northern Concrete Pipe Oldcastle Infrastructure Oldcastle Infrastructure, Inc. (dba Quality Precast) Upper Peninsula Concrete Pipe Co. Wieser Concrete Products, inc.	Portland, MI White Lake, MI, and Toledo, OH Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Elgin, IL Kalamazoo, MI Escanaba, MI Portage, WI
909.04E Precast Concrete End Section For Culverts & Sewers	County Materials Corporation Green Infrastructure Partners, Inc. Northern Concrete Pipe Oldcastle Infrastructure Upper Peninsula Concrete Pipe Co.	Marathon, WI Taylor, MI Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Elgin and Romeoville, IL Escanaba, MI
909.04G Precast Concrete Three-Sided or Arch Culverts	ADL Systems, Inc. Ecospan Advance Concrete Products Adspan Contech Engineered Solutions, LLC BEBO Contech Engineered Solutions, LLC Conspan Mack Industries Conspan Northern Concrete Pipe Northern Arch Northern Concrete Pipe Hyspan Peninsula Prestress, Inc. Low/Span Upper Peninsula Concrete Pipe Co. Conspan Low/Span Wieser Concrete Products, Inc.	Design Portland, MI Highland, MI Huber Heights, OH Huber Heights, OH White Lake, MI Bay City, MI Bay City, MI Clarksville, MI Escanaba, MI Portage, WI

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
909.05A Corrugated Steel Pipe	Armco Steel Corporation Bark River Culvert & Equipment Co. Contech Engineered Solutions, LLC Jensen Bridge & Supply Co. Lane Enterprises, Inc. Cadillac Culvert St. Regis Culvert, Inc. Worthington Steel	South Bend, IN Escanaba, MI Mason, MI; Mitchell and South Bend, IN; Portage, WI; Shakopee, MN; Ashland and Winchester, KY; Anderson, SC and Canfield, OH Grand Rapids and Sandusky, MI Pulaski, PA Cadillac, MI Charlotte, MI Delta, OH
909.06 Corrugated Polyethylene Pipe (CPE/HDPE)	Advanced Drainage Systems, Inc.	Owosso, MI; Findlay, London and Wooster, OH
909.07B Pipe for Underdrains Corrugated Plastic Tubing (Perforated & Non-Perforated) (Wrapped & Non-Wrapped)	Advanced Drainage Systems, Inc. Baughman Tile Co., Inc. Cervell Drainage Products Hancor, Inc. Haviland Drainage Prinsco, Inc.	Napoleon, OH; Owosso and Clifford, MI Paulding, OH Lordstown, OH Findlay, OH Haviland, OH Chatsworth, IL
909.07C Pipe for Underdrains Underdrain Outlet 2. Corrugated Steel Pipe	Armco Steel Corporation Bark River Culvert & Equipment Co. Contech Engineered Solutions, LLC Jensen Bridge & Supply Co. Lane Enterprises, Inc. Cadillac Culvert St. Regis Culvert, Inc. Worthington Steel	South Bend, IN Escanaba, MI Mason, MI; Mitchell & South Bend, IN; Portage, WI; Shakopee, MN; Ashland and Winchester, KY; Anderson, SC; and Canfield, OH Grand Rapids and Sandusky, MI Pulaski, PA Cadillac, MI Charlotte, MI Delta, OH

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
909.08B Culvert, Downspouts 1. Corrugated Steel Pipe	Armco Steel Corporation Bark River Culvert & Equipment Co. Contech Engineered Solutions, LLC Jensen Bridge & Supply Co. Lane Enterprises, Inc. Cadillac Culvert St. Regis Culvert, Inc. Worthington Steel	South Bend, IN Escanaba, MI Mason, MI; Mitchell and South Bend, IN; Portage, WI; Shakopee, MN; Ashland and Winchester, KY; Anderson, SC; and Canfield, OH Grand Rapids and Sandusky, MI Pulaski, PA Cadillac, MI Charlotte, MI Delta, OH
912.05 Structural Timber & Lumber	American Timber and Steel Co., Inc. Central Nebraska Wood Preservers, Inc. Iowa Wood Preservers, Inc. John Biewer Lumber Company Straits Wood Treating, Inc. Midwest Timber Woodstock, Inc.	Norwalk, OH Sutton, NE Oskaloosa, IA Lansing and St Clair, MI Bay City, MI Edwardsburg, MI West Branch, MI
912.08 Wood Posts and Blocks for Guardrail and Highway Signs (Dimension Sawed)	American Timber and Steel Co., Inc. Central Nebraska Wood Preservers, Inc. Iowa Wood Preservers, Inc. John Biewer Lumber Company Straits Wood Treating, Inc. Midwest Timber Woodstock, Inc.	Norwalk, OH Sutton, NE Oskaloosa, IA St. Clair, MI Bay City, MI Edwardsburg, MI West Branch, MI

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
913.06 Precast Reinforced Concrete Units for Drainage Structures (Tops, Risers and Sump Bases)	Advance Concrete Products Co. Bush Concrete Products, Inc. Consumers Concrete Products Green Infrastructure Partners, Inc. County Materials Corporation Elmer's Grand Valley Concrete Products Mack Industries Mack Vault of Toledo-a Div. of Mack Industries Northern Concrete Pipe Norwalk Concrete Industries Oldcastle Infrastructure Oldcastle Infrastructure, Inc. (dba Quality Precast) Upper Peninsula Concrete Pipe Co.	Highland, MI (Specialty Items) Muskegon, MI Kalamazoo, MI Taylor, MI Marathon, WI Traverse City, MI Grand Rapids, MI White Lake, MI Bowling Green, OH Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Norwalk, OH Elgin, IL Kalamazoo, MI Escanaba, MI
913.07 Precast Concrete Bases	See Spec. 913.06, Drainage list	
913.09 Slope Pavement Blocks	4D, Inc. Bark River Concrete Products Best Block Company Carlesimo Products, Inc. Concrete Service, Inc. Consumers Concrete Products Fendt Builder's Supply, Inc. Ferguson Block Co., Inc. Grand Blanc Cement Products Jansen Block Co. Northern Concrete Pipe	Midland, MI Bark River, MI Warren, MI Farmington, MI Traverse City, MI Kalamazoo and South Haven, MI Ann Arbor and Farmington Hills, MI Davison, MI Grand Blanc, MI Grand Rapids, MI Grand Rapids, MI

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
914.07 Transverse Pavement Joints 1. Dowel Bars (Uncoated) See Spec. 914.07A for Epoxy Coating Manufacturers (Coaters).	Alton Steel, Inc. CMC Steel CMC New Jersey CMC Tennessee Cascade Steel Rolling Mills Nucor Steel Kankakee Inc. Marion Inc. Steel Dynamics, Inc.	Alton, IL Sayreville, NJ Knoxville, TN McMinnville, OR Bourbonnais, IL Marion, OH Pittsboro, IN; Roanoke, VA
914.07 Load Transfer Assemblies; Dowel Baskets	American Highway Barnsco Boomer Construction Materials CMC Paving Solutions CMT Highway, LLC Pacific Highway Products, LLC TyE Bar, LLC	Kankakee, IL Detroit, MI Detroit, MI Kankakee, IL Durant, IA Marion, OH Bethel Park, PA
914.07A Tranverse Pavement Joints 1. Dowel Bars (Epoxy Coated) For coating info. See QPL 914.07A2 for approved material and manufacturers.	Barnsco Boomer Construction Materials CMC Paving Solutions CMT Highway, LLC Pacific Highway Products, LLC TyE Bar, LLC <u>Epoxy Coating Companies</u> ABC Coating Co. of MI, Inc. American Highway CMC Rebar CMT Highway, LLC Lane Enterprises Midwest Pipe Coating, Inc. Simcote	Detroit, MI Detroit, MI Kankakee, IL Durant, IA Marion , OH Bethel Park, PA Wyoming, MI Kankakee, IL Kankakee, IL East Moline, IL Carlisle, PA Schererville, IN Marion, OH
914.08 Transverse End of Pour Joint Devices B. Deformed Bars	Bar Manufacturers See Reinforcement Bar Manufacturers Spec. 905.03	Epoxy Coating Material See Reinforcement Bar, Spec 905.03C and QPL 905.03C.
914.09 Straight and Bent Tie Bars for Longitudinal Pavement Joints, (Lane Ties)	Bar Manufacturers See Reinforcement Bar Manufacturers Spec. 905.03	Epoxy Coating Material See Reinforcement Bar, Spec 905.03C and QPL 905.03C.

Approved Manufacturers		
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location
916.02 Silt Fence (full assembly) Must be assembled using a qualified geotextile fabric listed in the QPL 910.04.	ACF Environmental – Ferguson Waterworks American Excelsior Co. Inc. Cherokee Manufacturing Core and Main DGI Industries Environmental Protection Products Geo-Synthetics Geoproducts, Inc. Hanes Geo Components Klein Brothers Hardwood Inc. MKB Company Newberry Wood Products Pallen Enterprises Rhino Seed and Landscape Supply Western Green WINFAB (Willacoochee) Industrial Fabrics, Inc.	South Bend, IN; Richmond, VA Westland, MI South Saint Paul, MN Schaumburg, IL Bennington, NH Williamsburg, MI Waukesha, WI Birmingham, MI Charlotte and Winston-Salem, NC, Wixom and Wyoming, MI Milford, MI Belleville, PA; Portage, WI Newberry, MI Conyer, GA Bradley, MI Evansville, IN Nashville, GA
918.06 Precast Concrete Handholes & Manholes for Electrical & Telephone Connections	Advance Concrete Products Bush Concrete Products, Inc. Carlesimo Products, Inc. Consumers Concrete Products Elmer's Grand Valley Concrete Products, Inc. Hartford Concrete Products, Inc. Mack Industries Northern Concrete Pipe Norwalk Concrete Industries Oldcastle Infrastructure Oldcastle Infrastructure, Inc. (dba Quality Precast) Trucast LLC Upper Peninsula Concrete Pipe Co.	Highland, MI Muskegon, MI Farmington, MI Kalamazoo, MI Traverse City, MI Grand Rapids, MI Hartford City and Ashley, IN White Lake, MI Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Norwalk, OH Elgin, IL Kalamazoo, MI Zeeland, MI Escanaba, MI
919.05 Wood Sign Posts	American Timber and Steel Co., Inc. John Biewer Lumber Company Straits Wood Treating, Inc. Midwest Timber Woodstock, Inc.	Norwalk, OH St. Clair, MI Bay City, MI Edwardsburg, MI West Branch, MI

Qualified Products List

The materials in this section may be accepted for use on Michigan Department of Transportation projects based on the trade name, model number, etc., as listed.

This Qualified Products List is in accordance with the 2020 Standard Specifications for Construction.

Also see Section 5.01 of the MQAP Manual.

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
603.03B2 Adhesive Systems for Grouting Dowel Bars and Tie Bars for Full-Depth Concrete Pavement Repairs Note: Use these Qualified Products for grouting repairs to existing concrete in the same direction of traffic in the same lane of repair. For grouting lane ties (deformed bars positioned transverse to the direction of traffic located between traffic lanes) use QPL 712.03J, “Adhesive Systems for Structural Anchors and Lane Ties”.	Ultrabond ASF-1000	Adhesives Technology Corp.
	Ultrabond ASF-2000	Adhesives Technology Corp.
	Ultrabond 1	Adhesives Technology Corp.
	Ultrabond 2	Adhesives Technology Corp.
	Ultrabond HS-1CC	Adhesives Technology Corp.
	UltraBond HS-200	Adhesives Technology Corp.
	UltraBond 1300	Adhesives Technology Corp.
	Inject-Tite Standard Set	ANKR-Tite Fastening Systems
	Inject-Tite Fast Set	ANKR-Tite Fastening Systems
	Aka Bond	Axson North America (Formerly Akemi Plastics)
	Aka Bond 550XP	Axson North America (Formerly Akemi Plastics)
	Aka Bond 550XPP	Axson North America (Formerly Akemi Plastics)
	BHS-1250	Blackhawk Sales Company, Inc.
	BHS-1250XP	Blackhawk Sales Company, Inc.
	CanRez 800	Cansto Coatings
	Araldite AW / HW 8561	Ciba Specialty Chemicals Corp.
	Spec Bond 201	Conspec by Dayton Superior, Inc.
	Highway Fast Set Epoxy	Dayton Superior Corp.
	Pro-Poxy 300 Fast	Dayton Superior Corp.
	DeWALT AC50	DeWALT
	DeWALT AC100+ Gold	DeWALT
	DeWALT PE1000+	DeWALT
	DeWALT Pure50+	DeWALT
	DeWALT Pure110+	DeWALT
	TRU Grip HI-Modepoxy 590	J. Dedoes, Inc.
	Tru-Grip 591	J. Dedoes, Inc.
	AWA Gel	E-Chem
	Dural Fast Set Epoxy Gel	Euclid Chemical Company
	Dural HS Gel	Euclid Chemical Company
	Futura Bond 566	Futura Adhesives & Chemicals
	Hilti RSE DOT	Hilti, Inc.
	Redhead A7+	ITW Commercial Construction
	Redhead C6+	ITW Commercial Construction
	Redhead G5+	ITW Commercial Construction
	Epcon A7	ITW Ramset/Red Head
	Epcon-Ceramic 6	ITW Ramset/Red Head
	SurePoxy 117	Kaufman Products
	Kelipoxy II	Kelken Construction Systems
(Continued)	Dynapoxy EP-430 FAST	Pecora Corporation

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
603.03B2 Adhesive Systems for Grouting Dowel Bars and Tie Bars for Full-Depth Concrete Pavement Repairs	Poly-Carb Mark 198.4 Polyject/Polybac 1257 Polyject/Polybac 1295 Speed Bond #1 Sikadur Injection Gel Sikadur 881 DBA Sikadur DOT-SP13 Arcylic -Tie AT Epoxy Tie SpecPoxy 3000 FS Dowel Bar Adhesive #5 Pro Poxy 300 Pro Poxy 300 FAST Rezi-Weld Gel Paste Rezi-Weld Gel Paste State	Olin Epoxy-Poly-Carb (Blue Cube Operations LLC) Olin Epoxy-Poly-Carb (Blue Cube Operations LLC) Polygem, Inc. Polygem, Inc. Prime Resins, Inc. Sika Corporation Sika Corporation Sika Corporation Simpson Strong-Tie Company, Inc. Simpson Strong-Tie Company, Inc. SpecChem Superior Epoxies & Coatings Unitex Unitex W.R. Meadows, Inc. W.R. Meadows, Inc.
706.03S Penetrating Water Repellent Treatment for Concrete Surfaces (Protective Coating for Concrete)	Application Rate, sq ft/gal ATS-200 150-200 Baracade Silane 100C 150-200	 Advanced Chemical Technologies, Inc. Euclid Chemical Company
707.02 Bushings for Pins & Link Plates	CJ Garmax	TriStar Garlock

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
712.03J Adhesive Systems for Structural Anchor & Lane Ties* Note: *Lane Ties defined as deformed bars positioned transverse to the direction of traffic located between lanes. For grouting dowel bars and tie bars (bars positioned to existing concrete in the direction of the traffic in the same lane as the repair) use QPL 603.03B2, “Adhesive Systems for Grouting Dowel Bars for Full-Depth Concrete Pavement Repairs”. Note 1. Anchors shall be installed per manufacturer’s recommendations with a minimum embedment depth of 12 diameters for reinforcing steel and 9 diameters for threaded bolts. Pull-out Testing is required per MQAP Manual Section 3.03. Note 2. Material is limited to the shelf-life recommendations by the manufacturer.	Name — Adhesive Type — Mixing & Inject. Ultrabond 1 — Epoxy — Yes HS-200 — Epoxy — Yes Hilti HIT-HY 100 — Urethane-Methacrylate — Yes Hilti HIT-HY 200-A V3 — Urethane-Methacrylate — Yes Hilti HIT-HY 200-R V3 — Methacrylate — Yes Hilti HIT-RE-500v3 — Epoxy — Yes Redhead A7+ — Epoxy — Yes Super Por-Rok — Non-Shrink Grout — Yes DeWALT Pure 110+ — Epoxy — Yes DeWALT Pure 220+ — Epoxy — Yes Sika AnchorFix 500 — Epoxy — Yes Pro-Poxy 300 — Epoxy — Yes Rezi Weld Gel — Paste State Epoxy — Yes	Adhesives Technology Corp. Adhesives Technology Corp. Hilti, Inc. Hilti, Inc. Hilti, Inc. Hilti, Inc. ITW Commercial Construction CGM, Inc. DeWALT DeWALT Sika Corporation Unitex W.R. Meadows, Inc.

Qualified Products List (QPL)		
Spec # and Material Name	Product Name	Manufacturers or Suppliers
712.03K Structure Expansion Anchors (Mechanical Expansion Anchors) Pull-out Testing is required per MQAP Manual Section 3.03. Note: Mechanical Expansion Anchors shall be set by applying the manufacturer's specified torque. The turn of the nut method will not be an acceptable alternative.	1. Pre-Drilled Flush Type a) Hilti HDI (3/8", ½" , 3/4" dia. anchors only) 2. Pre-Drilled Stud Type - Not suitable for lane ties or for guardrail end shoes because of exposed thread. a) Kwik-Bolt III 3/8" dia. anchor - min. embedment = 2 ½" 1/2" dia. anchor - min. embedment = 3 ½" 5/8" dia. anchor - min. embedment = 4"	
712.03L Mechanical Reinforcement Splicing Note: Splices used to connect precast structural elements shall be high strength splices.	BPI Barsplicer System Grip-Twist Threaded Position Coupler Taper Threaded Grip-Twist Zap Screwlok Tru-Splice Stainless Steel Bar-Lock L-Series DBDI Lenton Lenton Form Saver Lenton Interlok (High Strength) Lenton Position Coupler NMB Splice Sleeve (High Strength)	BarSplice Products, Inc., Dayton, OH BarSplice Products, Inc., Dayton, OH BarSplice Products, Inc., Dayton, OH BarSplice Products, Inc., Dayton, OH Contractors Materials Company, Cincinnati, OH Dayton Superior Corp., Miamisburg, OH Dayton Superior Corp., Miamisburg, OH nVent Lenton, Solon, OH nVent Lenton, Solon, OH nVent Lenton, Solon, OH nVent Lenton, Solon, OH Splice Sleeve North America, Inc., Livonia, MI

Qualified Products List (QPL)		
Spec # and Material Name	Product Name	Manufacturers or Suppliers
712.03Y Embedded Galvanic Anodes	LifeAnode 65, 105 and 160 MasterProtect CP Models: 8065, 8105, 8150 RebaGuard RebaGuard Plus RebaGuard Ultra Sentinel-GL Mapeshield I 70, I 105, I 10/10, I 10/20, I 30/10, and I 30/20 NoCo Patchguard Sika Galvashield XP Sika Galvashield XP+ Sika FerroGard 650, 670, 675 Galvashield XP2 Galvashield XP4 Glavashield XPX Galvashield XP+ Galvashield XPC Galvashield XPT	ARTAZN LLC BASF Chemical Company CPT/No Corrosion CPT/No Corrosion CPT/No Corrosion Euclid Chemical Co. Mapei Corporation NoCo Sika Corporation Sika Corporation Sika Corporation Vector Corrosion Technologies, Inc. Vector Corrosion Technologies, Inc. Vector Corrosion Technologies, Inc. Vector Corrosion Technologies, Inc. Vector Corrosion Technologies, Inc. Vector Corrosion Technologies, Inc.
713.02B Sealant for Perimeter of Beam Repairs Note: No silicone materials - only polyurethane (PU) or PU blended materials that are paintable. Typically 1 week cure prior to painting. All non-sag material.	Bostik 2020 Duralink (F1200) Loxon H1 Loxon S1 Sikaflex-15LM SikaHyflex-150 LM Sikaflex NP1 Vulkem 116 XtraBond 9500	Bostik US Chem Link Sherwin-Williams Sherwin-Williams Sika Corporation Sika Corporation Sika Corporation Tremco, Inc. Premier Industrial Supply
715.02 Coating Systems for New Hanger Assemblies	See Coating Systems for Steel Structures, Hanger Assemblies and End Diaphragms QPL 915	

Qualified Products List (QPL)		
Spec # and Material Name	Product Name	Manufacturers or Suppliers
715.02 Abrasive, Low Dusting Note: The blasting profile produced by these abrasives will depend on the equipment used. It is the responsibility of the contractor to produce a profile within the 1.0 to 2.8 mils specified range. The abrasive additive, Blastox, may be used with any of the listed low-dusting abrasives.	20/40 40/70 KinetiX 20/70 Black Magic Coal Slag Black Diamond Abrasive - Coal Slag GMA Garnet Blast Black Shot Granulated Slag Jetmag 32B4 StarBlast XL Emerald Creek Garnet Blackjack MSM, Waupaca Materials Green Diamond Products 3060, 3050, 2050, 1650 and 8x16 Black Beauty Black Beauty Fine Black Beauty Platinum Fine and Medium Black Beauty Medium Sure/Cut Velocity Fine and Coarse Alluvial River Garnet Ebony Grit - Copper Slag International Garnet 20-40 International Garnet 30-60 Galaxy Garnet 30-60 Sharpshot XL - Iron Silicate	10X Engineered Materials, Wabash, IN 10X Engineered Materials, Wabash, IN 10X Engineered Materials, Wabash, IN Abrasives, Inc., Minneapolis, MN U.S. Minerals, Tinley Park, IL GMA Garnet Pty Ltd, Narngulu, WA, Australia Bell & MacKenzie Co. Ltd, Hamilton, Ontario Carpenter Brothers Inc., Mequon, WI The Chemours Company, Wilmington, DE Emerald Creek Garnet, Fernwood, ID Faulks Brothers Constr. Co., Inc., Waupaca, WI Green Diamond Performance Materials, Riddle, OR Harsco Environmental, Camp Hill, PA Harsco Environmental, Camp Hill, PA Harsco Environmental, Camp Hill, PA Harsco Environmental, Camp Hill, PA Harsco Environmental, Camp Hill, PA Marco Group International, Beaver Falls, PA Opta Minerals Inc. Opta Minerals Inc. Opta Minerals Inc. Opta Minerals Inc. Universal Minerals Kentucky, Inc., Louisville, KY

Qualified Products List (QPL)		
Spec # and Material Name	Product Name	Manufacturers or Suppliers
803.02B Detectable Warning Surfaces (ADA Compliant Sidewalk Ramps), 1. Cast-in-Place	AlertCast	AlertTiles, Wilmington, NC
	ADA Solutions Cast in Place Paver - Composite	ADA Solutions, Jefferson, OH
	ADA Solutions Cast in Place Replaceable - Rectangular & Radius - Composite	ADA Solutions, Jefferson, OH
	ADA Solutions Iron Dome© - Cast in Place Replaceable - Cast Iron	ADA Solutions, Jefferson, OH
	Iron Dome SF	ADA Solutions, A Division of SureWerx USA Inc, Jefferson, OH
	CAST-DWD	Pioneer Detectable, LLC
	DetecTile Replaceable Tactile Panel	DetecTile Corporation
	Duralast® Detectable Warning Plates	East Jordan Iron Works, East Jordan, MI
	Access Tile Cast In Place Replaceable - Composite	SureWerx, Elgin, IL
	Advantage Classic - Cast Iron	SureWerx, Elgin, IL
	Advantage Premier - Cast Iron	SureWerx. Elgin, IL
	Armor-Tile Cast in Place - Composite	SureWerx, Elgin, IL
	Composite DWP	Neenah Enterprises, Inc., Neenah, WI
	NF Detectable Warning Plate	Neenah Foundry Company, Neenah, WI
	TufTile Cast Iron Tile	TufTile, Inc.
	TufTile Galvanized Steel Tile	TufTile, Inc.
	TufTile Polymer Tactile Tile	TufTile, Inc.
2. Surface Applied* *Note: Surface applied detectable warning surfaces may only be used to retrofit existing concrete	ADA Solutions Surface Applied - Composite	ADA Solutions, Jefferson
	Alerttile	Detectable Warning Systems, Wilmington, NC
	Armor-Tile Surface Applied - Composite	SureWerx, Elgin, IL

Qualified Products List (QPL)			
Spec # and Material Name	Product Name		Manufacturers or Suppliers
811.03D1 Waterborne, Liquid Pavement Marking Material	Product ID UC15-55184 UC35-55185 UC15-55186 UC35-55187 982211 982212 982221 982222 982201 982202 985205 985203 800171 800327 TM-2582 TM-2204 TM-2583 TM-2205	Color White Yellow White Yellow White Yellow White Yellow White Yellow Blue Black White Yellow White White Yellow Yellow	 Diamond Vogel Diamond Vogel Diamond Vogel Diamond Vogel Ennis-Flint/PPG Ennis-Flint/PPG Ennis-Flint/PPG Ennis-Flint/PPG Ennis-Flint/PPG Ennis-Flint/PPG Ennis-Flint/PPG Ennis-Flint/PPG Ingevity Ingevity Sherwin-Williams Sherwin-Williams Sherwin-Williams Sherwin-Williams
811.03D2 Low Temperature Waterborne, Liquid Pavement Marking Material	White 985351 TM2372	Lead Free Yellow 985352 TM2373	 Ennis-Flint/PPG Sherwin-Williams
811.03D3 Regular Dry Paint, Liquid Pavement Marking Material	White 985151 TM5626 2070	Lead Free Yellow 985152 TM5627 2076	 Ennis-Flint/PPG Sherwin-Williams Swarco/Colorado Paint Company

Qualified Products List (QPL)		
Spec # and Material Name	Product Name	Manufacturers or Suppliers
811.03D4 Cold Plastic Tape, Preformed Pavement Marking Material, Permanent (Long Line, Legends & Crosswalks)	Wet Reflective Long Line: White / Yellow / Adhesive 380 AW / 381 AW / P50 DeltaLine XRP-R / D-20 DeltaLine XRP-R / D-20 Standard Long Line: White / Yellow / Adhesive 380I ES / 381I ES / P50 Director 60 / Director 60 / DP-E4 Director 60 HPT / DP-E4 Director 60 HPT / DP-E4 Shadow Tape: Black / Adhesive 385 AW / P50 385 ES / P50 Director 60 / DP-E4 Special Markings (symbols, legends, stop bars, crosswalks, crosshatching): White / Yellow / Adhesive 270 ES / 271 ES / P50 380I ES / 381I ES / P50 ATM 300 / ATM 300 / ATM Permanent Primer Director 60 / Director 60 / DP-E4 Director 60 HPT / DP-E4 Director 60 HPT / DP-E4	3M Brite-line Technologies, LLC 3M Swarco Swarco 3M 3M Swarco 3M 3M Advanced Traffic Markings Swarco Swarco
811.03D5 Thermoplastic, Liquid Pavement Marking Material	White / Yellow 884285 / 884685 Swarcotherm EWH 131 / Swarcotherm EYH 132 Viatherm E413W	Ennis-Flint/PPG Swarco Geveko Markings
811.03D5 Thermoplastic, Blocks Rumble Strips	Viatherm E411W	Geveko Markings

Qualified Products List (QPL)			
Spec # and Material Name	Product Name		Manufacturers or Suppliers
811.03D6 Thermoplastic, Sprayable, Liquid Pavement Marking Material	White 01-WAK-BADA 01-WHK-BADA 0321012 W1SS7056 W2SS7056 617496 Thermodrop 884822 884822PT 884824 ED-9951-WHT-000 800079 RZMIAW/10102211/ Retro Zip 1157MWHSI 3023MWASI	Yellow 01-YAK-AADA 01-YHK-AADA 0321212 Y1SS7006 Y2SS7006 617369 Thermodrop 883241 883241PT 883240 ED-9952-YEL-000 800255 RZMIAY/10102212/ Retro Zip 2798MYHSI 3021MYASI	 Crown USA, Inc. Crown USA, Inc. Crown USA, Inc. Ennis-Flint/PPG Ennis-Flint/PPG Ennis-Flint/PPG Ennis-Flint/PPG Ennis-Flint/PPG Ennis-Flint/PPG Gentem Inc. Ingevity Retro Industries, LLC Retro Industries, LLC Swarco Swarco
811.03D7 Polyurea, Liquid Pavement Marking Material	5000 LPM 5001 LPM LS90 HPS-5 FT988 6180 MFUA-12 6186 MFUA-12	White Yellow White and Yellow White and Yellow White and Yellow White Yellow	3M 3M Epo-Plex Ennis-Flint/PPG FasTech Adhesives, Inc. Swarco/Colorado Paint Co. Swarco/Colorado Paint Co.
811.03D8 Modified Epoxy, Liquid Pavement Marking Material	HPS-4 MFUA-10	White and Yellow White and Yellow	Ennis-Flint/PPG Swarco
811.03D9 Preformed Thermoplastic, Preformed Pavement Marking Material	Tuff-Mark Preformed Thermoplastic PreMark PreMark XF HotTape Preformed Thermoplastic OPTAMARK CHOICE Preformed Thermoplastic PREFORM SWARCO Preformed Thermoplastic		Crown USA, Inc. Ennis-Flint/PPG Ennis-Flint/PPG Ennis-Flint/PPG Gentem Inc. Geveko Markings Ingevity Preform, LLC Swarco

Qualified Products List (QPL)				
Admixtures for Concrete Air Entraining - ASTM C 260; Chemical - ASTM C 494 (See Notes Following Listing of Admixtures)				
Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt
903.01 Air Entraining Admixtures 903.02 Liquid Chemical Admixtures	CHRYSO, INC.			
	EnviroMix SE 30	A	Water-reducer	8 - 12
	Quad 842	A	Water-reducer	4 - 8.5
		F	High-range water-reducer	8.5 - 20
	ADVA 140M	A	Water-reducer	5 - 9
		F	High-range water-reducer	9 - 16
	ADVA 405	F	High-range water-reducer	11 - 18
	ADVA Cast 198	F	High-range water-reducer	4 - 15
	ADVA Cast 575	F	High-range water-reducer	3.5 - 10
	ADVA Cast 585	F	High-range water-reducer	4 - 10
	ADVA Cast 600	A	Water-reducer	2 - 4
		F	High-range water-reducer	4 - 10
	Airalon 7000	AE	Air-entraining	0.5 - 3
	Concera SA8080	F	High-range water-reducer	11-18
	Daracem 19	F	High-range water-reducer	6 - 20
	Daraset 400	C	Accelerator (non-chloride)	15
	Daravair 1400	AE	Air-entraining	1
	Darex AEA ED	AE	Air-entraining	0.5 - 5.0
	Darex II AEA	AE	Air-entraining	1 - 5
	MIRA 62	A	Water-reducer	4.5
		MR	Mid-range water-reducer	6 - 12
		F	High-range water-reducer	12 - 15
	MIRA 95	A	Water-reducer	2.0 - 6.0
		F	High-range water-reducer	10 - 15
		MR	Mid-range water-reducer	6.0 - 10.0
	MIRA 110	MR	Mid-range water-reducer	9 - 12
		F	High-range water-reducer	12 - 15
	Polarset	C	Accelerator (non-chloride)	8 - 60
	Recover	D	Water-reducer retarder	2.5 - 6
	Terapave AEA	AE	Air-entraining	1.5
	WRDA 82	A	Water-reducer	3
	ZYLA 630	A	Water-reducer	4 - 7
		D	Water-reducer retarder	2 - 7
(Continued)	ZYLA R	D	Water-reducer retarder	6 - 12

Qualified Products List (QPL)				
Admixtures for Concrete Air Entraining - ASTM C 260; Chemical - ASTM C 494 (See Notes Following Listing of Admixtures)				
Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt
903.01 Air Entraining Admixtures	EUCLID CHEMICAL CO. Eucon AEA 92 Accelguard G3	 AE E	 Air-entraining Water-reducer accelerator (non-chloride)	 1.5 16 - 90
903.02 Liquid Chemical Admixtures	Accelguard NCA Eucon Air Mix 200 EUCON Air MAC6 EUCON MR	C AE AE A MR F	Accelerator (non-chloride) Air-entraining Air-entraining Water-reducer Mid-range water-reducer High-range water-reducer	15 3 0.5 - 4 4.5 5.5 12
	EUCON MRX	MR F	Mid-range water-reducer High-range water-reducer	3.5 7.5
	EUCON SE	A D	Water-reducer Water-reducer retarder	2.5 4.5
	EUCON WR	A D	Water-reducer Water-reducer retarder	2.5 - 10 2.5 - 10
	EUCON WR-91	A MR D	Water-reducer Mid-range water-reducer Water-reducer retarder	3 5 6
	EUCON A+	A MR	Water-reducer Mid-range water-reducer	3.5 4.5
	EUCON Retarder75	D	Water-reducer retarder	3.5
	EUCON Stasis	D	Water-reducer retarder	1 - 16
	EUCON AIR MAC12	AE	Air-entraining	1.5 - 4
	PLASTOL 5700	F	High-range water-reducer	2 - 10
	PLASTOL 6400	F	High-range water-reducer	4.5 - 12
	PLASTOL 6420	MR F	Mid-range water-reducer High-range water-reducer	2 - 5.5 5.5 - 10
(Continued)	PLASTOL ULTRA 209	F	High-range water-reducer	3.5 - 12

Qualified Products List (QPL)				
Admixtures for Concrete Air Entraining - ASTM C 260; Chemical - ASTM C 494 (See Notes Following Listing of Admixtures)				
Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt
903.01 Air Entraining Admixtures 903.02 Liquid Chemical Admixtures	<u>MAPEI Corporation</u>			
	Dynamon EW 100	A	Water-reducer	4
	Dynamon SX	A	Water-reducer	2 - 3
		MR	Mid-range water-reducer	3 - 5
		F	High-range water-reducer	5 - 12
	Dynamon SX 37	A	Water-reducer	1.5
		MR	Mid-range water-reducer	2.5
		F	High-range water-reducer	4.5
	Dynamon Easy 75	A	Water-reducer	2.0
		MR	Mid-range water-reducer	4.0
		F	High-range water-reducer	6.0
	Mapeair 154	AE	Air-entraining	0.5
	Mapeair N	AE	Air-entraining	1.0
	Mapeair SA	AE	Air-entraining	0.4 - 3
	Mapeair SA-50	AE	Air-entraining	0.5 - 3
	MapeCube 60	A	Water-reducer	8.0
	Mapecrete Resolve	D	Water-reducer retarder	3.0
	Mapefast Super Set	C	Accelerator (non-chloride)	16 - 32
	Mapefast Super Set II	E	Water-reducer accelerator (non-chloride)	10
	Mapefast Super Set Plus	C	Accelerator (non-chloride)	10 - 90
		E	Water-reducer accelerator (non-chloride)	10 - 90
	Mapeplast 400NC	A	Water-reducer	3.0
	Mapeplast 440NS	A	Water-reducer	5.5
		D	Water-reducer retarder	8.0
	Mapeplast KB-1200	A	Water-reducer	3 - 5
		MR	Mid-range water-reducer	5 - 8
	Mapeplast Paver Plus	A	Water-reducer	2 - 8
	Mapetard R	D	Water-reducer retarder	3 - 5
	Polychem VR	AE	Air-entraining (vinsol resin)	0.5
	Polychem SA-14	AE	Air-entraining	0.5 - 3.0
	Polychem RENU	D	Water-reducer retarder	3
(Continued)	Polychem SPC	F	High-range water-reducer	5.5

Qualified Products List (QPL)				
Admixtures for Concrete Air Entraining - ASTM C 260; Chemical - ASTM C 494 (See Notes Following Listing of Admixtures)				
Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt
903.01 Air Entraining Admixtures	Master Builders Solutions US LLC			
	MasterSet DELVO	D	Water-reducer retarder	3
	MasterGlenium 3400	F	High-range water-reducer	3
903.02 Liquid Chemical Admixtures	MasterGlenium 7500	A	Water-reducer	1.5
		F	High-range water-reducer	3 – 15
	MasterGlenium7511	A	Water-reducer	2 – 4
		MR	Mid-range water-reducer	4 – 6
		F	High-range water-reducer	6 – 15
	MasterGlenium 7700	F	High-range water-reducer	4 – 15
	MasterGlenium 7710	F	High-range water-reducer	4
	MasterGlenium 7720	A	Water-reducer	1.7
		MR	Mid-range water-reducer	2.6
		F	High-range water-reducer	3.2
	MasterGlenium 7920	F	High-range water-reducer	4
		MR	Mid-range water-reducer	2
	MasterGlenium 7925	F	High-range water-reducer	4
		MR	Mid-range water-reducer	2
	MasterGlenium 7960	A	Water-reducer	2
		MR	Mid-range water-reducer	3
		F	High-range water-reducer	4
	MasterAir AE 90	AE	Air-entraining	1
	MasterAir AE 200	AE	Air-entraining	1
	MasterAir AE 400	AE	Air-entraining	0.5
	MasterEase 5000	A	Water-reducer	1 - 5
	MasterPolyheed 900	A	Water-reducer	4
		MR	Mid-range water-reducer	7
	MasterPolyheed 980	A	Water-reducer	4.0
		MR	Mid-range water-reducer	11.0
		F	High-range water-reducer	13.0
	MasterPolyheed 997	A	Water-reducer	3
		MR	Mid-range water-reducer	6
		F	High-range water-reducer	10
	MasterPolyheed 1725	A	Water-reducer	2.5 – 4
		MR	Mid-range water-reducer	5.5 – 7
		F	High-range water-reducer	8 – 12
	MasterPolyheed 100	A	Water-reducer	4
		MR	Mid-range water-reducer	8
	MasterPozzolith 200	A	Water-reducer	2
		D	Water-reducer retarder	4
	MasterPozzolith 700	A	Water-reducer	2
		D	Water-reducer retarder	5
(Continued)				

Qualified Products List (QPL)				
Admixtures for Concrete Air Entraining - ASTM C 260; Chemical - ASTM C 494 (See Notes Following Listing of Admixtures)				
Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt
903.01 Air Entraining Admixtures 903.02 Liquid Chemical Admixtures (Continued)	Master Builders Solutions US LLC (cont.) MasterSet AC 534 MasterSet AC 534V1 MasterSet FP 20 MasterSet R 99 MasterRheobuild 1000 Master X-Seed 66	 C C C D MR F A	 Accelerator (non-chloride) Accelerator (non-chloride) Accelerator (non-chloride) Water-reducer retarder Mid-range water-reducer High-range water-reducer Water-reducer	 10 10 10 2.5 9 13 4

Qualified Products List (QPL)				
Admixtures for Concrete Air Entraining - ASTM C 260; Chemical - ASTM C 494 (See Notes Following Listing of Admixtures)				
Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt
903.01 Air Entraining Admixtures	Premiere Concrete Admixtures			
	EcoFlo Green	F	High-range water-reducer	8 - 16
		A	Water-reducer	2 - 4
903.02		MR	Mid-range water-reducer	5 - 8
Liquid Chemical Admixtures	Optiflo 700	A	Water-reducer	3 - 5
		MR	Mid-range water-reducer	5 - 10
		F	High-range water-reducer	12.0 - 16.0
	OptiFlo 50	A	Water-reducer	3 - 5
		MR	Mid-range water-reducer	5 - 6
		D	Water-reducer retarder	6
	OptiFlo 500	A	Water-reducer	2 - 3.5
		D	Water-reducer retarder	3.5 - 5
	OptiFlo MR	A	Water-reducer	3 - 5
		MR	Mid-range water-reducer	5 - 12
		G	High-range water-reducer retarder	12.0 - 16.0
	OptiFlo N2A	A	Water-reducer	3 - 6
		MR	Mid-range water-reducer	6 - 9
		G	High-range water-reducer retarder	13 - 15
	OptiFlo Plus	MR	Mid-range water-reducer	5 - 12
	OptiFlo 100R	D	Water-reducer retarder	3 - 5
	ConAir	AE	Air-entraining	0.5 - 4
	ConAir 260	AE	Air-entraining	0.5 - 4
	ConAir X	AE	Air-entraining	0.5 - 4
	UltraFlo 2000	A	Water-reducer	2 - 4
		MR	Mid-range water-reducer	4 - 6
		F	High-range water-reducer	6 - 12
	UltraFlo 5600	MR	Mid-range water-reducer	6 - 10
		F	High-range water-reducer	10 - 24
		A	Water-reducer	3 - 6
	UltraFlo DP	F	High-range water-reducer	5 - 12
	NitroCast K	E	Water-reducer accelerator (non-chloride)	10 - 90
	NitroCast NC	E	Water-reducer accelerator (non-chloride)	10 - 90
(Continued)	ProLong L	D	Water-reducer retarder	2.5 - 6.5

Qualified Products List (QPL)				
Admixtures for Concrete Air Entraining - ASTM C 260; Chemical - ASTM C 494 (See Notes Following Listing of Admixtures)				
Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt
903.01 Air Entraining Admixtures 903.02 Liquid Chemical Admixtures	SIKA CORP.			
	Sika Plastocrete-10N	A	Water-reducer	2
		D	Water-reducer retarder	3.5
	Sika Plastocrete-250	A	Water-reducer	2
		D	Water-reducer retarder	5
	Sika Plastiment XR	D	Water-reducer retarder	3
	Sika AEA-14	AE	Air-entraining	2
	Sika AIR 260	AE	Air-entraining	2
	Sika AIR 360	AE	Air-entraining	1
	SikaControl Air-160	AE	Air-Entraining	1
	Sikament AFM	A	Water-reducer	2
		MR	Mid-range water-reducer	5
		F	High-range water-reducer	10
	Sikament SPMN	MR	Mid-range water-reducer	6.5
		F	High-range water-reducer	10
	Sikament 475	A	Water-reducer	3
		F	High-range water-reducer	7
		MR	Mid-range water-reducer	5
	Sikament 686	A	Water-reducer	3
		MR	Mid-range water-reducer	5.5
		F	High-range water-reducer	8
	SikaPlast 200	A	Water-reducer	3
		G	High-range water-reducer retarder	13
		MR	Mid-range water-reducer	6.5
	Sikaplast 300 GP	A	Water-reducer	5
		MR	Mid-range water-reducer	7.5
	SikaSet NC	C	Accelerator (non-chloride)	10
		E	Water-reducer accelerator (non-chloride)	10
	Sikatard 440	D	Water-reducer retarder	3
	SikaTard-550	D	Water-reducer retarder	3
	Rapid - 1	C	Accelerator (non-chloride)	20
	ViscoCrete 1000	A	Water-reducer	1.5
		MR	Mid-range water-reducer	3
		F	High-range water-reducer	8
	ViscoCrete 1100	A	Water-reducer	2.5
		MR	Mid-range water-reducer	4.0
		F	High-range water-reducer	4.5
	ViscoCrete 2100	F	High-range water-reducer	5
	ViscoCrete 4100	F	High-range water-reducer	5
(Continued)				

Qualified Products List (QPL)				
Admixtures for Concrete Air Entraining - ASTM C 260; Chemical - ASTM C 494 (See Notes Following Listing of Admixtures)				
Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Type	Producer and Description	Recommended Dosage min. or range fl oz/cwt
903.01 Air Entraining Admixtures 903.02 Liquid Chemical Admixtures (Continued)	<u>SIKA CORP. (cont.)</u> ViscoCrete 5100 ViscoCrete 6100 ViscoFlow-585 Viscoflow-2020	 F F A MR F A MR	 High-range water-reducer High-range water-reducer Water-reducer Mid-range water-reducer High-range water-reducer Water-reducer Mid-range water-reducer	 5 5 3.0 5.0 7.0 3 6

Spec. 903 Admixture Notes:

1. Dosage Rate

   The dosage rate indicated is that recommended by the producer or that used in qualification tests for approval of the admixture. There is no assurance that the desired water-reduction and/or retardation will be achieved with these dosages with a particular cement being used, as the effect is dependent on the cement chemistry, concrete temperature, and other factors. Increasing the dosage appreciably above that recommended may result in abnormal behavior of the concrete, such as extremely long or very short setting times. Reducing the dosage below that recommended may have the effect of substantially no change from concrete without the admixture. The dosage shown for retarding admixtures will normally produce a 1- to 3-hour retardation in the setting of the concrete, compared to similar concrete without the admixture, when used at normal temperatures (approximately 70°F). Increased dosage, within reasonable limits, will usually increase the retardation. Use of a retarding admixture will not slow the stiffening of concrete due to loss of slump.

2. Air-Entraining Admixtures

   The contractor is responsible for verifying the compatibility of all chemical admixtures and the air-entraining admixture. If admixtures are from more than one manufacturer, run a trial batch prior to concrete placement. Provide test results for slump, air-entrainment and seven-day compression for two (2) cylinders. Actual dosage for Air-Entrainers may vary from those listed on the Qualified Products List as required by the mix design.

3. Lignin Type Admixtures

   Lignin (or lignosulfonate) admixtures typically will cause the entrainment of additional air in air-entrained concrete. This type admixture does not generally entrain air by itself, but makes other air-entraining materials much more efficient. Thus, a change in dosage of either the chemical admixture or the air-entraining admixture may have a more significant effect on the air content than normally expected. It is the contractor's responsibility to be sure the specific admixture proposed for use is compatible with his operations so that excessive air content in the concrete is not developed. Most lignosulfonate type water-reducers will provide a moderate retardation if used at higher dosage rates.

4. High-Range Water-Reducers

   Type F and G high range water-reducing (HRWR) admixtures (frequently called "superplasticizers") are capable of greater water reduction and greater strength gain than regular Type A water-reducers, or can provide substantial increase in slump while maintaining a cohesive concrete without loss of strength. Type G admixtures will also provide retardation of setting similar to Type D admixtures. Problems with this type of admixture include the following: (a) Loss of slump is frequently much more rapid than with plain concrete or when other admixtures are used, especially for older formulations of superplasticizers; (b) Effectiveness depends on the chemistry of the Portland cement, and the cements generally available in Michigan do not have the most favorable chemistry; (c) The air-void system may be adversely affected. Type F and G admixtures are to be used only according to the provisions of the Standard Specifications.

5. Admixtures Containing Chlorides

Some Type A and D admixtures may contain chlorides, as noted in the above listing. Section 903.03 of the Standard Specifications permits the use of these admixtures, except they are prohibited in concrete for bridge superstructure, prestressed concrete, and concrete containing galvanized steel or aluminum.

(End of Admixture Notes)

Qualified Products LIST (QPL)			
Spec. # and Material Name	Product Name		Manufacturers or Suppliers
905.03C Bar Reinforcement (Epoxy Coating) Note: Epoxy Coating Material Only. The Coating Applicator and Bar Manufacturer can be Approved Manufacturers, see Approved Manufacturers List.	<u>Epoxy Coating Product Name</u> Scotchkote FBEC 413 Resicoat RB-600 Nap-Gard 7-2719 Rebar FBE Nap-Gard 7-2750 Pureflex Green Greenbar 720A009 Greenbar 720A009LG Vectrashield PFY80006	<u>Repair Coating Product Name</u> Scotchkote 323R Thermal Chem BarPatch #803 Nap-Gard 7-1868 Nap-Gard 7-1868 Tnemec Series 66 G8925 Greenbar 920966S Vectrashield Patch Kit	 3M Akzo Nobel Powder Coatings Axalta Coating Systems Axalta Coating Systems Axalta Coating Systems IFS Coatings, Inc. Valspar (Sherwin Williams) Valspar (Sherwin Williams) Valspar (Sherwin Williams)
906.09 Shear Developers (Studs)	<u>Markings</u> B C N X TW		 Bluearc Stud Welding Cox Industries Nelson Stud Welding Co. (Div. of Gregory Ind.) Stud Welding Associates, Inc. Tru-Weld from Tru-Fit Products Corp.
909.01 Recycled Rubber Adjusting Rings for Manholes and Drainage Structures	Flex-O-Ring Pivoted Turnbuckle Pro-Ring Infra-Riser Ladtech HDPE HDPE Recycled Manhole Adjusting Ring UGT Grade Ring Whirlygig		American Highway Products American Highway Products Cretex Specialty Products East Jordan Iron Works Ladtech, Inc. P. Spear Company Underground Technologies Whirlygig, Inc.

Qualified Products List (QPL)				
Spec. #	Pipe Material	Joint System	Pipe Diameter (Inches)	Approved Manufacturers
909.03 Watertight Joint Systems	Corrugated Polyethylene Pipe	Bell/Spigot N-12WT Pro-Link Ultra WT Rubber Gasket	12 thru 60	ADS – Hancor
	Corrugated Polyethylene Pipe	Compression Gasket	12 thru 24	Baughman Tile Co.
	Corrugated Polyethylene Pipe	Haviland Smooth-Flow WT Compression Gasket	12 thru 36	Haviland Drainage Products Co.
	Corrugated Polyethylene Pipe	MaxSeal Gasket	12 thru 60	JM Eagle
	Corrugated Polyethylene Pipe	Gold Flow Corrugated SLCP Compression Gasket	12 thru 36	Prinsco, Inc.
	Corrugated Polyethylene Pipe	Gold Flow WT w/SpringSeal gaskets	12 thru 36	Prinsco, Inc
	Corrugated Polyethylene Pipe	Bell/Spigot Polyisoprene Gaskets	12 thru 60	Southeast Culvert, Inc.
	Corrugated Polyethylene Pipe	Vertex Single Compression Gasket	12 thru 60	Southeast Culvert, Inc.
	Corrugated Polyvinyl Chloride Pipe (PVC)	Integrally Formed Elastomeric Gasket, Bell/Spigot	12 thru 36	Contech Engineered Solutions, LLC
	Concrete Pipe	Single Offset Self-Lubricating Gasket, Tylox - Hamilton Kent	12 thru 24	Green Infrastructure Partners, Inc.
	Concrete Pipe	Press Seal Gasket Corp.-4G, 4F; Hamilton Kent-Tylox Super Seal; Universal Polymer & Rubber-Profile Gasket	12 thru 33	Northern Concrete Pipe, Inc.
(Continued)	Concrete Pipe	Press Seal Gasket Corp.-4G, 4F, O-ring, M875;	36 thru 72	Northern Concrete Pipe, Inc.

Qualified Products List (QPL)				
Spec. #	Pipe Material	Joint System	Pipe Diameter (Inches)	Approved Manufacturers
909.03 Watertight Joint Systems	Concrete Pipe	Hamilton Kent-Tylox SuperSeal Press Seal Gasket Corp.O-ring, M875;	78 thru 144	Northern Concrete Pipe, Inc.
	Concrete Pipe	Hamilton Kent Compression Gasket	30 thru 72	Oldcastle Infrastructure
	Concrete Pipe	Compression Gasket, Profile Cross Section, O-Ring Cross Section, Pipe Gasket & Supply	12 thru 24	Upper Peninsula Concrete Pipe Co.
	Concrete Pipe	Profile X-Section Gasket, Hamilton Kent	12 thru 36	County Materials Corp.
	Corrugated Metal Pipe	H12 Hugger Band with Single Bolt Bar and Strap with Compression Gasket	12 thru 24	Contech Engineered Solutions, LLC
	Corrugated Metal Pipe	Gasket-Bidco Wrap 12 x 3/8 Band	12 thru 18 Band 7 24 thru 30 Band 12 & larger Band 24	Jensen Bridge & Supply Co.
	Corrugated Metal Pipe	12 Bolted Band Angle with Compression Gasket Bidco Wrap 6 x 1/8 Band	12 thru 72	Cadillac Culvert
	Corrugated Metal Pipe	Bolted Corrugated Steel Band with Compression Gasket Ensolite IV Series	12 thru 24	St. Regis Culvert Inc.

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
909.05A1 Polymer Coated Corrugated Steel Pipe	Trenchcoat Protective Film	Valfilm USA
909.06 Class A, B and F Bury Plastic Pipe Smooth Lined Corrugated Plastic Pipe (CPE/HDPE); Corrugated Polyvinyl Chloride Pipe (CPV)	N12 Dual Wall (CPE/HDPE) A-2000 PVC (CPV) Smooth Flow (CPE) GoldFlo WT HDPE (CPE/HDPE)	Advanced Drainage Systems (ADS) Contech Engineered Solutions, LLC Haviland Drainage Products Prinsco, Inc.
909.10 Drainage Marker Post	See Delineator Posts, Flexible Material, QPL 919.03D	
910.04 Silt Fence Geotextile (fabric only) Fabricated Fence must be assembled by an Approved Manufacturer listed in 916.02.	LS125N GTX-2023-01-233 ANITA-100SF ANITA-124SF Belton 940 Stronghold 100G Kintex SF-3 GTF - 180 NCIF SF77 NCIF SF100 Propex 2130 SKAPS W100 TerraTex SF-D WINFAB 105SF	ACF Environmental, Richmond, VA Acme Landscape & Geotextiles, Gujarat, INDIA Anita Plastics, Inc., Solon, OH Anita Plastics, Inc., Solon, OH Belton Industries, Inc., Norcross, SC Cherokee Manufacturing LLC, Morganton, NC Geoproducts, Inc., Birmingham, MI LinQ Industrial Fabrics Nanjing Cenmen Industrial Fabrics (NCIF) Geosynthetics, Linyi, Shandong, China Nanjing Cenmen Industrial Fabrics (NCIF) Geosynthetics, Linyi, Shandong, China Propex Fabrics, Inc., Austell, GA Skaps Industries, Athens, GA Hanes Geo Components, Winston-Salem, NC Willacoochee Industrial Fabrics, Inc., Willacoochee, GA

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
912.08Q Recycled Plastic Or Rubber Guardrail Offset Blocks	Model Type B/BD, MGS-8 and MGS-8D Dura-Bull Bloclout SPI #4 Diamond Block Eco-Block Mondo Block P-Block Thrie Beam Block EDEN Block Polylumber PL6814R King Block 8 in. King MASH-16 Composite Block Type T/TD Mondo Block Thrie Beam Block EDEN Block Polylumber King Size King Block 8 in. King MASH-16 Composite Block	 Creative Building Products Diamond Roadway Products Eco-Composites LLC Mondo Polymer Technologies, Inc. Monroeville Industrial Moldings Monroeville Industrial Moldings Project Back to EDEN Ramco International Valtir, LLC Valtir, LLC Mondo Polymer Technologies Monroeville Industrial Moldings Project Back to EDEN Ramco International Valtir, LLC Valtir, LLC
914.04A Hot-Poured Joint and Crack Sealant (Joint and Crack Sealer in Concrete Pavements, Bridges, Other Structures)	Deery 101 ELT Roadsaver 522 3725 Elastoflex 72 MACSEAL 6690-4 MOD Dura-Fill 3725 3405-M Michigan	Crafco, Inc. Crafco, Inc. Crafco, Inc. Maxwell Products McAsphalt, Ind. P & T Products W.R. Meadows
914.04C HMA Crack Treatment and Overband	Roadsaver 515MN Deery 3723 Nuvo Spec 3405 Dura-Fill 3405MI Pure Asphalt 3405	Crafco, Inc. Crafco, Inc. Maxwell Products P & T Products Pure Asphalt Company, Inc.

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
914.06 Epoxy Resin Adhesive (Crack Injection)	Crackbond LR321 LV Crackbond LR321 SLV Akabond 817 Akabond 818 Akabond 819 BHS-1617 BHS-1618 BHS-1619 Arndite 8560 Pro-Poxy 50 EP-SLV True Grip 150 NIP124LV CI 060 Dynapoxy EP-450 E Bond 550 Sikadur 35, Hi-Mod LV Sikadur 52 Rezi-Weld LV State	Adhesives Technology Corp. Adhesives Technology Corp. Axson, Eaton Rapids, MI (formerly Akemi Corp.) Axson, Eaton Rapids, MI (formerly Akemi Corp.) Axson, Eaton Rapids, MI (formerly Akemi Corp.) Blackhawk Sales Co, Inc., Rock Island, IL Blackhawk Sales Co, Inc., Rock Island, IL Blackhawk Sales Co, Inc., Rock Island, IL Ciba Corporation, East Lansing, MI Dayton Superior (Unitex) E-Chem, LLC J. Dedoes, Inc., Milford, MI Epoxy Unlimited, Harrison Twp, MI Hilti Inc., Columbus, OH Pecora Corporation Ridgemoor Supply, Kentwood, MI Sika Corporation, Lyndhurst, NJ Sika Corporation, Lyndhurst, NJ W.R. Meadows
914.07A Transverse Pavement Joint 2. Dowel Bar Coating (Epoxy)	Scotchkote 426 Resicoat RB 601 Nap-Gard 7-2732P PFR 70001	3M Akzo Nobel Powder Coatings Axalta Coating Systems, LLC Valspar (Sherwin Williams)
3. Alternate Bond Release Agent	Bond Release Agent - Tectyl 506 Safecote HP BCG Protec 6116 DS MA	Daubert Chemical Daubert Chemical Bradley Coatings Group
914.08 Transverse Pavement Joint, Deformed Dowel Bar Coating	See Reinforcement Bar Coating, QPL 905.03C	
914.09 Straight & Bent Tie Bars for Longitudinal Pavement Joints (Lane Ties), Coating	See Reinforcement Bar Coating, QPL 905.03C	

Qualified Products List (QPL)			
Spec. # and Material Name	Product Name	Manufacturers or Suppliers	
914.11 Preformed Waterproofing Membrane Note: Not to be used on Treated Wood Materials.	Carlisle CCW 711-Highway and Bridge Membrane Geotac Waterproofing Membrane Geotac Polyester HS Petrotac 4591 Protecto Wrap M400 AR MEL-DEK	Carlisle Coatings and Waterproofing Crafco Inc. Crafco Inc. Propex Operating Company Protecto Wrap Co. W.R. Meadows, Inc.	
915 Coating Systems for Steel Structures, Hanger Assemblies and End Diaphragms Notes: *Indicates product can be used on faying surfaces of slip critical bolted connections which require Class “B”. +Information from the Slip Coefficient and Creep Resistance Test Certificate is given for use with primed bolted connections to meet Class “B” requirements.	 *Carbozinc 859 +100 hrs min cure, 6 mils max DFT, 10 oz/gal max thin Carboguard 893 Carbothane 133 LV *Interzinc 315B +48 hrs min cure, 4 mils max DFT, no thinner allowed Intergard 475HS Interthane 870UHS *Zinc Clad 4100 +72 hrs min cure, 5 mils max DFT, 6 oz/gal max thin Macropoxy 646 Fast Cure Epoxy Hi-Solids Polyurethane 250	Coats 1st 2nd 3rd 1st 2nd 3rd 1st 2nd 3rd	 Carboline Company International Protective Coatings Sherwin-Williams

Qualified Products List (QPL)					
Spec. # and Material Name	Seed Varieties				
917.11 Seed Varieties Varieties of Seed on QPL Date of Testing Not to Exceed One Year Approved MDOT seed mixtures, see Table 917-2 in the Spec Book. *Species	*Kentucky Blue Grass	*Perennial Ryegrass	*Hard Fescue	*Creeping Red Fescue	*Fults Salt Grass
	Arc Baron Bristol Brooklawn Cannon Corsair Diva Fielder Guiness Midnight Nassau NuBlue NuBlue Plus Parade Raven Rugby II SR 2100 SR 2150 Touchdown Wildwood	Advent Accent II Charger II Grand Slam Fiesta 4 Manhattan 5 Palace II Palmer III Pennant III Pepper II Pillar II Prelude III Premium Primary II Process Quickstart II Saguaro Savant Sideways SR 4650 SR 4660ST	Aurora II Aurora Gold Clarinet Eureka II Matterhorn Nanook Nordic Reliant II Reliant IV Rescue Rescue 911 Scaldis II Spartan II SR 3150	Celestial Chorus Cindy Lou Dawson Epic Garnet Hector Kent Kevin Maxima 1 Ruddy Seabreeze GT Shademaster II Shoreline Silverlawn SR 5250	Fults Fults II Salty Sea Salt

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
917.14B1 Turf Mulch Blankets, High Velocity Mulch Blankets (Two-Sided Net)	AEC Premier Straw Highway Double Net Curlex II Contech High Velocity ERO-MAT ECB EX32 ECB S32 ECS-2D Enviroscape HV Straw Mulch Blanket S2000 Erosion Control Blanket DS-150 ETRS-2-RD Excel SS-2 (Regular) S150 S2000D Straw Blanket Erosion King High Velocity Double Net S2 Erosion Control Blanket WinterStraw HVW	American Excelsior Co. American Excelsior Co. Contech Engineered Solutions, LLC ErosionControlBlanket ErosionControlBlanket Hanes Geo Components MKB MKB MKB MKB MKB MKB Rhino Seed & Landscape Supply S.I. Geosolutions / Land Winters Excelsior Company
917.14B2 Turf Mulch Blankets, Mulch Blankets (Single Sided Net)	AEC Premier Straw Highway Single Net Curlex 1-CL Curlex I Contech ERO-MAT ECB EX31 ECB S31 ECS-1D Mulch Blanket Erosion Control Blanket DS-75 Enviroscape Straw Mulch Blanket S1000 ETRS-1-RD Excel SR-1 (Regular) S75 S1000D Straw Blanket Futerra Mulch Blanket Erosion King Bio Jute Straw Blanket Erosion King Mulch Blanket S1 Erosion Control Blanket ERO-MAT V75S WinterStraw SNW	American Excelsior Co. American Excelsior Co. American Excelsior Co. Contech Engineered Solutions, LLC ErosionControlBlanket ErosionControlBlanket MKB MKB MKB MKB MKB MKB Profile Products, LLC Rhino Seed & Landscape Supply Rhino Seed & Landscape Supply Synthetic Ind. / BonTerra America Verdyol-Canada Winters Excelsior Company

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
917.14C Mulch Binders (Tackifiers)	1. Latex Base Adhesive BUTOFAN NS 268 EZ Straw Seeding Mulch w/Tack 2. Paperfiber Mulch Binders Applegate Mulch Cellin Fiber Mulch Geopro Basis Plus Hydro Green Hydroseeding Mulch Hydro Green Hydroseeding Mulch Profile SB 50/50 Profile Cellulose Profile Cellulose w/Tack Rhino Greenstar Rhino Greenstar Plus 3. Excelsior/Guar Gum Base Adhesive Excel Fiber Mulch Profile Wood Fiber with Tackifier 4. Guar Gum Base Adhesive EcoTak-OP5 Finn A500 Hydro-Stik Landtack ConTack Lawn Tack 5. Hydrophilic Polymers Agro Tack MP Exact-Tac (E-T) Con-Tack A/T FlocLoc Eco-Tak-SAT 11 RMB Plus .	 BASF Corp. Rhino Seed & Turf Supply Applegate Insulation System Cellin Manufacturing, Inc. Hanes Geo Components Nu-Wool, Inc. Nu-Wool, Inc. Profile Products, LLC Profile Products, LLC Profile Products, LLC Rhino Seed & Landscape Supply Rhino Seed & Landscape Supply American Excelsior Co. Profile Products, LLC Eastern Products, Inc. Finn Corporation Midwest Land Supply, Inc. Profile Products, LLC Rhino Seed & Landscape Supply Agro Diversified Industries American Excelsior Co. Profile Products, LLC Profile Products, LLC Eastern Products, Inc. Reinco Mulch Binder Corp
918.08C Light Standards, Frangible Transformer Bases	TB1-17 TB1-17 Modified TB2-17 TB3-17	Akron Foundry Co. Akron Foundry Co. Akron Foundry Co. Akron Foundry Co.

Qualified Products List (QPL)					
Spec. # and Material Name	Product Name				Manufacturers or Suppliers
919.02B1 Reflective Sheeting	Type III Series 3870	Type IV Series 3930	Type IX Series 3990	Type XI Series 4000	3M
	--	T-6500 Series	T-9500 Series	T-11500 Series	Avery Dennison
	Nikkalite Ultralite Grade II	Nikkalite CRG 94000 Series	--	--	Nippon Carbide Industries (USA) Inc.
	--	Oralite 5900 Series	Oralite 7900 Series	Oralite 9900 Series	ORAFOL Americas Inc.
919.03D Delineator Post, Flexible					
1. Ground Mount	FTSTR Series				PEXCO LLC, Davidson Traffic Control Products
	Shur-Flex Driveable Delineator				Shur-Tite
	Safe-Hit SQR-LOC Flexible Delineator				Valtir, LLC
2. Surface Mount	IRS Multipurpose Delineator Post				Impact Recovery Systems
	OmegaPost				Impact Recovery Systems
	Pexco Bike Bollard				PEXCO LLC, Davidson Traffic Control Products
	City Post				PEXCO LLC, Davidson Traffic Control Products
	Flexi-Guide FG 300 Model UR				PEXCO LLC, Davidson Traffic Control Products
	Flexi-Guide FG 300 Model EFX				PEXCO LLC, Davidson Traffic Control Products
	TSM Series Flexible Delineator Post				PEXCO LLC, Davidson Traffic Control Products
	K71 Flexible Marker Post				US Reflector
	SM 700 Series				Flexstake
	TM 750 Series				Flexstake
	Shur-Flex Surface Mount Delineator				Shur-Tite
	U-Flex				Shur-Tite
	Dura-Post				Valtir, LLC
	Safe-Hit Delineator Post				Valtir, LLC
920.02C Wet Reflective Optics	Connected Roads All Weather Elements Series 50/51				3M
	Reflective Elements Series All Weather 50/51				3M
	Visi-Ultra				Potters Industries LLC
	Duralux				Swarco

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
921.05A Steel Clamps for Traffic Signal Strain Poles	Strain Clamps	Utility Metals
922.06A Temporary Traffic Control, Temporary Pavement Markings Type R and NR Tape Paint - See Specific Paint Type in QPL 811.03D *WR Tape is wet-night retro reflective	<u>White (Type)</u> <u>Yellow (Type)</u> 710IR (WR) 711IR (WR) Visaline TWR (NR) Visaline TWR (NR)	 3M Volare/ Swarco Industries, Inc
922.06B Temp. Raised Pavement Markers	Type 1: Model 932 Chip Seal Marker TRPM Chip Seal Marker Type 2: Model 932 Overlay Marker Temporary Overlay Marker Type 3: Stimsonite Model 88	Apex Universal, Inc. PEXCO LLC, Davidson Traffic Control Products Apex Universal, Inc. PEXCO LLC, Davidson Traffic Control Products Stimsonite Corporation
922.06C Temporary Pavement Marking, Pavement Marking Cover	<u>Black (Type)</u> <u>Other (Type)</u> ATM-19-285 715IR (WR)	 ATM 3M

Qualified Products List (QPL)		
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
1005.02B Non-Shrinking Mortar and Grout Type H-1(Non-Metallic) Pre-Mixed H-2 eliminated.	Boomer Premium Grout	Boomer Construction Materials, Detroit, MI
	Conset Grout-XT	ChemMasters, Madison, OH
	Conset One	ChemMasters, Madison, OH
	1107 Advantage Grout	Dayton Superior, Kansas City, KS
	Sure Grip Grout	Dayton Superior, Kansas City, KS
	NS Grout	Euclid Chemical Co., Cleveland, OH
	Five Star Grout	Five Star Products, Inc.
	SureGrout	Kaufman Products, Inc., Baltimore, MD
	Crystex	L&M Construction Chemicals, Inc., Omaha, NE
	Duragrout	L&M Construction Chemicals, Inc., Omaha, NE
	Quikrete Precision Grout	Quikrete Technical Center, Atlanta, GA
	SikaGrout-928	Sika Corporation, Lyndhurst, NJ
	SC Multipurpose Grout	SpecChem
	Superb Grout 611	Specco Industries, Lemont, IL
	Sealtight 588-10K	W. R. Meadows, Inc., Elgin, IL

Qualified Products List (QPL)			
Spec. # and Material Name	Product Name		Manufacturers or Suppliers
1006 Prepackaged Hydraulic Fast Set* Mortar Note: *Percentage based upon weight of prepackaged bag containing both cement and sand. Example Calculation: 50 lb bag approved at 60% extension = 50 x 0.60 = 30 lb coarse aggregate per bag.		Max. Aggregate Extension, %	
	Burke Fast Patch 928	50*	Edoco, a Dayton Superior Co., Kansas City, KS
	Chem Speed 65	50*	Chem Masters
	HD-50 Heavy Duty Concrete Patch	60*	Dayton Superior Corp.
	Express Repair	60*	Euclid Chemical Co.
	FasTrac 246	0*	FasTrac Construction Products
	Five Star Highway Patch	60*	Five Star Products, Inc.
	Durapatch Hiway	50*	L&M Construction Chemicals, Inc.
	Planitop 18	60*	Mapei Corporation
	Planitop 18ES	40*	Mapei Corporation
	Planitop 18 TG	40*	Mapei Corporation
	Commercial Grade Fast Set DOT Mix	45.5*	Quikrete
	DOT Repair Mix	50*	Rapid Set
	SikaEmaco 1060	60*	Sika Corporation
	SikaQuick Set 45	60*	Sika Corporation

Selecting and Shipping Samples

The following instructions will apply for the selection, identification, and shipment of samples unless otherwise specified:

1. Samples shall be selected with care and shall be representative of the material sampled.

2. Pack samples to withstand rough shipment. Liquid materials shall be shipped in screw-top cans or friction-top cans with lids soldered in place unless otherwise specified or required. Friction-top cans with lids not soldered in place and glass jars must be surrounded and packed with suitable absorbent material in sufficient quantity to absorb all the liquid if the tops of the cans should come off or the glass jars should become broken. All packages containing liquid samples shall be marked "Fragile-Liquid."

   Mark pipe, tile, and concrete test specimens conspicuously, "Handle with Care-Fragile."

3. The sample identification form must be legibly prepared and filled out in detail. All available information for proper identification of the sample shall be given including the lot number, batch number, serial number, or other identification marks.

   The sample identification form shall be securely attached to the container in which the sample is shipped by means of a tag envelope. Also, include duplicate identification sheet inside wrappings, or if shipped in cloth sack, inside the sack.

4. Aggregate samples shipped to the Testing Laboratory shall be shipped in a closely woven bag. Do not use sacks which have contained sugar.

5. Cement and Pozzolanic Admixtures shall be shipped in plastic lined cloth bags.

6. The method of transportation of the samples will depend on the size, weight or quantity of material being shipped, and the time element. Small and light-weight samples shall be sent via UPS, bus, parcel post, or express. Large and heavy-weight samples shall be sent by motor freight. The sampler, being familiar with conditions, shall make shipment in the manner deemed most appropriate and economical.

7. Cloth bags, plastic liners, screw-top cans and friction-top cans may be obtained from the Laboratory. All containers must be clean and free from foreign materials. Cloth bags or sacks must be clean, free from tears or holes, and tightly woven to prevent loss of fine material.

8. All samples shall be consigned to the Michigan Department of Transportation, Construction Field Services Division, Secondary Governmental Complex, 8885 Ricks Road, Lansing, Michigan 48909, unless otherwise noted.

Appendix

Visual Inspection Items - Alphabetical

This list is intended as a quick reference, alphabetical by material name, for materials which normally require some form of testing but have VI quantities listed. It does not include materials which are accepted by VI basis only.

Visual Inspection Items - By Specification Number

This list is intended as a quick reference, by specification number for materials which normally require some form of testing but have VI quantities listed. It does not cover materials which are accepted on a VI basis only.

This Visual Inspection Items List is in accordance with the 2020 Standard Specification for Construction.

Visual Inspection Items - Alphabetical

SEC.	Material	Maximum V.I.
909	Acrylonitrile-Butadiene-Styrene (ABS) Pipe for Underdrain	600 ln ft
902	Aggregate, Coarse	500 tons
902	Aggregate, Dense-Graded	1500 tons
902	Aggregate, Fine	500 tons
902	Aggregate, Open-Graded	1500 tons
904	Asphalt, Liquid (RC-250)	5 gal - 150 lbs
905	Bar Reinforcement (all)	500 lbs
914	Bituminous Fiber Joint Filler	150 sq ft
914	Bolts for Structure Exp. Anchor	250 units
914	Bond Release	20 gal max
922	Calcium Chloride Solids	5000 lbs
922	Calcium Chloride Solutions	1000 gals
Misc.	Cast & Ductile Iron Pipe	250 ft
901	Cement	45 tons
Misc.	Clay Pipe	10 pcs
913	Clay and Sand Lime Brick	1000 pcs
913	Concrete Block	1000 pcs
913	Concrete Brick	1000 pcs
909	Concrete Pipe, Non-Reinforced	10 pcs
909	Concrete Pipe, Reinforced & Elliptical	5 pcs of 42” dia or less
Misc.	Corrugated Galv. Steel Plates	10 plates
909	Corrugated Aluminum Sheets	25 sheets
909	Corrugated Aluminum Alloy Pipe	250 ln ft
909	Corrugated Plastic Pipe	<12 in dia 250 ft
	“ “	>12 in dia 100 ft
909	Corrugated Plastic Pipe, Smooth Lined	100 ft
909	Corrugated Plastic Tubing for Underdrains	250 ft
909	Corrugated Steel Pipe	*
	12" or less	125 ln ft
	15" to 54"	50 ln ft
	60” or greater	25 ln ft
909	Corrugated Steel Pipe for Underdrains	*
909	Corrugated Steel Sheets	*
	12" or less	125 ln ft
	15” to 54”	50 ln ft
	60" or greater	25 ln ft
909	Coupling Bands	5 pcs
914	Deformed Bars	500 lbs
919	Delineator Posts, Steel	80 posts
919	Delineator Reflectors (Plastic and Reflective Sheeting)	25 pcs each color
914	Dowel Bars	1200 bars
918	Electrical Conduit, Plastic	400 ln ft
918	Electrical Conduit, Rigid	400 ln ft
Misc.	Fiberglass and Bit. Cotton Fabric	5 rolls
910	Geotextile Blanket	500 sq yd
910	Geotextile Liner/ Riprap	500 sq yd

Visual Inspection Items - Alphabetical

SEC.	Material	Maximum V.I.
910	Geotextile Liner/Heavy Riprap	500 sq yd
910	Geotextile Stabilizer/Separator	500 sq yd
916	Geotextile Silt Fence	500 ln ft
920	Glass Beads, Standard	500 lbs
902	Granular, Class I	1500 tons
902	Granular, Class II (Subbase)	1500 cu yd
902	Granular, Class II (Abutment b.f.)	100 cu yd
902	Granular, Class IIA	1500 cu yd
902	Granular, Class III	3000 cu yd
902	Granular, Class IIIA	1500 cu yd
908	Guardrail Beam Elements/End Sections	125 ln ft
908	Guardrail Posts, Steel	25 posts
918	Handholes, Precast Concrete	10 pcs
907	High Tensile Wire Fence (Wire)	250 ft
903	Insulating Blanket	10 sheets
903	Interim Curing (Linseed Based)	50 gals
914	Joint Assemblies	Field Insp. Req./100 assemblies
903	Membrane Curing Compound	200 gals
908	Metallic Waterstop (Sheet Lead & Copper)	25 sq ft
902	Mineral Filler (Bit. Mixes)	10 tons
909	Polyethylene Pipe (Downspouts)	<12 in dia 250 ft
	“ “	>12 in dia 100 ft
913	Precast Concrete Bases and Sumps	10 pcs total
918	Precast Concrete Handholes	10 pcs
909	Precast Concrete End Sections	10 pcs
913	Precast Units for Dr. Structures	10 pcs total
907	Rail for Braces (Chain Link)	250 ft
919	Reflective Sheeting	1 roll for less than 3” width
905	Reinforcement Steel	500 lbs
917	Seed and Seeding Mixtures	1100 lbs
913	Slope Paving Blocks	1000 pcs
909	Smooth Plastic Pipe for Underdrains (Outlet)	250 ft
907	Steel Chain Link Fence Fabric	250 ft
909	Steel End Sections	4 pcs
919	Steel, Galvanized Sign Posts	20 posts
907	Steel Posts/Chain Link Fence	25 line, 25 gate posts
919	Steel Posts/Delineator	80 posts
905	Steel Wire Fabric (Mesh)	500 sq yds
913	Structural Tile	1000 tiles
907	Top Rail (Chain Link)	250 ft
907	Tension Wire	500 ft
914	Tie Bars (Lane Ties)	500 lbs
910	Wall Drain	250 sq ft
919	Wood Sign Posts	20 posts

*See Remarks in Acceptance Requirements Section

Visual Inspection Items – by Specification Number

SEC.	Material	Maximum V.I.
901	Cement	45 tons
902	Coarse Aggregate	500 tons
902	Dense-Graded Aggregate	1500 tons
902	Open-Graded Aggregate	1500 tons
902	Granular, Class I	1500 tons
902	Granular, Class II (Subbase)	1500 cu yds
902	Granular, Class II (Abutment b.f.)	100 cu yds
902	Granular, Class IIA	1500 cu yds
902	Granular, Class III	3000 cu yds
902	Granular, Class IIIA	1500 cu yds
902	Fine Aggregate	100 tons
902	Mineral Filler (Bit. Mixes)	10 tons
903	Membrane Curing Compound	200 gals
903	Insulating Blanket	10 sheets
903	Interim Curing (Linseed Based)	50 gals
904	Liquid Asphalt (RC-250)	5 gals
905	Bar Reinforcement (all)	500 lbs
905	Steel Wire Fabric (Mesh)	500 sq yds
907	High Tensile Wire Fence (Wire)	250 ft
907	Steel Chain Link Fence Fabric	250 ft
907	Tension Wire	500 ft
907	Top Rail (Chain Link)	250 ft
907	Steel Posts/Chain Link Fence	25 line, 25 gate posts
907	Rail for Braces (Chain Link)	250 ft
908	Metallic Waterstop (Sheet Lead & Copper)	25 sq ft
908	Guardrail Beam Elements/End Sections	125 ft
908	Guardrail Posts, Steel	25 posts
909	Reinforced Concrete Pipe & Elliptical RCP	5 pcs of 42 in dia or less
909	Non-Reinforced Concrete Pipe	10 pcs
909	Corrugated Steel Pipe	*
	12" or less	125 ln ft
	15" to 54"	50 ln ft
	60" or greater	25 ln ft
909	Corrugated Steel Sheets	*
	12" or less	125 ln ft
	15" to 54"	50 ln ft
	60" or greater	25 ln ft
909	Steel End Sections	4 pcs
909	Coupling Bands	5 pcs
909	Corrugated Aluminum Sheets	25 sheets
909	Corrugated Aluminum Alloy Pipe	250 ln ft
909	Corrugated Plastic Pipe	<12 in dia - 250 ft
	“ “	>12 in dia 100 ft
909	Corrugated Plastic Pipe, Smooth Lined	100 ft
909	Precast Concrete End Sections	10 pcs

Visual Inspection Items – by Specification Number

SEC.	Material	Maximum V.I.
909	Acrylonitrile-Butadiene-Styrene (ABS) Pipe for Underdrain	600 ln ft
909	Corrugated Steel Pipe for Underdrains	*
909	Smooth Plastic Pipe for Underdrains (Outlet)	250 ln ft
909	Corrugated Plastic Tubing for Underdrains	250 ln ft
909	Polyethylene Pipe (Downspouts)	<12 in dia 250 ft
	" "	>12 in dia 100 ft
910	Geotextile Blanket	500 sq yd
910	Geotextile Liner/Riprap	500 sq yd
910	Geotextile Stabilizer/Separator	500 sq yd
910	Geotextile Liner/Heavy Riprap	500 sq yd
910	Wall Drain	250 sq ft
913	Clay and Sand Lime Brick	1000 pcs
913	Concrete Brick	1000 pcs
913	Concrete Block	1000 units
913	Precast Units for Dr. Structures	10 pcs total
913	Precast Concrete Bases and Sumps	10 pcs total
913	Structural Tile	1000 tiles
913	Slope Paving Blocks	1000 pcs
914	Bituminized Fiber Joint Filler	150 sq ft
914	Dowel Bars	1200 bars
914	Joint Assemblies	Field Insp. Req./100 assemblies
914	Bond Release	20 gal max
914	Deformed Bars	500 lbs
914	Tie Bars	500 lbs
914	Bolts for Structure Exp. Anchor	250 units
916	Geotextile Silt Fence	500 ft
917	Seed and Seeding Mixtures	1100 lbs
918	Precast Concrete Handholes	10 pcs
918	Electrical Conduit, Polyethylene	400 ft
918	Electrical Conduit, Rigid	400 ft
919	Reflective Sheeting	1 roll for less than 3" width
919	Delineator Reflectors (Plastic & Reflective Sheeting)	25 pcs each color
919	Steel Delineator Posts	80 posts
919	Galvanized Steel Sign Posts	20 posts
919	Wood Sign Posts	20 posts
920	Glass Beads, Standard	500 lbs
922	Calcium Chloride Solids	5000 lbs
922	Calcium Chloride Solutions	1000 gals
Misc	Clay Pipe	10 pcs
Misc	Cast & Ductile Iron Pipe	250 ft
Misc	Fiberglass and Bit. Cotton Fabric	5 rolls
Misc	Corrugated Galvanized Steel Plates	10 plates

*See Remarks in Acceptance Requirements Section

If you require assistance accessing this information or require it in an alternative format, contact the Michigan Department of Transportation's (MDOT) Americans with Disabilities Act (ADA) coordinator at Michigan.gov/MDOT-ADA.