MATERIALS SOURCE GUIDE

October 2018



CONSTRUCTION FIELD SERVICES DIVISION

FOREWORD

This manual has been prepared to give information and guidance to personnel associated with sampling, testing and inspection of materials used in Michigan Department of Transportation and Federal Aid Secondary projects. Its purpose is to supplement the Materials Quality Assurance Procedures (MQAP) Manual, Hot Mix Asphalt (HMA) Production Manual, Procedures for Aggregate Inspection, Density Control Handbook, and the Michigan Construction Manual to standardize procedures and assure adequate, uniform quality control.


Buy America step certification is required for pay items and materials as listed in the following document located at the web link: http://www.michigan.gov/documents/mdot/MDOT_BuyAmericaStepCertPayItems_40195 4_7.pdf Please also review the Special Provision for Source of Steel and Iron (Buy America), 12SP105(A) the following web link: at http://mdotcf.state.mi.us/public/dessssp/spss_source/12SP105(A)v7.pdf To reference The Buy America - Compliance Listing of Approved Manufacturers, Qualified Products List Stock Suppliers navigate to the following http://www.michigan.gov/mdot/0,4616,7-151-9622 11044 11367-291113--,00.html

For copies of the most recent Materials Source Guide you can:

Download from the internet at web address:

http://www.michigan.gov/mdot/0,1607,7-151-9622_11044_11367-22505--,00.html

Or Navigate by:



Periodically check the website for updates to the Materials Source Guide. Updated guides can be downloaded and printed.

TABLE OF CONTENTS

<u>Title</u> Pa	<u>age</u>
Definitions	. 4
Index (In reference to the Materials Acceptance Requirements Table)	11
Materials Acceptance Requirements, including Special	27
Approved Suppliers List	55
Approved Manufacturers List	59
Qualified Products List6	39
Tested Stock Suppliers List	91
Selecting and Shipping Samples	93
Appendix Visual Inspection Items by Quantity - Alphabetical	95
Visual Inspection Items by Quantity - by Specification Number	

This manual is in accordance with the 2012 Standard Specifications for Construction.

DEFINITIONS

(References to the Materials Quality Assurance Procedures Manual-MQAP)

BASIS OF ACCEPTANCE: Refers to the method by which materials incorporated into MDOT projects are accepted. Below is a list of all the current Basis of Acceptance methods used by MDOT for acceptance of materials.

- <u>Visual Inspection (VI)</u>: (See MQAP Section 1.06) Materials which may be visually inspected by MDOT personnel for acceptance or rejection. When a maximum VI limit is given for materials with another specified basis of acceptance, materials may be accepted by VI up to maximum VI quantities as indicated for that material, per item, per contract. (NOTE: All materials should be visually inspected prior to incorporation into the job without quantity limit, and may be rejected on that basis even though material may be acceptable on another basis.)
- Tested Stock (Tested Stock): (See MQAP Section 2.01) Tested stock samples represent a defined quantity (batch, heat, lot, tank, etc.) of the manufacturer's or supplier's inventory that is sampled and tested by MDOT and has been set aside for use on state and federally funded projects. Approved material(s) may then be shipped to any MDOT project until the approved quantity is depleted. Distribution of form 1922 "Shipment of Tested Stock Report" as detailed in the MQAP is required upon shipment of approved Tested Stock material(s) to MDOT projects.
- General Certification (Gen Cert): (See MQAP Section 3.01) When this certification is specified as the basis of acceptance in the contract documents, it must be provided in accordance with Section 3.01 of the MQAP. A general certification must include a general description of the material(s), a list of the applicable specifications (ASTM, AASHTO, MDOT or other designations as appropriate), and a statement that the material(s) conforms to these specifications.
- Test Data Certification (Test Data Cert): (See MQAP Section 3.01) When this certification is specified as the basis of acceptance in the Materials Acceptance Requirements Table, in addition to the requirements of a General Certification, the certification must also include laboratory test report(s) for samples obtained from the same lot(s), batch, heat, etc. of material represented by the certification and tested according to applicable specifications (ASTM, AASHTO, MDOT).
- Approved Manufacturer (Appr Mfr): (See MQAP Section 3.02) A manufacturer who has submitted quality control documentation and/or material samples, and has been given approval status to certify specific material(s). General Certification per the requirements of Section 3.01 of the MQAP must accompany all Approved Manufacturer shipments to either an Approved Supplier location or the MDOT project site. Strict adherence to the requirements for Certification Documentation and Distribution is required of all Approved Manufacturers.
 - Approved Supplier: (See MQAP Section 3.02) When Approved Manufacturer is specified as the basis of acceptance in the contract documents, the material must be supplied by the manufacturer or, without modification to the material, by an Approved Supplier. An Approved Supplier must recertify Approved Manufacturer material(s). Strict adherence to the requirements for Certification Documentation and Distribution is required of all Approved Suppliers for the recertification of material(s). All original Approved Manufacturer General Certification(s) must accompany the material(s) shipment to the MDOT project site. When Approved Manufacturer is specified, a supplier may not distribute or recertify material(s) unless they have been granted Approved Supplier status.
- <u>Special Provision</u>: Revisions and additions to the Standard and Supplemental Specifications applicable to an individual project. Special Provisions have been reviewed

and approved for use by MDOT. Materials acceptance may be defined by these documents included in the project proposals.

- <u>Fabrication Inspection</u> (<u>Fabrication Inspection</u>): Materials subjected to Fabrication Inspection are those that are typically manufactured offsite and shipped to the project. Refer to the proper subsection of Chapter 4 of the MQAP to find the requirements of the various Fabrication Inspections currently performed by MDOT.
- Acceptance Testing (Test): Sampling and testing of a material to determine compliance
 with specification requirements prior to incorporation into the project. Acceptance testing
 is the required basis of acceptance for some materials, as indicated in the contract
 documents, but may be applied to all materials regardless of the basis of acceptance.

OTHER DEFINITIONS

<u>Manufacturer</u>: A producer or fabricator of materials with control over the quality, workmanship and handling of material.

<u>Supplier</u>: A supplier has no control, other than through careful handling, over the quality and workmanship of material.

CERTIFICATION DOCUMENTATION (See MQAP Section 3.01)

Where more than one piece of paper is included in the certification document, all pages must be numbered (__ of __)and include Contract I.D. in order to reunite them should they become separated.

Upon delivery to a supplier, all certified material, either bundled or palleted, shall be stenciled, stamped or otherwise identified as per ASTM, AASHTO, or MDOT specification to allow the manufacturer's material to be recognized and checked against the manufacturer's certification documentation.

General Certification – This documentation must consist of all of the following:

- o Company name, address and contact information.
- Date the certification was produced.
- Contract number (Control Section/Job Number).
- Name of contractor.
- If material is certified by a supplier or Contractor, the manufacturer's name must be included on the certification.
- A list of all applicable specifications (ASTM, AASHTO, MDOT or other designations as appropriate) which the material is certified to meet.
- Any applicable specification modifier such as class, grade, type, etc.
- o Name of material (MDOT designation and Spec Number).
- Identification markings on shipment as required by the General Materials Certification Procedures, in the Quality Assurance Procedures Manual, Section 3.01.03.B.
- A statement, signed by a responsible representative of the manufacturer, supplier, or Contractor that the material represented by the certification meets all MDOT listed specification requirements.

Test Data Certification - When this certification is specified as the basis of acceptance in the Materials Acceptance Requirements Table, in <u>addition</u> to the requirements of a General Certification, the following information must also be included:

Laboratory test report(s) for samples obtained from the lot(s) of material represented by the certification and tested according to applicable specifications (ASTM, AASHTO, MDOT).

CERTIFICATION DISTRIBUTION

All certification documents except those issued by Approved Manufacturers/Approved Suppliers must be distributed as follows: Submit to the Construction/Project Engineer. The Contractor is ultimately responsible for all materials documentation distribution to the Project Engineer's office.

Approved Manufacturer/Approved Supplier Certifications must follow the above distribution requirements with the addition of one a copy being mailed, emailed, or faxed on the date of shipment to:

Michigan Department of Transportation Construction Field Services Division **Materials Control** P.O. Box 30049 Lansing, Michigan 48909

Facsimile: (517) 322-5664

Email: MDOT-MaterialsControl@michigan.gov

CERTIFICATIONS AND RECERTIFICATIONS

Information required on certifications may vary from one material to the next. The following examples of certification documents are ONLY provided for reference.

MATERIALS SOURCE LIST (See MQAP Section 1.04)

A completed and signed Materials Source List (Form 501) is required project documentation, and required for payment of associated items of work. The Materials Source List is not a substitute for other required material quality control and quality assurance documentation. Prime contractors are responsible for accurate submission of the Materials Source Lists for all materials including their subcontractors.

MATERIALS SOURCE LIST

8

Page

Michigan Department Of Transportation 0501 (07/13)

FOR OFFICE USE ONLY (Owner Agency) REMARKSIOTHER DATE SUBMITTED DATE RECEIVED CONTROL SECTION CERTS JOB NUMBER BASIS OF ACCEPTANCE 3 TELEPHONE NUMBER **6**, TELEPHONE NUMBER Submit to Construction Project Engineer. Construction Project Engineer to forward to Region Materials Supervisor. (Please Print or Type at Helds) INSTRUCTIONS: Use the "Materials Source Guide" for material name and specification number. Enter 'SP' for MDOT SPEC# for materials special provision. To avoid delays, submit as soon as possible. No testing of materials will be conducted until forms are received. 1681 (NAME, ADDRESS, LOCATION, PIEB) SOURCE OF MATERIAL CONTRACTOR APPX Ę. Check here if there are any revisions. Mark any revisions with an asterisk PRINT NAME PRINT NAME TYPE/SIZE or CLASS MDOT MATERIAL/PRODUCT NAME CONSTRUCTION/PROJECT ENGINEER OWNER AGENCY (Rep. Signature) CONTRACTOR'S SIGNATURE PROJECT LOCATION MDOT SPEC

Enter Your Company Letterhead/Logo Here (Name, Address, Contact Info)

GENERAL CERTIFICATION

Date:	Name of Contractor:
Control Section/Project #:	Project/Job Location:
We certify that the following described materials MICHIGAN DEPARTMENT OF TRANSPORTA	s/products meet the specification requirements of the TION, ASTM, or AASHTO.
MDOT MATERIAL NAME: As described in the	e MDOT Materials Source Guide
MDOT SPEC #: As described in the MDOT I	Materials Source Guide
LOT #, HEAT OR IDENTIFICATION:	
CLASS, GRADE OR TYPE:	
SIZE OR WEIGHT:	
	Signature of Company Representative
	Printed Name of Company Representative
	Title of Company Representative

<u>DISTRIBUTION</u>: Submit to the Construction/Project Engineer

Enter Your Company Letterhead/Logo Here (Name, Address, Contact Info)

APPROVED SUPPLIER RECERTIFICATION

Control Section/Job #: ______ DATE: _____

Contract ID:

CONTRACTOR:	
We certify that the following described material meets the specification requirements of the MICH DEPARTMENT OF TRANSPORTATION for the above project and this material is certified by nanufacturers indicated below.	
MDOT MATERIAL NAME: As described in the MDOT Materials Source Guide	
MDOT SPEC #: As described in the MDOT Materials Source Guide	
MANUFACTURER:	
LOT, HEAT OR IDENTIFICATION:	
QUANTITY:	
MDOT MATERIAL NAME: As described in the MDOT Materials Source Guide	
MDOT SPEC #: As described in the MDOT Materials Source Guide	
MANUFACTURER:	
LOT, HEAT OR IDENTIFICATION:	
QUANTITY:	
MDOT MATERIAL NAME: As described in the MDOT Materials Source Guide	
MDOT SPEC #: As described in the MDOT Materials Source Guide	
MANUFACTURER:	
LOT, HEAT OR IDENTIFICATION:	
QUANTITY:	

All steel furnished on this certification is of domestic origin and is in compliance with the project "Buy America" provision.

Signature of Company Representative

Printed Name of Company Representative

Title of Company Representative

<u>DISTRIBUTION</u>: Submit to the Construction/Project Engineer. Submit one additional Copy MAILED or FAXED to Construction Field Services Division, MDOT, P.O. BOX 30049, LANSING, MI 48909. FAX # (517)322-5664 or via email to MDOT-MaterialsControl@michigan.gov , COMPLETE ON DATE OF MATERIAL SHIPMENT.

MATERIALS ACCEPTANCE REQUIREMENTS TABLE DEFINITIONS

<u>Sampling Frequency</u>: (**If Required**) Amount of material or number of items, as defined in the Materials Acceptance Requirements Table or other contract documents, which require a sample when submitting material to the Construction Field Services Division for testing.

<u>Size of Sample</u>: <u>Minimum</u> size of sample required for testing as defined in the Materials Acceptance Requirements Table or other contract documents.

<u>Maximum VI Quantity</u>: Maximum amount of material which can be accepted by visual inspection for each material, per item, per project.

Remarks: Special notes pertaining to individual materials.

<u>Special Instructions</u>: More detailed information pertaining to particular types of materials, and referenced in "Remarks" or listed in the Materials Source Guide.

NOTE: When the Basis of Acceptance is not "Test", the sampling criteria provided may be used as guidance if the Project/Construction Engineer determines there may be a problem with the material and requests sampling and testing.

Page 10 of 98 October 2018

ALPHABETICAL INDEX TO 2012 MATERIAL SPECIFICATION NUMBERS IN THE MATERIAL ACCEPTANCE REQUIREMENTS TABLE

-A-

ABS Pipe	Misc. #7
Abrasive, Low Dusting Blasting	715.02 & 716.02
Abutment Backfill	902
Accelerators, Concrete	903.04
Adhesive Systems for Structural Anchors and Lane Ties	712.03J
Adhesive Systems for Dowel Bars & Tie Bars	603.03B2
Adjusting Rings for Manholes and Drainage Structures (Recycled Rubber)	909.01
Adjusting Rings for Manholes and Drainage Structures (Precast Concrete)	913.06
Admixture, Air Entraining	903.01
Admixture, Latex Emulsion for Concrete	903.03
Admixture, Mineral Filler, Bituminous Mixtures	902
Admixture, Pozzolanic (Fly Ash) for Concrete	901.07
Admixture, Water Reducing and/or Retarding	903.02
Admixture for Expansive Grout Type E-1	702.02C
Aggregates	902
Air Entraining Admixture	903.01
Aluminum Alloy Pipe (Corrugated)	909.05B
Aluminum Alloy Sheets, Corrugated	909.05B
Aluminum Alloy Structural Plate	Misc. #9
Aluminum Sheets for Signs	919.02A3
Anchor Bolts, Studs, Rods	908.14
Anchor Bolts and Nuts, Other Purposes	908.14D
Anchors, Concrete Adhesive Bonded (Resin)	712.03J
Anchors, Expansion	712.03K
Approved Manufacturers	Page 58
Approved Suppliers	Page 54
Arrow Bars, Lighted	922.07
Arrow Boards, Type C Solar Assist	922.07
Asphalt Binder	904.03A
Asphalt Emulsion, Bond Coat	904.03C
Asphalt Release Agents	501.02
Asphalt Rubber, Overband Crackfill	502.02B
Assemblies, Load Transfer	914.07

Back-up Plates for Guardrail	908.11C
Backer Rod, Foam	914.04B
Backfill, Abutment	902
Band Clamps, Strain Pole	921.05A
Bar Chairs	905.03D
Barbed Wire	907.03B
Barricades	922.03E
Barrier Reflector Markers	922.04A
Barrier Reflector Markers, Temporary	922.04A
Bases, Precast Concrete	913.07
Baskets, Dowel, Load Transfer	914.07
Beam Guardrail	908.11A
Beam Plates, Sealant for Perimeter	713.02B
Bearings, Elastomeric	914.12
Bent Tie Bars, Lane Ties	914.09
Bituminized Fiber Joint Filler	914.03
Bituminized Fiberglass and Cotton Fabric	Misc. #14
Bituminous Materials (Asphalt Binder)	904.03A
Blasting Abrasive, Low Dusting	715.02 & 716.02
Blasting Abrasive, Steel Grit	715.02
Block, Concrete	913.05
Bolts, Mechanical Expansion Anchors	914.10
Bolts, Adhesive Anchor Systems	914.10
Bolts, Anchor, Studs, Rods	908.14
Bolts, Anchor, Other Purposes	908.14D
Bolts, High Strength	906.07
Bond Breaker Tape	603.03B11
Bond Release Agent, Concrete (Dowel Bars)	914.07A
Bonded Anchors, Concrete Adhesive	712.03J
Brick, Clay and Sand Lime	913.03
Brick, Concrete	913.03C
Bridge Deck Drain Extensions, Fiberglass	909.08C
Bridge Railing, Base Plate and Post Elements	908.09A
Bridge Railing, Hardware	908.09C
Bridge Railing, Tube, Parapet	908.09B
Bridge Railing, Tube, Rectangle (Galvanized)	908.09A
Bridge Sign Connections	810.03O
Bushings for Pins and Link Plates	707.02

Cable, Electrical	918.03
Cable, Prestress Strand	905.07
Calcium Chloride	922.12A
Cantilever, Sign Support	919.07
Caps, Expansion for Dowel Bars	914.07C
Casing, Steel Pipe	909.05D
Cast Iron Pipe	Misc. #2
Castings, Miscellaneous Metals (Manhole)	908
Catch Basins	908
Cedar Posts (Wood Fence)	912.07B
Cement	901
Certification Verification of Cement	901
Certification Verification of Expansive Grout	702.02C
Chain Link Fence Fabric	907.04A
Chairs, Steel Reinforcement	905.03D
Chemical Fertilizer for Grass Seeding	917.10
Chemical Weed Sprays	917.16
Class B Plastic Pipe	909.06
Clay Brick	913.03
Clay Pipe	Misc. #3
Coarse Aggregate	902
Coating for Dowel Bars	914.07A
Coating for Rebar, Epoxy	905.03
Coating Systems for Steel Structures, Hangers Assemblies and End Intermediate, Top)	d Diaphragms (Prime, 915
Cobblestone	916.01A
Cold Applied Pipe Joint Sealer (Mastic)	909.09
Cold Plastic Pavement Marking, Permanent	811.03D4
Cold Plastic Pavement Marking, Temporary (Tape)	922.06A
Column Break-Away Sign Support	919.06
Compost	917.08
Compression Gasket	909.03
Concrete Accelerators	903.04
Concrete Adhesive System for Bonded Anchors (Resin)	712.03J
Concrete Barriers, Temporary	922.04
Concrete Barrier Reflector Markers	922.04A
Concrete Bases, Precast	913.07
Concrete Block	913.05
Concrete Brick	913.03C

Concrete End Sections, Precast	909.04E
Concrete Expansion Anchors	712.03K
Concrete Pipe, Reinforced and Non-Reinforced	909.04A - C
Conduit, Electrical	918.01, 918.01A, B, D, F
Conduit, Electrical (Polyethylene)	918.01D & E
Cones, Traffic	922.03A
Contraction Baskets	914.07
Copper Sheet (Waterstop)	908.08
Corrugated Aluminum Alloy Pipe	909.05B
Corrugated Aluminum Alloy Sheets	909.05B
Corrugated Poly-Pipe, Culverts and Sewers	909.06
Corrugated Poly-Tubing, Underdrains	909.07B
Corrugated Plate, Structural	Misc. #8
Corrugated Steel Pipe	909.05A
Corrugated Steel Pipe (Polymer Coated)	909.05A1
Corrugated Steel Sheets	909.05A1
Cotton Fabric, Bituminized	Misc. #14
Coupling Bands	909.05A4
Cover, Sign	922.02D
Covers and Lids, Manholes	908
Crack Injection	914.06
Culvert, Cast Iron	Misc. #2
Culverts, Class B	909.06
Curing Compound	903.06
Curtain, Turbidity	916.07
Cut-offs for Piling	906.05
-D-	
Deck Drain Extensions, Bridge	909.08C
Deformed Steel Bars for End-of Pour Joint Devices	914.08
Delineator Posts, Flexible	919.03D
Delineator Posts, Steel	919.03D
Delineator Reflectors	919.03A, B
Dense Graded Aggregate	902
Detectable Warning Surfaces	803.02B
Dimension (Sawed) Posts, Wood	912.08
Ditch Lining (Geotextile Blanket)	910.03A
Dowel Bar Grouting Systems	603.03B2
Dowel Bars for Load Transfer (Steel)	914.07

Dowel Baskets, Load Transfer	914.07
Downspouts, Bridge Deck	909.08A
Downspouts, Culvert	909.08B
Drain Pipe (Underdrain)	909.07A, B
Drainage Marker Post	909.10
Drainage Casting, Misc. Metals	908
Drainage Structures, Precast Reinforced Concrete	913.06
Drainage Structure Adjusting Rings, Precast Concrete	913.06
Ductile Iron Pipe	Misc. #2
Dust Palliative, Calcium Chloride	922.12A
-E-	
Edge Drain (Tubing)	909.07B
Elastomeric Bearings, Pads	914.12
Electrical Cable	918.03
Electrical Conduit (Galvanized Steel and Non-Metallic)	918.01A
Electrical Conduit (Polyethylene)	918.01D
Electrical Conduit (Polyvinyl Chloride)	918.01B
Electrical Traffic Control Devices	921.03
Embedded, Galvanic Anodes	712.03Y
Emulsified Asphalt	904.03C
Emulsion, Latex Admixture for Concrete	903.03
End Sections, Grate, for Culverts	401.03E
End Sections, Slope, Steel	909.05C
End Sections, Steel	909.05C
End Sections, Precast Concrete	909.04E
End Sections, Guardrail	908.11A
End-of-Pour Joint Devices/Deformed Steel Bars	914.08
Epoxies for Adhesive Systems	712.03J
Epoxy Binder, Joint Spall Repair	914.05
Epoxy Coated Dowel Bars	914.07A
Epoxy Coated Steel Reinforcing Bars	905.03
Epoxy Coating for Bar Reinforcement	905.03
Epoxy Coating for Dowel Bars	914.07A
Epoxy Mastic	712.03D
Epoxy Resin Adhesive for Crack Injection	914.06
Excelsior Mulch Blankets	917.15B
Expansion Anchors, Structure	712.03K
Expansion Baskets	914.07

Expansion Caps for Dowel Bars	014.070
Expansion Joint Devices, Bridge	
Expansive Grout Type E-1, Admixture	
External Type Gasket for Pipe	
Extruded Aluminum Sections for Sign Panels	919.02A1
-F-	
Fabric, Bituminous, Cotton, Fiberglass	Micc #14
Fabric, Filter, for Underdrain (Geotextile Blanket)	
Fabric for Chain Link Fence	
Fabric for Woven Wire Fence	
Fabric Reinforcement, Welded Steel Wire (Mesh)	
Fast Set Patching, Hydraulic Mortar	
Fence, High Tensile Wire	
Fence, Horizontal Rail	
Fence Fabric, Chain Link	
Fence Fabric, Woven Wire	
Fence Gates, Chain Link	
Fence Gates, Woven Wire	
Fence Pedestrian, Posts and Rail	
Fence Protective	
Fence Posts, Steel	
Fence Posts, Wood	,
Fertilizer	917.10
Fiber Joint Filler, Bituminized	914.03
Fiberglass Fabric	Misc. #14
Filter Bags, Geotextile	910.03A
Filter Fabric for Wrapped Underdrain (Knitted Sock)	910.03A
Fine Aggregate	
Flexible Metal Conduit	918.01
Fly Ash, Mineral Filler for Bituminous Mixtures	902
Fly Ash, Pozzolanic Admixture for Concrete	901.07
Foam Backer Rod	914.04B
Foundation Piling	906.05
-G-	
Galvanic Anodes, Embedded	712.03Y
Galvanized Bridge Tube Railing	908.09B
Galvanized Conduit, Electrical	918.01A

Galvanized Slotted Drain Pipe	Misc. #5
Galvanized Steel Sheets, Corrugated	909.05A1
Gasket, Compression	909.03
Gasket, External Type for Pipe	909.03
Geocomposite Wall Joint Drain	910.05B
Geogrid	910.03D
Geotextile Blanket	910.03A
Geotextile Pipe Wrap Liner	910.03A
Geotextile Rip Rap Liner	910.03B
Geotextile Separator	910.03C
Glare Screen	804.01
Glass Beads	920.02
Granular Material	902
Grass Seed	917.12
Gray Iron Castings	908.05
Grit, Steel, Blasting Abrasive	715.02
Grounding Rods	918.02C
Grounding System	918.02
Grout Under Masonry Plates	712.03X
Grout, For Full-Depth Concrete Pavement Repairs	603.03B2
Grouting Cracks by Pressure Injection, Intrusion	914.06
Grouts and Mortars	702.02A, B, C
Guar Gum Base Adhesive, Mulch Binder	917.15C
Guardrail Anchorage, Bridge, Beam Elements, End Sections, Shoes and Departing End Terminals	908.11A
Guardrail Approach Terminals	
Guardrail Hardware	
Guardrail Offset Blocks, Recycled Plastic or Rubber	912.08Q
Guardrail Posts and Blocks, Wood (Dimension Sawed)	912.08
Guardrail Posts for Beam Guardrail, Steel	908.12
Guardrail Reflectorized Washer	908.13
Guardrail Steel Beam Elements	908.11A
Guide Posts	912.07B
Guy Wire, Electrical	918.11A
-H-	
H Piling	906.05
Handholes, Polymer, Light Weight Composite	
Handholes, Precast	
Hanger Assemblies, Coating Systems	

Hardware, Fence	907.04E
Hardware, Guardrail	908.11B
Hardware, Sign	919.02C
Headwall, Precast Concrete	401.03E
Herbicide, Spray	917.16
High Strength Steel Bolts, Nuts and Washers	906.07
High Tensile Fence Wire	907.05A
Highway Lighting Materials (Luminaires)	918.09
Hollow Load and Non-Load Bearing Block (Concrete)	913.05
Hydraulic Anchor Systems	712.03J
-l-	
Insulation, Blankets and Polystyrene	903.07C & D
Interim Linseed Oil Curing Compound	903.07A
Iron Pipe, Cast and Ductile Iron and Fittings	Misc. #2
-J-	
Jacked-In-Place Steel Pipe	909.05D
Joint Filler	914.03, 914.03B
Joint Filler, Fiber (Bituminized)	914.03
Joint Sealer, Pipe Gaskets (O-Ring)	909.03
Joint Sealer for Pipe, Cold Applied (Mastic)	909.09
Joint Spall Repair, Epoxy	
Joint Wall Drain, Geocomposite	910.05B
-K-	
-L-	
Lane Ties	914.09
Latex Base Adhesive for Mulch	917.15C
Latex Emulsion Admixture for Concrete	903.03
Lead Sheet (Waterstop)	908.07
Light Standards	918.08
Lighted Arrows	922.07A
Limestone Dust, Bituminous Mineral Filler	902
Liner for Riprap	910.03B
Link Plates for Steel Bridge Construction	906.08
Linseed Oil Interim Curing Compound	903.07A
Liquid Asphalt, MC & RC-250	904.03B

Load Transfer, Dowel Bars (Steel)	914.07
Load Transfer Assemblies, Dowel Baskets	914.07
Load-Bearing Block (Concrete)	913.05
Loop Sealant, Traffic	921.08B
Low Dusting Blasting Abrasive	715.02 & 716.02
Lumber, Structural	912.05
Luminaires	918.09
-M-	
Mail Box Posts	912.07B
Malleable Iron Castings	908.03
Manhole, Block	913.05
Manhole, Brick	913.03C
Manhole Castings	908
Manhole Covers and Lids	908
Marking Tape, Cold Plastic, Permanent	811.03D4
Marking Tape, Temporary Lane	922.06A
Masonry Plate, Grout	712.03X
Masonry Units, Precast Drainage	913.06
Mastic (Cold Applied Joint Sealer for Pipe)	909.09
Mechanical Reinforcement Splicing	712.03L
Membrane, Preformed Waterproofing	914.11
Membrane Curing Compound	903.06
Mesh Reinforcement (Pavement)	905.06
Metal End Sections	909.05C
Metallic Waterstop, Sheet Copper	908.08
Metallic Waterstop, Sheet Lead	908.07
Mineral Filler for Bituminous Mixtures	902
Mortars and Grouts	702.02A, B, C
Mulch Anchoring	917.15C
Mulch Binder, Tackifiers, Non-Asphalt Emulsion	917.15C
Mulch Blanket, Excelsior and Straw	917.15B2
Mulch Blanket, High Velocity	917.15B1
Mulch Blanket, Straw	917.15B2
Mulching Materials for Nursery Stock	917.14
-N-	
Non-Load Bearing Block	913.05
Non-Reinforced Concrete Pipe	909.04C

Non Shrink Mortors and Crouts Type III (Non Matellia)	702.020
Non-Shrink Mortars and Grouts, Type H1 (Non-Metallic)	
Nursery Stock (Trees, Bushes)	917.03
-O-	
O-Ring, Compression Gasket	909 03
Open-Graded Aggregate	
Outlet, Drainage Pipe (Underdrain)	
Outlet Ending (Underdrain)	
Overband Crackfill	
CVCIDANA CIACNIII	
-P-	
PVC Sanitary Sewer Pipe	909.06
Paint for Coating Existing Steel Structures (Prime, Intermediate, Top)	915
Paint for Pavement Marking	811.03D
Patching, Fast Set Hydraulic Mortar	703
Pavement Lane Ties	914.09
Pavement Marking Cover (Temporary)	922.06C
Pavement Marking, Glass Beads	920.02
Pavement Marking, Modified Urethane	811.03D8
Pavement Marking, Polyurea	811.03D7
Pavement Marking, Thermoplastic, Liquid	811.03D5
Pavement Marking, Thermoplastic, Sprayable	811.03D6
Pavement Marking, Thermoplastic, Preformed	811.03D9
Pavement Marking, Waterborne, Liquid, Paint	811.03D1
Pavement Marking Regular Dry Paint	811.03D3
Pavement Marking Tape, Cold Plastic	811.03D4
Pavement Marking Tape, Type R/NR	922.06A
Pavement Markers, Raised (Temporary)	922.06B
Pavement Reinforcement (Mesh)	905.06
Pavement Tie Bars	914.09
Penetrating Water Repellents	706.03S
Perforated Poly-Tubing, Underdrain	909.07B
Pile Points	906.05
Piling, H Piling and Special Sections	906.05
Piling, Steel Sheet	906.06
Piling, Steel Shells	906.05
Piling, Timber	912.06
Pins for Steel Bridge Construction	906.08
Pipe, Cast and Ductile Iron	Misc. #2

Pipe, Clay	Misc. #3
Pipe, Concrete	909.04A - C
Pipe, Corrugated Aluminum Alloy	909.05B
Pipe, Corrugated Polyethylene (CPE/HDPE)	909.06
Pipe, Corrugated Steel	909.05A
Pipe, Downspouts	909.08A, B
Pipe, Gasket	909.03
Pipe, Plastic, Class B	909.06
Pipe Joint Sealers	909.09
Pipe, Steel Casing	909.05D
Pipe Wrap, Geotextile	910.03A
Plastic Drums	922.03
Plastic Guardrail Blocks	912.08Q
Plywood for Signs	919.02A2
Poles, Tower Lighting	918.10A
Polyethylene Pipe for Culverts and Sewers(CPE/HDPE)	909.06
Polyethylene Tubing for Underdrain	909.07B
Polymer Coated Corrugated Steel Pipe	909.05A1
Polystyrene, Insulation	903.07D
Polyvinyl Chloride Pipe (CPV/PVC)	909.06
Portable Signs	922.07C
Post Tensioning, Tendons	905.08
Posts, Delineator, Flexible (Plastic)	919.03D
Posts, Delineator, Steel	919.03D
Posts, Dimension Sawed (Wood)	912.08
Posts, Drainage Marker	909.10
Posts, Mailbox	912.07B
Posts, Signs, Steel	919.04
Posts, Wood for Fencing	912.07B
Posts, Wood Sign	912.08, 919.05
Posts for Chain Link Fence (Steel)	907.04C
Posts for Woven Wire Fence (Steel)	907.03D
Pozzolanic Admixture for Concrete (Fly Ash)	901.07
Precast Concrete Bases	913.07
Precast Concrete Box Sections	909.04D
Precast Concrete End Sections	909.04E
Precast Concrete 3 Sided or Arch Sections	909.04G
Precast Concrete Handholes	918.06
Precast Concrete Headwalls	401.03E

Precast Reinforced Concrete Drainage Structures	913.06
Precast Sumps	913.07
Prefabricated Drainage System	910.05A
Preformed Waterproofing Membrane	914.11
Premixed Grouts and Mortars, Type H1 (Non-Metallic)	702.02B
Prestress Strand for Concrete	905.07
Prestressed Concrete Beams	708.03A
Protective Coating for Concrete, Water Repellent	706.03S
Protective Fence	907.06
-Q-	
Qualified Products List	Page 68
-R-	
R C 250, Liquid Asphalt Waterproofing Primer	
Railing, Bridge Tube Element (Galvanized)	
Raised Pavement Markers (Temporary)	
Recertifiers	Page 54
Recycled Plastic or Rubber Guardrail Offset Block	912.08Q
Recycled Rubber Adjusting Rings	909.01
Recycled Rubber Joint Filler	914.03B
Reflective Sheeting	919.02B1
Reflective Sheeting, Temporary Signs	922.02B
Reflectorized Washers, Guardrail	908.13
Reflectors, Delineator	919.03A, 919.03B
Reflectors, Marker, Concrete Barriers	922.04A
Reflectors, Marker, Concrete Barriers, Temporary	922.04A
Regular Dry Pavement Marking Paint	811.03D3
Reinforced Concrete Pipe	909.04A
Reinforcing Steel Bars	905.03
Release Agents, Asphalt	501.02
Retarding Admixtures	903.02
Rip Rap	916.01C
Rubber, Recycled, Joint Filler	914.03B
Rustic Construction, Timber	912.09
-S-	
Sand Lime Brick	913.03
Sawn Wood Posts and Blocks	912.08

Sealant for Perimeter of Beam Plates	713.02B
Sealer for Pipe Joints, Cold Applied (Mastic)	909.09
Seeding Mixtures	917.12
Selecting and Shipping Samples	Page 91
Separator, Geotextile	910.03C
Sewer Pipe, Concrete	909.04A - C
Sewer Pipe, PVC Sanitary	909.06
Shear Developers (Studs)	906.09
Sheet Copper (Waterstop)	908.08
Sheet Lead (Waterstop)	908.07
Sheeting, Reflective	919.02B1
Sheeting, Reflective, Temporary Signs	922.02B
Shelf Life, Curing Compound (Linseed Oil Base)	903.07A
Shipping and Selecting Samples	Page 91
Shotcrete, Waterproofing	710.03D
Shredded Bark, Mulching Materials	917.14
Sign Hardware	919.02C
Sign Paddles	922.11
Sign Posts	919.04, 919.05
Sign Support, Cantilever	919.07
Sign Support, Truss	919.08
Signals, Electrical Traffic Control	921.03
Signs, Permanent	919.02
Signs, Portable	922.07C
Signs, Temporary, Prismatic	922.02
Signs, Temporary, Cover	922.02D
Signs, Temporary, Reflective Sheeting	922.02B
Silt Fence	916.02
Silt Fence, Geotextile	910.04
Slag Cement	901.06
Sleeves, Steel for Guardrail	908.11C
Sleeves, Steel for Wood Sign Posts	919
Slope Paving Block	913.09
Slotted Drain Pipe, Galvanized	Misc. #5
Sod	917.13
Span Wire, Electrical	921.02
Splicing, Reinforcement (Mechanical)	712.03L
Sprays, Chemical (Weed Control)	917.16
Standard Mortars and Grouts	702.02A

Steel Barbed Wire	907.03B
Steel Beam Guardrail Elements	908.11A
Steel Castings	908.04
Steel Grit Blasting Abrasive	715.02
Steel H Piling	906.05
Steel Pipe, Jacked-In-Place	909.05D
Steel Posts for Beam Guardrail	908.12
Steel Posts for Fence	907.03D, 907.04C
Steel Posts for Signs	919.04
Steel Reinforcing Bars	905.03
Steel Sheet, Corrugated Galvanized	909.05A1
Steel Sheet Piling	906.06
Steel Sleeves for Guardrail	908.11C
Steel Sleeves for Wood Sign Posts	919
Straight Tie Bars, Lane Ties	914.09
Strain Poles (Traffic Signal)	921.05
Strain Pole Band Clamps	921.05A
Strand for Prestressed Concrete	905.07
Straw Mulch Blankets	917.15B
Structural Plate for Pipe (Corrugated)	Misc. #8
Structural Steel	906.04
Structural Tile	913.08
Structural Timber and Lumber	912.05
Structure Expansion Anchors	712.03K
Stud Shear Developers	906.09
Subbase	902
Sumps, Precast	913.07
-Т-	
Tackifiers for Mulch	917.15C
Tape, Bond Breaker	603.03B11
Tape, Lane Marking, Temporary	922.06A
Temporary Concrete Barriers	
Temporary Overlay and Chip Seal Markers	922.06B
Temporary Seal for Cracks Injection	914.06
Temporary Signs	922.02
Tendons for Post Tensioning	
Tension Wire	907.04B
Tested Stock Listings	Page 88

Thermoplastic Pavement Marking	811.03D5, 811.03D6
Three Coat/Clear System, Post	907.03D
Tie Bar Grouting Systems	603.03B2
Tie Bars for Longitudinal Sawed Joints	914.09
Tile, Structural	913.08
Timber and Lumber, Structural	912.05
Timber Piling	912.06
Tower Lighting Units	918.10A
Traffic Cones	922.03A
Traffic Loop Sealant	921.08B
Treated Wood	912.05
Truss, Sign Support	919.08
Tube Railing, Galvanized	908.09B
Turbidity Curtain	916.07
-U-	
Underdrain Outlet Endings	404.02C
Underdrain Pipe	909.07A, B, C
-V-	
Vests	922.11
-W-	
Wall Joint Drain, Geocomposite	910.05B
Warning Flashers and Lights	922.07B
Washers, Reflectorized	908.13
Water	911
Water Main Materials	923
Water Reducing/Retarding Admixture	903.02
Water Repellent, Penetrating Sealer	706.03S
Waterproofing Membrane, Preformed	914.11
Waterproofing Primer, Liquid Asphalt, RC 250	904.03B
Waterstop (Metallic)	908.07, 908.08
Watertight Joints	909.03
Weed Spray (Herbicides)	917.16
Welded Wire Reinforcement (Mesh)	905.06
Wet Reflective Beads/Elements	920.02C
Wire, Electrical Cable	918.03
Wire, High Tensile Fence	907.05A
Wire, Rope	908.11B
Wire Mesh	905.06

Wood Fence Posts	912.07E
Wood Mulch/Chips	917.14
Wood Posts and Lath for Silt Fence	916.02
Wood Posts for Guardrail (Dimensioned Sawed)	912.08
Wood Posts for Signs	912.08, 919.05
Woven Wire Fence Materials	907.03
Wrap, Filter Fabric	910.03A

-X- -Y- -Z-

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

		quanty.			
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
401.03E End Section Grate for Culverts	VI	-	-	-	See Standard Plans for Sizes.
401.03E Precast Concrete Headwalls	Gen Cert	-	-	-	24" or less. For larger than 24" construct per Section 706 of Standard Specifications.
404.02C Underdrain Outlet Endings	VI	-	-	-	See Standard Plans.
501.02 Asphalt, Release Agents	VI	-	-	-	
NOTE: Must be approved by the project	engineer. No fu	el or oil based agei	nts.	-	•
502.02B Overband Crackfill, Asphalt Rubber (Alt. 2)	VI See Remark	-	-	-	Must be a Qualified Product (502.02B).
603.03B2 Adhesive Systems for Grouting Dowel Bars and Tie Bars for Full-Depth Concrete Pavement Repairs	VI See Remark	-	-	-	Must be a Qualified Product (603.03B2).
NOTE: Use for grouting to existing concr positioned transverse to the direction of t Lane Ties (712.03J).	rete in the same raffic located be	direction of traffic in etween traffic lanes	n the same lane a) select from Adl	as the repair. hesive Anchor	For grouting lane ties (deformed bars Systems for Structural Anchors and
603.03B11 Bond Breaker Tape	VI	-	-	-	
702.02A Standard Mortars and Grouts	VI	-	-	-	
702.02B Non-Shrinking Mortar and Grout, Type H-1(Non-Metallic) Pre-Mixed	VI See Remark	-	-	-	Must be a Qualified Product (702.02B).
702.02C Admixture for Expansive Grout, Type E-1	Test Data Cert	-	-	-	
NOTE: Certification to include manufactor	urers recommer	nded dosage per sa	ck of cement.	•	•
703 Prepackaged Hydraulic Fast Set Mortar	VI See Remark	-	-	-	Must be a Qualified Product (703).
706.03K4 Expansion Joint Devices for Bridges	See Remark	-	-	-	See project plans for list of approved devices and details.
706.03S Penetrating Water Repellent (Protective Coating for Concrete)	VI See Remark	-	-	-	Must be a Qualified Product (706.03S).

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
707.02 Bushings for Pins and Link Plates	VI See Remark	-	-	-	Must be a Qualified Product (707.02).
708.03A Prestressed Concrete	Fabrication Inspection	-	-	-	MQAP Manual Section 4.04.
710.03D Waterproofing Shotcrete	VI	-	-	-	
712.03A1c Abrasive, Low Dusting	Gen Cert	-	-	-	See Section 715.02.
712.03D Epoxy Mastic	VI	-	-	-	
712.03J Adhesive Anchor Systems for Structural Anchors and Lane Ties	VI See Remark	-	-	-	Must be a Qualified Product (712.03J).
712.03K Structure Expansion Anchors (Mechanical Expansion Anchors)	VI See Remark	-	-	-	Must be a Qualified Product (712.03K). Pull-out testing is required see MQAP Manual Section 4.03.
712.03L Mechanical Reinforcement Splicing	VI See Remark	1 per project	2 splices	-	See Special Instructions. Must be a Qualified Product (712.03L).
712.03X Grout Under Masonry Plates	VI	-	-	-	
712.03Y Embedded Galvanic Anodes	VI See Remark	-	-	-	Must be a Qualified Product (712.03Y).
713.02B Sealant for Perimeter of Beam Repairs	VI See Remark	-	-	-	Must be a Qualified Product (713.02B).
715.02 Coating Systems for New Hanger Assemblies	VI See Remark	-	-	-	Must be a Qualified Product (915).
715.02 Abrasive, Low Dusting	VI See Remark	-	-	-	Must be a Qualified Product (715.02).
715.02 Abrasive, Steel Grit	VI	-	-	-	Verify uniform profile after blasting of 1 to 2.8 mils per SSPC.
716.02 Abrasive, Low Dusting	VI See Remark	-	-	-	See Section 715.02.

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
803.02B Detectable Warning Surfaces	VI See Remark	-	-	-	Must be a Qualified Product (803.02B).
804.01 Glare Screen	VI	-	-	-	Included in Concrete Spec.
808.03C Temporary Fence Materials	VI	-	-	-	
810.030 Bridge Sign Connections	Fabrication Inspection	-	-	-	MQAP Manual Section 4.06
811.03D1 Waterborne, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 6.15. Must be a Qualified Product (811.03D1).
811.03D2 Low Temperature Waterborne, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 6.15. Must be a Qualified Product (811.03D2).
811.03D3 Regular Dry Paint, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 6.15. Must be a Qualified Product (811.03D3).
811.03D4 Cold Plastic Tape, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 6.16. Must be a Qualified Product (811.03D4).
811.03D5 Thermoplastic Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 6.15. Must be a Qualified Product (811.03D5).
811.03D5 Thermoplastic, Blocks Rumble Strips and Snowmobile Crossings	VI See Remark	-	-	-	MQAP Manual Section 6.15. Must be a Qualified Product (811.03D5).
811.03D6 Thermoplastic, Sprayable, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 6.15. Must be a Qualified Product (811.03D6).
811.03D7 Polyurea, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 6.15. Must be a Qualified Product (811.03D7).
811.03D8 Modified Urethane, Liquid Pavement Marking Materials	VI See Remark	-	-	-	MQAP Manual Section 6.15. Must be a Qualified Product (811.03D8).
811.03D9 Preformed Thermoplastic, Preformed Pavement Marking Material	VI See Remark				MQAP Manual Section 6.15. Must be a Qualified Product (811.03D9).
901 Cement	Appr Mfr	See Remark	10 lb	45 ton	See Special Instructions, see MQAP Manual Section 3.07.
901.06 Slag Cement	Appr Mfr	-	10 lb	-	See Special Instructions for Cement.

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
901.07 Fly Ash, Pozzolanic Admixtures for Concrete	Appr Mfr	-	10 lb	-	See Special Instructions for Cement.
902 Coarse Aggregates	Test	See Remark	50 lb	100 ton	
902 Dense-Graded Aggregates	Test	See Remark	50 lb	500 ton	See Special Instructions
902 Open-Graded Aggregates	Test	See Remark	50 lb	100 ton	Refer to Chapter 3 of the Procedures for Aggregate Inspection Manual for sampling
902 Granular Material Class I	Test	See Remark	50 lb	100 ton	information.
902 Granular Material Class II (Subbase) and Class IIA	Test	See Remark	50 lb	500 cyd	See Current List of all Prequalified Aggregate Sources at Construction Field Services Web Page.
902 Class II (Abutment B. F.)	Test	See Remark	50 lb	100 cyd	Actual Current List of Prequalified Aggregate Sources web page
902 Granular Material Class III	Test	See Remark	50 lb	500 cyd	address: http://www.michigan.gov/document s/mdot/MDOT_PrequalifiedAggreg
902 Granular Material Class IIIA	Test	See Remark	25 lb	100 cyd	ateSourceList_387538_7.pdf
902 Fine Aggregate	Test	See Remark	25 lb	100 ton	
902 Mineral Filler for HMA Mixtures	Test See Remark	1 per project	1 qt	10 ton	Refer to Section 902.11 of the 2012 Standard Specifications.
903.01 Air Entraining Admixtures	VI See Remark	-	-	-	Must be a Qualified Product (903.01).
903.02 Water Reducing and Water Reducing Retarding Admixtures for Concrete	VI See Remark	-	-	-	Must be a Qualified Product (903.02).
903.03 Latex Admixture for Concrete	Appr Mfr	1 per lot	1 qt	-	
903.04 Concrete Accelerators 1. Calcium Chloride 2. All Others	VI VI See Remark	-	-	- -	For calcium chloride note the chemical composition. Other accelerators must be Qualified Products (903.04).

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality

		quality.			
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
903.06 Membrane Curing Compound	Test Data Cert	1 per lot or batch	1 qt	200 gal	
NOTE: Curing compounds must not be containers.	used after ONE	year from manufac	ture. Date of ma	nufacture mu	st be clearly printed on the outside of
903.07A Interim Curing (Linseed Oil Based)	Test Data Cert	1 per lot or batch	1 qt	50 gal	See Note for 903.06 above.
903.07C Insulating Blanket	Test Data Cert	-	-	10 sheets	
903.07D Polystyrene Insulation	Test Data Cert	-	-	-	
904.03A Asphalt Binder for HMA Mixtures	See Remark	1 per batch	(2) 1 qt containers	-	See Special Instructions.
904.03B Liquid Asphalt (MC)	Gen Cert	1 per batch	See Remark	-	1 gal from the top and 1 gal from the bottom of tank.
904.03B Liquid Asphalt (RC-250)	Gen Cert	1 per batch	2 qt	5 gal	
904.03C Emulsified Asphalt	Appr Mfr * See Remark	See Remark	See Remark	-	See Special Instructions.
905.03 Bar Reinforcement (Uncoated)	Appr Mfr *	1 per project per mfr per size	See Remark	500 lb	See Special Instructions.
905.03 Bar Reinforcement (Epoxy Coated) 1. Bar 2. Epoxy Coating Companies 3. Epoxy Coating Material (905.03C)	Appr Mfr * Appr Mfr * VI See Remark	1 per project per mfr per size	See Note	500 lb	See Special Instructions. Epoxy coating must be a Qualified Product (905.03C).
905.03D Bar Chairs and Wire Ties for Epoxy Control Steel Beinforcement	VI	-	-	-	

Coated Steel Reinforcement

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
905.06 Welded Steel Wire Reinforcement (Mesh)	Appr Mfr *	1 per project per mfr	See Remark	500 syd	See Special Instructions.
905.07 Strand for Prestressed Concrete	Appr Mfr *	1 per heat	2 pcs each 60 in long	-	See Special Instructions.
905.08 Tendons for Post Tensioning of Box Beams (Prestressing Strand)	Appr Mfr * See Remark	1 per heat	2 pcs each 60 in long	-	See Special Instructions.
905.08 Tendons for Post Tensioning of Box Beams (Post Tensioning Bar)	Test	1 per heat per project	2 pcs each 30 in long	-	
906.04 Structural Steel	Fabrication Inspection	-	-	-	MQAP Manual Section 4.05.
906.05 Foundation Piles (Steel H Piling and Special Sections, Steel Shells for Castin- Place Concrete Piles and Pile Points)	Test Data Cert	-	-	-	
906.05 Pile Cutoffs	Gen Cert	-	-	-	
906.06 Steel Piles (Temporary and Permanent Steel Sheet Piling)	Gen Cert	-	-	-	
906.07 High Strength Steel Bolts, Nuts, and Washers for Structural Joints	Test	1 assembly per dia per length per heat per project	3 assemblies	-	See Special Instructions.
906.08 Pins and Link Plates for Steel Bridge Construction	Fabrication Inspection	-	-	-	MQAP Manual Section 4.05
906.09 Shear Developers (Studs)	VI See Remark	-	-	-	Must be a Qualified Product (906.09).
907.03A - C Woven Wire Fence (Woven Wire Fabric, Barbed Wire, Smooth Line Wire)	Test Data Cert	1 per project per mfr	Full width of roll 5 ft	400 ft	
			6 ft 4 ft		

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
907.03D Woven Wire Fence (Steel Posts)	Test Data Cert	1 per project per mfr	1 post	25 posts	
907.03E Woven Wire Fence (Treated Wood Posts)	See Remark	-	-	-	See Section 912.07B.
907.03F Woven Wire Fence (Gates)	VI	-	-	-	
907.04A Steel Chain Link Fence (Fabric)	Test Data Cert	See Remark	5 ft full width of roll	250 ft	1 per height and/or mesh size, per project and 1 per mfr per project.
907.04B Steel Chain Link Fence (Tension Wire)	Gen Cert	1 per project per mfr	3 ft	500 ft	
907.04C Steel Chain Link Fence (Post for Fence and Gates), (Pedestrian Fence and Structure Fencing (Steel))	Test Data Cert	1 per project per mfr	1 post	25 posts	See Special Instructions.
NOTE: An alternative zinc/clear coat sys subsection 907.03D of the Standard Spec	tem will be allow cifications for Co	wed for pipe section onstruction.	ns only. This alte	rnative coatin	g system shall comply with
907.04C Steel Chain Link Fence (Top Rail), ((Horz. Rail) (Pedestrian Fence))	Test Data Cert	1 per project per mfr See Remark	5 ft	250 ft	See Special Instructions.
907.04D & E Steel Chain Link Fence (Gates, Fence Fittings and Hardware)	VI	-	-	-	
907.05A High Tensile Wire Fence (Wire)	Test	1 per project per mfr	3 ft	250 ft	
907.05B High Tensile Wire Fence (Treated Wood Posts)	See Remark	-	-	-	See Section 912.07B.
907.05C High Tensile Wire Fence (Hardware)	VI	-	-	-	
907.06 Protective Fence	VI	-	-	-	
908 Castings, Manhole 908.03 Malleable Iron 908.04 Steel 908.05 Gray Iron	VI	-	-	-	

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
908.07 Sheet Lead	Gen Cert	-	-	25 sft	
908.08 Sheet Copper	Gen Cert	1 per consignment	13 in square or equivalent area	25 sft	May be accepted in field if weight requirements can be documented.
908.09A Tubing, Steel Railings (Base Plate, Angle, and Non-Tubular Post Elements)	Fabrication Inspection	1 per heat per project	1 base plate, 1 post 9 in length	-	MQAP Manual Section 4.05. See Special Instructions.
908.09B Tubing, Steel Railings (Rail Elements and Tubular Post Elements)	Fabrication Inspection	1 per heat per project	36 in long, galv		MQAP Manual Section 4.05. See Special Instructions.
908.09C Tubing, Steel Railings (Hardware)	Test	1 assembly per heat per diameter per project	1 assembly	-	See Special Instructions.
908.10 Hardware for Timber Construction	VI	-	-	-	
908.11A Guardrail, Steel Beam Elements, End Sections	Appr Mfr *	1 per project per mfr	1 piece at least 1 ft length	125 ft	Including Anchorage, Bridge, Shoes, Departing End Terminals.
908.11A Guardrail Approach Terminals	Appr Mfr *	-	-	-	
908.11B & C B. Hardware	VI	-	-	-	Item supplied by guardrail supplier.
C. Steel Sleeves, Soil Plates, Bearing Plates, Backup Plates					
908.11B Wire Rope	Gen Cert	-	•	1	
908.12 Steel Posts for Beam Guardrail	Appr Mfr *	1 per 1000 posts or fraction thereof	1 post	25 posts	
908.13 Reflective Washers	VI See Remark	-	-	-	Inspect galvanizing, dimensions and type of sheeting.
908.14 Anchor Bolts, Nuts, and Washers	Test	1 assembly per heat per diameter per project	1 assembly	-	See Special Instructions.

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
908.14D Anchor Bolts and Nuts for Other Purposes	Gen Cert	1 assembly per heat per diameter per project	1 assembly	-	See Special Instructions.
909.01 Recycled Rubber Adjusting Rings for Manholes and Drainage Castings	VI See Remark	-	-	ı	Must be a Qualified Product (909.01).
909.03 Watertight Joint Systems	VI See Remark	-	-		Must be a Qualified Product (909.03).
909.03 Gasket, Compression (O-Rings)	VI	-	-	-	Part of Watertight Joint System.
909.03 Gasket, External Rubber Type	VI	1 per lot or shipment	18 in length full width of gasket	-	Part of Watertight Joint System.
909.04A Reinforced Concrete Pipe	Appr Mfr *	1 percent of number of pcs of each size	See Remark	5 pieces of 42 in or smaller	See Special Instructions.
909.04B Reinforced Concrete Elliptical Pipe	Appr Mfr *	1 percent of number of pcs of each size	See Remark	5 pieces of 42 in or smaller	See Special Instructions.
909.04C Non-Reinforced Concrete Pipe	Appr Mfr *	See Remark	See Remark	10 pcs	See Special Instructions.
909.04D Precast Concrete Box Sections	Appr Mfr * See Remark	-	-	-	Spans 20 ft. and greater require QA inspection. QA inspection may be required for spans from 10-20 ft Box = 4 sided. See MQAP Manual section 4.11.
909.04E Precast Concrete End Section for Culverts and Sewers	Appr Mfr *	1 percent of number of pcs	Full size units	10 pcs	Strength test by coring or cylinders, VI dimensions and conditions. Test for air content.
909.04G Precast Concrete Three-Sided or Arch Culverts	Appr Mfr See Remark	-	-	-	Spans 20 ft. and greater require QA inspection. QA inspection may be required for spans from 10-20 ft, See MQAP Manual section 4.11.
909.05A Corrugated Steel Pipe	Appr Mfr *	See Remark	See Remark	-	See Special Instructions.

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

		. ,			
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.05A1 Corrugated Steel Sheets (Galvanized)	Gen Cert	See Remark	See Remark	-	See Special Instructions.
909.05A1 Polymer Coating, Galvanized Corrugated Steel Pipe	VI See Remark	-	-	-	Coating must be from Qualified Products List (909.05A1).
909.05A4 Coupling Bands	Gen Cert	-	-	5 pcs	
909.05B Corrugated Aluminum Alloy Sheet	Gen Cert	See Remark	See Remark	25 sheets	See Special Instructions.
909.05B Corrugated Aluminum Alloy Pipe	Gen Cert	1 per 1000 ft	See Remark	250 ft	Sample Size: A 6 in by 3 in (minimum) section cut from the end of the pipe avoiding the seams. Do not damage coating.
909.05C Steel End Section	Gen Cert	-	-	4 pcs	
909.05D 1. Steel Pipe (Jacked-in-Place)	Gen Cert	-	-	-	
909.05D 2. Casing, Steel Pipe	VI	-	-	-	
909.06 1. Corrugated Polyethylene Pipe (CPE/HDPE), (Smooth Lined Type S)	Test or Tested Stock if ≥12 in. dia	≥12 in. dia 1 per 1000 ft straight lengths	See Remark	12 in. dia and over, 100 ft	Over 12 in. dia- one 10 ft length and one 6 ft length plus coupling. See Special Instructions.
909.06 2. Corrugated Polyvinyl Chloride (CPV) Pipe	Test	1 per 1000 ft straight lengths	See Remark	12 in. dia and over, 100 ft	Over 12 in. dia- one 10 ft and one 6 ft. length plus coupling.
909.06 3. Plastic Pipe Class A, B and F Bury (CPE/HDPE & CPV)	VI See Remark	-	-	-	Must be a Qualified Product (909.06).
NOTE : Watertight Joint Systems (909.03 by "Test" or "Tested Stock" for use on pro) and Pipe (401 oject.	& 402; Class A,B a	ind F Bury) must	be listed on Q	PL. Pipe (909.06) must be accepted
909.06 4. Smooth Polyvinyl Chloride (PVC) Pipe and Fittings for Sanitary Sewer	VI	1 per 6000 ft	1 piece, 5 ft in length	-	Sample must include bell end of pipe.
909.07A Pipe for Underdrains Smooth Perforated Plastic Pipe (PVC)	Test	1 per 2500 ft or fraction thereof	5 ft length	250 ft	Sample must include bell end of pipe.

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
909.07B Pipe for Underdrains Corrugated Plastic Tubing (Perforated and Non-Perforated) (Wrapped and Non-Wrapped)	Appr Mfr * 4-, 6-, or 8- in dia	1 per 5000 ft sample from coils	See Remark	250 ft	Sample Size, one 10 ft length plus coupling. For perforated tubing wrapped in fabric, tie fabric securely in place before cutting sample. Do not disturb fabric after cutting.
909.07C Outlet Pipe for Underdrains 1. Polyvinyl Chloride (PVC) Pipe	Test	1 per 2500 ft or fraction thereof	5 ft length	250 ft	See 404.02C for Underdrain Outlet Endings. Sample must include bell end of pipe.
909.07C Outlet Pipe for Underdrains 2. Corrugated Steel Pipe	Appr Mfr *	See Remark	See Remark	ı	See Special Instructions for 909.05A,. See 404.02C for Underdrain Outlet Endings.
909.07C Outlet Pipe for Underdrains 3. Corrugated Aluminum Alloy Pipe	Gen Cert	1 for 1000 ft	6 in x 3 in	250 ft	See 404.02C for Underdrain Outlet Endings. See 909.05B.
909.08A Bridge Deck Downspouts	VI	-	-	-	
909.08B Culvert, Downspouts 1. Corrugated Steel Pipe	Appr Mfr *	See Remark	See Remark	-	See 909.05A Corrugated Steel Pipe.
909.08B Culvert, Downspouts 2. Corrugated Aluminum Alloy Pipe	Gen Cert	1 per 1000 ft	6 in x 3 in	250 ft	See 909.05B.
909.08B Culvert, Downspouts 3. Corrugated Polyethylene Pipe (Corrugated Lined Type C) (CPE/HDPE)	Test	See Remark	See Remark	<12 in. dia up to 250 ft >12 in. dia up to 100 ft	See 909.06 (1)
909.08C Bridge Deck Drain Extensions (Polyethylene)	Gen Cert	-	-	ı	
909.09 Cold Applied Pipe Joint Sealer (Mastic)	VI	1 per shipment from a single container	1 qt	1	
909.10 Drainage Marker Post	See Delineator Posts	-	-	-	
910.03A Geotextiles 1. Blankets 2. Filter Bags	Test	See Remark	See Remark	See Remark	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

		• •			
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
910.03A Knitted Sock Pipe Wrap	See Remark	-	-	-	See 909.07B Certified with Corrugated Plastic Tubing.
910.03B Liner for Rip-Rap	Test	See Remark	See Remark	See Remark	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.
910.03B Liner for Heavy Rip-Rap	Test	See Remark	See Remark	See Remark	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.
910.03C Separator/Stabilization Geotextile	Test	See Remark	See Remark	See Remark	See Special Instruction 910.03. Anticipate up to 28 calendar days for the testing of geotextile samples.
910.03D Geogrids	Test	1 per type per project	1 pc 6 ft long full roll width	-	Sample must be <u>rolled</u> not folded. Anticipate up to 28 calendar days for the testing of geotextile samples.
910.04 Silt Fence; (Geotextile Fabric only)	VI See Remark	-	-	-	Must be a Qualified Product (910.04).
910.05A Prefabricated Drainage System	Appr Mfr *	1 per 10,000 ft or less	1 pc 6 ft long plus 3 syd filter-wrap	-	Test Data Cert must be attached to sample ID Form.
910.05B Wall Drain	Test	1 per 1000 ft or less	1 pc 6 ft long plus 3 syd filter-wrap	100 sft	
911 Water	Test See Remark	1 per source	1 qt	-	Water approved for drinking by the Michigan Dept of Public Health may be used without sampling and testing.
912.05 Structural Timber and Lumber	Appr Mfr *	Each Charge	22 cores See Remark	-	48 cores if treatment is creosote.
912.06 Timber Piles	VI	-	-	-	

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

		quanty.			
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
912.07B Treated Wood; Fence Posts, Guide Posts, Guard Posts and Mail Box Posts	VI	-	-	-	
912.08 Wood Posts and Blocks for Guardrail and Highway Signs (Dimension Sawed)	Appr Mfr *	Each Charge	22 cores	-	Cedar post need not be treated.
NOTE: All post must be treated except l approved manufacturer.	Northern White (Cedar. General Cer	tification docume	ent required fo	r Northern White Cedar in lieu of
912.08Q Recycled Plastic or Rubber Guardrail Offset Blocks	VI See Remark	-	-	-	Must be a Qualified Product. May only be used on Steel Posts (912.08Q).
912.09 Timber for Rustic Construction	Gen Cert	-	-	-	
913.03 Clay and Sand Lime Brick and Block	Test	1 per 250,000 or fraction thereof	6 pcs	1000 pcs	
913.03C Concrete Brick	Test Data Cert	See Remark	6 pcs	1000 pcs	1 from each 10,000 bricks or fraction thereof; 2 from lots more than 10,000 to 100,000; 3 from each lot over 100,000.
913.05 Concrete Block	Test Data Cert	See Remark	4 pcs	1000 pcs	One from lot of 10,000 or fraction thereof; 2 from lots more than 10,000.
913.06 Precast Reinforced Concrete Units for Drainage Structures (Tops, Risers and Sump Bases)	Appr Mfr *	1 percent per size	See Remark	10 pcs total	Submit QA cylinder test results and core samples. Submit sample 1-3 sq.in. from wall of unit if absorption is required.
913.06 Precast Drainage Structure Adjusting Rings	Gen Cert	-	-	-	
913.07 Precast Concrete Bases, for Drainage Structures	Appr Mfr *	5 percent of total	-	10 pcs total	
913.08 Structural Tile	Test	1 per proj.	6 tiles	1000 tiles	
913.09 Slope Pavement Blocks	Appr Mfr *	1 per 25,000	6 blocks	1000 pcs	
914.03 Bituminized Fiber Joint Filler	Test Data Cert	1 per 1000 sft or fraction thereof	2 ft See Remark	150 sft	Sample for structure to be at least 5 in. wide. ¼ in. filler need not be sampled.

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
914.03B Recycled Rubber Joint Filler	VI See Remark	-	-	-	Must be a Qualified Product (914.03B).
914.04B Backer Rod for Use with Hot-Poured Joint Sealant	VI	-	-	-	
914.05 Epoxy Binder, For Joint Spall Repair	Test	1 per lot or batch number	See Remark	5 gal	See Special Instructions.
914.06 Epoxy Resin Adhesive and Temporary Seal (Crack Injection)	VI See Remark	-	-	-	Must be a Qualified Product (914.06).
914.07 Transverse Pavement Joints 1. Dowel Bars	Appr Mfr	-	1 bar	1200 bars	Bond Release Agent must be a Qualified Product (914.07A). See Special Instructions 914.07.
Dowel Baskets (Load Transfer Assemblies)	Appr Mfr	-	Full size unit	100 assemblies	Fabrication Inspection required, MQAP Manual Section 4.07.
914.07A Coatings for Dowel Bars 1. Epoxy Coating Companies	Appr Mfr *	1 per project per mfr	1 bar	240 bars	
Epoxy Coating Material	VI See Remark	-	-	-	Coating must be a Qualified Product (905.03C).
Bond Release a. Bituminous Material b. Alternate Bond Release Agents	Gen Cert VI See Remark	- -	- -	20 gal max -	Must be a Qualified Product (914.07A) or meet Standard Spec 914.07A.
914.07C Dowel Bar Expansion Caps	VI	-	-	-	Caps must conform to Standard Plan R-40 Series.
914.08 End-of-Pour Joint Devices	VI	-	-	-	
914.08 Deformed Bars 1. Bars 2. Epoxy Coating	Appr Mfr * VI See Remark	1 per project per mfr	-	500 lb	Epoxy Coating must be Qualified Product (905.03C).

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
914.09 Straight and Bent Tie Bars for Longitudinal Pavement Joints (Lane Ties) 1. Bars	Appr Mfr *	1 per project	2 hor	500 lb	Coating must be a Qualified
2. Epoxy Coating	VI See Remark	per mfr	2 bar		Product (905.03C). See Note.
914.10 Bolts for Structure Expansion Anchors	Test	1 per 5000 pcs or fraction thereof	1 bolt	250 units	
914.11 Preformed Waterproofing Membrane and Joint Waterproofing Membrane	VI See Remark	-	-	-	Must be a Qualified Product (914.11). Do not use on Treated Wood Materials.
914.12 Elastomeric Bearings	Test Data Cert	-	-	-	
915 Bridge Coating Systems	VI See Remark	-	-	ı	Must be a Qualified Product (915).
916.01A Cobblestone	VI	-	-	-	
916.01C Riprap	VI	-	-	-	
916.02 Silt Fence 1. Fabricated Fence 2. Fabric (see 910.04) NOTE: Sample to include identifying	Appr Mfr * VI See Remark	See Remark	See Remark	500 ft	1 sample for the first 3000 ft or fraction thereof; 1 sample for each additional 10,000 ft or fraction thereof; 1 piece 8 ft long by full fence height include 2 attached posts and lath. As per 910.04 of
markings of fabricator. Indicate on sample ID description of markings. Note where markings were found.					Standard Specifications, fabric must be from the Qualified Product List (910.04).
916.07 Turbidity Curtain	VI				
917.03 Nursery Stock	VI	-	-	-	
917.05 Balling Material	VI	-	-	-	
917.06A Wire for Bracing and Guying	VI	-	-	-	
917.06B Hose for Bracing and Guying	VI	-	-	-	
917.06C Stakes for Bracing and Guying	VI	-	-	-	

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
917.08 Compost	VI	-	-	1	
917.10 Chemical Fertilizer for Grass Seed	VI See Remark	-	-	-	Provide the bag label, showing the guaranteed analysis.
917.12 Grass Seeding Mixtures	VI See Remarks	1 per lot per shipment	1/2 lb	1100 lbs	For projects that include more than 5 acres of seeding, see Grass Seed Testing Special Provision in contract. Varieties of seed must be
Grass Seed Varieties	VI See Remark				Qualified Product (917.12).
917.13 Sod	VI	-	-	1	
917.13A Pegs for Sodding	VI	-	-	1	
917.14 Mulching Materials for Nursery Stock	VI	-		-	Only shredded hardwood, wood chips or wood products not allowed.
917.15B1 & 2 High Velocity Mulch Blankets and Standard Mulch Blanket	VI See Remark	-	-	-	Must be a Qualified Product (917.15B 1 & 2). High velocity - netting 2 sides. Standard - netting 1 side.
917.15C Mulch Anchoring - Latex, Recycled Newsprint, Wood Fiber, Guar Gum, Other Tackifiers	VI See Remark	-	-	1	Must be a Qualified Product (917.15C).
917.16 Weed Control (Herbicides)	Test Data Cert	-	-	,	
918.01 Flexible Metal Conduit	VI	-	-	-	
918.01A Electrical Conduit, Rigid (Galvanized Steel)	Gen Cert	See Remark	6 ft, include coupling, if applicable	400 ft	1 sample for 2500 ft or fraction thereof; 2 samples over 2500 to 10,000 ft; 1 sample for each additional 10,000 ft.
918.01B & C Electrical Conduit (Polyvinyl Chloride) Schedule 40 and 80	Gen Cert	See Remark	6 ft sample w/ bell end incl coupling	400 ft	1 sample for 2500 ft or fraction thereof; 2 samples over 2500 to 10,000 ft; 1 sample for each additional 10,000 ft.

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
918.01D & E Electrical Conduit (Polyethylene/HDPE) Schedule 40 and 80	Gen Cert	See Remark	See Remark	400 ft	1 sample for 2500 ft or fraction thereof; 2 samples over 2500 to 10,000 ft; 1 sample for each addi- tional 10,000 ft; 6 ft plus a sepa- rate section consisting of 2- 18 in. long pcs. connected by the joint.
918.01F Electrical Conduit (Rigid Fiberglass)	Gen Cert	See Remark	6 ft sample w/ bell end incl. coupling	400 ft	1 sample for 2500 ft or fraction thereof; 2 samples over 2500 to 10,000 ft; 1 sample for each additional 10,000 ft.
918.02 Grounding System	VI	-	-	-	
918.02C Grounding Rods	VI	-	-	-	
918.03 Electrical Cable	See Note	- -	-	-	

NOTE: Suitability and compliance with specifications will be determined by the agency responsible for maintaining the system. This agency shall provide the project engineer with a memo or other appropriate form indicating that the inspection has been made and that the material is acceptable.

918.06 Precast Concrete Handholes and Manholes for Electrical and Telephone Connections	Appr Mfr *	1 percent per size	-	10 pcs	
918.06D Light Weight Composite Handholes	VI See Remark	-	-	-	Must be a Qualified Product (918.06D).
918.08 Light Standards (Steel and Aluminum Light Standards)	Gen Cert	-	-	-	
918.08C Light Standards, Frangible Transformer Bases	VI See Remark	-	-	-	Must be a Qualified Product (918.08C).
918.09 Luminaries	Gen Cert	-	-	-	
918.10A Tower Lighting Units	Fabrication Inspection	-	-	-	MQAP Manual Section 4.06.
918.11A Guy Wire	Test	1 per size	3 ft	-	
919 Steel Sleeves for Wood Posts	Gen Cert	-	-	-	

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
See Remark	-	-	-	General Cert must be attached and inspected at project site.
Tested Stock See Remark	1 from each width in shipment	12 in. long and full width of section	-	Test Data Cert must be attached to the Sample ID form.
Gen Cert See Remark	-	-	-	Grade mark on materials serves as certification.
Tested Stock See Remark	See Note	Min. of 12 in. square	100 sft	Test Data Cert must be attached to the Sample ID form.
Stock Supplier up	o to 10,000 sft; 4 sa	mples per heat p	per Tested Sto	ock Supplier over 10,000 sft.
VI See Remark	1 per run or lot	See Remark	1 roll, for less than 3 in. in width	Must be a Qualified Product (919.02B1) 4 pcs each 12 in. square. For rolls less than 12 in. width, at least 7.5 ft.
Gen Cert See Remark	-	-	-	Identifying marks on items may serve as certification.
Gen Cert	1 per shipment per color	21 pcs	25 pcs each color	
Gen Cert	1 per shipment per color	2 pcs each color	25 pcs each color	
Gen Cert	1 per project per mfr	1 post	80 post	
VI See Remark	-	-	-	Must be a Qualified Product (919.03D).
Test Data Cert	1 per project per mfr	See Remark	20 posts	Sample 30 in. length min. length. Posts for temporary signs may be painted.
Appr Mfr *	Each charge	22 cores	20 posts	General Cert to Construction Field Services. See 912.08.
Fabrication Inspection	-	-	-	MQAP Manual Section 4.06.
	See Remark Tested Stock See Remark Gen Cert See Remark Tested Stock See Remark Stock Supplier up VI See Remark Gen Cert See Remark Gen Cert Gen Cert Gen Cert Gen Cert Appr Mfr * Fabrication	Basis of Acceptance If Required by the Engineer** See Remark - Tested Stock See Remark	Basis of Acceptance I Frequency If Required by the Engineer** See Remark Tested Stock See Note Min. of 12 in. square Stock Supplier up to 10,000 sft; 4 samples per heat part of the see Remark Gen Cert See Remark Gen Cert See Remark Gen Cert 1 per run or lot See Remark Gen Cert 1 per shipment 21 pcs per color Gen Cert 1 per shipment 22 pcs each color Gen Cert 1 per project per mfr VI See Remark Test Data Cert 1 per project per mfr Fast Data Cert Per mfr Appr Mfr * Each charge 22 cores Fabrication	Basis of Acceptance I Frequency If Required by the Engineer** See Remark

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

		quanty.			
Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
919.07 Cantilever Sign Supports	Fabrication Inspection	-	-	-	MQAP Manual Section 4.06.
919.08 Truss Sign Supports	Fabrication Inspection	-	-	-	MQAP Manual Section 4.06.
920.02 Glass Beads	Gen Cert	1 from each lot	2 lb	500 lbs	
920.02C Wet Reflective Beads/Elements	VI See Remark	-	-	-	Must be a Qualified Product (920.02C).
921.02 Span Wire	Gen Cert	1 per size	3 ft	-	
921.03 Traffic Signals and Mounting Assemblies	See Note	-	-	-	
NOTE: Compliance with specifications w project engineer with a memo or other appropriate the complex of the com	ill be determine ppropriate form i	d by the agency res	ponsible for mai spection has be	ntaining the sy en made and	vstem. Agency must provide the the material is acceptable.
921.05 Traffic Signal Strain Pole	Gen Cert	-	-	-	
921.05A Strain Pole Band Clamps	VI See Remark	-	-	-	Must be a Qualified Product (921.05A).
921.08B Traffic Loop Sealant	Gen Cert	2 from each lot	Tubes	-	
922.02 Temporary Traffic Control Temporary Signs	See Remark	-	-	-	See MQAP Manual Section 4.10.
922.02B Temporary Traffic Control Reflective Sheeting (Signs)	See Remark	-	-	-	See MQAP Manual Section 4.10.
922.02D Temporary Traffic Control Sign Covers	See Remark	-	-	-	See MQAP Manual Section 4.10.
922.03 Temporary Traffic Control A. Cones	See Remark	-	-	-	See MQAP Manual Section 4.10.
B. Drums					
922.03E Temporary Traffic Control Type III Barricade, Reflective Sheeting	See Remark	-	-		See MQAP Manual Section 4.10.

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

Spec. No. and Material Name	Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
922.04 Temporary Traffic Control Temporary Concrete Barriers (TCB)	Test Data Cert See Remark	Each project	-	-	Contractor must provide certifications and documentation confirming the TCB provided meets the requirements of subsection 922.04.A of the Standard Specifications for Construction.
922.04A Barrier Reflector Markers Temporary	See Remark	-	-	-	See MQAP Manual Section 4.10.
922.04A Barrier Reflector Markers Permanent	VI	-	-	-	
922.06A Temporary Traffic Control Temporary Pavement Markings; Type R and NR Tape	VI See Remark	-	-	-	Must be a Qualified Product (922.06A).
922.06A2 Temporary Traffic Control Temporary Pavement Markings; Paint	VI See Remark	-	-	,	Must be a Qualified Product (811.03D).
922.06B Temporary Traffic Control Temporary Raised Pavement Markers	VI See Remark	-	-	-	Must be a Qualified Product (922.06B).
922.06C Temporary Traffic Control Pavement Marking Cover	VI See Remark	-	-	1	Must be a Qualified Product (922.06C).
922.07A Temporary Traffic Control Lighted Arrows; Type B and C (Solar Assist)	See Remark	-	-	-	See MQAP Manual Section 4.10.
922.07B Temporary Traffic Control Warning Flashers and Lights; Type A, B, C	See Remark	Each project	3 each type	-	See MQAP Manual Section 4.10.
922.07C Temporary Traffic Control Portable Changeable Message Signs	See Remark	-	-	-	See MQAP Manual Section 4.10.
922.11 Temporary Traffic Control Sign Paddles and Vests	See Remark	-	-	-	See MQAP Manual Section 4.10.
922.12A Temporary Traffic Control Dust Palliative 1. Calcium Chloride Solids	Test Data Cert	1 per project	5 lb	5000 lb	

See Miscellaneous area at the end of table for materials deleted from the 2012 Standard Specifications for Construction.

* Must be tested unless provided by an Approved Manufacturer.

** When the Basis of Acceptance is not "Test", the sampling criteria below may be used when there are concerns with material quality.

Basis of Acceptance	Sample Frequency If Required by the Engineer**	Sample Size	Maximum VI Quantity	Remarks (QPL Reference)
Test Data Cert	1 per project	1 qt	1000 gal	
Gen Cert	-	-	250 ft of pipe	See contract documents as applicable.
Gen Cert	-	-	250 ft	
Gen Cert	See Remark	See Remark	10 pieces	See Special Instructions.
VI See Remark	-	-	-	MDOT approval of Design is required. Coating thickness checked at project site.
Test	1 per 6000 ft	1 piece, 6 ft in length	600 ft	If bell and spigot joint, sample from bell end.
Gen Cert	1 per 100 plates or fraction thereof	1 piece at least 3 in. by 3 in.	10 plates	
Gen Cert	-	-	-	
VI	-	-	-	
Gen Cert	See Remark	1 piece full width of roll, min of 3 ft	5 rolls	1 per 100 rolls (50 sft per roll) or fraction thereof; for lots of more than 100 rolls - 1 sample plus 1 for each 500 rolls or fraction thereof. Do not sample from first 3-4 ft of roll.
	Test Data Cert Gen Cert Gen Cert VI See Remark Test Gen Cert VI Cen Cert VI VI VI VI VI	Basis of Acceptance If Required by the Engineer** Test Data Cert	Basis of Acceptance If Required by the Engineer** Test Data Cert	Basis of Acceptance If Required by the Engineer** Sample Size VI Quantity Test Data Cert 1 per project 1 qt 1000 gal Gen Cert 250 ft of pipe Gen Cert See Remark See Remark 10 pieces VI See Remark 1 per 6000 ft 1 piece, 6 ft in length Gen Cert 1 per 100 plates or fraction thereof 3 in. by 3 in. Gen Cert See Remark 1 piece full width of roll,

****** See following pages for SPECIAL INSTRUCTIONS *********

SPECIAL INSTRUCTIONS

712.03L Mechanical Reinfocement Splicing

The contractor must make test splices, witnessed by the Engineer, on the largest bar sizes that are to be spliced. See Bridge Field Services Advisory (BFSA) 2012-03. Test splice consists of 2 pieces of reinforcing bar joined by the coupler with 12 inches of bar exposed on each end of the coupler.

901 Cement

Samples of fly ash and slag cement must be accompanied by a sample of the Portland cement with which it is being used. The plastic lined cement sample bags furnished by the laboratory will hold 10 pounds when full.

902 Prequalified Aggregate Suppliers

Quality Assurance tests will be conducted by Department personnel at the frequencies stated in Chapter 3 of the MDOT Aggregate Supplier Program, found in the Procedures for Aggregate Inspection Manual.

Every Project Engineer will verify passing quality assurance tests by contacting the Region/Transportation Service Center's Material's Supervisor. Enter a telephone record memo or copy of the test report in the project file.

The statement on each delivery ticket is required documentation of the Pre-Qualified Supplier Program and is to be provided by the supplier. This statement represents the results of quality control testing and does not signify acceptance by MDOT.

904.03A Asphalt Binder for HMA Mixtures

If the Asphalt Binder is supplied from a source currently on the Approved Asphalt Binder Certifier List, a certification meeting the requirements of Section 3.05.05 of the Materials Quality Assurance Procedures Manual is required. See the contract documents for sampling, acceptance, and daily monitoring requirements.

If the binder is supplied from a source that is **not** currently shown in the Approved Asphalt Binder Certifier List, the asphalt binder must be sampled, tested, and approved for use prior to incorporation into the project. See contract documents for sampling, acceptance, and monitoring requirements.

See Current List of Asphalt Binder Certifiers at Construction Field Services Web Page.

Instructions to Construction Field Services web page: From MDOT home page (michigan.gov/mdot), click on about MDOT (left side), then click on Highway Field Services, and then click Construction Field Services. The <u>Approved Asphalt Binder</u> Certifier List is under Resources & Publications.

Actual Current List of Approved Asphalt Binder Certifier web page address: http://michigan.gov/documents/AppBinderCertlist_49824_7.pdf

Page 48 of 98 October 2018

904.03C Emulsified Asphalt

Size of Sample – For CV Sampling see Section 3.06.06 of the *Materials Quality Assurance Procedures Manual*. For all other sampling see contract documents for criteria. Submit the samples in plastic containers only.

905.03 Bar Reinforcement (Uncoated)

Sample size must be 2 pieces, one 24 in. and one 36 in. Sample ID must include the name of the bar manufacturer, lot number, and heat number. Mill Cert must be attached to the Sample ID form.

905.03C Bar Reinforcement (Epoxy Coated)

Sample size must be 2 pieces, one 24 in. and one 36 in. Sample ID must include the name of the epoxy coating company, epoxy resin trade name, name of bar manufacturer, lot number, and heat number. Mill Cert must be attached to the Sample ID form. Epoxy coating must be a Qualified Product (905.03C).

905.06 Welded Steel Wire Reinforcement

Sample size must be one piece, full width of fabric with two transverse wires. Longitudinal wires must extend 6 in. to 8 in. either side of transverse wires. Sampling not required when larger wire is less than 0.13 in. (w1.5) in dia. Include on sample ID the size that the wires are supposed to be. Sample may be folded or cut into approx. 3 ft. sections. If cut, pieces should be wired together and identified. Mill Cert must be attached to the Sample ID form.

905.07 Strand for Prestressed Concrete

Do not obtain sample from within 5 feet of the end of the reel. Mill Cert must be attached to the Sample ID form.

905.08 Tendons for Post Tensioning of Box Beams - Prestressing Strand

Do not obtain sample from within 5 feet of the end of the reel. Mill Cert must be attached to the Sample ID form.

906.07 High Strength Steel Bolts

An assembly is typically a combination of a bolt, nut, and washer but may be any combination of a bolt, nut, washer, lock washer, etc. depending on the project specifications. Mill Certs must be included for each component of the assembly and be attached to the sample ID form.

907.04C Steel Chain Link Fence-Posts for Fence and Gates

An alternative zinc/clear coat system will be allowed for pipe sections only. This alternative coating system shall comply with subsection 907.03D of the Standard Specifications for Construction.

907.04C Steel Chain Link Fence-Top Rail, Horizontal Rail

An alternative zinc/clear coat system will be allowed for pipe sections only. This alternative coating system shall comply with subsection 907.03D of the Standard Specifications for Construction.

908.09A Tubing, Steel Railings (Base Plate, Angle, and Non-Tubular Post Elements)

Mill Cert must be attached to the Sample ID form.

908.09B Tubing, Steel Railings (Rail Elements and Tubular Post Elements)

Mill Cert must be attached to the Sample ID form.

908.09C Tubing, Steel Railings (Hardware)

An assembly is typically a combination of a bolt, nut, and washer but may be any combination of a bolt, nut, washer, lock washer, etc. depending on the project specifications.

908.14 Anchor Bolts, Nuts, and Washers

An assembly is typically a combination of a bolt, nut, and washer but may be any combination of a bolt, nut, washer, lock washer, etc. depending on the project specifications. For Type C, D, E and J cantilevers, the sampling frequency is 1 assembly per heat, per diameter, per foundation, for a max of 3 per project. Full length bolts are required for testing but if the total length is less than 20", a second sample must be submitted for testing. Non MDOT standard plan bolts require shop drawings along with a Mill Cert attached to the Sample ID form. Stainless steel anchors bolts are not required to be tested.

908.14D Anchor Bolts and Nuts for Other Purposes

A General Cert is acceptable for stainless steel anchor bolts, pedestal foundations for pedestrian signals, push buttons, controller cabinets, and Hawks signals and repeaters. Anchor bolts for all other purposes require testing. An assembly is typically a combination of a bolt, nut, and washer but may be any combination of a bolt, nut, washer, lock washer, etc. depending on the project specifications.

909.04A Reinforced Concrete Pipe 909.04B

Size of Sample - Full size units for strength test. For absorption tests, 26-inch square to 81-inch square in area from the wall of each piece of pipe tested.

Number of Samples - One percent of the number of pieces of each size.

Reinforced concrete pipe 42-inch diameter and larger may be tested by coring. Size of core will be 4-inch nominal diameter (but not less than 3 ¼ inches actual). Up to 1 percent of the number of pieces of pipe for each size, but not less than 3 pieces, will be selected for coring. One core will be drilled and tested from each of these test pieces. Reinforcement will be inspected prior to incorporation in the pipe.

909.04C Nonreinforced Concrete Pipe

Size of Sample - Same as reinforced concrete pipe.

Number of Samples - One percent of the number of pieces, but not less than 2 pieces of each size except that at the option of the department the following sampling schedule will apply for 4 inches through 24 inches in diameter sewer pipe for quantities of 500 or more:

Sampling Schedule - Per the following:

Concrete Pipe Number of Samples

500 to 1,000 pieces 6 1,001 to 2,000 pieces 8 2,001 to 5,000 pieces 11

Over 5,000 pieces 2 samples per 1,000 or fraction thereof

909.05A Corrugated Steel Pipe

Size of Sample - A 6-inch by 3-inch (minimum) section cut from the pipe. The sample should be taken from the end of the pipe avoiding the seams. Care should be taken to assure the coating is not damaged during sampling. Mill Cert must be attached to the Sample ID form.

Number of Samples - Per the following:

Diameter of Pipe Quantity Represented (maximum)

12 inches or less 2500 ft 15 inches through 54 inches 1000 ft 60 inches and over 500 ft

Less than 5 percent of the quantity in the above table may be visually inspected.

909.05A1 Corrugated Galvanized Steel Sheets

Size of Sample - One strip the full width of the sheet and 3 ½ inches in the direction of the length of the sheet. The strip may be cut from the end of the sheet for material coated in coils. If the sheets were individually coated after being cut to length, as indicated by heavy accumulations of zinc at one end, the sample strip shall be cut from the end opposite the heavy accumulation and after cutting 4 inches from the end of the sheet. Mill Cert must be attached to the Sample ID form.

Number of Samples - Per the following:

Diameter of Pipe	Length of Sheet	Quantity Represented
<u>(max)</u>		
12 inches or less	44 inches or less	2500 ft
15 through 54 inches	50 to 175 inches, approx*	1000 ft
60 inches and over	190 inches and over*	500 ft

^{*}Larger pipe may be made from combination of shorter sheets. Less than 5 percent of the quantity in the table above may be visually inspected.

NOTE: Normally each heat and thickness is to be sampled. Exception may be made where quantities are limited and/or mixtures of heat numbers are excessive.

909.05B Corrugated Aluminum Alloy Sheets

Size of Sample - A transverse strip full width of the sheet and at least 3 inches in length cut from the end of the sheet.

Number of Samples - A sample shall be taken from each of 3 different sheets for lots weighing 5 tons or less, from 4 sheets for lots weighing more than 5 tons and less than 10 tons, and from 5 sheets for lots weighing 10 tons or more.

909.06 Corrugated Polyethylene Pipe (Smooth Lined Type S or Corrugated Type C)

If the manufacturer has developed a history of five consecutive passing tests over the past two years for a given diameter of pipe (12 to 24-inch), at the discretion of the MDOT testing laboratory the sampling frequency may become 1 per 2500 ft for that diameter of pipe provided the stockpile consists of pipe manufactured with a single "Plant" and "Date" code. The Tested Stockpile sampling frequency of one sample per 1000 ft of pipe (12 to 36-inch) may be re-instituted if the manufacturer experiences three failing test results for a given diameter of pipe over a one year period. Up to date information on sampling frequency may be acquired from MDOT's Construction Field Services Division.

For perforated pipe wrapped in geotextile fabric, tie fabric securely in place on sample before cutting pipe sample. Do not disturb fabric after cutting.

Suppliers shall provide MDOT inspector with list of date codes on pipe in stockpile to be tested prior to sampling.

Each size pipe is a different material. Stockpile each pipe size separately.

Preparation of 30 & 36 Inch Diameter Corrugated Polyethylene Pipe

The manufacturer will be responsible for preparing the sample specimens and delivering them to the laboratory for testing.

Preparation by manufacturer of each 20 foot length of pipe sample include:

- Cut three specimens from each length of pipe sampled, at least once the diameter in length. (For 30 in. pipe this would mean three specimens just over 30 inches in length, cuts may be made in the valley of the first corrugation beyond 30 inches, etc.)
- 2. Cut 1 specimen from each length of pipe sampled at least 60 inches in length.
- 3. Assemble a joint from each length of pipe sampled with approximately 6 inches of pipe protruding from each end of the joint.
- 4. Mark all specimens cut from the sample length of pipe so they can be identified at the laboratory as having come from the same length of pipe.

Call the CFS- Materials Testing Laboratory in Lansing with any questions regarding the above instructions. (517-322-1217)

Perforated Pipe

Tested Stock is not permitted.

Soil tight sleeves shall be submitted with a pipe section 12 inches minimum length and gasket fully inserted into one end of the sleeve. A second gasket shall be supplied already installed on either the 10-ft specimen or on a separate specimen at least 12 inches in length, from the same stockpile.

Single Gasket Bell and Spigot Fused Coupling System - Couplers shall be submitted as attached part of 10-ft specimen and a second piece of the specimen, minimum of 12 inches in length, with gasket installed shall be included with the sample.

Each size pipe is a different material. Stockpile each pipe size separately.

910.03 Geotextiles

Sampling Frequency - Obtain samples to represent the required quantity of geotextile according to the following schedule:

<u>Geotextile</u>	First Sample	Additional Samples
Blanket	500 to 1500 syd	7,500 syd or less
Liner for Riprap	500 to 1500 syd	5,000 syd or less
Separator/Stabilization	500 to 1500 syd	25,000 syd or less
Liner for Heavy Riprap	500 to 1500 syd	4,000 syd or less

Maximum for VI - 500 syd (4500 sq ft)

Size of Sample - Sample must be a minimum of 75 sft, taken across the full roll width. For rolls over 15 ft wide, sample must be a minimum of 5 ft long, taken across the full roll width.

Geotextile samples submitted for testing must be identified with the lot number and/or roll number, the name of the manufacturer, and the product or style number.

NOTES:

Geotextiles must be unwrapped one full roll circumference prior to sampling.

Geotextiles must be <u>rolled</u>, not folded, and shipped in a manner to prevent creases in the fabric.

914.05 Epoxy Binder, For Joint Spall Repair

Normal Sampling Frequency - 1 per lot or batch number

Size of Sample - For material mixed at 1:1 ratio - 1 quart of each component: For material mixed at 2:1 ratio - 1/2 gallon of resin and 1 quart of curing agent. Material limited to shelf life of one year from date of manufacture. Material must be labeled with date of manufacture.

914.07 Load Transfer Assemblies; Dowel Baskets

Fabrication Inspection required per Chapter 4.07 of the Materials Quality Assurance Procedures Manual.

Assemblies must meet the requirements of Standard Plan, R-40-H.

All shipments of load transfer assemblies will be accompanied by proper certification documentation.

- Certification from steel (dowel bar) manufacturer.
- Certification from epoxy coating company.
- Documentation on epoxy coating.
- Certification from assembly manufacturer.
- Documentation on bond release.

When shipment is made to a project, each bundle will bear a legible tag with the following information:

- Assembly manufacturer name and plant location.
- Control section/project number.
- Lot number or other identification that will also be shown on the accompanying certification.
- Supplier and/or contractor's name.

Misc. #3 Clay Pipe

Normal Sampling Frequency - One percent of the number of pieces, but not less than 2 pieces of each size except that at the option of the department the following sampling schedule will apply for 4-inch through 24-inch diameter sewer pipe for quantities of 500 or more:

Sampling Schedule - Per the following:

Clay Pipe	Number of Samples	
500 to 1,000 pieces	6	
1,001 to 2,000 pieces	8	
2,001 to 5,000 pieces	11	
Over 5,000 pieces	2 samples per 1,000 or fraction thereof	

Size of Sample - Full size units for strength test. For absorption tests, 26 inches square to 82 inches square in area from the wall of each piece of pipe tested.

APPROVED SUPPLIERS

The firms listed in this section have received written permission from the Construction Field Services Division to recertify material for use on Michigan Department of Transportation projects. Supplying materials is also allowed by manufacturers listed in the Approved Manufacturers List.

When recertification of any materials is made by any firm not found on this list, please notify the Construction Field Services Division, Materials Control, immediately.

See also Section 3.02 of the Materials Quality Assurance Procedures Manual.

A.J. Rehmus & Son, Inc., Bay City, MI

ABC Coating Co. of Illinois, Inc., Peotone, IL

ABC Coating Co. of Michigan, Inc., Wyoming, MI

ABC Coating Co. of Minnesota, Inc., Minneapolis, MN

ABC Coating Co. of Oklahoma, Inc., Tulsa, OK

Action Traffic & Maintenance Co., Flint, MI

Allied Seed, L.L.C., Nampa, ID

Alro Steel Corporation, Alpena, MI

Art Thureson, Inc., Waterford, MI

Austin Morgan Companies, Clarkston, MI

B&R Reinforcing, Columbus, OH

BARNSCO, Walled Lake, MI

Bella Concrete Construction, LLC, Houghton Lake, MI

Boomer Construction Materials, Detroit, MI

Burt Forest Products Co., Ann Arbor, MI

C & D Hughes, Inc., Charlotte, MI

C.A. Hull Co., Inc., Walled Lake, MI

Cadillac Culvert, Cadillac, MI

Carroll Distributing and Construction Supply, Inc. (Store 16), Wyoming, MI

Causie Contracting, Inc., Mason, MI

Central Michigan Contracting, Inc., Houghton Lake, MI

Chiles Michigan, Inc., Flat Rock, MI

Cipparrone Contracting, Inc., Southfield, MI

CMA Supply, South Bend, IN

Co-Pipe Products, Taylor, MI

Concrete Central Inc., Grand Rapids and Traverse City, MI

Core and Main LP, Canton, Kentwood and Shelby Twp., MI

CSI Geoturf, Inc., Highland, Traverse City, and Byron Center, MI

D.J. McQuestion & Sons, Inc., LeRoy, MI

Dale Dukes & Sons, Inc., Big Rapids, MI

Davis Construction, Lansing, MI

Dayton Superior Corporation, Miamisburg, OH, Oregon, IL, Valparaiso, IN

Diane Dukes, Inc., Big Rapids, MI

Doan Construction, Ypsilanti, MI

Dornbos Sign & Safety Inc., Charlotte, MI

Eastlund Concrete Construction, Holt, MI

East Jordan Iron Works, Inc., Wyoming, MI

Edward R. White Contractor, Inc., Waterford, MI

Elsey Construction Products, Harper Woods, MI

Environmental Protection Products, Williamsburg, MI

Ersco Corp., Wyoming, MI

ETNA Supply Co., Chesterfield, Flint, Grand Ledge, Grand Rapids and Holland, MI

ETNA Supply Co., Jackson, Kalamazoo, Mt. Pleasant and Muskegon, MI

ETNA Supply Co., Saginaw, Sault Ste. Marie, Springfield, Traverse City and Wixom, MI

ETNA Supply Co., South Bend, IN and Toledo, OH

Evergreen Seed Supply, Deshler, OH

F&M Concrete Construction, LLC, Dimondale, MI

Ferguson Enterprises, Inc., Flushing, Kalamazoo, Kentwood, Lansing, and Warren, MI

Firelands Supply Co., Norwalk, OH

Fort Wayne Contracting, Inc., Detroit, MI

Frederick Steel Company, Cincinnati, OH

Future Fence Co., Sterling Heights, MI

G3 Steel Group, Troy, MI

Geo Products, Birmingham, MI

Give 'Em-A-Brake Safety, Grandville, MI

Grant Welding Service, Grant, MI

Harbor Pipe and Supply, Traverse City, MI

Harris Rebar/Ambassador Steel Corporation, Comstock Park and Lansing, MI, Bourbonnais, IL

Harris Rebar, Bethlehem, PA

Hunt Brothers Concrete Contractors, Inc., Whittemore, MI

Hymmco, Saginaw, MI

Indiana Material Handling, IMH Products, Inc., Indianapolis, IN

J & J Contracting, Ithaca, MI

J.D. Russell Co., Utica, MI

JISI Group, LLC, Sterling Heights, MI

Jacklin Steel Supply Co., Escanaba, MI

Jensen Bridge and Supply Co., Grand Rapids and Sandusky, MI

John Deere Landscapes, Ann Arbor, and Grand Blanc, MI

John Deere Landscapes, Clinton and Commerce Townships, MI

John Deere Landscapes, Grand Rapids, Holland, and Kalamazoo, MI

John Deere Landscapes, Dimondale, Livonia, Madison Heights, and Saginaw, MI

John Deere Landscapes, Shelby Township

John Deere Landscapes, Taylor, and Traverse City, MI

Kalamazoo Forest Products, Inc., Otsego, MI

Kamminga & Roodvoets, Inc., Grand Rapids, MI

Kenmark, Inc., Buckley, MI

Kerkstra Precast Inc., Grandville, MI

Klein Brothers Hardwood, Inc., Milford, MI

L.J. Construction, Inc., Clifford, MI

L.W. Lamb, Inc., Saugatuck, MI

Lane Enterprises, Inc., Carlisle, PA

Mack Industries, Inc., White Lake, MI

Manthei Development Corp., Charlevoix, MI

Martin J. Concrete, Inc., Coopersville, MI

Meadow Burke, Palisades Park, NJ

Metro Rebar, West Bloomfield, MI

Michigan Highway Signs, Flint, MI

Michigan Pipe and Valve, Jackson, Saginaw, and Traverse City, MI

Midway Contractor Supply, Negaunee, MI

Midwest Pipe Coatings, Schererville, IN

Milbocker & Sons, Inc., Allegan, MI

Miller Products & Supply Company, Iron Mountain, MI

Nationwide Fence & Supply Co., Chesterfield, MI

North Coast Roofing Systems, Grand Rapids, MI

Northern Concrete Pipe, Bay City, Charlotte, Clarkston, and Wyoming, MI; Sylvania, OH

Northern Construction Services Corp., Niles, MI

NuTek Steel, Toledo, OH

OEM Distribution, LLC, Detroit, MI

Oglesby Construction, Inc., Norwalk, OH

One Supply Group, Auburn Hills, MI

P.K. Contracting, Inc., Lake City, MI

Power Line Supply Company, Reed City, MI

Rathco Safety Supply, Inc., Portage, MI

Remington Construction Company, Inc., Mattawan, MI

Rhino Seed and Landscape Supply, Bradley and Brighton, MI

Rightway Fence Co., Sterling Heights, MI

Sanches Construction Company, Lansing, MI

Simcote, Inc., Saint Paul, MN and Marion, OH

Snowden, Inc., Escanaba, MI
Standale Lumber, Grandville, MI
Striker Supply, Traverse City, MI
Sweeney Construction Materials, Novi, MI
Titusville Fabricators, Inc., Franklin, PA
Tri-Valley Landscaping, Inc., Saginaw, MI
UP Concrete Pipe Co., Escanaba, MI
Van Laan Construction Supply, Dutton, MI
Wady Industries, Maqouketa, IA
Watson Bowman Acme Corp., Amherst, NY
Weyand Bros. Inc., Saginaw, MI

APPROVED MANUFACTURERS

The materials in this section may be accepted for use on Michigan Department of Transportation projects on the basis of certification from the suppliers listed under specific materials.

This Approved Manufacturers List is in accordance with the 2012 Standard Specifications for Construction.

See also Section 3.02 of the Materials Quality Assurance Procedures Manual.

Page 59 of 98

		APPROVED MANUFAC	TURE	RS	
Spec. # and M Name	aterial	Approved Manufacturers		Manufacturers Location	
901 Cement	Buzzi Unicem USA		Chatta	nooga, TN, Festus MO, Greencastle,	
		Fairborn Cement Company	Fairbo	rn, OH	
		Central Plains Cement-Sugar Creek Plant	Sugar	Sugar Creek, MO	
		Continental Cement Company	Hannil	oal, MO	
		Argos USA, LLC		sburg, WV	
		CRH Canada Group, Inc.		t and Dundee, MI; Duluth, MN; sauga, Ontario, Canada	
		Illinois Cement Company	LaSall		
		LafargeHolcim		a, MI, and Paulding, OH	
		LafargeHolcim, St. Genevieve Plant		sdale, MO	
		LeHigh Cement Company, LLC		sport and Mitchell, IN; Picton, Ontario,	
		St. Mary's Cement	Detroi	t and Charlevoix, MI; Bowmanville and iry's, Ontario, Canada	
901.06 Slag Cement		CRH Canada Group, Inc.	Detroi	t and Dundee, MI; Mississauga, o, Canada	
Clay Comon		LafargeHolcim		Chicago, IL	
		Skyway Cement Company, LLC	Chicag		
		St. Mary's Cement		t, MI; Milwaukee, WI	
Spec. # and Material Name		Approved Manufacturers	Class	Source or Plant Location	
901.07	Waste I	ste Mgmt./FlyAsh Direct		Zimmer Power Plant, Moscow, OH	
Pozzolanic		Mgmt./FlyAsh Direct	F F	Miami Fort Unit 7 & 8, North Bend, OH	
Admixtures	Waste I	Mgmt./FlyAsh Direct	F	Avon Lake Unit 9, Cleveland, OH	
(Fly Ash) for	Waste I	Mgmt./FlyAsh Direct	С	Joppa Generating Station, Joppa, IL	
Concrete	Boral R	esources	F	Conesville Power Plant, Conesville, OH	
		esources	С	Erickson Power Plant, Lansing, MI	
		esources	F	Sammis Power Station, Stratton, OH	
		esources	F	Monroe Power Plant Monroe, Michigan	
		esources	C	Schahfer Station, Unit 15, Wheatfield, IN	
		esources	F	Schahfer Station, Unit 17 & 18, Wheatfield, IN	
		esources	С	Labadie Power Station, Labadie, MO	
		esources	C F	Rush Island Power Station, Festus, MO Zimmer Power Station, Moscow, OH	
Charah, Inc. Charah, Inc.		F	Miami Fort Unit 7 & 8, North Bend, OH		
	CRH Canada Group, Inc.		C	Bell River Unit #1, St. Clair, MI	
	CRH Canada Group, Inc		C	Bell River Unit #2, St. Clair, MI	
LafargeHolcim		C	Will Co. Plant, Romeoville, IL		
LafargeHolcim		C	Elm Road Generating Station, Oak Creek, IL		
	LafargeHolcim		C	Columbia, Portage, WI	
	LafargeHolcim		C	Edgewater Sta. Unit 5, Sheboygan, WI	
	Lafarge		C	Pleasant Prairie, Kenosha, WI	
	Lafarge	Holcim	С	Weston #3, Wausau, WI	
	Lafarge	Holcim	С	Presque Isle Power Plant, Marquette, MI	

APPROVED MANUFACTURERS			
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location	
903.03	Trinseo		
Latex Admixture For Concrete	BASF Corporation		
	Polytherm Systems, Inc., General Tire	es	
904.03C		nalts at Construction Field Services Web	
Emulsified Asphalt	Page.		
	(michigan.gov/mdot), click on about M Services, and then click Construction I	Instructions to Construction Field Services web page: From MDOT home page (michigan.gov/mdot), click on about MDOT (left side), then click on Highway Field Services, and then click Construction Field Services. The Approved Emulsified Asphalt Suppliers List is under Resources & Publications.	
	Actual Construction Field Services we	h nage address:	
	http://www.michigan.gov/documents/m		
905.03	American Steel & Wire	Joliet, IL	
Bar Reinforcement (Uncoated)	ASI Alton Steel, Inc.	Alton, IL	
,	Austeel	Lemont, IL	
	Barbary Coast	Mississippi, Norfolk, Illinois	
	Byer Steel (formerly A.B. Steel)	Cincinnati, OH	
	CMC Steel	and the second s	
	CMC Steel (Texas)	Seguin, TX	
	CMC Steel	Cayce-West, Columbia, SC	
	Cascade Steel Rolling Mills	McMinnville, OR	
	ERSCO Construction Supply	Wyoming, MI	
	EVRAZ Rocky Mountain Steel	Pueblo, CO	
	Gerdau Ameristeel Corporation	,	
	Beaumont Steel Mill Div.	Vidor, TX	
	Charlotte Steel Mill Div.	Charlotte, NC	
	Jackson Steel Mill Div.	Jackson, TN	
	Jacksonville Steel Mill Div.	Jacksonville, FL	
	Knoxville Steel Mill Div.	Knoxville, TN	
	Midlothian Steel Mill Div.	Midlothian, TX	
	St. Paul Steel Mill Div.	St. Paul, MN	
	Sayreville Steel Mill Div.	Sayreville, NJ	
	Nucor Steel	Cay: c:c, ::c	
	Nucor Steel Auburn, Inc.	Auburn, NY	
	Nucor Steel Birmingham, Inc.	Birmingham, AL	
	Nucor Steel Connecticut, Inc	Wallingford, CT	
	Nucor Steel Jackson, Inc.	Flowood, MS	
	Nucor Steel Kankakee, Inc.	Bourbonnais, IL	
	Nucor Steel Marion, Inc.	Marion, OH	
	Steel Dynamics Inc.	Pittsboro, IN	

APPROVED MANUFACTURERS			
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location	
905.03C	ERSCO Construction Supply	Wyoming, MI	
Bar Reinforcement (Epoxy Coated)	Metal Partners International	Hammond, IN	
	Epoxy Coating Companies		
	ABC Coating Co.		
	ABC Coating Co. of OK, Inc.	Tulsa, OK	
	ABC Coating Co. of MI, Inc.	Wyoming, MI	
	ABC Coating Co. of IL, Inc.	Peotone, IL	
	ABC Coating Co. of MN, Inc.,	Minneapolis, MN	
	Ambassador Steel Corp./Harris Rebar	Bourbonnais, IL	
	American Highway Technology	Kankakee, IL	
	(A Division of Dayton Superior)	Rankakee, iL	
	CMC Rebar	Kankakee, IL	
	CMC Coating of Texas	Waxahachie, TX	
	Co-Steel Sayreville	Sayreville, NJ	
	Dayton Superior Corporation	Valparaiso, IN	
	Gerdau Ameristeel, Muncie Epoxy Coating	Muncie, IN	
	Harris Rebar	Bethlehem, PA	
	Lane Enterprise, Epoxy Coating Div.	Carlisle, PA	
	Midwest Pipe Coatings	Schereville, IN	
	Simcote	Ocherevine, iiv	
	Simcote	Saint Paul, MN	
	Simcote	Marion, OH	
	Simplex	Ontario, CA, Carlyle, IL	
	Titusville Fabricators, Inc.	Pittsburgh, PA	
	Wady Industries, Inc.	Maquoketa, IA	
905.06	Engineered Wire Products	Upper Sandusky and Warren, OH	
Welded Steel Wire Reinforcement	Hallett Wire Products Co.	Opper Sandusky and Warren, Orr	
(Mesh)	Insteel Wire Products	Kingman, AZ; Jacksonville, FL;	
(moon)	Insteel Wife Froducts	Hickman, KY; St Joseph, MO; Mt Airy,	
		NC; Hazelton, PA; Gallatin, TN; Dayton,	
		TX	
	Iowa Steel & Wire	Centerville, IA	
	Numesh	Glen Falls, NY	
	Nucor Steel Connecticut, Inc.	Wallingford, CT	
	Oklahoma Steel & Wire Co. Inc.	Madill, OK	
	Structural Reinforcement Products Inc.	Hazelton, PA	
905.07	Bekaert Corporation	Van Buren, AR	
Strand for Prestressed Concrete	Insteel Wire Products	Sanderson, FL; Gallatin, TN; Houston,	
Oliana for Freshessed Colloide	I III STEEL WITE I TOUUCIS	TX	
	RettCo Steel, LLC	Newnan, GA	
	Sumiden Wire Products Corporation	Stockton, CA; Dickson, TN	
	Strand-Tech Manufacturing, Inc.	Summerville, SC	
905.08	Wire Mesh Corporation (WMC)	St. Matthews, SC	
Tendons for Lateral Post Tensioning	vviid iviesii dorporation (vvivid)	ot. Matthews, oo	
Tondono for Edicial Fost Tensioning			
908.11A	Contech Engineered Solutions, LLC		
Guardrail, Steel Beam Elements,	Gregory Highway Products		
Anchorage, Bridge, Shoes, Departing	Highway Safety Corporation	Glastonbury, CT	
End Terminals (End Sections)	IMH Products, Inc.	Indianapolis, IN	
	R.G. Steel Corporation	Pulaski, PA	
	SPIG Industry LLC	Abingdon, VA	
	Trinity Industries, Inc.	Lima, OH	

APPROVED MANUFACTURERS			
Spec. # and Material Name		Approved Manufacturers	Manufacturers Location
908.11A Guardrail Approach Terminals Remarks: Approach Terminals are proprietary items, accepted as complete units. All systems must be approved by the NCHRP and MDOT Barrier Advisory Commission.	Type1 SRT 350 FLEAT - 350 refer to Design Std. Plans 61(X) latest version Type 2 ET-Plus SKT - 350 refer to Design Std. Plans 62(X) latest version	Trinity Industries, Inc. * Road Systems, Inc. Gregory Highway Products R.G. Steel Corporation Highway Safety Corporation Trinity Industries, Inc. * Road Systems, Inc. Gregory Highway Products R.G. Steel Corporation Highway Safety Corporation	*NOTES: Road Systems, Inc. (RSI) developed both SKT 350 and FLEAT-350 systems. RSI does not manufacture beams. The 3 listed companies under RSI are distributors and distribute SKT and FLEAT smart parts that make-up the approved approach terminals.
908.12	Type 3 CAT FLEAT - MT refer to Design Std. Plans 63(X) latest version	Trinity Industries, Inc. * Road Systems, Inc. Gregory Highway Products R.G. Steel Corporation Highway Safety Corporation Contech Engineered Solutions, LLC	
Steel Posts for Beam G	uardrail	Gregory Highway Products Highway Safety Corporation IMH Products, Inc. R.G. Steel Corporation SPIG Industry LLC Trinity Industries, Inc.	Glastonbury, CT Indianapolis, IN Pulaski, PA Abingdon, VA Lima, OH
909.04A Reinforced Concrete Pi	pe	Co-Pipe Products, Inc. County Materials Corporation Northern Concrete Pipe Upper Peninsula Pipe Co.	Taylor, MI Marathon, WI Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Escanaba, MI
909.04C Non-Reinforced Concrete Pipe		Co-Pipe Products, Inc. Northern Concrete Pipe Upper Peninsula Pipe Co.	Taylor, MI Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Escanaba, MI
909.04D Precast Concrete Box S	Sections	Co-Pipe Products, Inc. County Materials Corporation Hanson Pipe & Products Mack Industries Northern Concrete Pipe Upper Peninsula Pipe Co.	Taylor, MI Marathon, WI Windsor, Canada White Lake, MI, and Toledo, OH Bay City, Charlotte, Clarkston, and Wyoming, MI; Toledo (Sylvania), OH Escanaba, MI

APPROVED MANUFACTURERS			
Spec. # and Material Name	Approved Manufactu	ırers	Manufacturers Location
909.04E	County Materials Corporation		Marathon, WI
Precast Concrete End Section For	Northern Concrete Pipe		Bay City, Charlotte, Clarkston, and
Culverts & Sewers	LI B : L B: O		Wyoming, MI; Toledo (Sylvania), OH
909.04G	Upper Peninsula Pipe Co.	Decign1	Escanaba, MI
Precast Concrete Three-Sided or Arch	ADL Systems, Inc.	Design ¹ Ecospan ^{2, 4}	Portland, MI
Culverts	Advance Concrete Products	Adspan	Highland, MI
	Advanced Infrastructure Tech.	Auspan	Tilgiliand, ivii
NOTES:	(Composite Bridge System)	CBS ²	Orono, ME
1) Manufacturers are only approved for	Contech Engineered	020	5.5 <u>5</u>
the culvert design(s) listed.	Solutions, LLC	BEBO ^{2, 3}	Huber Heights, OH
²⁾ Approved on an experimental basis	Contech Engineered		
and will require evaluation during and	Solutions, LLC	Conspan	Huber Heights, OH
after construction. Contact the	Mack Industries	Conspan	White Lake, MI
department's Structural Fabrication	Northern Concrete Pipe	Northern Arch	Bay City, MI
Unit to coordinate evaluation process.	Northern Concrete Pipe	Hyspan	Bay City, MI
3) 1 1 1 1 1 1 1 1 1	Northern Concrete Pipe	P3	Wyoming, MI
³⁾ Use is restricted to models 42/0-3 and 48/0-1 and is only permitted when	,	System ²	,, yeg,
detailed on the plans and when	Upper Peninsula Concrete	Conspan	Escanaba, MI
analyzed by the department's			
Hydraulics Unit.			
4) Use is restricted to Arch-Box (AB)			
Series up to 48 feet in span length.			
** Effective January 1, 2011, all			
manufacturers must be certified by the			
Precast/Prestressed Concrete Institute			
(PCI), the National Precast Concrete			
Association (NPCA), or the American			
Concrete Pipe Association (ACPA).			
909.05A	Armco Steel Corporation		South Bend, IN
Corrugated Steel Pipe	Bark River Culvert & Equipmer	nt Co.	Escanaba, MI
	Contech Engineered Solutions		Mason, MI, Mitchell and South Bend,
			IN, Portage, WI, Shakopee, MN,
			Ashland and Winchester, KY,
	Lancar Bridge C C L C		Anderson, SC, and Canfield, OH
	Jensen Bridge & Supply Co.		Grand Rapids and Sandusky, MI
	Lane Enterprises, Inc. Cadillac Culvert		Pulaski, PA Cadillac, MI
	St. Regis Culvert, Inc.		Charlotte, MI
	Worthington Steel		Delta, OH
909.07B	Advanced Drainage Systems, I	nc.	Napoleon, OH, and Owosso, MI
Pipe for Underdrains	Baughman Tile Co., Inc.		Paulding, OH
Corrugated Plastic Tubing	Cervell Drainage Products		Lordstown, OH
(Perforated & Non-Perforated)	Hancor, Inc.		Findlay, OH
(Wrapped & Non-Wrapped)	Haviland Drainage		Haviland, OH
	Prinsco, Inc.		Chatsworth, IL

APPROVED MANUFACTURERS			
Spec. # and Mate	erial Name	Approved Manufacturers	Manufacturers Location
909.07C		Armco Steel Corporation	South Bend, IN
Pipe for Underdrains		Bark River Culvert & Equipment Co.	Escanaba, MI
Underdrain Outlet		Contech Engineered Solutions, LLC	Mason, MI, Mitchell & South Bend, IN,
Corrugated Steel Pi	pe		Portage, WI, Shakopee, MN, Ashland
			and Winchester, KY, Anderson, SC,
			and Canfield, OH
		Jensen Bridge & Supply Co.	Grand Rapids and Sandusky, MI
		Lane Enterprises, Inc.	Pulaski, PA
		Michigan Culvert Co.	Mason, MI
		Cadillac Culvert	Cadillac, MI
		St. Regis Culvert, Inc.	Charlotte, MI
909.08B	. Daidea Dada	Armco Steel Corporation	South Bend, IN
Downspouts from Other		Bark River Culvert & Equipment Co.	Escanaba, MI
Corrugated Steel Pip	De	Contech Engineered Solutions, LLC	Mason, MI, Mitchell and South Bend, IN, Portage, WI, Shakopee, MN,
			Ashland and Winchester, KY,
			Anderson, SC, and Canfield, OH
		Jensen Bridge & Supply Co.	Grand Rapids and Sandusky, MI
		Lane Enterprises, Inc.	Pulaski, PA
		Michigan Culvert Co.	Mason, MI
		Cadillac Culvert	Cadillac, MI
		St. Regis Culvert, Inc.	Charlotte, MI
910.05A	<u>Approved</u>		
Prefabricated	Products	Advanced Davine no Overtence Inc	
Drainage System	AdvanEdge 18" SITEDRAIN Strip	Advanced Drainage Systems, Inc.	Columbus and Napoleon, OH, Owosso,
Products name	6412, 6418, 6424	American Wick Drain Corporation	MI Monroe, NC
approved, all others	(TNS-R042,	American wick Drain Corporation	Worlde, NC
must be tested per	SKAPS GT-142 or		
project	Propex Geotex		
	401)		
	CCW –HC Drain	Carlisle Coating Waterproofing	
	(Mirafi 140N)		
	Stripdrain 80 and 100	Contech Engineered Solutions, LLC	Bloomfield Hills, MI
	JDRainSWD (Mirafi 140N)	JDR Enterprises, Inc.	Alpharetta, GA
	MDM Hydraway Drain 2000	Monsanto Co.	St. Louis, MO
	PDS 30	Pro Drain Systems	Highland, MI
912.05	•	American Timber and Steel Co., Inc.	Norwalk, OH
Structural Timber & Lur	nber	Central Nebraska Wood Preservers, Inc.	Sutton, NE
		Iowa Wood Preservers, Inc.	Oskaloosa, IA
		John Biewer Lumber Company	Lansing and St Clair, MI
		Straits Wood Treating, Inc.	Bay City, MI
		Midwest Timber	Edwardsburg, MI
		Woodstock, Inc.	West Branch, MI

APPROVED MANUFACTURERS			
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location	
912.08	American Timber and Steel Co., Inc.	Norwalk, OH	
Wood Posts and Blocks for Guardrail	Central Nebraska Wood Preservers, Inc.	Sutton, NE	
and Highway Signs	Iowa Wood Preservers, Inc.	Oskaloosa, IA	
(Dimension Sawed)	John Biewer Lumber Company	St. Clair, MI	
	Straits Wood Treating, Inc.	Bay City, MI	
	Midwest Timber	Edwardsburg, MI	
	Woodstock, Inc.	West Branch, MI	
913.06	Advance Concrete Products Co.	Highland, MI (Specialty Items)	
Precast Reinforced Concrete Units for	Bush Concrete Products, Inc.	Muskegon, MI	
Drainage Structures (Tops, Risers and	Carlesimo Products, Inc.	Farmington, MI	
Sump Bases)	Consumers Concrete Products	Kalamazoo, MI	
	Co-Pipe Products, Inc.	Taylor, MI	
	County Materials Corporation	Marathon, WI	
	Elmer's	Traverse City, MI	
	Grand Valley Concrete Products	Grand Rapids, MI	
	Hanson Pipe and Products (form.	Windsor, Ontario, Canada	
	Centennial)		
	Kerkstra Precast, Inc.	Grandville and Jenison, MI	
	Mack Industries	White Lake, MI	
	Mack Vault of Toledo-a Div. of Mack	Bowling Green, OH	
	Industries		
	Northern Concrete Pipe	Bay City, Charlotte, Clarkston, and	
		Wyoming, MI; Toledo (Sylvania), OH	
	Norwalk Concrete Industries	Norwalk, OH	
	Quality Precast, Inc.	Kalamazoo, MI	
	Upper Peninsula Pipe Co.	Escanaba, MI	
913.07	See Spec. 913.06, Drainage list		
Precast Concrete Bases, Sumps			
913.09	4D, Inc.	Midland, MI	
Slope Pavement Blocks	Bark River Concrete Products	Bark River, MI	
	Best Block Company	Warren, MI	
	Carlesimo Products, Inc.	Farmington, MI	
	Concrete Service, Inc.	Traverse City, MI	
	Consumers Concrete Products	Kalamazoo and South Haven, MI	
	Fendt Builder's Supply, Inc.	Ann Arbor and Farmington Hills, MI	
	Ferguson Block Co., Inc.	Davison, MI	
	Grand Blanc Cement Products	Grand Blanc, MI	
	Jansen Block Co.	Grand Rapids, MI	
	Northern Concrete Pipe	Grand Rapids, MI	

APPROVED MANUFACTURERS			
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location	
914.07	American Steel & Wire	Joliet, IL	
Transverse Pavement Joints	ASI Alton Steel, Inc.	Alton, IL	
1. Dowel Bars	Austeel	Lemont, IL	
	Barbary Coast	Mississippi, Norfolk, Illinois	
	Barnsco	Walled Lake, MI	
For coating info. See QPL 905.03C for	Bayou Steel Corporation	Harriman, TN	
approved material and manufacturers.	Boomer Construction Materials	Detroit, MI	
	Byer Steel (formerly A.B. Steel)	Cincinnati, OH	
See Spec. 905.03C for Epoxy Coating	CMC Steel	,	
Manufacturers (Coaters).	CMC Steel (Texas)	Seguin, TX	
	CMC Steel	Cayce-West, Columbia, SC	
	CMT Manufacturing, Highway Division	Durant, IA	
	Cascade Steel Rolling Mills	McMinnville, OR	
	Erect-A-Line	Dallas, TX	
	ERSCO Construction Supply	Wyoming, MI	
	Gerdau Ameristeel Corporation	,, yog,	
	Charlotte Steel Mill Div.	Charlotte, NC	
	Jackson Steel Mill Div.	Jackson, TN	
	Jacksonville Steel Mill Div.	Jacksonville, FL	
	Knoxville Steel Mill Div.	Knoxville, TN	
	Midlothian Steel Mill Div.	Midlothian, TX	
	St. Paul Steel Mill Div.	St. Paul, MN	
	Sayreville Steel Mill Div.	Sayreville, NJ	
	Metal Partners International	Hammond, IN	
	Nucor Steel	Traininona, iiv	
	Nucor Steel Auburn, Inc.	Auburn, NY	
	Nucor Steel Kankakee, Inc.	Bourbonnais, IL	
	Nucor Steel Marion, Inc.	Marion, OH	
	Nucor Steel Utah, Inc.	Plymouth, UT	
	Roadway Construction Products	Clarkson, KY	
	Simplex	Ontario, CA, Carlyle, IL	
	Steel Dynamics, Inc.	Pittsboro, IN	
914.07	American Highway Technology (A Division	Kankakee, IL	
Load Transfer Assemblies; Dowel	of Dayton Superior)	Namarco, IL	
Baskets	Barnsco	Walled Lake, MI	
	CMT Manufacturing, Highway Division	Durant, IA	
	Dayton Superior Corporation	Valparaiso, IN	
	Boomer Construction Materials	Detroit, MI	
	Erect-A-Line	Dallas, TX	
	Roadway Construction Products	Clarkson, KY	
	1		
914.08	Simplex Bar Manufacturers	Ontario, CA, Carlyle, IL Epoxy Coating Material	
Transverse End of Pour Joint Devices	See Reinforcement Bar Manufacturers	See Reinforcement Bar, Spec 905.03C	
B. Deformed Bars			
914.09	Spec. 905.03	and QPL 905.03C.	
Straight and Bent Tie Bars for	Bar Manufacturers	Epoxy Coating Material	
Longitudinal Pavement Joints, (Lane	See Reinforcement Bar Manufacturers	See Reinforcement Bar, Spec 905.03C	
Ties)	Spec. 905.03	and QPL 905.03C.	
1100)			

APPROVED MANUFACTURERS			
Spec. # and Material Name	Approved Manufacturers	Manufacturers Location	
916.02	American Excelsior Co. Inc.	Westland, MI	
Silt Fence	C.S.I. / Geo Turf, Inc.	Highland, MI	
	DGI Industries	Bennington, NH	
Qualified Geotextile Fabric products	Environmental Protection Products	Williamsburg, MI	
listed in the QPL 910.04.	Geo-Synthetics	Waukesha, WI	
	Geoproducts, Inc.	Birmingham, MI	
	Hanes Geo Components.	Charlotte, NC, Wixom and Wyoming, MI	
	Jensen Bridge & Supply Co.	Wauseon, OH, Grand Rapids and	
		Sandusky, MI	
	Klein Brothers Hardwood Inc.	Milford, MI	
	Pallen Enterprises	Conyer, GA	
	Rhino Seed and Landscape Supply	Bradley, MI	
	Willacoochee Industrial Fabrics, Inc.	Willacoochee, GA	
918.06	Advance Concrete Products	Highland, MI	
Precast Concrete Handholes &	Bush Concrete Products, Inc.	Muskegon, MI	
Manholes for Electrical & Telephone	Carlesimo Products, Inc.	Farmington, MI	
Connections	Consumers Concrete Products	Kalamazoo, MI	
	Elmer's	Traverse City, MI	
	Grand Valley Concrete Products, Inc.	Grand Rapids, MI	
	Hartford Concrete Products, Inc.	Hartford City and Ashley, IN	
	Kerkstra Precast, Inc.	Jenison, MI	
	Mack Industries	White Lake, MI	
	Northern Concrete Pipe	Bay City, Charlotte, Clarkston, and	
		Wyoming, MI; Toledo (Sylvania), OH	
	Norwalk Concrete Industries	Norwalk, OH	
	Quality Precast, Inc.	Kalamazoo, MI	
	Upper Peninsula Pipe Co.	Escanaba, MI	
919.05	American Timber and Steel Co., Inc.	Norwalk, OH	
Wood Sign Posts	John Biewer Lumber Company	St. Clair, MI	
	Straits Wood Treating, Inc.	Bay City, MI	
	Midwest Timber	Edwardsburg, MI	
	Woodstock, Inc.	West Branch, MI	

QUALIFIED PRODUCTS LIST

The materials in this section may be accepted for use on Michigan Department of Transportation projects based on the trade name, model number, etc., as listed.

This Qualified Products List is in accordance with the 2012 Standard Specifications for Construction.

Also see Section 6.01 if the MQAP Manual.

QUALIFIED PRODUCTS LIST (QPL)					
	Product Name	,			
Spec. # and Material Name 502.02B	Alt. 2	Manufacturers or Suppliers			
Overband Crackfill, Asphalt Rubber	K-T 1190 AR Plus Type 2 Deery 102 Roadsaver 221 Dura-Fill 3405	Bit-Mat Products Crafco, Inc. Crafco, Inc. Crafco, Inc. P&T Products, Inc.			
	1190	Right Pointe			
	ColJoint ARS II	Colas Solutions			
603.03B2 Adhesive Systems for Grouting Dowel Bars and Tie Bars for Full-Depth Concrete Pavement Repairs	ASF-1000 Ultrabond 1, 2, 3 Ultrabond 365 UltraBond HS-200	Adhesives Technology Corp. Adhesives Technology Corp. Adhesives Technology Corp. Adhesives Technology Corp.			
NOTE: Use these Qualified Products for grouting repairs to existing concrete in	Ultrabond RT66 Ultrabond Speed Set 2 Inject-Tite Standard Set	Adhesives Technology Corp. Adhesives Technology Corp. Adhesives Technology Corp. ANKR-Tite Fastening Systems			
the same direction of traffic in the same lane of repair. For grouting lane ties (deformed bars positioned transverse to	Inject-Tite Standard Set Inject-Tite Fast Set Aka Bond Aka Bond 550XP	ANKR-Tite Fasterling Systems ANKR-Tite Fasterling Systems Axson North America (Formerly Akemi Plastics) Axson North America (Formerly Akemi Plastics)			
the direction of traffic located between traffic lanes) use QPL 712.03J, "Adhesive Systems for Structural	Aka Bond 550XPP Sonneborn Rapid Gel BHS-1250	Axson North America (Formerly Akemi Plastics) Axson North America (Formerly Akemi Plastics) BASF Construction Chemical Blackhawk Sales Company, Inc.			
Anchors and Lane Ties".	BHS-1250XP CanRez 800 Araldite AW / HW 8561	Blackhawk Sales Company, Inc. Cansto Coatings Ciba Specialty Chemicals Corp.			
	Spec Bond 201 Highway Fast Set Epoxy TRU Grip HI-Modepoxy 590	Conspec by Dayton Superior, Inc. Dayton Superior Corp. J. Dedoes, Inc.			
	Tru-Grip 591 Dural Fast Set Epoxy Gel Futura Bond 566	J. Dedoes, Inc. Euclid Chemical Company Futura Adhesives & Chemicals			
	Hilti RSE DOT Redhead A7+ Redhead C6+	Hilti, Inc. ITW Commercial Construction ITW Commercial Construction			
	Epcon A7 Epcon-Ceramic 6 SurePoxy 117	ITW Ramset/Red Head ITW Ramset/Red Head Kaufman Products			
	Kelipoxy II Dynapoxy EP-430 FAST Poly-Carb	Kelken Construction Systems Pecora Corporation Olin Epoxy-Poly-Carb (Blue Cube Operations			
	Mark 198.4	LLC) Olin Epoxy-Poly-Carb (Blue Cube Operations LLC)			
	Polyject/Polybac 1257 Polyject/Polybac 1295 AC 50 Silver AC 100+ Gold	Polygen, Inc. Polygen, Inc. Powers Fasteners, Inc. Powers Fasteners, Inc.			
	PE 1000+ Pure 50+ Pure 110+	Powers Fasteners, Inc. Powers Fasteners, Inc. Powers Fasteners, Inc.			
	T308+ Speed Bond #1 Sikadur Injection Gel	Powers Fasteners, Inc. Prime Resins, Inc. Sika Corporation			
	Sikadur 881 DBA Sikadur DOT-SP13 Arcylic -Tie AT	Sika Corporation Sika Corporation Simpson Strong-Tie Company, Inc.			
	Epoxy Tie Dowel Bar Adhesive #5 Pro Poxy 300	Simpson Strong-Tie Company, Inc. Superior Epoxies & Coatings Unitex			
	Pro Poxy 300 FAST CIA Gel 7000 Rezi-Weld Gel Paste	Unitex USP Structural Connectors W.R. Meadows, Inc.			
	Rezi-Weld Gel Paste State	W.R. Meadows, Inc.			

QUALIFIED PRODUCTS LIST (QPL)							
Spec. # and Material Name	Product Na	me	Manufacturers or Suppliers				
702.02B Non-Shrinking Mortar and Grout Type H-1(Non-Metallic) Pre Mixed	MBT 928 Grout MasterFlow 100 Set Grout		BASF Construction Chemical, Shakopee, MN BASF Construction Chemical, Shakopee, MN BASF Construction Chemical, Shakopee, MN				
H-2 eliminated.	Boomer Premium Grout Upcon Super Flow Grout Celtite 10-50 Hi-Flow Conset Grout-XT		Boomer Construction Materials, Detroit, MI Bostik Const. Prod. Co., Cleveland, OH Celtite Inc., Georgetown, KY ChemMasters, Madison, OH				
	Conspec 100 Enduro 50 Grout Gifford-Hills Supreme Grout		Conspec by Dayton Superior, Kansas City, KS Conspec by Dayton Superior, Kansas City, KS Cormix, Inc., Cleveland, OH (form. Gifford-Hill)				
	1107 Advantage Grout Sure Grip Grout NS Grout Five Star Grout		Dayton Superior, Kansas City, KS Dayton Superior, Kansas City, KS Euclid Chemical Co., Cleveland, OH Five Star Products, Inc.				
	Pro-Grout 90 SureGrout Crystex		G.C.M., Inc., Bensalem, PA Kaufman Products, Inc., Baltimore, MD L&M Construction Chemicals, Inc., Omaha, NE				
	Duragrout Quikrete Precision Grout SC Miltipurpose Grout		L&M Construction Chemicals, Inc., Omaha, NE Quikrete Technical Center, Atlanta, GA SpecChem				
	Superb Grout 611 Sealite 588 Grout		Specco Industries, Lemont, IL W. R. Meadows, Inc., Elgin, IL				
703 Prepackaged Hydraulic Fast Set* Mortar		Max. Aggregate Extension, %					
NOTE: *Percentage based upon weight of prepackaged bag containing both cement and sand. Example Calculation:	MasterEmaco T 1060 MasterEmaco T 545 Burke Fast Patch 928 Chem Speed 65	60* 60* 50* 50*	BASF Construction Chemical BASF Construction Chemical Edoco, a Dayton Superior Co., Kansas City, KS Chem Masters				
50 lb bag approved at 60% extension = 50 x 0.60 = 30 lb coarse aggregate per bag.	HD-50 Heavy Duty Concrete Patch Express Repair Five Star Highway Patch	60* 60* 60*	Dayton Superior Corp. Euclid Chemical Co. Five Star Products, Inc.				
	Durapatch Hiway Planitop 18 Commercial Grade Fast Set DOT Mix	50* 60* 45.5*	L&M Construction Chemicals, Inc. Mapei Corporation Quikrete				
706.03S Protective Coating for Concrete		Application Rate, sq ft/gal 125-200	PASE Construction Chemical				
(Penetrating Water Repellent Treatment of Structure Concrete Surfaces)	MasterProtect H 200 MasterProtect H 400 Barracade Silane 40 Aquapel Plus 20% Silane Stifel S Powerseal 40	125-200 125-200 125 125 125 125	BASF Construction Chemical BASF Construction Chemical Euclid Chemical Co. L&M Construction Chemicals, Inc. Nox-Crete Chemicals Vexcon Chemicals				
707.02 Bushings for Pins & Link Plates	CJ Garmax	120-200	TriStar Garlock				

QUALIFIED PRODUCTS LIST (QPL)							
Spec. # and Material Name	Product Name			Manufacturers or Suppliers			
712.03J	-	Adhesive	Mixing				
Adhesive Systems for Structural Anchor	<u>Name</u>	Type	& Inject.				
& Lane Ties*	Ultrabond 1	Ероху	Yes	Adhesives Technology Corp.			
	HS-200	Epoxy	Yes	Adhesives Technology Corp.			
NOTE: *Lane Ties defined as deformed	Tru-Grip 591	Epoxy	Yes	J. Dedoes, Inc.			
bars positioned transverse to the direction of traffic located between lanes.	Hilti HTE 50	Epoxy	Capsule	Hilti, Inc.			
For grouting dowel bars and tie bars	Hilti HIT-HY 200-A		Yes	Hilti, Inc.			
(bars positioned to existing concrete in	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Methacrylate	.,	Line 1			
the direction of the traffic in the same	Hilti HIT-HY 200-R	•	Yes	Hilti, Inc.			
lane as the repair) use QPL 603.03B2,	HVU	Urethane- Methacrylate	Capsule	Hilti, Inc.			
"Adhesive Systems for Grouting Dowel	Hilti HIT-RE-500v3	,	Yes	Hilti, Inc.			
Bars for Full-Depth Concrete Pavement	Ceramic 6	Ероху	Yes	ITW Ramset/Red Head			
Repairs".	Epcon Acrylic 7	Methacrylate	Yes	ITW Ramset/Red Head			
Note 1. Anchors shall be installed per	Super Por-Rok	Non-Shrink Grout		Novex Systems International, Inc.			
manufacturer's recommendations with a	DeWALT Pure 110-		Yes	Powers Fasteners, Inc.			
minimum embedment depth of 12	Sika AnchorFix 500		Yes	Sika Corporation			
diameters for reinforcing steel and 9	Acrylic-Tie	Methacrylate	Yes	Simpson Strong-Tie Anchor Systems			
diameters for threaded bolts.	SET	Ероху	Yes	Simpson Strong-Tie Anchor Systems			
	Pro-Poxy 300	Ероху	Yes	Unitex			
Note 2. Material is limited to the shelf life	CIA-Gel 7000	Ероху	Yes	USP Structural Connectors			
recommendations by the manufacturer.	Rezi Weld Gel	Ероху	Yes	W.R. Meadows, Inc.			
	Paste State						
712.03K	Pre-Drilled Flush Type						
Structure Expansion Anchors	a) Hiliti HDI (3/8	3" (10mm), ½" (13n	nm), 3/4" (1	9mm), dia. anchors only)			
(Mechanical Expansion Anchors)	2 Pro Drillod Stud	Type Not suitable	for land tid	es or for guardrail end shoes because of			
Pull-out Testing is required per MQAP	exposed thread.	Type - Not Suitable	וטו ומוופ נופ	es of for guardian end shoes because of			
Manual Section 4.03.		It II or Kwik-Bolt III					
			n. embedm	ent = 2 ½" (65mm)			
NOTE: Mechanical Expansion Anchors	1/2" (13mi	n) dia. anchor - mir	n. embedm	ent = 3 ½" (90mm)			
shall be set by applying the manu-	5/8" (16mm) dia. anchor - min. embedment = 4" (100mm)						
facturer's specified torque. The turn of							
the nut method will not be an acceptable alternative.							
712.03L	BPI Barsplicer Syst	em		BarSplice Products, Inc., Dayton, OH			
Mechanical Reinforcement Splicing		Grip-Twist Threaded Position Coupler		BarSplice Products, Inc., Dayton, OH			
	Taper Threaded Gr			BarSplice Products, Inc., Dayton, OH			
NOTE: Splices used to connect precast	Zap Screwlok			BarSplice Products, Inc., Dayton, OH			
structural elements shall be high	Bar-Lock L-Series			Dayton Superior Corp., Miamisburg, OH			
strength splices.	DB SAE			Dayton Superior Corp., Miamisburg, OH			
	Lenton			PENTAIR, Solon, OH PENTAIR, Solon, OH			
	Lenton Form Saver Lenton Interlok (Hig	h Strongth)		PENTAIR, Solon, OH PENTAIR, Solon, OH			
	Lenton Position Co			PENTAIR, Solon, OH PENTAIR, Solon, OH			
	NMB Splice Sleeve			Splice Sleeve North America, Inc., Livonia, MI			
712.03Y	MasterProtect CP N		, 8150	BASF Chemical Company			
Embedded Galvanic Anodes	Sentinel-GL			Euclid Chemical Co.			
	Sika Galvashield XI			Sika Corporation			
	Sika Galvashield XI			Sika Corporation			
	Sika FerroGard 650, 670, 675			Sika Corporation Vector Corrosion Technologies			
	Galvashield XP Galvashield XP+			Vector Corrosion Technologies Vector Corrosion Technologies			
713.02B	MasterSeal NP 1			BASF Construction Chemicals, Shakapee, MN			
Sealant for Perimeter of Beam Repairs	Bostik 2020			Bostik US			
	Duralink (F1200)			Chem Link			
NOTE: No silicone materials - only	Loxon H1			Sherwin-Williams			
polyurethane (PU) or PU blended	Loxon S1			Sherwin-Williams			
materials that are paintable. Typically 1	Sikaflex-15LM			Sika Corporation			
week cure prior to painting. All non-sag	Vulkem 116			Tremco, Inc.			
material. 715.02	XtraBond 9500 Premier Industrial Supply See Coating Systems for Steel Structures,						
Coating Systems for New Hanger	Hanger Assemblies						
Assemblies	QPL 915	and End Diapinay	0				
				<u>l</u>			

QUALIFIED PRODUCTS LIST (QPL)					
			, ,		
Spec. # and Material Name	Produc		Manufacturers or Suppliers		
715.02	Black Diamond Abrasive	e - Coal Slag	U.S. Minerals, Tinley Park, IL		
Abrasive, Low Dusting	GMA Garnet Blast Black Shot Granulated S	Slan	GMA Garnet Pty Ltd, Narngulu, WA, Australia Bell & MacKenzie Co. Ltd, Hamilton, Ontario		
NOTE: The blasting profile produced by	Jetmag 32B4	nag	Carpenter Brothers Inc., Mequon, WI		
these abrasives will depend on the	StarBlast XL		the Chemours Company, Wilmington, DE		
equipment used. It is the responsibility	Emerald Creek Garnet		Emerald Creek Garnet, Fernwood, ID		
of the contractor to produce a profile	Blackjack MSM, Waupad	ca Materials	Faulks Brothers Constr. Co., Inc., Waupaca, WI		
within the 1.0 to 2.8 mils specified range.	Alluvial River Garnet		Marco Group International, Beaver Falls, PA		
The abrasive additive, Blastox may be used with any of the listed low-dusting	Ebony Grit - Coal Slag Black Beauty		Opta Minerals Inc. Harsco Minerals International, Gary, IN		
abrasives.	Sharpshot XL - Iron Silic	ata	Universal Minerals Kentucky, Inc., Louisville, KY		
803.02B	Sharpshot AL - Horr Sille	ale	Oniversal Minerals Remucky, Inc., Louisville, R1		
Detectable Warning Surfaces (ADA					
Compliant Sidewalk Ramps),					
1. Cast-in-Place	Access Tile Cast In Plac	e Replaceable	Access Products, Inc., Buffalo, NY		
	Advantage Classic		Advantage Tactile Systems, Buffalo, NY		
	Advantage Premier		Advantage Tactile Systems, Buffalo, NY		
	AlertCast		AlertTiles, Wilmington, NC		
	Cast in Place Truncated	Dome Warning	ADA Solutions, Wilmington, MA		
	System Irondome		ADA Salutiona Wilmington MA		
	Composite Wet Set Rep	laceable Pectangular	ADA Solutions, Wilmington, MA ADA Solutions, Wilmington, MA		
	and Radius	iaceable, Nectarigular	ADA Goldtions, Willington, MA		
	DetecTile Replaceable T	actile Panel	DetecTile Corporation		
	EJIW Detectable Warnin		East Jordan Iron Works, East Jordan, MI		
	Armor-Tile Cast in Place		Engineered Plastics, Inc., Williamsville, NY		
	Armor-Tile Cast in Place	Composite	Engineered Plastics, Inc., Williamsville, NY		
	NF Detectable Warning	Plate	Neenah Foundry Company, Neenah, WI		
	TufTile		TufTile		
O Occidence Associate	TufTile Polymer Tactile		TufTile		
2. Surface Applied*	Surface Applied Panel S	ystem with Beveled	ADA Solutions, North Billerica, MA		
*NOTE: Surface applied detectable	Edges		Detectable Manager Cycleron Milesia etca NG		
warning surfaces may only be used	Alerttile	ind Composite Morning	Detectable Warning Systems, Williamsville, NC		
to retrofit existing concrete	Armor-Tile Surface Appli System	led Composite warning	Engineered Plastics, Inc., Williamsville, NY		
	TopMark		Ennis-Flint		
811.03D1	Product ID	Color	Elino i int		
Waterborne, Liquid Pavement Marking	TM-2582	White	Sherwin-Williams		
Material	TM-2204	White	Sherwin-Williams		
	TM-2583	Yellow	Sherwin-Williams		
	TM-2205	Yellow White	Sherwin-Williams		
	982211 982212	Yellow	Ennis-Flint Ennis-Flint		
	982221	White	Ennis-Flint		
	982222	Yellow	Ennis-Flint		
	982201	White	Ennis-Flint		
	982202	Yellow	Ennis-Flint		
	985205	Blue	Ennis-Flint		
	985203 14228	Black White	Ennis-Flint Ozark Materials, LLC		
	24228	Yellow	Ozark Materials, LLC		
811.03D2	White	Lead Free Yellow	Ozari Matorialo, ELO		
Low Temperature Waterborne, Liquid	985251	985252	Ennis-Flint		
Pavement Marking Material	TM2372	TM2373	Sherwin-Williams		
811.03D3	<u>White</u>	Lead Free Yellow			
Regular Dry Paint, Liquid Pavement	TM-5604	TM-5607	Sherwin-Williams		
Marking Material	982271	982282	Ennis-Flint		

QU	ALIFIED PRODUCTS LIS	T (QPL)
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
811.03D4	Wet Reflective Long Line:	
Cold Plastic Tape, Permanent (Long	White Yellow Adhesive	
Line, Legends & Crosswalks)	380 AW 381 AW P50	3M
	DeltaLine XRP-R DeltaLine XRP-R D-20	Brite-line Technologies, LLC
	Standard Long Line:	
	<u>White</u> <u>Yellow</u> <u>Adhesive</u>	
	380I ES 381I ES P50	3M
	Director 60 DP-E4	Swarco
	Director 60 HPT Director 60 HPT DP-E4	Swarco
	Shadow Tape:	
	Black Adhesive	
	385 ES P50	3M
	Director 60 DP-E4	Swarco
	Special Markings (symbols, legends, stop bars, crosswalks, crosshatching):	
	White Yellow Adhesive	
	270 ES 271 ES P50	3M
	380I ES 381I ES P50	3M
	ATM 300 ATM 300 ATM Permanent	
	Primer	Advanced Traine Markings
	Director 60 Director 60 DP-E4	Swarco
	Director 60 HPT Director 60 HPT DP-E4	Swarco
811.03D5	White Yellow	
Thermoplastic, Liquid Pavement Marking	884285 884685	Ennis-Flint
Material	Swarcotherm EWH 131 Swarcotherm EYH 132	Swarco
044.0005	Viatherm E413W	Geveko Markings
811.03D5 Thermoplastic, Blocks	Viatherm E411W	Geveko Markings
Rumble Strips		
811.03D6	White Yellow	
Thermoplastic, Sprayable, Liquid	01-WAK-BADA 01-YAK-AADA	Crown Technology
Pavement Marking Material	01-WHK-BADA 01-YHK-AADA	Crown Technology
	W1SS7056 Y1SS7006	Ennis-Flint
	W2SS7056 Y2SS7006	Ennis-Flint
	884822 883241	Ennis-Flint
	884824 883240	Ennis-Flint
	11128 21128 1457MANUSI 2709MANUSI	Ozark Materials, LLC
	1157MWHSI	Swarco Swarco
811.03D7	5000 LPM White	3M
Polyurea, Liquid Pavement Marking	5001 LPM Yellow	3M
Material	LS90 White and Yellow	Epo-Plex
	HPS-5 White and Yellow	Ennis Flint
811.03D8	HPS-4 White and Yellow	Ennis-Flint
Modified Urethane, Liquid Pavement Marking Material	MFUA-10 White and Yellow	Swarco
811.03D9	PreMark	Ennis-Flint
Preformed Thermoplastic, Preformed	HotTape	Ennis-Flint
Pavement Marking Material	Preformed Thermoplastic	Ozark Materials, LLC
	SWARCO Preformed Thermoplastic	Swarco

ADMIXTURES FOR CONCRETE

Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Туре	Producer and Description	Recommended Dosage min. or range fl oz/cwt
	BASF CONSTR. CHEM.			02/0111
903.01	MasterSet DELVO	D	Water-reducer retarder	3
Air Entraining Admixtures	MasterGlenium 3400	F	High-range water-reducer	3
903.02	MasterGlenium 7500	Α	Water-reducer	1.5
Water Reducing and Water Reducing Retarding		F	High-range water-reducer	3 - 15
Admixtures for Concrete	MasterGlenium 7700	F	High-range water-reducer	4 - 15
903.04	MasterGlenium 7710	F	High-range water-reducer	4
Concrete Accelerators	MasterGlenium 7920	F	High-range water-reducer	4
		MR	Mid-range water-reducer	2
	MasterGlenium 7925	F	High-range water-reducer	4
		MR	Mid-range water-reducer	2
	MasterAir AE 90	AE	Air-entraining	1
	MasterAir AE 200	AE	Air-entraining	1
	MasterPolyheed 900	Α	Water-reducer	4
		MR	Mid-range water-reducer	7
	MasterPolyheed 997	Α	Water-reducer	3
		MR	Mid-range water-reducer	6
		F	High-range water-reducer	10
	MasterPolyheed 1725	Α	Water-reducer	2.5 - 4
		MR	Mid-range water-reducer	5.5 - 7
		F	High-range water-reducer	8 - 12
	MasterPolyheed 100	Α	Water-reducer	4
		MR	Mid-range water-reducer	8
	MasterPozzolith 200	Α	Water-reducer	2
		D	Water-reducer retarder	4
	MasterPozzolith 700	Α	Water-reducer	2
		D	Water-reducer retarder	5
	MasterSet AC 534	С	Accelerator (non-chloride)	10
	MasterSet FP 20	С	Accelerator (non-chloride)	10
	MasterGlenium 7511	Α	Water-reducer	2 - 4
		MR	Mid-range water-reducer	4 - 6
		F	High-range water-reducer	6 - 15
	MasterRheobuild 1000	MR	Mid-range water-reducer	9
		F	High-range water-reducer	13
(Continued)				

ADMIXTURES FOR CONCRETE

903.01	Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Туре	Producer and Description	Recommended Dosage min. or range fl oz/cwt
Air Entraining Admixtures Accelguard G3 Accelguard G3 Accelguard NCA Eucon Air Mix 200 AE Air-entraining Admixtures for Concrete Bos. 14 Accelerators Accelerator Accelerator		EUCLID CHEMICAL CO.			
Accelguard G3		Eucon AEA 92	AE	Air-entraining	1.5
Water Reducing and Water Reducing Retarding Admixtures for Concrete Eucon Air Mix 200 AE Air-entraining 3 903.04 Concrete Accelerators EUCON MR A Water-reducer 4.5 EUCON MRX MR Mid-range water-reducer 12 EUCON WR MR Mid-range water-reducer 3.5 F High-range water-reducer 7.5 EUCON WR A Water-reducer retarder 2.5 - D Water-reducer retarder 2.5 - EUCON WR-91 A Water-reducer retarder 5 EUCON A+ A Water-reducer retarder 6 EUCON Retarder75 D Water-reducer retarder 4.5 EUCON Stasis D Water-reducer retarder 1 - 1 EUCON AIR MAC12 AE Air-entraining 1.5 - High-range water-reducer 4.5 -	All Entraining Admixtures	Accelguard G3	E	Water-reducer accelerator (non-chloride)	16 - 90
Reducing Retarding EuCon Air Mix 200 EUCON Air MAC6 EUCON Air MAC6 EUCON MR A Water-reducer 4.5		Accelguard NCA	С	Accelerator (non-chloride)	15
Admixtures for Concrete EUCON Air MAC6 AE Air-entraining 0.5- 903.04 Concrete Accelerators EUCON MR A Water-reducer 4.5 EUCON MRX MR Mid-range water-reducer 12 EUCON WR A Water-reducer 7.5 EUCON WR-91 A Water-reducer retarder 2.5- D Water-reducer 3.5 MR Mid-range water-reducer 5 D Water-reducer retarder 6 D Water-reducer retarder 6 EUCON A+ A Water-reducer retarder 4.5 EUCON Retarder75 D Water-reducer retarder 3.5 EUCON Stasis D Water-reducer retarder 1-4 EUCON AIR MAC12 AE Air-entraining 1.5- PLASTOL 6400 F High-range water-reducer 4.5-	Water Reducing and Water	Eucon Air Mix 200	AE	Air-entraining	3
BUCON MR		EUCON Air MAC6	AE	Air-entraining	0.5 - 4
MR	000.04	EUCON MR	Α		4.5
F High-range water-reducer 12			MR	Mid-range water-reducer	5.5
EUCON MRX MR Mid-range water-reducer 3.5 F High-range water-reducer 7.5 EUCON WR A Water-reducer 2.5 - D Water-reducer retarder 3 MR Mid-range water-reducer 5 D Water-reducer retarder 6 EUCON A+ A Water-reducer 3.5 MR Mid-range water-reducer 4.5 EUCON Retarder75 D Water-reducer retarder 3.5 EUCON Stasis D Water-reducer retarder 1 - 1 EUCON AIR MAC12 AE Air-entraining 1.5 - PLASTOL 6400 F High-range water-reducer 4.5 -			F	High-range water-reducer	12
F High-range water-reducer 7.5		EUCON MRX	MR		3.5
EUCON WR A Water-reducer 2.5 - D Water-reducer retarder 2.5 - EUCON WR-91 A Water-reducer 3 MR Mid-range water-reducer 5 D Water-reducer retarder 6 EUCON A+ A Water-reducer 4.5 MR Mid-range water-reducer 4.5 EUCON Retarder75 D Water-reducer retarder 3.5 EUCON Stasis D Water-reducer retarder 1 - 1 EUCON AIR MAC12 AE Air-entraining 1.5 - PLASTOL 6400 F High-range water-reducer 4.5 -			F		7.5
D Water-reducer retarder 2.5 -		EUCON WR			2.5 - 10
EUCON WR-91 A Water-reducer 3 MR Mid-range water-reducer 5 D Water-reducer retarder 6 EUCON A+ A Water-reducer 3.5 MR Mid-range water-reducer 4.5 EUCON Retarder75 D Water-reducer retarder 3.5 EUCON Stasis D Water-reducer retarder 1 - 1 EUCON AIR MAC12 AE Air-entraining 1.5 - PLASTOL 6400 F High-range water-reducer 4.5 -				Water-reducer retarder	2.5 - 10
D Water-reducer retarder 6 EUCON A+ A Water-reducer 3.5 MR Mid-range water-reducer 4.5 EUCON Retarder75 D Water-reducer retarder 3.5 EUCON Stasis D Water-reducer retarder 1 - 1 EUCON AIR MAC12 AE Air-entraining 1.5 - 1 PLASTOL 6400 F High-range water-reducer 4.5 - 1		EUCON WR-91	Α	Water-reducer	3
D Water-reducer retarder 6 EUCON A+ A Water-reducer 3.5 MR Mid-range water-reducer 4.5 EUCON Retarder75 D Water-reducer retarder 3.5 EUCON Stasis D Water-reducer retarder 1 - 1 EUCON AIR MAC12 AE Air-entraining 1.5 - 1 PLASTOL 6400 F High-range water-reducer 4.5 - 1			MR	Mid-range water-reducer	5
MR Mid-range water-reducer 4.5 EUCON Retarder75 D Water-reducer retarder 3.5 EUCON Stasis D Water-reducer retarder 1 - 1 EUCON AIR MAC12 AE Air-entraining 1.5 - 1 PLASTOL 6400 F High-range water-reducer 4.5 -			D	Water-reducer retarder	6
EUCON Retarder75 EUCON Stasis D Water-reducer retarder D Water-reducer retarder 1 - 1 EUCON AIR MAC12 PLASTOL 6400 F High-range water-reducer 3.5 High-range water-reducer 4.5 -		EUCON A+	Α	Water-reducer	3.5
EUCON Stasis D Water-reducer retarder 1 - 1 EUCON AIR MAC12 PLASTOL 6400 F Water-reducer retarder AE Air-entraining 1.5 - High-range water-reducer 4.5 -			MR	Mid-range water-reducer	4.5
EUCON AIR MAC12 AE Air-entraining 1.5 - PLASTOL 6400 F High-range water-reducer 4.5 -		EUCON Retarder75	D	Water-reducer retarder	3.5
PLASTOL 6400 F High-range water-reducer 4.5 -		EUCON Stasis	D	Water-reducer retarder	1 - 16
		EUCON AIR MAC12	AE	Air-entraining	1.5 - 4
PLASTOL ULTRA 209 F High-range water-reducer 3.5 -		PLASTOL 6400	F	High-range water-reducer	4.5 - 12
		PLASTOL ULTRA 209	F	High-range water-reducer	3.5 - 12

ADMIXTURES FOR CONCRETE

Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Туре	Producer and Description	Recommended Dosage min. or range fl oz/cwt
Spec. # and Material Name 903.01 Air Entraining Admixtures 903.02 Water Reducing and Water Reducing Retarding Admixtures for Concrete 903.04 Concrete Accelerators	Manufacturer or Supplier and Trade Name GENERAL RESOURCE TECHNOLOGY (GRT) Dynamon SX KB-1200 Polychem VR Polychem SA-14 Polychem SA-50 Polychem 400 NC Polychem Super Set Polychem R Polychem SPC	Type F MR AE AE AC D F	High-range water-reducer Mid-range water-reducer Water-reducer Mid-range water-reducer Air-entraining (vinsol resin) Air-entraining Water-reducer Accelerator (non-chloride) Water-reducer retarder High-range water-reducer	Dosage min. or
(Continued)				

ADMIXTURES FOR CONCRETE

Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Туре	Producer and Description	Recommended Dosage min. or range fl oz/cwt
903.01	PREMIERE CONCRETE			
Air Entraining Admixtures	ADMIXTURES			
903.02	EcoFlo Green	F	High-range water-reducer	8 - 16
Water Reducing and Water Reducing Retarding	Optiflo 700	Α	Water-reducer	3 - 5
Admixtures for Concrete		MR	Mid-range water-reducer	5 - 10
903.04	OptiFlo 50	Α	Water-reducer	3 - 5
Concrete Accelerators		MR	Mid-range water-reducer	5 - 6
		D	Water-reducer retarder	6
	OptiFlo 500	A	Water-reducer	2 - 3.5
		D	Water-reducer retarder	3.5 - 5
	OptiFlo MR	A	Water-reducer	3 - 5
		MR	Mid-range water-reducer	5 - 12
		F	High-range water-reducer	12 - 16
	OptiFlo N2A	A	Water-reducer	3 - 6
		MR	Mid-range water-reducer	6 - 9
	On CELL Divis	G	High-range water-reducer retarder	13 - 15
	OptiFlo Plus	MR	Mid-range water-reducer	5 - 12
	OptiFlo 100R	D	Water-reducer retarder	3 - 5
	ConAir	AE	Air-entraining	0.5 - 4
	ConAir 260	AE	Air-entraining	0.5 - 4
	ConAir X	AE	Air-entraining	0.5 - 4
	UltraFlo 2000	A	Water-reducer	2 - 4
		MR	Mid-range water-reducer	4 - 6
	UltraFlo 4600	F MR	High-range water-reducer	6 - 12 7 - 12
	Oltrario 4600	F	Mid-range water-reducer	12 - 20
	UltraFlo 5600	Г MR	High-range water-reducer	6 - 10
	Ulitario 5600	F	Mid-range water-reducer	10 - 24
	UltraFlo DP	F	High-range water-reducer High-range water-reducer	5 - 12
	NitroCast K	E	Water-reducer accelerator (non-chloride)	10 - 90
	ProLong L	D	Water-reducer retarder	2.5 - 6.5
	FroLong E	Б	water-reducer retarder	2.0 - 0.3
(Cantinual)				
(Continued)	<u> </u>	1		

ADMIXTURES FOR CONCRETE

Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Туре	Producer and Description	Recommended Dosage min. o range fl oz/cwt
903.01 Air Entraining Admixtures	RUSSTECH LC-400R RSA-10	D AE	Water-reducer retarder Air-entraining	3.5 - 6 1
903.02 Water Reducing and Water Reducing Retarding Admixtures for Concrete	Superflo 2000 RM	F	High-range water-reducer	8 - 20
903.04 Concrete Accelerators				
(Continued)				

ADMIXTURES FOR CONCRETE

Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Туре	Producer and Description	Recommended Dosage min. o range fl oz/cwt
	SIKA CORP.			
903.01 Air Entraining Admixtures	Plastocrete 10N	Α	Water-reducer	2
All Entraining Admixtures		D	Water-reducer retarder	3.5
903.02	Plastocrete 161	Α	Water-reducer	3
Water Reducing and Water		D	Water-reducer retarder	6
Reducing Retarding Admixtures for Concrete	Plastiment XR	D	Water-reducer retarder	3
	Sika AEA-14	AE	Air-entraining	2
903.04 Concrete Accelerators	Sika AIR 260	AE	Air-entraining	2
Concrete Accelerators	Sika AIR 360	AE	Air-entraining	1
	Sikament AFM	Α	Water-reducer	2
		MR	Mid-range water-reducer	5
		F	High-range water-reducer	10
	Sikament NC	С	Accelerator (non-chloride)	10
		E	Water-reducer accelerator (non-chloride)	10
	Sikament SPMN	MR	Mid-range water-reducer	6.5
		F	High-range water-reducer	10
	Sikament 475	Α	Water-reducer	3
		F	High-range water-reducer	7
		MR	Mid-range water-reducer	5
	Sikament 686	Α	Water-reducer	3
		MR	Mid-range water-reducer	5.5
		F	High-range water-reducer	8
	SikaPlast 200	Α	Water-reducer	3
		G	High-range water-reducer retarder	13
		MR	Mid-range water-reducer	6.5
	SikaSet NC	С	Accelerator (non-chloride)	10
		Е	Water-reducer accelerator (non-chloride)	10
	Sikatard 440	D	Water-reducer retarder	3
	Rapid - 1	С	Accelerator (non-chloride)	20
	ViscoCrete 1000	Α	Water-reducer	1.5
		MR	Mid-range water-reducer	3
		F	High-range water-reducer	8
	ViscoCrete 2100	F	High-range water-reducer	5
	ViscoCrete 4100	F	High-range water-reducer	5
	ViscoCrete 6100	F	High-range water-reducer	5
	Viscoflow-2020	Α	Water-reducer	3
		MR	Mid-range water-reducer	6
		MR	Mid-range water-reducer	

ADMIXTURES FOR CONCRETE

Spec. # and Material Name	Manufacturer or Supplier and Trade Name	Туре	Producer and Description	Recommended Dosage min. or range fl oz/cwt
	GCP APPLIED TECHNOLOGIES,			
903.01 Air Entraining Admixtures	ADVA 140M	А	Water-reducer	5 - 9
All Entraining Admixtures	ADVA 140W	F	High-range water-reducer	9 - 16
903.02	ADVA 405	F.	High-range water-reducer	11 - 18
Water Reducing and Water Reducing Retarding	ADVA Cast 198	, F	High-range water-reducer	4 - 15
Admixtures for Concrete	ADVA Cast 150	, F	High-range water-reducer	3.5 - 10
	ADVA Cast 575	F '	High-range water-reducer	4 - 10
903.04 Concrete Accelerators				
Concrete Accelerators	ADVA Cast 600	A	Water-reducer	2 - 4
		F	High-range water-reducer	4 - 10
	Daracem 19	F	High-range water-reducer	12.5
	Daraset 400	С	Accelerator (non-chloride)	15
	Daratard 17	D	Water-reducer retarder	2
	Daravair 1400	AE	Air-entraining	1
	Darex II AEA	AE	Air-entraining	1 - 5
	MIRA 62	Α	Water-reducer	4.5
		MR	Mid-range water-reducer	6 - 12
		F	High-range water-reducer	12 - 15
	MIRA 95	F	High-range water-reducer	10 - 15
	MIRA 110	MR	Mid-range water-reducer	9 - 12
		F	High-range water-reducer	12 - 15
	Polarset	С	Accelerator (non-chloride)	8 - 60
	Recover	D	Water-reducer retarder	2.5 - 6
	Terapave AEA	AE	Air-entraining	1.5
	WRDA 82	Α	Water-reducer	3
	ZYLA 630	Α	Water-reducer	4 - 7
		D	Water-reducer retarder	2 - 7
	ZYLA R	D	Water-reducer retarder	6 - 12

SPEC. 903 ADMIXTURE NOTES:

1. Dosage Rate

The dosage rate indicated is that recommended by the producer or that used in qualification tests for approval of the admixture. There is no assurance that the desired water-reduction and/or retardation will be achieved with these dosages with a particular cement being used, as the effect is dependent on the cement chemistry, concrete temperature, and other factors. Increasing the dosage appreciably above that recommended may result in abnormal behavior of the concrete, such as extremely long or very short setting times. Reducing the dosage below that recommended may have the effect of substantially no change from concrete without the admixture. The dosage shown for retarding admixtures will normally produce a 1- to 3-hour retardation in the setting of the concrete, compared to similar concrete without the admixture, when used at normal temperatures (approximately 70°F). Increased dosage, within reasonable limits, will usually increase the retardation. Use of a retarding admixture will not slow the stiffening of concrete due to loss of slump.

2. Air-Entraining Admixtures

The contractor is responsible for verifying the compatibility of all chemical admixtures and the airentraining admixture. If admixtures are from more than one manufacturer, run a trial batch prior to concrete placement. Provide test results for slump, air-entrainment and seven-day compression for two (2) cylinders. Actual dosage for Air-Entrainers may vary from those listed on the Qualified Products List as required by the mix design.

3. Lignin Type Admixtures

Lignin (or lignosulfonate) admixtures typically will cause the entrainment of additional air in air-entrained concrete. This type admixture does not generally entrain air by itself, but makes other air-entraining materials much more efficient. Thus, a change in dosage of either the chemical admixture or the air-entraining admixture may have a more significant effect on the air content than normally expected. It is the contractor's responsibility to be sure the specific admixture proposed for use is compatible with his operations so that excessive air content in the concrete is not developed. Most lignosulfonate type water-reducers will provide a moderate retardation if used at higher dosage rates.

4. High-Range Water-Reducers

Type F and G high range water-reducing (HRWR) admixtures (frequently called "superplasticizers") are capable of greater water reduction and greater strength gain than regular Type A water-reducers, or can provide substantial increase in slump while maintaining a cohesive concrete without loss of strength. Type G admixtures will also provide retardation of setting similar to Type D admixtures. Problems with this type of admixture include the following: (a) Loss of slump is frequently much more rapid than with plain concrete or when other admixtures are used, especially for older formulations of superplasticizers; (b) Effectiveness depends on the chemistry of the Portland cement, and the cements generally available in Michigan do not have the most favorable chemistry; (c) The air-void system may be adversely affected. Type F and G admixtures are to be used only according to the provisions of the Standard Specifications.

5. Admixtures Containing Chlorides

Some Type A and D admixtures may contain chlorides, as noted in the above listing. Section 903.03 of the Standard Specifications permits the use of these admixtures, except they are prohibited in concrete for bridge superstructure, prestressed concrete, and concrete containing galvanized steel or aluminum.

(End of Admixture Notes)

QUALIFIED PRODUCTS LIST (QPL)					
Spec. # and Material Name	Product Name		Manufacturers or Suppliers		
905.03C Bar Reinforcement (Epoxy Coating)	Epoxy Coating Product Name Scotchkote FBEC 413	Repair Coating Product Name Scotchkote 323R	3M		
NOTE: Epoxy Coating Material Only. The Coating Applicator and Bar Manufacturer can	Resicoat RB-600	Thermal Chem BarPatch #803	Akzo Nobel Powder Coatings		
be Approved Manufacturers, see Approved Manufacturers List.	Nap-Gard 7-2719 Rebar FBE	Nap-Gard 7-1868	Axalta Coating Systems		
	Nap-Gard 7-2750	Nap-Gard 7-1868	Axalta Coating Systems		
	Pureflex Green		IFS Coatings, Inc.		
	Greenbar 720A009	Greenbar 920966S	Valspar (Sherwin Williams)		
	Vectrashield PFY80006	Vectrashield Patch Kit	Valspar (Sherwin Williams)		
906.09	<u>Markings</u>				
Shear Developers (Studs)	В		Bluearc Stud Welding		
	С		Cox Industries		
	N		Nelson Stud Welding Co. (Div. of Gregory Ind.)		
	X		Stud Welding Associates, Inc.		
	TW		Tru-Weld from Tru-Fit Products Corp.		
909.01	Flex-O-Ring		American Highway Products		
Recycled Rubber Adjusting Rings for Manholes and Drainage Structures	Pro-Ring		American Highway Products		
Marinoles and Drainage Structures			Cretex Specialty Products		
	Infra-Riser		East Jordan Iron Works		
	Ladtech HDPE		Ladtech, Inc.		
	HDPE Recycled Manhole	Adjusting Ring	P. Spear Company		
	UGT Grade Ring		Underground Technologies		
	Whirlygig		Whirlygig, Inc.		

Spec. #	Pipe Material	Joint System	Pipe Diameter (Inches)	Approved Manufacturers
		Bell/Spigot N-12WT Pro-Link Ultra WT Rubber Gasket	12 thru 60	ADS – Hancor
	Corrugated Polyethylene Pipe	Compression Gasket	12 thru 24	Baughman Tile Co.
	Corrugated Polyethylene Pipe	Haviland Smooth-Flow WT Compression Gasket	12 thru 36	Haviland Drainage Products Co.
	Corrugated Polyethylene Pipe	MaxSeal Gasket	12 thru 60	JM Eagle
	Corrugated Polyethylene Pipe	Hamilton Kent In-Line Bell Spring Seal	12 thru 15	Lane Enterprises
	Corrugated Polyethylene Pipe	SpringSeal Gasket	18 thru 24	Lane Enterprises
	Corrugated Polyethylene Pipe	Gold Flow Corrugated SLCP Compression Gasket	12 thru 36	Prinsco, Inc.
	Corrugated Polyethylene Pipe	Gold Flow WT w/SpringSeal gaskets	12 thru 36	Prinsco, Inc
	Corrugated Polyethylene Pipe	Bell/Spigot Polyisoprene Gaskets	12 thru 60	Southeast Culvert, Inc.
	Corrugated Polyethylene Pipe	Vertex Single Compression Gasket	12 thru 60	Southeast Culvert, Inc.
	Corrugated Polyvinyl Chloride Pipe (PVC)	Integrally Formed Elastomeric Gasket, Bell/Spigot	12 thru 36	Contech Engineered Solutions, LLC
	Concrete Pipe	Single Offset Self-Lubricating Gasket, Tylox - Hamilton Kent	12 thru 24	Co-Pipe Products Inc.
	Concrete Pipe	Press Seal Gasket Corp4G, 4F; Hamilton Kent-Tylox Super Seal; Universal Polymer & Rubber- Profile Gasket	12 thru 33	Northern Concrete Pipe, Inc.
	Concrete Pipe	Press Seal Gasket Corp4G, 4F, O-ring, M875;	36 thru 72	Northern Concrete Pipe, Inc.
	Concrete Pipe	Hamilton Kent-Tylox Super SeaPress Seal Gasket Corp.O- ring, M875;	78 thru 144	Northern Concrete Pipe, Inc.
	Concrete Pipe	Compression Gasket, Profile Cross Section, O-Ring Cross Section, Pipe Gasket & Supply	12 thru 24	Upper Peninsula Concrete Pipe Co.
	Concrete Pipe	Profile X-Section Gasket, Hamilton Kent	12 thru 36	County Materials Corp.
	Corrugated Metal Pipe	H12 Hugger Band with Single Bolt Bar and Strap with Compression Gasket	12 thru 24	Contech Engineered Solutions, LLC
	Corrugated Metal Pipe	Gasket-Bidco Wrap 12 x 3/8 Band	12 thru 18 Band 7 24 thru 30 Band 12 & larger Band 21	Jensen Bridge & Supply Co.
	Corrugated Metal Pipe	12 Bolted Band Angle with Compression Gasket Bidco Wrap 6 x 1/8 Band	12 thru 72	Cadillac Culvert
	Corrugated Metal Pipe	Bolted Corrugated Steel Band with Compression Gasket Ensolite IV Series	12 thru 24	St. Regis Culvert Inc.

C	UALIFIED PRODUCTS L	LIST (QPL)
Spec. # and Material Name	Product Name	Manufacturers or Suppliers
909.05A1 Polymer Coated Corrugated Steel Pipe	Trenchcoat Protective Film	Valfilm USA
909.06 Class A, B and F Bury Plastic Pipe Smooth Lined Corrugated Plastic Pipe (CPE/HDPE); Corrugated Polyvinyl Chloride Pipe (CPV) 909.10	N12 Dual Wall (CPE/HDPE) A-2000 PVC (CPV) HDPE Corrugated Class B (CPE/HDPE) Lane HDPE (CPE/HDPE) GoldFlo WT HDPE (CPE/HDPE) See Delineator Posts 2. Plastic Material, QPL 91	Advanced Drainage Systems (ADS) Contech Engineered Solutions, LLC Lane Enterprises Lane Enterprises Prinsco, Inc. 9.03D
Drainage Marker Post		
910.04 Silt Fence (Geotextile Fabric only)	Belton 940 Geoturf S1200 Geoturf S1240 Geoturf S1240OR Geoturf S1400 Kintex SF-3 GTF - 180 Propex 2130 SKAPS W100 TerraTex SF-D Willacoochee, Style 1210	Belton Industries, Inc., Norcross, SC CSI Geoturf, Inc., Highland, MI Geoproducts, Inc., Birmingham, MI LinQ Industrial Fabrics Propex Fabrics, Inc., Austell, GA Skaps Industries, Athens, GA Hanes Geo Components, Winston-Salem, NC Willaccochee Industrial Fabrics, Inc., Willacoochee, GA
	WINFAB 105SF	Willacoochee Industrial Fabrics, Inc., Willacoochee, GA
912.08Q Recycled Plastic Or Rubber Guardrail Offset Blocks	Model Type B/BD, MGS-8 and MGS-8D Dura-Bull Bloclout SPI #4 Diamond Block Eco-Block Mondo Block P-Block Thrie Beam Block EDEN Block Polylumber PL6814R King Block Type T/TD Mondo Block Thrie Beam Block EDEN Block Type T/TD Mondo Block Thrie Beam Block EDEN Block Polylumber King Size King Block	Creative Building Products Diamond Roadway Products Eco-Composites LLC Mondo Polymer Technologies, Inc. Monroeville Industrial Moldings Monroeville Industrial Moldings Project Back to EDEN Ramco International Trinity Industries, Inc. Mondo Polymer Technologies Monroeville Industrial Moldings Project Back to EDEN Ramco International Trinity Industries, Inc.
914.03B Recycled Rubber Joint Filler	Reflex	The J D Russell Company

QUALIFIED PRODUCTS LIST (QPL)			
Spec. # and Material Name	Product Name	Manufacturers or Suppliers	
914.06 Epoxy Resin Adhesive & Temporary Seal (Crack Injection)	Crackbond LR321 Crackbond SLV302 Akabond 817	Adhesives Technology Corp. Adhesives Technology Corp. Axson, Eaton Rapids, MI (formerly Akemi	
, , , ,	Akabond 818	Corp.) Axson, Eaton Rapids, MI (formerly Akemi Corp.)	
	Akabond 819	Axson, Eaton Rapids, MI (formerly Akemi Corp.)	
	MasterInject 1380	BASF Construction Chemical, Shakopee, MN	
	MBT P&R Concresive 1360	BASF Construction Chemical, Shakopee, MN	
	BHS-1617 BHS-1618 BHS-1619	Blackhawk Sales Co, Inc., Rock Island, IL Blackhawk Sales Co, Inc., Rock Island, IL Blackhawk Sales Co, Inc., Rock Island, IL	
	Arndite 8560 True Grip 150	Ciba Corporation, East Lansing, MI J. Dedoes, Inc., Milford, MI	
	NIP124LV CI 060	Epoxy Unlimited, Harrison Twp, MI Hilti Inc., Columbus, OH	
	Dynapoxy EP-450 E Bond 550 Sikadur 35, Hi-Mod LV Sikadur 52	Pecora Corporation Ridgemoor Supply, Kentwood, MI Sika Corporation, Lyndhurst, NJ Sika Corporation, Lyndhurst, NJ	
	Pro Poxy 50 Super LV	Unitex, Kansas City, MO	
914.07A Transverse Pavement Joint 1. Dowel Bar Coating (Epoxy)	See Reinforcement Bar Coating, QPL 905.03C		
2. Bond Release	Bond Release Agent - Tectyl 506 BCG Protec 6116 DS MA	Daubert Chemical Bradley Coatings Group	
914.08 Transverse Pavement Joint, <u>Deformed</u> Dowel Bar Coating	See Reinforcement Bar Coating, QPL 905.03C		
914.09 Straight & Bent Tie Bars for Longitudinal Pavement Joints (Lane Ties), Coating	See Reinforcement Bar Coating, QPL 905.03C		
914.11 Preformed Waterproofing Membrane	Carlisle CCW 711-Highway and Bridge Membrane Geotac Waterproofing Membrane Geotac Polyester HS	Carlisle Coatings and Waterproofing Crafco Inc. Crafco Inc.	
NOTE: Not to be used on Treated Wood Materials.	Protecto Wrap M400 AR Sealtight Mel-Dek	Protecto Wrap Co. W.R. Meadows, Inc.	

QUALIFIED PRODUCTS LIST (QPL)						
Spec. # and Material Name	Product Name				Manufacturers or Suppliers	
P15 Coating Systems for Steel Structures, Hanger Assemblies and End Diaphragms NOTES: *Indicates product can be used on faying surfaces of slip critical bolted	*Carbozinc 859 +100 hrs min cure, 6 mils max DFT, 10 oz/gal max thin Carboguard 893 Carbothane 133 VOC #Carbozinc 11 HS Inorganic Zinc Primer +18 hrs min cure, 6 mils max DFT, 15 oz/gal max thin			Coats 1 st 2 nd 3 rd	Carboline Company	
connections which require Class "B". +Information from the Slip Coefficient and Creep Resistance Test Certificate is given for use with primed bolted connections to meet Class "B" requirements.	Intergard 475HS Interthane 870UHS #Interzinc® 22 Inorga			1 st 2 nd 3 rd	International Protecti	ve Coatings
#Alternative primer can only be used on faying surfaces of slip critical bolted connections which require Class "B".	*Amercoat 68HS +168 hrs min cure, 3 mils max DFT, 4 oz/gal max thin Amercoat 399 Amercoat 450H #Dimetcote 9VOC Zinc-Rich Primer +24 hrs min cure, 4 mils max DFT, 7 oz/gal max thin			1 st 2 nd 3 rd	PPG Industries	
	*Zinc Clad III HS +168 hrs min cure, 5 mils max DFT, 12 oz/gal max thin Macropoxy 646 Fast Cure Epoxy Acrolon 218 HS #Corothane I GalvaPac One Pack Zinc Primer +24 hrs min cure, 4 mils max DFT, 0 oz/gal max thin Zinc Clad 4100 +72 hrs min cure, 5 mils max DFT, 6 oz/gal max thin Macropoxy 646 Fast Cure Epoxy Hi-Solids Polyurethane 250 #Corothane I GalvaPac One Pack Zinc Primer +24 hrs min cure, 4 mils max DFT, 0 oz/gal max thin		1 st 2 nd 3 rd 1 st 2 nd 3 rd	Sherwin-Williams Sherwin-Williams		
917.12 Seed Varieties Varieties of Seed on QPL Date of Testing Not to Exceed One Year Approved MDOT seed mixtures, see Table 917-1 in the Spec Book. *Species	*Kentucky Blue Grass Arc Baron Bristol Cannon Corsair Diva Guiness Midnight Nassau NuBlue NuBlue Plus Parade Raven Rugbyll Touchdown Wildwood	*Perennial Ryegrass Advent Accent II Charger II Fiesta 4 Manhattan 5 Palmer III Pennant III Prelude III Prelude IV Premium Quickstart II SR 4220 SR 4420	*Hard Fe Aurora II Aurora G Matterho Nordic Reliant II Rescue Rescue S Scaldis I Spartan SR 3100 SR 3150	Gold rn V 911 I	*Creeping Red Fescue Cindy Lou Dawson Epic Hector Kent Seabreeze GT Sea Link Shademaster II SR 5210	*Fults Salt Grass Fults Fults II Salty

QUALIFIED PRODUCTS LIST (QPL)					
Spec. # and Material Name	Product Name	Manufacturers or Suppliers			
917.15B1 Turf Mulch Blankets,	AEC Premier Straw Highway Double Net Curlex II	American Excelsior Co. American Excelsior Co.			
High Velocity Mulch Blankets (Two Sided Net)	Contech High Velocity ERO-MAT ECS-2 Mulch Blanket	Contech Engineered Solutions, LLC East Coast Erosion Control Blankets			
(Enviroscape HV Straw Mulch Blanket S2000 ECB EX32	Enviroscape ECM ErosionControlBlanket			
	ECB S32	ErosionControlBlanket			
	ETRS-2 RD S2 Erosion Control Blanket	Erosion Tech S.I. Geosolutions / Land			
	WS072B ECS-2D	Green Fix America Hanes Geo Components			
	Erosion Control Blanket DS-150	North American Green			
	Erosion King High Velocity Double Net Excel SS-2 (Regular)	Rhino Seed & Landscape Supply Western Excelsior Corp.			
	WinterStraw HVW	Winters Excelsior Company			
917.15B2 Turf Mulch Blankets,	AEC Premier Straw Highway Single Net Curlex 1-CL	American Excelsior Co. American Excelsior Co.			
Mulch Blankets (Single Sided Net)	Curlex I Contech ERO-MAT	American Excelsior Co. Contech Engineered Solutions, LLC			
	Futerra Mulch Blanket	Profile Products, LLC			
	ECS-1 Mulch Blanket ECS-1D Mulch Blanket	East Coast Erosion Control East Coast Erosion Control			
	Enviroscape Straw Mulch Blanket S1000 ECB EX31	Enviroscape ECM ErosionControlBlanket			
	ECB S31	ErosionControlBlanket			
	ETRS-1 RD WS05	Erosion Tech Green Fix America			
	Erosion Control Blanket DS-75	North American Green			
	Xcel Excelior Erosion Control Blankets Erosion King Mulch Blanket	PPS Packaging Co. Rhino Seed & Landscape Supply			
	S1 Erosion Control Blanket ERO-MAT V75S	Synthetic Ind. / BonTerra America Verdyol-Canada			
	Excel SR-1 (Regular) WinterStraw SNW	Western Excelsior Corp. Winters Excelsior Company			
917.15C	1. Latex Base Adhesive	. ,			
Mulch Binders (Tackifiers)	BUTOFAN NS 268 EZ Straw Seeding Mulch w/Tack	BASF Corp. Rhino Seed & Turf Supply			
	2. Paperfiber Mulch Binders				
	Applegate Mulch Cellin Fiber Mulch	Applegate Insulation System Cellin Manufacturing, Inc.			
	Geoturf Hydro Mulch Geoturf Hydro Mulch Plus	CSI Geoturf, Inc. CSI Geoturf, Inc.			
	Geopro Basis Plus	Hanes Geo Components			
	Hydro Green Hydroseeding Mulch Hydro Green Hydroseeding Mulch	Nu-Wool, Inc. Nu-Wool, Inc.			
	Rhino Greenstar Rhino Greenstar Plus	Rhino Seed & Landscape Supply			
	3. Excelsior/Guar Gum Base Adhesive	Rhino Seed & Landscape Supply			
	Excel Fiber Mulch ConWed 2000	American Excelsior Co. Profile Products, LLC			
	4. Guar Gum Base Adhesive	· ·			
	Geotack EcoTak-OP5	CSI Geoturf, Inc. Eastern Products, Inc.			
	Finn A500 Hydro-Stik Landtack	Finn Corporation Midwest Land Supply, Inc.			
	ConTack	Profile Products, LLC			
	Lawn Tack 5. Hydrophilic Polymers	Rhino Seed & Landscape Supply			
	Agro Tack MP	Agro Diversified Industries			
	Exact-Tac (E-T) Geotack II	American Excelsior Co. CSI Geoturf, Inc.			
	Con-Tack A/T Eco-Tak-SAT 11	Profile Products, LLC Eastern Products, Inc.			
	RMB Plus	Reinco Mulch Binder Corp.			

QUALIFIED PRODUCTS LIST (QPL)					
Spec. # and Material Name		Produc	ct Name		Manufacturers or Suppliers
918.06D Light Weight Composite Handholes	Armorcast Box and Cover Assembly A6001640TAPCX12 PHA Series Hand Holes Quazite Box PG1730BA12 & Cover PG1730HA Polymer Concrete Pull Box & Cover FCA 173012			Arborcast Products Company Highline Products, Inc. Hubbell NewBasis Synertech Molded Products	
918.08C	11 Inch Bo		er S1730HBE	BUA	Akron Foundry Co.
Light Standards, Frangible Transformer Bases	TB1-17 Mc				ANOTH buildly Co.
	13 Inch Bo TB1-17 TB1-17 Mc	odified			Akron Foundry Co.
919.02B1 Reflective Sheeting	Type III Series 3870	Type IV Series 3930	Type IX Series 3990	Type XI Series 4000	3M
		T-6500 Series	T-9500 Series	T-11500 Series	Avery Dennison
	Nikkalite Ultralite Grade II	Nikkalite CRG 94000 Series			Nippon Carbide Industries (USA) Inc.
		5900 Series	7900 Series		ORAFOL Americas Inc.
919.03D Delineator Post, Plastic, Flexible 1. Ground Mount	Survivor Delineator Post Flexi-Guide 400 Series Flexi-Guide 500 Series Flexstake HD 600 Series Flexstake HD 650 Series Flexstake TM 750 Series SH248GP3 Shur-Flex Driveable Delineator SQR-LOC Flexible Delineator			Carsonite PEXCO, Davidson Traffic Control Products PEXCO, Davidson Traffic Control Products Flexstake Flexstake Flexstake Safe-Hit Shur-Tite Trinity Highway/Safe-Hit Impact Recovery Systems	
920.02C	IRS Multipurpose Delineator Post City Post Flexi-Guide FG 300 Model UR Flexi-Guide FG 300 Model EFX K71 Flexible Marker Post SM 700 Series TM 750 Series TSM Series Flexible Delineator Post Shur-Flex Surface Mount Delineator Connected Roads All Weather Elements			PEXCO, Davison Traffic Control Products PEXCO, Davison Traffic Control Products PEXCO, Davison Traffic Control Products US Reflector Flexstake Flexstake New Direction Mfg., Inc. Shur-Tite 3M	
Wet Reflective Beads/Elements	Series 50/51 Reflective Elements Series All Weather 50/51 Visi-Ultra			3M Potters Industries LLC	
921.05A Steel Clamps for Traffic Signal Strain Poles	gnal Strain Clamps Utility Metals				

QUALIFIED PRODUCTS LIST (QPL)					
Spec. # and Material Name	Product Name		Manufacturers or Suppliers		
922.06A	White (Type)	Yellow (Type)			
Temporary Traffic Control, Temporary	5160 (NR)	5161 (NR)	3M		
Pavement Markings	710 (WR) (R)	711 (WR) (R)	3M		
	620 (R)	621 (R)	3M		
Type R and NR Tape	ATM 200 (R)	ATM 200 (R)	ATM		
	Deltaline TWR (R)	Deltaline TWR (R)	Brite-line Technologies, LLC		
Paint - See Specific Paint Type in	Series 100 (R)	Series 100 (R)	Brite-line Technologies, LLC		
QPL 811.03D	Flex-O-Line 200 (NR)	Flex-O-Line 200 (NR)	FOL Tape, LLC		
	Prismoline (R)	Prismoline (R)	Linear Dynamics/ Carrier & Gable		
*WR Tape is wet-night retro reflective	RW-140 (R)	RY-140 (R)	Market Manager Rd Tape, Trelleborg Ind. AB		
	Aztec 100-W (NR)	100-Y (NR)	Tape4, LLC		
	Aztec 102 (R)	390 (R)	Tape4, LLC		
	Director-2 (R)	Director-2 (R)	Volare/ Swarco Industries, Inc.		
	Visaline CG (NR)	Visaline CG (NR)	Volare/ Swarco Industries, Inc.		
	Visaline TWR (NR)	Visaline TWR (NR)	Volare/ Swarco Industries, Inc		
922.06B	Type 1: Model 932 Chip Seal Marker		Apex Universal, Inc.		
Temp. Raised Pavement Markers	TRPM Chip S	Seal Marker	PEXCO, Davidson Traffic Control Products		
	Type 2: Model 932 O	verlay Marker	Apex Universal, Inc.		
	Temporary O	verlay Marker	PEXCO, Davidson Traffic Control Products		
	Type 3: Stimsonite M	odel 88	Stimsonite Corporation		
922.06C	Black (Type)	Other (Type)			
Temporary Pavement Marking, Pavement	ATM-19-285		ATM		
Marking Cover	3M-715		3M		

TESTED STOCK SUPPLIERS

The suppliers in this section may ship Tested Stock material to Michigan Department of Transportation projects with appropriate identification on material.

See Material Quality Assurance Procedures Manual, Section 2.01, General Tested Stock Procedures.

This Tested Stock List is in accordance with the 2012 Standard Specifications for Construction.

Page 91 of 98

TESTED STOCK				
Spec # and Material Name	Tested Stock Manufacturers	Tested Stock Suppliers		
909.06 1. Corrugated Polyethylene Pipe (CPE/HDPE) (Smooth Lined Type S)	Advanced Drainage Systems, Inc. Baughman Tile Company	Advanced Drainage Systems, Inc.		
919.02A1 Metal Sections (Extruded Aluminum)		Michigan Highway Signs Rathco, Inc. Rocal, Inc.		
919.02A3 Aluminum Sheet		Dornbos Sign and Safety Inc. Michigan Highway Signs Rathco, Inc. Rocal, Inc.		

SELECTING AND SHIPPING SAMPLES

The following instructions will apply for the selection, identification, and shipment of samples unless otherwise specified:

- 1. Samples shall be selected with care and shall be representative of the material sampled.
- 2. Pack samples to withstand rough shipment. Liquid materials shall be shipped in screw-top cans or friction-top cans with lids soldered in place unless otherwise specified or required. Friction-top cans with lids not soldered in place and glass jars must be surrounded and packed with suitable absorbent material in sufficient quantity to absorb all the liquid if the tops of the cans should come off or the glass jars should become broken. All packages containing liquid samples shall be marked "Fragile-Liquid."
 - Mark pipe, tile, and concrete test specimens conspicuously, "Handle with Care-Fragile."
- 3. The sample identification form must be legibly prepared and filled out in detail. All available information for proper identification of the sample shall be given including the lot number, batch number, serial number, or other identification marks.
 - The sample identification form shall be securely attached to the container in which the sample is shipped by means of a tag envelope. Also, include duplicate identification sheet inside wrappings, or if shipped in cloth sack, inside the sack.
- 4. Aggregate samples shipped to the Testing Laboratory shall be shipped in a closely woven bag. Do not use sacks which have contained sugar.
- 5. Cement and Pozzolanic Admixtures shall be shipped in plastic lined cloth bags.
- 6. The method of transportation of the samples will depend on the size, weight or quantity of material being shipped, and the time element. Small and light-weight samples shall be sent via UPS, bus, parcel post, or express. Large and heavy-weight samples shall be sent by motor freight. The sampler, being familiar with conditions, shall make shipment in the manner deemed most appropriate and economical.
- 7. Cloth bags, plastic liners, screw-top cans and friction-top cans may be obtained from the Laboratory. All containers must be clean and free from foreign materials. Cloth bags or sacks must be clean, free from tears or holes, and tightly woven to prevent loss of fine material.
- 8. All samples shall be consigned to the Michigan Department of Transportation, Construction Field Services Division, Secondary Governmental Complex, 8885 Ricks Road, Lansing, Michigan 48909, unless otherwise noted.

Page 93 of 98

<u>APPENDIX</u>

Visual Inspection Items - Alphabetical

This list is intended as a quick reference, alphabetical by material name, for materials which normally require some form of testing but have VI quantities listed. It does not include materials which are accepted by VI basis only.

<u>Visual Inspection Items - By Specification Number</u>

This list is intended as a quick reference, by specification number for materials which normally require some form of testing but have VI quantities listed. It does not cover materials which are accepted on a VI basis only.

This Visual Inspection Items List is in accordance with the 2012 Standard Specification for Construction.

Page 94 of 98

VISUAL INSPECTION ITEMS - Alphabetical

SEC.	MATERIAL	MAXIMUM V.I.
Misc.	ABS Pipe	600 In ft
919	Aluminum Sheet	100 sq ft
902	Aggregate, Coarse	100 tons
902	Aggregate, Dense-Graded	500 tons
902	Aggregate, Fine	100 tons
902	Aggregate, Open-Graded	100 tons
904	Asphalt, Liquid (RC-250)	5 gal - 150 lbs
905	Bar Reinforcement (all)	500 lbs
914	Bituminous Fiber Joint Filler	150 sq ft
501	Bituminous Mixtures Polite for Structure Fun. Anchor	500 tons/project/mix
914 914	Bolts for Structure Exp. Anchor Bond Release	250 units
922	Calcium Chloride Solids	20 gal max 5000 lbs
922	Calcium Chloride Solids Calcium Chloride Solutions	1000 gals
Misc.	Cast & Ductile Iron Pipe	250 ft
901	Cement	45 tons
Misc.	Clay Pipe	10 pcs
913	Clay and Sand Lime Brick	1000 pcs
913	Concrete Block	1000 pcs
913	Concrete Brick	1000 pcs
909	Concrete Pipe, Non-Reinforced	10 pcs
909	Concrete Pipe, Reinforced & Elliptical	5 pcs of 42" dia or less
Misc.	Corrugated Galv. Steel Plates	10 plates
909	Corrugated Aluminum Sheets	25 sheets
909	Corrugated Aluminum Alloy Pipe	250 In ft
909	Corrugated Plastic Pipe	<12 in dia 250 ft
	u u	>12 in dia 100 ft
909	Corrugated Plastic Pipe, Smooth Lined	Same as CPP
909	Corrugated Plastic Tubing for Underdrains	250 ft
909	Corrugated Steel Pipe	*
	12" or less	125 ln ft
	15" to 54"	50 In ft
000	60" or greater	25 In ft
909 909	Corrugated Steel Pipe for Underdrains	*
909	Corrugated Steel Sheets 12" or less	125 In ft
	15" to 54"	50 ln ft
	60" or greater	25 In ft
909	Coupling Bands	5 pcs
914	Deformed Bars	500 lbs
919	Delineator Posts, Steel	80 posts
919	Delineator Reflectors (Plastic and Reflective Sheeting)	25 pcs each color
914	Dowel Bars	1200 pcs
918	Electrical Conduit, Plastic	400 İn ft
918	Electrical Conduit, Rigid	400 In ft
914	Epoxy Binder	5 gals
Misc.	Fiberglass and Bit. Cotton Fabric	5 rolls
910	Geotextile Blanket	500 sq yd
910	Geotextile Liner/ Riprap	500 sq yd
910	Geotextile Liner/Heavy Riprap	500 sq yd
910	Geotextile Stabilizer/Separator	500 sq yd
916	Geotextile Silt Fence	500 In ft
920	Glass Beads	500 lbs

(Continued)

VISUAL INSPECTION ITEMS - Alphabetical

SEC.	MATERIAL	MAXIMUM V.I.
902	Granular, Class I	100 tons
902	Granular, Class II (Subbase)	500 cu yd
902	Granular, Class II (Abutment b.f.)	100 cu yd
902	Granular, Class IIA	500 cu yd
902	Granular, Class III	500 cu yd
902	Granular, Class IIIA	100 cu yd
908	Guardrail Beam Elements/End Sections	125 In ft
908	Guardrail Posts, Stee	25 posts
918	Handholes, Precast Concrete	10 pcs
907	High Tensile Wire Fence (Wire)	250 ft
903	Insulating Blanket	10 sheets
903	Interim Curing (Linseed Based)	50 gals
914	Joint Assemblies	Fab. Insp. Req./100 assemblies
914	Joint Sealant, Hot Poured	100 lbs
909	Mastic (Cold-Applied Joint Sealer)	10 gals
903 908	Membrane Curing Compound Metallia Waterston (Sheet Load & Capper)	200 gals
908	Metallic Waterstop (Sheet Lead & Copper)	25 sq ft 10 tons
902	Mineral Filler (Bit. Mixes) Polyethylene Pipe (Downspouts)	<12 in dia 250 ft
909	" " "	>12 in dia 250 it
913	Precast Concrete Bases and Sumps	10 pcs total
918	Precast Concrete Handholes	10 pcs
909	Precast Concrete End Sections	10 pcs
913	Precast Units for Dr. Structures	10 pcs total
909	PVC Pipe (Sanitary Sewer)	600 ft
907	Rail for Braces (Chain Link)	250 ft
919	Reflective Sheeting	1 roll for less than 3" width
905	Reinforcement Steel	500 lbs
917	Seed and Seeding Mixtures	100 lbs
913	Slope Paving Blocks	1000 pcs
909	Smooth Plastic Pipe for Underdrains (Outlet)	250 ft
907	Steel Chain Link Fence Fabric	250 ft
909	Steel End Sections	4 pcs
919	Steel, Galvanized Sign Posts	20 posts
907	Steel Posts/Chain Link Fence	25 line, 25 gate posts
919	Steel Posts/Delineator	80 posts
905	Steel Wire Fabric (Mesh)	500 sq yds
913	Structural Tile	1000 tiles
907	Top Rail (Chain Link)	250 ft
907	Tension Wire	500 ft
914	Tie Bars (Lane Ties)	500 lbs
910	Wall Drain	100 sq ft
919	Wood Sign Posts	20 posts

^{*}See Remarks in Acceptance Requirements Section

VISUAL INSPECTION ITEMS – by Specification Number

SEC.	<u>MATERIAL</u>	MAXIMUM V.I.		
501	Bituminous Mixtures	500 tons/project/mix		
901	Cement	45 tons		
902	Coarse Aggregate	100 tons		
902	Dense-Graded Aggregate	500 tons		
902	Open-Graded Aggregate	100 tons		
902	Granular, Class I	100 tons		
902	Granular, Class II (Subbase)	500 cu yds		
902	Granular, Class II (Abutment b.f.)	100 cu yds		
902	Granular, Class IIA	500 cu yds		
902	Granular, Class III	500 cu yds		
902	Granular, Class IIIA	100 cu yds		
902	Fine Aggregate	100 tons		
902	Mineral Filler (Bit. Mixes)	10 tons		
903	Membrane Curing Compound	200 gals		
903	Insulating Blanket	10 sheets		
903	Interim Curing (Linseed Based)	50 gals		
904	Liquid Asphalt (RC-250)	5 gals		
905	Bar Reinforcement (all)	500 lbs		
905	Steel Wire Fabric (Mesh)	500 sq yds		
907 907	High Tensile Wire Fence (Wire) Steel Chain Link Fence Fabric	250 ft 250 ft		
907	Tension Wire	500 ft		
907	Top Rail (Chain Link)	250 ft		
907	Steel Posts/Chain Link Fence	25 line, 25 gate posts		
907	Rail for Braces (Chain Link)	250 ft		
908	Metallic Waterstop (Sheet Lead & Copper)	25 sq ft		
908	Guardrail Beam Elements/End Sections	125 ft		
908	Guardrail Posts, Steel	25 posts		
909	Reinforced Concrete Pipe & Elliptical RCP	5 pcs of 42 in dia or less		
909	Non-Reinforced Concrete Pipe	10 pcs		
909	Corrugated Steel Pipe	*		
	12" or less	125 In ft		
	15" to 54"	50 In ft		
	60" or greater	25 In ft		
909	Corrugated Steel Sheets	*		
	12" or less	125 ln ft		
	15" to 54"	50 In ft		
	60" or greater	25 ln ft		
909	Steel End Sections	4 pcs		
909	Coupling Bands	5 pcs		
909	Corrugated Aluminum Sheets	25 sheets		
909	Corrugated Aluminum Alloy Pipe	250 In ft		
909	PVC Pipe (Sanitary Sewer)	600 In ft		
909	Corrugated Plastic Pipe	<12 in dia - 250 ft		
000	Communicated Disease Disease Connected Linear	>12 in dia 100 ft		
909	Corrugated Plastic Pipe, Smooth Lined	Same as CPP		
909 909	Mastic (Cold-Applied Joint Sealer) Precast Concrete End Sections	10 gals		
909	Corrugated Steel Pipe for Underdrains	10 pcs		
909	Smooth Plastic Pipe for Underdrains (Outlet)	250 In ft		
909	Corrugated Plastic Tubing for Underdrains	250 in it 250 ln ft		
909	Polyethylene Pipe (Downspouts)	<12 in dia 250 ft		
503	" "	>12 in dia 250 ft		
(Contir	(Continued)			
, 5511111	· · · · · · · · · · · · · · · · · · ·			

VISUAL INSPECTION ITEMS – by Specification Number

SEC.	MATERIAL	MAXIMUM V.I.
910	Geotextile Blanket	500 sq yd
910	Geotextile Liner/Riprap	500 sq yd
910	Geotextile Stabilizer/Separator	500 sq yd
910	Geotextile Liner/Heavy Riprap	500 sq yd
910	Wall Drain	100 sq ft
913	Clay and Sand Lime Brick	1000 pcs
913	Concrete Brick	1000 pcs
913	Concrete Block	1000 units
913	Precast Units for Dr. Structures	10 pcs total
913	Precast Concrete Bases and Sumps	10 pcs total
913	Structural Tile	1000 tiles
913	Slope Paving Blocks	1000 pcs
914	Bituminized Fiber Joint Filler	150 sq ft
914	Hot Poured Joint Sealant	100 lbs
914	Epoxy Binder	5 gals
914	Dowel Bars	1200 bars
914	Joint Assemblies	Fab. Insp. Req./100 assemblies
914	Bond Release	20 gal max
914	Deformed Bars	500 lbs
914	Tie Bars	500 lbs
914	Bolts for Structure Exp. Anchor	250 units
916	Geotextile Silt Fence	500 ft
917	Seed and Seeding Mixtures	100 lbs
918	Precast Concrete Handholes	10 pcs
918	Electrical Conduit, Polyethylene	400 ft
918	Electrical Conduit, Rigid	400 ft
919	Aluminum Sheet	100 sq ft
919	Reflective Sheeting	1 roll for less than 3" width
919	Delineator Reflectors (Plastic & Reflective Sheeting)	25 pcs each color
919	Steel Delineator Posts	80 posts
919	Galvanized Steel Sign Posts	20 posts
919	Wood Sign Posts	20 posts
920	Glass Beads	500 lbs
922	Calcium Chloride Solids	5000 lbs
922	Calcium Chloride Solutions	1000 gals
Misc.	ABS Pipe	600 ln ft
Misc.	Clay Pipe	10 pcs
Misc.	Cast & Ductile Iron Pipe	250 ft
Misc.	Fiberglass and Bit. Cotton Fabric	5 rolls
Misc.	Corrugated Galvanized Steel Plates	10 plates

^{*}See Remarks in Acceptance Requirements Section