

Appendix B Inspection Frequency

Ancillary Structure Type	Routine Inspection Frequency	
	Month	Years
Culvert Less than 10-Foot Span	60	5
Retaining Wall	24	2
Cantilever Structure	24	2
Truss Structure	48	4
Embedded Pole – Wood	48	4
Embedded Pole – Steel	24	2
Steel Strain Pole	48	4
Spun Concrete Pole	48	4
Noise Wall	72	6
Mast Arm	48	4
Dynamic Message Sign (DMS) Support Structure	48	4
Frangible Pole Structure	48	4
Non-Frangible Pole Structure	48	4
High-Mast Lighting Tower (HMLT)	24	2
Communication Tower – Arm’s Length Inspection	120	10
Comm. Tower – Visual Inspection	60	5
Environmental Sensor Station (ESS) Tower – Arm’s Length Inspection	48	4
ESS – Visual Inspection	24	2