



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 001

Proposal ID: 59000-217985

Description: 1.98 mi of hot mix asphalt overlay, shoulder widening, guardrail and pavement markings on Crystal Road from north of M-46 to south of Tamarack Road, Montcalm County. This is a Local Agency Project. ** 596 Cb **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of Ea. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 3.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
217985A	24A0345		HRRR 59000

Location: Crystal Road from M-46 to Tamarack Road.

Route:

Classification Ratings

Cb = 61.09%	Ea = 9.89%	I = 0.49%	J = 1.60%
MOT = 5.02%	Misc = 9.83%	N3 = 2.13%	N93A = 1.14%
N96L = 8.82%			

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$54,200.00	1100001	1.000	LSUM
0020	_Curb Grading	2057001	460.000	Ft
0090	Post, Mailbox	8070095	20.000	Ea
0140	Plastic Drum, Fluorescent, Furn	8120252	6.000	Ea
0145	Plastic Drum, Fluorescent, Oper	8120253	6.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 002

Proposal ID: 58000-218284

Description: Intersection signing improvements on various routes at multiple intersections, Monroe County. This is a Local Agency project. ** 123 N6 **

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
218284A	24A0375		HSIP 58000

Location: On various routes at multiple intersections.

Route:

Classification Ratings

MOT = 4.18%

Misc = 9.02%

N6 = 86.80%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$11,000.00	1100001	1.000	LSUM
0055	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	10.000	Ea
0060	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	10.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 003

Proposal ID: 31000-206727

Description: 2.46 mi of hot mix asphalt crush, shape and resurface, aggregate shoulders and pavement markings on Otter Lake Tapiola Road north of Valley Road, Houghton County. This is a Local Agency project. ** 986 Cb **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of Ea. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
206727A	24A0357		STL 31000

Location: Otter Lake Tapiola Road north of Valley Road.

Route:

Classification Ratings

Cb = 67.30%	Ea = 13.49%	I = 0.22%	K = 0.13%
MOT = 1.48%	Misc = 9.25%	N3 = 0.57%	N6 = 0.32%
N92D = 7.15%	N94B = 0.09%		

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$89,700.00	1100001	1.000	LSUM
0125	Plastic Drum, Fluorescent, Furn	8120252	100.000	Ea
0130	Plastic Drum, Fluorescent, Oper	8120253	100.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 004

Proposal ID: 31000-220744

Description: Bridge reconstruction including removal culvert and replacement with 14-foot by 6-foot concrete box culvert, wingwalls and approach work on Old M-28 from M-28 to the Ontonagon County line, Houghton County. This is a Local Agency project. ** 283 Ea **

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220744A	24A0370		ER 31000

Location: Old M-28 from M-28 to Ontonagon County line.

Route:

Classification Ratings

Ea = 79.67%

Fa = 9.27%

MOT = 1.82%

Misc = 9.25%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$25,700.00	1100001	1.000	LSUM
0070	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0075	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 005

Proposal ID: 23000-215121

Description: Bridge rehabilitation including concrete substructure repairs, fascia box beam repairs, replacement of waterproofing, guardrail and approach work on Smithville Road over the Grand River, Eaton County. This is a Local Agency project. ** 384 Fa **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of Cb. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215121A	24A0379		BO 23000

Location: Smithville Road over the Grand River.

Route:

Classification Ratings

Cb = 14.23%	Ea = 8.66%	Fa = 6.10%	Fb = 0.63%
I = 1.14%	MOT = 3.84%	Misc = 27.42%	N2 = 0.04%
N3 = 0.35%	N6 = 0.02%	N7 = 8.21%	N91A = 14.63%
N91B = 0.52%	N91C = 3.70%	N93A = 1.14%	N96L = 9.35%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$35,000.00	1100001	1.000	LSUM
0020	_Abandoned Utility, Rem	2047001	356.000	Ft
0240	_Riprap, Underwater, Heavy	8137031	185.000	Ton



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 006

Proposal ID: 50000-214709

Description: Bridge rehabilitation including epoxy deck overlay, deck patching, replacement of deck expansion joint and pavement markings on 21 Mile Road over the middle branch of the Clinton River and 22 Mile Road over the north branch of the Clinton River, Macomb County. This is a Local Agency project. ** 768 N9-1A **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of Fa. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
214709A	N/A		MCS 50000

Location: 21 Mile Road over the middle branch of the Clinton River and 22 Mile Road over the north branch of the Clinton River.

Route:

Classification Ratings

Fa = 11.17%	Fb = 0.69%	MOT = 30.62%	Misc = 9.28%
N3 = 0.80%	N4 = 0.31%	N7 = 4.02%	N91A = 30.05%
N91C = 5.42%	N91E = 7.22%	N96L = 0.21%	N96M = 0.21%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$69,750.00	1100001	1.000	LSUM
0010	Project Cleanup	2090001	1.000	LSUM
0055	Plastic Drum, Fluorescent, Furn	8120252	10.000	Ea
0060	Plastic Drum, Fluorescent, Oper	8120253	10.000	Ea
0110	_Reimbursed Permit Fees	1077060	295.000	Dlr



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 007

Proposal ID: 11021-127449-2

Description: 6.77 mi of hot mix asphalt shoulder widening, intersection reconstruction, intermittent cold milling and single course hot mix asphalt resurfacing, drainage improvements, guardrail replacement and pavement markings on US-12 from the Galien/Bertrand Township line easterly to Mayflower Road, Berrien County. ** 9685 Cb or 9685 Ea **In addition to the above minimum prequalification requirement for prime contractors this project includes subclassifications of Cb and Ea. If the prime contractor is not prequalified in those subclassifications it must use prequalified subcontractors. Those subcontractors must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 6.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
127449A	23A0954		ST 11021

Location: US-12 from Galien Township line to Mayflower Road.

Route:

Classification Ratings

B = 0.04%	Cb = 28.60%	Ea = 35.64%	Fa = 4.14%
Fb = 0.00%	H = 0.51%	I = 5.91%	J = 1.59%
K = 0.96%	L = 0.24%	MOT = 3.13%	Misc = 12.78%
N2 = 1.03%	N3 = 0.67%	N6 = 0.81%	N91A = 0.01%
N93A = 0.43%	N93D = 0.07%	N94B = 0.03%	N95D = 0.03%
N96L = 3.36%	N96M = 0.03%		

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	_Railroad Protection, at Grade Crossing, Amtrak	1027060	16,000.000	Dir
0010	Mobilization, Max\$880,500.00	1100001	1.000	LSUM
0020	_Clearing, Spec	2017012	0.380	Acre
0075	_Monitoring Well, Abandon	2037050	2.000	Ea
0660	Post, Mailbox	8070095	89.000	Ea
0895	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	200.000	Ea
0900	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	200.000	Ea
0990	Plastic Drum, Fluorescent, Furn	8120252	300.000	Ea
0995	Plastic Drum, Fluorescent, Oper	8120253	300.000	Ea



Cost Summaries For Primes

Report v1

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
1085	_HMA Spillway	8147011	68.000	Syd
1170	_Slope Restoration, Non-Freeway, Type G	8167011	7,774.000	Syd
1190	Monument Box	8210001	4.000	Ea
1195	Monument Box Adj	8210005	1.000	Ea
1200	Monument Preservation	8210010	6.000	Ea
1205	Protect Corners	8210020	30.000	Ea
1210	Centerline Corrugations, Milled, HMA	8220013	30,610.000	Ft
1215	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	61,050.000	Ft
1220	Contractor Staking	8240001	1.000	LSUM
1225	Staking Plan Errors and Extras, Max \$180/hour	8240002	95.000	Hr



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 008

Proposal ID: 21022-220487

Description: Bridge preventive maintenance includes epoxy polymer bridge deck overlay, joint sealing and pavement markings on US-2 over the Escanaba River, Delta County. This project includes a 5 year epoxy performance warranty. ** 365 N9-1A **

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220487A	N/A		M 21022

Location: US-2 over the Escanaba River. (Str 2085 - B01-21022)

Route: US-2

Classification Ratings

MOT = 6.05%

Misc = 9.78%

N3 = 5.83%

N91A = 78.34%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$33,200.00	1100001	1.000	LSUM
0060	Plastic Drum, Fluorescent, Furn	8120252	80.000	Ea
0065	Plastic Drum, Fluorescent, Oper	8120253	80.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 009

Proposal ID: 63052-211194

Description: 0.71 mi of construction of in-fill sidewalk segments and installation of pedestrian countdown signals on the north/east side of Telegraph Road (US-24) from Franklin Road to north of Square Lake Road, on the north side of Square Lake Road from Franklin Road to Telegraph Road and on the west side of Franklin Road from Telegraph Road to Square Lake Road, Oakland County. ** 1106 Ea or 1106 J **In addition to the above minimum prequalification requirement for prime contractors this project includes subclassifications of Ea and J. If the prime contractor is not prequalified in those subclassifications it must use prequalified subcontractors. Those subcontractors must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 6.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
211194A	24A0462		TA 63052

Location: US-24 at Square Lake Road.

Route:

Classification Ratings

B = 0.93%	Ba = 0.02%	Cb = 1.46%	Ea = 22.64%
H = 5.76%	I = 9.93%	J = 28.57%	K = 1.26%
L = 5.87%	MOT = 6.85%	Misc = 13.69%	N/A = 0.02%
N2 = 0.44%	N3 = 1.34%	N6 = 1.03%	N96M = 0.20%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0010	_Audio-Visual Filming	1047051	1.000	LSUM
0015	Mobilization, Max\$100,600.00	1100001	1.000	LSUM
0080	Project Cleanup	2090001	1.000	LSUM
0130	Pavt, Cleaning	5010001	1.000	LSUM
0150	_Maintaining Water Sprinkler System	8007050	15.000	Ea
0340	Plastic Drum, Fluorescent, Furn	8120252	100.000	Ea
0345	Plastic Drum, Fluorescent, Oper	8120253	100.000	Ea
0530	Protect Corners	8210020	1.000	Ea
0540	Contractor Staking	8240001	1.000	LSUM
0545	Staking Plan Errors and Extras, Max \$180/hour	8240002	8.000	Hr



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 010

Proposal ID: 59045-211319

Description: 33.73 mi of non-freeway sign upgrades on M-46 from US-131 to Douglas Road in the villages of Lakeview and Edmore, Montcalm County. ** 377 N6 **

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
211319A	24A0477		STG 59045

Location: M-46 from US-131 to Douglas Road.

Route: M-46

Classification Ratings

MOT = 8.45%

Misc = 12.73%

N6 = 78.82%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$34,300.00	1100001	1.000	LSUM
0120	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	300.000	Ea
0125	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	300.000	Ea
0165	Contractor Staking	8240001	1.000	LSUM
0170	Staking Plan Errors and Extras, Max \$180/hour	8240002	4.000	Hr



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 011

Proposal ID: 58071-214906

Description: Bridge rehabilitation including epoxy overlay, deck patching, substructure repairs, culvert walls patching, culvert walls underdrain extension, wingwall patching and joint waterproofing on Sulphur Creek culvert under M-125 and on M-52 bridge over Raisin River, Monroe and Washtenaw Counties. This project includes a 5 year performance warranty. ** 416 N9-1A **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of Fa. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
214906A	N/A		M 58071
Location: M-125 over Sulphur Creek. (C06-58071)			
Route:			
214906A	N/A		M 58071
Location: M-52 over Rasin River. (B01-81012)			
Route:			

Classification Ratings

Ea = 0.90%	Fa = 8.03%	Fb = 0.21%	I = 0.38%
MOT = 25.68%	Misc = 9.85%	N3 = 1.85%	N7 = 0.11%
N91A = 29.89%	N91C = 22.87%	N93F = 0.23%	

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$37,900.00	1100001	1.000	LSUM
0050	Plastic Drum, Fluorescent, Furn	8120252	88.000	Ea
0055	Plastic Drum, Fluorescent, Oper	8120253	88.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 012

Proposal ID: 82700-219207

Description: 4.22 mi of soft-binder fiber micro surfacing, upgrading sidewalk ramps and pavement markings on Old 700 (The Strand, Lakeside Drive and Sunset Drive) and Old 712 (Riverbank Road) on Belle Isle, Wayne County. ** 1800 N9-3I **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of N3. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219207A	24A0478		NH 82700

Location: Belle Isle Outer Loop on Old 700 (The Strand, Lakeside Drive and Sunset Drive) and Old 712 (Riverbank Road).

Route: Old 700 & Old 712

Classification Ratings

Cb = 0.28%	Ea = 0.51%	J = 1.07%	K = 0.03%
MOT = 12.27%	Misc = 12.58%	N3 = 20.64%	N6 = 1.25%
N93G = 1.67%	N93I = 49.69%		

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$163,700.00	1100001	1.000	LSUM
0035	Project Cleanup	2090001	1.000	LSUM
0045	Pavt, Cleaning	5010001	1.000	LSUM
0220	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	600.000	Ea
0225	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	600.000	Ea
0295	Contractor Staking	8240001	1.000	LSUM
0300	Staking Plan Errors and Extras, Max \$180/hour	8240002	18.000	Hr



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 013

Proposal ID: 82000-215695

Description: 1.51 mi of hot mix asphalt cold milling and resurfacing, concrete pavement repair, curb ramps, signing and pavement markings on Eureka Road from Fort Street (M-85) easterly to Jefferson Avenue (Biddle Avenue) in the city of Wyandotte, Wayne County. This is a Local Agency project. ** 3082 Cb **

DBE Goal Percent: 6.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215695A	24A0388		ST 82000

Location: Eureka Road from Fort Street (M-85) easterly to Jefferson Avenue (Biddle Avenue).

Route:

Classification Ratings

B = 0.39%	Ba = 0.88%	Cb = 65.66%	Ea = 0.49%
I = 0.04%	J = 2.08%	K = 3.36%	MOT = 4.85%
Misc = 12.15%	N3 = 0.93%	N6 = 0.78%	N93A = 8.39%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$265,700.00	1100001	1.000	LSUM
0025	_Pavt Repr, Remove, Patching	2047011	528.000	Syd
0030	_Misc Obstruction, Rem	2047021	3.000	Cyd
0050	Project Cleanup	2090001	1.000	LSUM
0060	Dr Structure, Temp Lowering	4030390	41.000	Ea
0200	_Field Office	8097043	4.000	Mo
0305	Plastic Drum, Fluorescent, Furn	8120252	550.000	Ea
0310	Plastic Drum, Fluorescent, Oper	8120253	550.000	Ea
0375	_Sodding, Modified	8167011	492.000	Syd
0380	Monument Box Adj	8210005	3.000	Ea
0385	Monument Preservation	8210010	3.000	Ea
0390	Staking Plan Errors and Extras, Max \$180/hour	8240002	15.000	Hr
0395	_Contractor Staking, Modified	8247051	1.000	LSUM



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 014

Proposal ID: 83000-215393

Description: 9.06 mi of hot mix asphalt overlay, aggregate shoulders and permanent pavement markings on 37 Road from 13th Street north to 28 Road, 28 Road from 37 Road west to 31 Road and 31 Road from 28 Road north to 24 Road, Wexford County. This is a Local Agency project. ** 1525 Cb **

DBE Goal Percent: 3.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215393A	24A0365		STL 83000

Location: 37 Road from 13th Street north to 28 Road, 28 Road from 37 Road west to 31 Road and 31 Road from 28 Road north to 24 Road.

Route:

Classification Ratings

Cb = 84.47%	Ea = 5.18%	J = 0.33%	MOT = 2.49%
Misc = 4.77%	N3 = 1.13%	N93A = 0.68%	N96L = 0.95%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$65,000.00	1100001	1.000	LSUM
0060	Post, Mailbox	8070095	5.000	Ea
0115	_HMA Spillway	8147011	32.000	Syd
0120	Monument Box Adj	8210005	14.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 015

Proposal ID: 22000-215119

Description: Bridge replacement with a 3-sided precast concrete culvert 47-foot x 7-foot, steel sheet piling, steel piles and approach work on Foster City Road over the Sturgeon River, Dickinson County. This is a Local Agency project. ** 2255 Ea or 2255 Fa **In addition to the above minimum prequalification requirement for prime contractors this project includes subclassifications of Ea and Fa. If the prime contractor is not prequalified in those subclassifications it must use prequalified subcontractors. Those subcontractors must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 3.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215119A	24A0436		BFP 22000

Location: Foster City Road over the Sturgeon River.

Route:

Classification Ratings

Cb = 6.51%	Ea = 45.76%	Fa = 13.13%	Fb = 1.23%
I = 0.19%	MOT = 2.43%	Misc = 11.05%	N2 = 0.06%
N3 = 0.09%	N6 = 0.03%	N7 = 1.67%	N95C = 12.44%
N95D = 3.17%	N96L = 2.23%		

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$205,000.00	1100001	1.000	LSUM
0150	Contractor Staking	8240001	1.000	LSUM
0155	Staking Plan Errors and Extras, Max \$180/hour	8240002	5.000	Hr
0245	_Riprap, Spec, CI II	8137031	258.000	Ton



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 016

Proposal ID: 46000-214671

Description: 1.00 mi of hot mix asphalt cold milling and resurfacing, sidewalk ramp upgrades and pavement markings on M-50 from (Chicago Boulevard) to Russel Road, Lenawee County. This is a Local Agency project. ** 594 Cb or Comb/Jt. 594 Ea, J or Comb/Jt. 594 Ea, N9-3A or Comb/Jt. 594 J, N9-3A
 **In addition to the above minimum prequalification requirement for prime contractors this project includes subclassifications of Cb, Ea, J and N9-3A. If the prime contractor is not prequalified in those subclassifications it must use prequalified subcontractors. Those subcontractors must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 5.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
214671A	24A0422		STUL 46000

Location: Adrian Street from M-50 to Russel Road.

Route:

Classification Ratings

Cb = 46.30% Ea = 8.34% I = 0.13% J = 10.09%
 K = 4.21% MOT = 5.62% Misc = 13.14% N3 = 0.66%
 N93A = 11.52%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$54,000.00	1100001	1.000	LSUM
0040	Project Cleanup	2090001	1.000	LSUM
0075	Dr Structure, Temp Lowering	4030390	30.000	Ea
0080	Pavt, Cleaning	5010001	1.000	LSUM
0200	Plastic Drum, Fluorescent, Furn	8120252	130.000	Ea
0205	Plastic Drum, Fluorescent, Oper	8120253	130.000	Ea
0260	Contractor Staking	8240001	1.000	LSUM
0265	Staking Plan Errors and Extras, Max \$180/hour	8240002	10.000	Hr



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 017

Proposal ID: 22000-215484

Description: 0.77 mi of hot mix asphalt base crushing, shaping and resurfacing, aggregate shoulders and pavement markings on North Milwaukee Avenue from Lehman Avenue to the northern city limit of Iron Mountain, Dickinson County. This is a Local Agency project. ** 287 Cb **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of N9-2D. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215484A	24A0398		STUL 22000

Location: North Milwaukee Avenue from Lehman Avenue to north city limit of Iron Mountain.

Route:

Classification Ratings

Cb = 61.77% Ea = 8.15% I = 0.05% MOT = 9.04%

Misc = 9.61% N3 = 1.33% N92D = 10.05%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$26,000.00	1100001	1.000	LSUM
0080	Post, Mailbox	8070095	11.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 018

Proposal ID: 63000-219554

Description: 1.90 mi of concrete pavement reconstruction, concrete curb, gutter, sidewalk and ramps, signing and pavement markings on 10 Mile Road from Evergreen Road to Greenfield Road, Oakland County. This is a Local Agency project. ** 5949 B **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of Ea. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 5.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219554A	24A0408		EDC 63000

Location: 10 Mile Road from Evergreen Road to Greenfield Road.

Route:

Classification Ratings

B = 50.86%	Ba = 1.56%	Cb = 0.55%	Ea = 11.49%
Fb = 0.08%	J = 4.28%	K = 1.51%	L = 7.41%
MOT = 7.17%	Misc = 12.55%	N3 = 2.39%	N6 = 0.15%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	_Reimbursed Permit Fees	1077060	1,000.000	Dir
0010	Mobilization, Max\$520,000.00	1100001	1.000	LSUM
0040	_Exploratory Investigation, Utility, Vertical, RCOC	2047001	100.000	Ft
0045	_Exploratory Investigation, Utility, RCOC	2047021	100.000	Cyd
0310	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	50.000	Ea
0315	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	50.000	Ea
0385	Plastic Drum, Fluorescent, Furn	8120252	500.000	Ea
0390	Plastic Drum, Fluorescent, Oper	8120253	500.000	Ea
0480	_Turf Establishment, THM Seed, Regular Mulch, Performance, RCOC	8167011	4,779.000	Syd
0620	Span Wire Tether	8200142	8.000	Ea
0715	_Backplate, TS, RCOC	8207050	16.000	Ea
0720	_Cabinet, ITS Type, Delivered, RCOC	8207050	2.000	Ea
0725	_Cabinet, ITS Type, RCOC	8207050	2.000	Ea
0730	_Camera, Traffic Monitoring, RCOC	8207050	2.000	Ea



Cost Summaries For Primes

Report v1

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0735	_Case Sign, One Way, 12 inch by 27 inch, Non-Illuminated, RCOC	8207050	4.000	Ea
0740	_Case Sign, One Way, 24 inch by 30 inch, Non-Illuminated, RCOC	8207050	4.000	Ea
0745	_Controller, Digital Type, Delivered, SCATS, RCOC	8207050	2.000	Ea
0750	_Global Positioning System Module, Rem, RCOC	8207050	1.000	Ea
0755	_Ground Rod, RCOC	8207050	10.000	Ea
0760	_Pedestal, Alum, RCOC	8207050	11.000	Ea
0765	_Pushbutton Support Post, RCOC	8207050	4.000	Ea
0770	_Pushbutton Support Post, Rem, RCOC	8207050	8.000	Ea
0775	_Street Name Sign, Non-Illuminated, Bracket Arm, RCOC	8207050	4.000	Ea
0780	_Street Name Sign, Non-Illuminated, Two Way, 6 foot, RCOC	8207050	1.000	Ea
0785	_Street Name Sign, Non-Illuminated, Two Way, 8 foot, RCOC	8207050	3.000	Ea
0790	_Video Traffic Detection Camera, Rem, RCOC	8207050	2.000	Ea
0795	_Sprinkler Line	8507001	1,000.000	Ft
0800	_Sprinkler Head, Relocate	8507050	50.000	Ea
0805	_Sprinkler Head, Replace	8507050	50.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 019

Proposal ID: 33000-208102

Description: Bridge rehabilitation including epoxy overlay, railing repairs, sidewalk repairs, substructure repairs, approach work on Martin Luther King Jr. Blvd over the Grand River, Shiawassee Street over the Grand River and Washington Avenue over the Grand River in the city of Lansing, Ingham County. This is a Local Agency project. ** 1282 N9-1A **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of Fa. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
208102A	24A0395		BFP 33000
Location: Martin Luther King Blvd Jr. over Grand River.			
Route:			
209873A	N/A		MCS 33000
Location: Shiawassee Street over Grand River.			
Route:			
209874A	24A0396		BFP 33000
Location: Washington Avenue over Grand River.			
Route:			

Classification Ratings

B = 4.79%	Cb = 6.34%	Ea = 2.03%	Fa = 11.60%
Fb = 4.61%	K = 0.09%	MOT = 11.63%	Misc = 10.13%
N3 = 0.44%	N4 = 7.80%	N91A = 28.50%	N91B = 4.35%
N91C = 3.64%	N91E = 3.35%	N93A = 0.61%	N93F = 0.09%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$118,420.00	1100001	1.000	LSUM
0030	Dr Structure, Temp Lowering	4030390	1.000	Ea
0160	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	106.000	Ea
0165	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	106.000	Ea
0175	Plastic Drum, Fluorescent, Furn	8120252	120.000	Ea



Cost Summaries For Primes

Report v1

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0180	Plastic Drum, Fluorescent, Oper	8120253	120.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 020

Proposal ID: 31000-220652

Description: Bridge reconstruction including replacement of 3 culverts with concrete box culvert approach work on Old Mill Hill Road north of Spring Brook Lane, on Tapiola Road west of Chassell Painesdale Road and on Tapiola Road north of Old Road, Houghton County. This is a Local Agency project. ** 604 Ea **

DBE Goal Percent: 2.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220652A	24A0373		ER 31000
Location: On Old Mill Hill Road north Of Spring Brook Lane.			
Route:			
220663A	24A0368		ER 31000
Location: On Tapiola Road west of Chassell Painesdale Road.			
Route:			
220665A	24A0369		ER 31000
Location: On Tapiola Road north of Old Road.			
Route:			

Classification Ratings

Cb = 2.31%	Ea = 57.82%	Fa = 9.80%	I = 1.45%
K = 0.34%	MOT = 18.71%	Misc = 9.23%	N3 = 0.26%
N94B = 0.08%			

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$54,500.00	1100001	1.000	LSUM
0160	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0165	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 021

Proposal ID: 35000-220783

Description: 0.70 mi of hot mix asphalt ultra-thin overlay and pavement markings on Nunn Road from M-55 to Tawas River Bridge, Iosco County. This is a Local Agency project. ** 88 Cb **

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220783A	24A0418		STL 35000

Location: Nunn Road from M-55 to the Tawas River.

Route:

Classification Ratings

MOT = 13.55%

Misc = 10.42%

N3 = 1.53%

N93I = 74.50%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$8,000.00	1100001	1.000	LSUM
0025	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	75.000	Ea
0030	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	75.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 022

Proposal ID: 41000-216298

Description: 0.80 mi of hot mix asphalt reconstruction, ditching, culverts, storm sewer, retaining wall, guardrail and pavement markings on 84th Street from Kraft Avenue easterly to Broadmoor Avenue (M-37), Kent County. This is a Local Agency project. ** 1713 Cb or 1713 Ea **In addition to the above minimum prequalification requirement for prime contractors this project includes subclassifications of Cb and Ea. If the prime contractor is not prequalified in those subclassifications it must use prequalified subcontractors. Those subcontractors must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 6.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
216298A	24A0403		STU 41000

Location: 84th Street from Kraft Avenue easterly to Broadmoor Avenue (M-37).

Route:

Classification Ratings

Cb = 24.85%	Ea = 48.42%	Fa = 3.07%	Fb = 0.08%
I = 1.17%	J = 0.33%	K = 4.66%	MOT = 2.48%
Misc = 11.47%	N2 = 0.81%	N3 = 0.24%	N7 = 0.02%
N91A = 0.17%	N93A = 0.33%	N94B = 0.32%	N96L = 1.59%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$155,800.00	1100001	1.000	LSUM
0045	_Salvage and Reinstall Fence	2047001	216.000	Ft
0240	_Driveway Opening, Conc, Det M, Modified	8007001	150.000	Ft
0260	Post, Mailbox	8070095	25.000	Ea
0310	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	120.000	Ea
0315	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	120.000	Ea
0325	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0330	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea
0375	_Roadside Seeding	8167011	21,000.000	Syd
0380	Monument Box	8210001	1.000	Ea
0385	Monument Preservation	8210010	1.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 023

Proposal ID: 44000-217981

Description: 0.38 mi of hot mix asphalt cold milling, wedging and resurfacing, aggregate shoulders, replace culvert and pavement markings on North Lake Road south of Hollenbeck Road, Lapeer County. This is a Small Business Program project. Only those approved by MDOT as a Small Business may be eligible to bid as a prime contractor. This is a Local Agency project. ** 375 Cb or 375 Ea **In addition to the above minimum prequalification requirement for prime contractors this project includes subclassifications of Cb and Ea. If the prime contractor is not prequalified in those subclassifications it must use prequalified subcontractors. Those subcontractors must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
217981A	24A0344		HRRR 44000

Location: North Lake Road south of Hollenbeck Road.

Route:

Classification Ratings

Cb = 46.65%	Ea = 22.79%	I = 7.71%	MOT = 9.55%
Misc = 10.80%	N3 = 0.59%	N6 = 1.01%	N93A = 0.91%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$34,100.00	1100001	1.000	LSUM
0015	_Pavt, Rem, Modified	2047011	84.000	Syd
0110	Post, Mailbox	8070095	4.000	Ea
0170	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	75.000	Ea
0175	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	75.000	Ea
0220	Monument Box	8210001	1.000	Ea
0225	Monument Box Adj	8210005	1.000	Ea
0230	Monument Preservation	8210010	1.000	Ea
0235	Protect Corners	8210020	4.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 024

Proposal ID: 82000-215639

Description: 327.00 mi of application of longitudinal line and intersection pavement markings on Rosa Parks Boulevard from Abbot Road to Wyoming Avenue in the city of Detroit, Wayne County. This is a Local Agency project. ** 1708 N3 **

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215639A	24A0420		STG 82000

Location: Rosa Parks Boulevard from Abbot Road to Wyoming Avenue.

Route:

Classification Ratings

MOT = 1.44%

Misc = 9.95%

N3 = 88.61%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$170,000.00	1100001	1.000	LSUM



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 025

Proposal ID: 80000-216342

Description: 0.98 mi of hot mix asphalt cold milling and resurfacing, concrete curb, gutter, sidewalk, ramps and pavement markings on Paw Paw Street from the south village limits of Lawrence to Bangor Road, Van Buren County. This is a Local Agency project. ** 516 Cb or Comb/Jt. 516 Ea, N9-3A **In addition to the above minimum prequalification requirement for prime contractors this project includes subclassifications of Cb, Ea and N9-3A. If the prime contractor is not prequalified in those subclassifications it must use prequalified subcontractors. Those subcontractors must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 3.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
----------------	------------------------	---------------------	-----------------

216342A	24A0428		STL 80000
---------	---------	--	-----------

Location: Paw Paw Street from the south village limits of Village of Lawrence to Bangor Road.

Route:

Classification Ratings

Cb = 49.19%	Ea = 11.18%	I = 0.83%	J = 5.35%
K = 4.96%	MOT = 5.27%	Misc = 9.87%	N3 = 2.03%
N6 = 0.04%	N93A = 11.29%		

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$34,000.00	1100001	1.000	LSUM
0025	_Pavt, Rem, Modified	2047011	116.000	Syd
0110	Dr Structure, Temp Lowering	4030390	19.000	Ea
0185	Post, Mailbox	8070095	2.000	Ea
0255	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	240.000	Ea
0260	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	240.000	Ea
0310	Monument Preservation	8210010	1.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 026

Proposal ID: 46041-220206

Description: 4.99 mi of hot mix asphalt cold milling and resurfacing, joint repair, shoulder gravel, centerline and shoulder corrugations and pavement markings on M-34 from Hazen Creek easterly to Industrial Drive and Industrial Drive from M-34 northerly to US-223 in the city of Adrian, Lenawee County. ** 1999 Cb or Comb/Jt. 1999 N9-3A, N9-3G **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of Cb, N9-3A, and N9-3G. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220206A	N/A		M 46041

Location: M-34 from Hazen Creek easterly to Industrial Drive and Industrial Drive from M-34 northerly to US-223.

Route:

Classification Ratings

Cb = 56.10%	Ea = 2.03%	ITS = 0.33%	K = 0.17%
MOT = 9.38%	Misc = 10.59%	N3 = 1.82%	N6 = 0.04%
N93A = 12.62%	N93G = 6.90%		

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	_Reimbursed Permit Fees	1077060	500.000	Dir
0010	Mobilization, Max\$181,800.00	1100001	1.000	LSUM
0025	Project Cleanup	2090001	1.000	LSUM
0040	Dr Structure, Temp Lowering	4030390	4.000	Ea
0050	Pavt, Cleaning	5010001	1.000	LSUM
0155	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	200.000	Ea
0160	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	200.000	Ea
0185	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0190	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea
0245	Monument Box Adj	8210005	9.000	Ea
0250	Centerline Corrugations, Milled, HMA	8220013	18,600.000	Ft
0255	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	3,000.000	Ft



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 027

Proposal ID: 02042-216166

Description: Bridge preventive maintenance including cleaning and coating structural steel on M-28 over Prairie Creek, Alger County. This project includes a 2 year bridge coating warranty. ** 275 N4 or 275 N9-1G
**

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
216166A	N/A		M 02042

Location: M-28 over Prairie Creek.

Route:

Classification Ratings

Fa = 1.56%

MOT = 11.79%

Misc = 11.38%

N3 = 3.66%

N4 = 71.61%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$25,000.00	1100001	1.000	LSUM
0015	Plastic Drum, Fluorescent, Furn	8120252	25.000	Ea
0020	Plastic Drum, Fluorescent, Oper	8120253	25.000	Ea
0070	Contractor Staking	8240001	1.000	LSUM
0075	Staking Plan Errors and Extras, Max \$180/hour	8240002	3.000	Hr



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 028

Proposal ID: 58011-217506

Description: 5.74 mi of overband crack, chip and fog seal and pavement markings on Old US-223 from US-223 to the Ohio State line, Monroe County. This project includes a 2 year chip seal pavement performance warranty. ** 631 Ca **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of N9-3I. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
217506A	24A0466		ST 58011

Location: On Old US-223 (Memorial Highway) from US-223 to Ohio State Line.

Route: Old US-223

Classification Ratings

Ca = 46.32%	Ea = 4.71%	MOT = 10.20%	Misc = 9.82%
N3 = 3.94%	N6 = 6.33%	N93E = 6.32%	N93I = 12.36%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$59,300.00	1100001	1.000	LSUM
0115	Plastic Drum, Fluorescent, Furn	8120252	120.000	Ea
0120	Plastic Drum, Fluorescent, Oper	8120253	120.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 029

Proposal ID: 31012-220845

Description: 1.92 mi of full depth concrete pavement repair, longitudinal joint repair and spalling and asphalt mastic repairs on M-26 from Green Acres Road northeasterly to Sheldon Avenue in the city of Houghton, Houghton County. ** 723 Ba **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of B. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220845A	24A0476		NH 31012

Location: M-26 from west of Green Acres Road to Sheldon Avenue.

Route: M-26

Classification Ratings

B = 11.31%	Ba = 61.86%	Cb = 0.65%	Ea = 2.15%
J = 0.31%	L = 1.11%	MOT = 8.21%	Misc = 12.20%
N6 = 0.03%	N93C = 0.34%	N93F = 1.84%	

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$65,800.00	1100001	1.000	LSUM
0130	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	500.000	Ea
0135	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	500.000	Ea
0210	Contractor Staking	8240001	1.000	LSUM
0215	Staking Plan Errors and Extras, Max \$180/hour	8240002	8.000	Hr



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 030

Proposal ID: 77011-212683

Description: 5.19 mi of paver placed surface seal, joint repairs, shoulder gravel and pavement markings on M-19 from the city of Memphis to I-69, St. Clair County. This project includes a 3 year pavement performance warranty. ** 1409 Cb **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of N9-3G. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
212683A	24A0486		ST 77011

Location: M-19 from the city of Memphis to I-69.

Route: M-19

Classification Ratings

Ca = 1.54% Cb = 72.85% Ea = 2.73% MOT = 7.78%

Misc = 12.95% N3 = 2.15%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$128,200.00	1100001	1.000	LSUM
0075	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	550.000	Ea
0080	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	550.000	Ea
0135	Monument Box	8210001	5.000	Ea
0140	Monument Preservation	8210010	5.000	Ea
0145	Centerline Corrugations, Milled, HMA	8220013	27,000.000	Ft
0150	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	54,000.000	Ft



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 031

Proposal ID: 38000-216546

Description: 0.51 mi of shared-use concrete path, ramp upgrades, enhanced warning signs, site clearing and turf restoration on MLK Equality Trail from Prospect Street to Martin Luther King Jr Drive in the city of Jackson, Jackson County. This is a Local Agency project. ** 638 Ea or 638 J **In addition to the above minimum prequalification requirement for prime contractors this project includes subclassifications of Ea and J. If the prime contractor is not prequalified in those subclassifications it must use prequalified subcontractors. Those subcontractors must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 5.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
216546A	24A0385		STUL 38000

Location: MLK Equality Trail from Prospect Street to Martin Luther King Jr Drive.

Route:

Classification Ratings

B = 0.25%	Cb = 0.76%	Ea = 27.08%	J = 32.41%
L = 1.19%	MOT = 3.99%	Misc = 30.78%	N2 = 2.44%
N3 = 0.43%	N6 = 0.67%		

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$57,900.00	1100001	1.000	LSUM
0030	_Pavt, Sawcut	2047001	108.000	Ft
0035	_HMA Surface, Rem, Modified	2047011	2,936.000	Syd
0070	Project Cleanup	2090001	1.000	LSUM
0180	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	70.000	Ea
0185	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	70.000	Ea
0230	_Turf Establishment, Performance	8167011	9,021.000	Syd
0255	_Conductor, THWM, in Conduit, 600 V, 1C, #8 AWG	8207001	260.000	Ft
0260	_Conduit, 1-1/2 inch, Sch 80/PVC (Empty)	8207001	75.000	Ft
0265	_Conduit, 3 inch, Sch 80/PVC (Empty)	8207001	130.000	Ft
0270	_Equipment Grounding Conductor, in Conduit, 1C, #8 AWG	8207001	130.000	Ft
0275	_Hand Hole, Polymer Conc, 11 inch x 18 inch (Open Bottom)	8207050	2.000	Ea



Cost Summaries For Primes

Report v1

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0280	_Infrared Bollard, Fdn	8207050	4.000	Ea
0285	_Infrared Bollard, Furn and Install	8207050	4.000	Ea
0290	_Perimeter Lit Flashing LED Sign Assembly	8207050	2.000	Ea
0295	_Post, Wood, Rem	8207050	4.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 032

Proposal ID: 73000-216787

Description: 1.55 mi of hot mix asphalt resurfacing, trenching, shoulder widening and pavement markings on Curtis Road from Bishop Road east to Ambrose Road, Saginaw County. This is a Local Agency project. ** 824 Cb or 824 Ea **In addition to the above minimum prequalification requirement for prime contractors this project includes subclassifications of Cb and Ea. If the prime contractor is not prequalified in those subclassifications it must use prequalified subcontractors. Those subcontractors must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 4.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
216787A	24A0389		FLAP 73000

Location: Curtis Road from Bishop Road east to Ambrose Road.

Route:

Classification Ratings

Cb = 49.17% Ea = 29.58% K = 0.42% MOT = 5.59%

Misc = 14.94% N93A = 0.28%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$74,900.00	1100001	1.000	LSUM
0125	Post, Mailbox	8070095	4.000	Ea
0145	Plastic Drum, Fluorescent, Furn	8120252	190.000	Ea
0150	Plastic Drum, Fluorescent, Oper	8120253	190.000	Ea
0180	_Slope Restoration, Modified	8167011	13,700.000	Syd
0185	Monument Box	8210001	4.000	Ea
0190	Monument Preservation	8210010	4.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 033

Proposal ID: 13000-216528

Description: 4.05 mi of chip seal and fog seal on Territorial Road from Helmer Road to Riverside Road from Gethings Road to Columbia Road, Calhoun County. This is a Local Agency project. ** 426 Ca **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of N3. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 4.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
216528A	24A0456		STUL 13000

Location: Territorial Road from Helmer Road to Riverside Road, from Gethings Road to Columbia Road.

Route:

Classification Ratings

Ca = 63.56% Ea = 3.70% MOT = 6.39% Misc = 10.80%

N3 = 15.54%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	_Railroad Protection, at Grade Crossing, Amtrak	1027060	4,000.000	Dlr
0010	_Railroad Protection, at Grade Crossing, Grand Trunk Western Railroad	1027060	4,000.000	Dlr
0015	Mobilization, Max\$38,100.00	1100001	1.000	LSUM



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 034

Proposal ID: 17000-216791

Description: Bridge replacement with a one-span prestress concrete type IV beam superstructure and approach work on Mackinaw Trail over Chub Creek, Chippawa County. This is a Local Agency project. ** 4155 Fa **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of Ea. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 2.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
216791A	24A0435		FLAP 17000

Location: Mackinaw Trail over Chub Creek.

Route:

Classification Ratings

Cb = 2.94%	Ea = 15.37%	Fa = 42.07%	Fb = 4.40%
I = 1.25%	MOT = 1.30%	Misc = 12.83%	N2 = 0.51%
N3 = 0.05%	N6 = 0.01%	N7 = 0.04%	N91B = 1.21%
N95C = 17.06%	N96L = 0.95%		

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$377,000.00	1100001	1.000	LSUM
0155	Contractor Staking	8240001	1.000	LSUM
0160	Staking Plan Errors and Extras, Max \$180/hour	8240002	8.000	Hr
0305	_Riprap, Spec, CI I	8137031	1,180.000	Ton



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 035

Proposal ID: 34000-211805

Description: 0.81 mi of hot mix asphalt cold milling and resurfacing, sidewalk ramp upgrades and pavement markings on Main Street from Bridge Street to east village limits of Saranac in the village of Saranac, Ionia County. This is a Local Agency project. ** 379 Cb **

DBE Goal Percent: 3.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
211805A	24A0425		STL 34000

Location: Main Street from Bridge Street to east village limits of Saranac.

Route:

Classification Ratings

Cb = 56.52%	Ea = 1.71%	J = 7.42%	K = 2.24%
MOT = 10.76%	Misc = 11.57%	N3 = 1.72%	N93A = 8.06%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$34,600.00	1100001	1.000	LSUM
0135	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	160.000	Ea
0140	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	160.000	Ea
0185	_Turf Restoration	8167011	1,000.000	Syd



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 036

Proposal ID: 31000-220647

Description: 0.27 mi of hot mix asphalt surfacing, aggregate shoulder, guardrail replacement and pavement markings on Canal Road from Gedvillas Road to Liminga Road, Larson Road from Obenhoff Road to Coles Creek Road, Obenhoff Road from Harma Road to Allouez Street and Old Mill Hill Road from Canal Road to Erickson Drive, Houghton County. This is a Local Agency project. ** 311 Cb or 311 Ea
 **In addition to the above minimum prequalification requirement for prime contractors this project includes subclassifications of Cb and Ea. If the prime contractor is not prequalified in those subclassifications it must use prequalified subcontractors. Those subcontractors must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220647A	24A0433		ER 31000
Location: Canal Road from Gedvillas Road to Liminga Road.			
Route:			
220648A	24A0434		ER 31000
Location: Larson Road from Obenhoff Road to Coles Creek Road.			
Route:			
220649A	24A0430		ER 31000
Location: Obenhoff Road from Harma Road to Allouez Street.			
Route:			
220651A	24A0431		ER 31000
Location: Old Mill Hill Road from Canal Road to Erickson Drive.			
Route:			

Classification Ratings

Cb = 39.70% Ea = 41.55% MOT = 6.17% Misc = 9.41%
 N3 = 1.74% N96L = 1.44%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$27,700.00	1100001	1.000	LSUM
0080	Plastic Drum, Fluorescent, Furn	8120252	55.000	Ea
0085	Plastic Drum, Fluorescent, Oper	8120253	55.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 037

Proposal ID: 37000-214145

Description: 3.39 mi of hot mix asphalt base crushing, shaping, pulverizing and resurfacing, concrete joint repairs, trenching for shoulder improvements, signing and pavement markings on Pere Marquette Road from US10BR east to Loomis Road and Loomis Road from Pere Marquette Road north to north of Herrick Road, Isabella County. ** 1328 Cb **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of Ea. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 3.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
214145A	24A0394		STL 37000
Location: Pere Marquette Road from US10BR east to Loomis Road.			
Route:			
220306A	N/A		EDD 37000
Location: Loomis Road from Pere Marquette Road north to north of Herrick Road.			
Route:			

Classification Ratings

Cb = 57.91%	Ea = 14.32%	I = 1.02%	MOT = 6.03%
Misc = 9.73%	N3 = 2.06%	N6 = 0.30%	N92D = 1.93%
N93A = 0.11%	N93G = 6.58%		

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$120,800.00	1100001	1.000	LSUM
0110	Post, Mailbox	8070095	6.000	Ea
0175	Plastic Drum, Fluorescent, Furn	8120252	125.000	Ea
0180	Plastic Drum, Fluorescent, Oper	8120253	125.000	Ea
0205	_HMA Spillway	8147011	15.000	Syd
0215	Monument Box Adj	8210005	3.000	Ea
0220	Monument Preservation	8210010	3.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 038

Proposal ID: 28000-214685

Description: 0.55 mi of hot mix asphalt reconstruction, concrete curb, gutter, sidewalk and ramps, signing and pavement markings on Veterans Drive from Fourteenth Street to the south city limits of Traverse City, Grand Traverse County. This is a Local Agency project. ** 2004 Cb or 2004 Ea **In addition to the above minimum prequalification requirement for prime contractors this project includes subclassifications of Cb, Ea and K. If the prime contractor is not prequalified in those subclassifications it must use prequalified subcontractors. Those subcontractors must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 5.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
214685A	24A0439		STUL 28000

Location: Veterans Drive from Fourteenth Street to the south city limits of Traverse City.

Route:

Classification Ratings

Cb = 24.19%	Ea = 13.74%	I = 0.12%	J = 7.36%
K = 38.80%	L = 0.26%	MOT = 2.01%	Misc = 12.53%
N3 = 0.86%	N6 = 0.11%	N94B = 0.02%	

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$200,000.00	1100001	1.000	LSUM
0030	_Pavt, Rem, Spec	2047011	11,699.000	Syd
0250	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	50.000	Ea
0255	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	50.000	Ea
0265	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0270	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 039

Proposal ID: 35000-215478

Description: 3.35 mi of hot mix asphalt surfacing and pavement markings on Sand Lake Road from north of M-55 to Indian Lake Road and Esmond Road from Putnam Road east to M-65, Iosco County. This is a Local Agency project. ** 557 Cb **

DBE Goal Percent: 3.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215478A	24A0371		STL 35000

Location: Sand Lake Road from north of M-55 to Indian Lake Road.

Route:

Classification Ratings

Cb = 85.53%

MOT = 2.75%

Misc = 10.34%

N3 = 1.38%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$50,700.00	1100001	1.000	LSUM
0035	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	250.000	Ea
0040	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	250.000	Ea
0080	Monument Box	8210001	6.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 040

Proposal ID: 79000-215507

Description: 6.95 mi of hot mix asphalt overlay, aggregate shoulders, signing and pavement markings on Hurds Corner Road from M-46 north to Bevens Road north to Deckerville Road, Tuscola County. This is a Local Agency project. ** 1267 Cb **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of Ea. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 3.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215507A	24A0372		STL 79000
Location: Hurds Corner Road from M-46 north to Bevens.			
Route:			
215508A	24A0376		EDD 79000
Location: Hurds Corner Road from Bevens Road north to Deckerville Road.			
Route:			

Classification Ratings

Cb = 64.13% Ea = 11.73% MOT = 6.36% Misc = 13.52%

N3 = 2.21% N6 = 2.05%

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$115,300.00	1100001	1.000	LSUM
0055	Post, Mailbox	8070095	2.000	Ea
0135	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	371.000	Ea
0140	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	371.000	Ea
0195	_Slope Restoration, Modified	8167011	8,300.000	Syd
0200	Monument Box	8210001	13.000	Ea
0205	Monument Preservation	8210010	13.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 041

Proposal ID: 29000-218088

Description: Bridge rehabilitation including deep concrete deck overlay, replacement of deck expansion joints and deck drains, steel beam end repairs, remove and replace hot mix asphalt bridge wearing surface and deck waterproofing membrane and approach work on Taft Road over the Maple River and Luce Road over the Pine River, Gratiot County. This is a Local Agency project. ** 850 Fa or 850 N4 **In addition to the above minimum prequalification requirement for prime contractors this project includes subclassifications of Fa and N4. If the prime contractor is not prequalified in those subclassifications it must use prequalified subcontractors. Those subcontractors must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
218088A	24A0449		BO 29000
Location: Taft Road over the Maple River.			
Route:			
218092A	24A0451		BFP 29000
Location: Luce Road over the Pine River.			
Route:			

Classification Ratings

Cb = 4.84%	Ea = 1.62%	Fa = 10.66%	Fb = 1.71%
I = 0.35%	MOT = 7.27%	Misc = 15.51%	N3 = 0.13%
N4 = 35.29%	N7 = 0.20%	N91A = 15.87%	N91C = 1.56%
N91F = 1.93%	N93A = 0.87%	N96L = 2.19%	

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$76,800.00	1100001	1.000	LSUM
0095	Plastic Drum, Fluorescent, Furn	8120252	6.000	Ea
0100	Plastic Drum, Fluorescent, Oper	8120253	6.000	Ea
0140	_Railroad Protection, at Grade Crossing, Great Lake Central Railroad	1027060	10,000.000	Dlr
0295	_Riprap, Heavy, Spec	8137031	150.000	Ton



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 042

Proposal ID: 81000-214923

Description: Traffic signal interconnection, actuation and optimization on Maple Road from Textile Road to Ann Arbor-Saline Road, Ann Arbor Saline Road from Maple Road to Waters Road, Lohr Road from Waters Road to Textile Road, Ellsworth Road from Maple Road to east of State Street and Textile Road from Maple Road to Platt Road, Washtenaw County. This is a Local Agency project. ** 1409 ITS or 1409 L **In addition to the above minimum prequalification requirement for prime contractors this project includes subclassifications of ITS and L. If the prime contractor is not prequalified in those subclassifications it must use prequalified subcontractors. Those subcontractors must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 0.00%

Project Information

Table with 4 columns: Project Number, Federal Project Number, Federal Item Number, Control Section. Row 1: 214923A, 24A0419, CPMG 81000

Location: Maple Road from Textile to Ann Arbor-Saline Road. Ann Arbor Saline Road from Maple to Waters Road. Lohr Road from Waters to Textile Road, Ellsworth Road from Maple to east of State Street and Textile Road from Maple Road to Platt Road.

Route:

Classification Ratings

Table with 4 columns of classification ratings: Cb = 0.09%, Ea = 0.36%, J = 1.25%, L = 21.63%, MOT = 1.71%, Misc = 74.13%, N3 = 0.15%, N6 = 0.68%

List of Items by Section

Table with 5 columns: Line Num, Item Description, Item ID, Quantity, Units. Lists various items like Mobilization, Plastic Drum, Turf Establishment, Backplate, Broadband Single Radio, etc.



Cost Summaries For Primes

Report v1

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0335	_TS, Controller, Rem	8207050	4.000	Ea
0340	_TS, MMU	8207050	1.000	Ea
0345	_Video Surveillance Camera, PTZ with Multiview	8207050	10.000	Ea
0350	_Video Surveillance Camera, Rem	8207050	5.000	Ea
0355	_Wireless Interconnect	8207050	15.000	Ea
0360	_Wireless Interconnect, Backhaul Radio	8207050	2.000	Ea
0365	_Wireless Repeater, Flex	8207050	41.000	Ea
0370	_Wireless Repeater, Rem, Modified	8207050	31.000	Ea
0375	_Wireless Vehicle Detection System, Modified	8207050	12.000	Ea
0380	_Wireless Vehicle Detection System, Rem, Modified	8207050	9.000	Ea
0385	_Wireless Vehicle Sensor Node, Modified	8207050	234.000	Ea
0390	_Wireless Vehicle Sensor Node, Rem, Modified	8207050	170.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 043

Proposal ID: 09000-219984

Description: 6.95 mi of hot mix asphalt cold milling and resurfacing, aggregate shoulders and pavement markings on Midland Road from 7 Mile Road to 8 Mile Road, Pine Road from Cass Avenue to Youngs Ditch Road, Freeland Road from Mackinaw Road to M-84, Munger Road from Pine Road to M-15, Parish Road from Fraser Road to M-13 and Midland Road from Auburn city limits to 8 Mile Road, Bay County. This is a Local Agency project. ** 1227 Cb **In addition to the above minimum prequalification requirement for prime contractors this project includes a subclassification of N9-3A. If the prime contractor is not prequalified in this subclassification it must use a prequalified subcontractor. This subcontractor must be designated prior to award of the contract to the confirmed low bidder.

DBE Goal Percent: 3.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219984A	24A0405		STL 09000
Location: Midland Road from 7 Mile Road to 8 Mile Road.			
Route:			
219998A	24A0406		STL 09000
Location: Pine Road from Cass Avenue to Youngs Ditch Road.			
Route:			
219999A	24A0407		STL 09000
Location: Freeland Road from Mackinaw Road to M-84.			
Route:			
220001A	24A0409		STL 09000
Location: Munger Road from Pine Road to M-15.			
Route:			
220002A	24A0411		STL 09000
Location: Parish Road from Fraser Road to M-13.			
Route:			
220007A	24A0412		STL 09000
Location: Midland Road from Auburn City Limits to 8 Mile Road.			
Route:			

Classification Ratings

Cb = 73.92%	Ea = 5.45%	K = 2.32%	MOT = 6.81%
Misc = 9.12%	N3 = 2.15%	N93A = 0.22%	



Cost Summaries For Primes

Report v1

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$105,800.00	1100001	1.000	LSUM
0095	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	200.000	Ea
0100	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	200.000	Ea
0125	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0130	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea



Cost Summaries For Primes

Report v1

Letting ID: 240503

Call Number: 044

Proposal ID: 77000-214712

Description: Bridge rehabilitation including superstructure replacement with 18-inch x 120-inch steel tub girders, galvanized steel sheet piling and approach work on Bluebill Street over Unnamed Creek, St. Clair County. This is a Local Agency project. ** 769 Fa **

DBE Goal Percent: 3.00%

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
214712A	24A0426		BO 77000

Location: Bluebill Street over Unnamed Creek.

Route:

Classification Ratings

B = 0.06%	Cb = 2.44%	Ea = 6.39%	Fa = 61.55%
Fb = 2.89%	I = 0.34%	J = 1.01%	K = 2.12%
MOT = 7.28%	Misc = 10.27%	N3 = 0.04%	N4 = 0.19%
N7 = 0.06%	N91A = 0.34%	N91B = 3.79%	N94B = 0.05%
N96L = 1.17%			

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
0005	Mobilization, Max\$70,000.00	1100001	1.000	LSUM
0035	_Pavt, Rem, Modified	2047011	595.000	Syd
0040	_Remove & Rebuild Paver Wall	2047051	1.000	LSUM
0060	Project Cleanup	2090001	1.000	LSUM
0150	Post, Mailbox	8070095	2.000	Ea
0195	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	22.000	Ea
0200	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	22.000	Ea
0230	Plastic Drum, Fluorescent, Furn	8120252	8.000	Ea
0235	Plastic Drum, Fluorescent, Oper	8120253	8.000	Ea