

Samuel Sorensen, PE Jackson TSC Construction Engineer

TMDOT



Cost and Schedule

- Preliminary Budget: \$109,000,000
- Anticipated Starting Date: Mid-July
- Anticipated Open to Traffic: November 2019
- Cooper Street Resurfacing: April May 2019
- Parnall Road Resurfacing: May 2020



Anticipated Milestone Dates

- Begin Work in Mid-July
- Close and Demo Cooper Street (M-106) Bridge Mid March 2019
- Resurface Cooper Street (M-106) April May 2019
- Shift traffic onto new EB lanes by end of May 2019
- Open Cooper Street (M-106) to traffic by October 2019
- Fully open I-94 by November 23, 2019
- Landscaping, Parnall Rd. and other Misc. work in spring 2020




3.5 Miles of Major Resurfacing





I-94 M-60 to Lansing Avenue







I-94 Lansing Avenue to Elm






I-94 Lansing Avenue to Elm





4.3 Miles of Major Resurfacing








Mine Mitigation

- Cooper Bridge over I-94 Grouting under the structure
- Approximately ½ mile of reconstruction over mines with Continuously Reinforced Concrete Pavement






Mine Mitigation

Potential Equipment





Bore Hole Image of Void







Traffic Impacts

- Maintain two lanes of traffic during daytime hours
- Single lane closures at night
- Nighttime I-94 detours for Cooper Street (M-106) demolition and beam placement
- Utilize Stopped Traffic Advisory System
- Penalties
 - 60 day detour of West Ave interchange loop ramps
 - Cooper St. closed between
 3/19 10/19






Stopped Traffic Advisory System Message Boards






Traffic Impacts – Daytime







Traffic Impacts – Nighttime





































WWW.MICHIGAN.GOV/I94JACKSON

